TRE-APP-APP21-38801251 - Briggs Ranch East Phase 5

SCOPE OF WORK: TREE REMOVAL FOR RESIDENTIAL DEVELOPMENT ***OVERALL TREE PLAN FOR BRIGGS RANCH EAST PHASE 5 UNITS 1, 2A, 2B, 3A & 3B***

// STATUS: APPROVED (UNIT 1 ONLY - 2010 TREE SURVEY METHOD)
AMENDMENT #1 APPROVED 11.24.21. HG
AMENDMENT #2 APPROVED 6.28.22. HG

// PLEASE SEE COMMENTS/CONDITIONS BELOW:

-(2)-1.5" CALIPER NATIVE LARGE SPECIES SHADE TREES AND (1)-1.5" CALIPER NATIVE MEDIUM SPECIES SHADE TREE REQUIRED PER LOT AT BUILDING STAGE FOR MITIGATION AND TREE CANOPY COVER REQUIREMENTS. 1 OUT OF THE 3 TREES SHALL BE PLANTED ON THE SOUTH OR WEST SIDE OF BUILDING FOR ENERGY CONSERVATION CREDIT.

-(62)-1.5" CALIPER NATIVE LARGE SPEICES STREETSCAPE TREES REQUIRED ALONG MANSIONS BLUFFS IN UNIT 1. ESTIMATE BOND AMOUNT \$24,800.00. STREETSCAPE BOND REQUIRED AT TIME OF UNIT 1 PLAT. -(69)-1.5" CALIPER NATIVE LARGE SPEICES STREETSCAPE TREES REQUIRED ALONG MANSIONS BLUFFS IN UNIT 3B. ESTIMATE BOND AMOUNT \$27,600.00. STREETSCAPE BOND REQUIRED AT TIME OF UNIT 3B PLAT.

-THE OVERALL TREE PLAN SHALL BE REVISED WITH EACH PLAT TO VERIFY COMPLIANCE WITH APPROVED TREE PLAN. THE EXHIBIT IS TO SHOW THE EXISTING AND FINAL GRAES FOR EACH INDIVIDUAL UNIT ALONG WITH THE TREES TO BE PRESERVED AND REMOVED. A \$100 AMENDMENT TO PLAN FEE SHALL BE ASSESSED FOR EACH PLAN REVISION.

-THE FOLLOWING TREE NOTE SHALL BE REQUIRED ON PLAT:

THIS SUBDIVISION IS SUBJECT TO A MASTER TREE PLAN (TRE-APP-APP21-38801251) WHICH REQUIRES COMPLIANCE BY THE OWNERS OF ALL PROPERTY WITHIN THE PLAT BOUNDARY, AND THEIR EMPLOYEES AND CONTRACTORS, AND SHALL BE BINDING ON ALL SUCCESSORS IN TITLE EXCEPT FOR OWNERS OF SINGLE-FAMILY RESIDENTIAL LOTS SUBDIVIDED HEREUNDER FOR WHICH CONSTRUCTION OF A RESIDENTIAL STRUCTURE HAS BEEN COMPLETED. THE MASTER TREE PLAN IS ON FILE AT THE CITY OF SAN ANTONIO ARBORISTS OFFICE. NO TREES OR UNDERSTORY SHALL BE REMOVED WITHOUT PRIOR APPROVAL OF THE CITY ARBORIST OFFICE PER 35-477(H).

-CONSTRUCTION ON INDIVIDUAL RESIDENTIAL LOTS OUTSIDE OF CITY LIMITS ARE REQUIRED TO SUBMIT A TREE PERMIT APPLICATION REFERENCING APPROVED TREE PRESERVATION PLAN TO VERIFY COMPLIANCE AT BUILDING STAGE. FAILURE TO DO SO COULD INCUR CESSATION OF ON-SITE CONSTRUCTION, ADDITIONAL MITIGATION, AND/OR WORK WITHOUT PERMIT PENALTIES. -PRIOR TO COMMENCEMENT OF ANY ACTIVITIES REQUIRING A TREE PERMIT, THE APPLICANT SHALL SCHEDULE A PRE-CONSTRUCTION MEETING WITH THE CITY ARBORIST TO REVIEW PROCEDURES FOR PROTECTION AND MANAGEMENT OF ALL SIGNIFICANT, HERITAGE OR MITIGATION TREES (CAN BE SCHEDULED WITH TREE FENCING INSPECTION).

-CALL 207.1111, OR GO ONLINE, TO SCHEDULE A PRE-CONSTRUCTION & FENCING INSPECTION (PER SECTION 35-477 OF THE UDC, SUBSECTION TREE PERMITS (5) (C)

-IT SHALL BE THE RESPONSIBILITY OF THE PERMIT HOLDER TO MAINTAIN A COPY OF THE APPROVED

TREE PLANS, APPROVED TREE PERMIT AND THE CONDITIONS OF APPROVAL IMPOSED BY THE CITY ARBORIST READILY AVAILABLE AT THE SITE AT ALL TIMES DURING WHICH AUTHORIZED WORK IS IN PROGRESS. ALL OFFSITE STAGING, STORAGE, PROJECT TRAILERS, EMPLOYEE PARKING, ETC. IS REQUIRED APPLY FOR A TEMPORARY USES APPLICATION AND TO COMPLY WITH THE TERMS AND CONDITIONS OF THE APPROVED TREE PERMIT.

-**FAILURE TO SCHEDULE A FENCING INSPECTION PRIOR TO START OF WORK MAY RESULT IN A STOP WORK ORDER OR A PENALTY OF \$1000.00 OR BOTH.

// NOTE: APPLICATION IS FOR TREE REMOVAL PURPOSES. TREE REVIEW APPROVAL IS FOR TREE REMOVAL WITHIN UNIT 1 ONLY. ANY SITE WORK OR TREE REMOVAL OUTSIDE OF UNIT 1 SHALL REQUIRE A SEPARATE TREE APPLICATION BE SUBMITTED AND APPROVED PRIOR TO START OF WORK.

// APPLICABLE UDC CODES:

35-523 (k) (5), 35-477 (j), 35-523 (k) (4), 21-170 (b), 35-511 (e), 35-523 (k) (2), 35-477 (5) (c), 35-477 (h) and 35-523 (j) (1)

Please forward a copy to the contractor on site with a copy of the plat or plan (if applicable) for posting on site. A copy of the approved permit and plan must be on site during site work.

// IF YOU HAVE ANY QUESTIONS, PLEASE FEEL FREE TO CONTACT ME AT HERMINIO.GRIEGO@SANANTONIO.GOV OR (210) 207-6042.

									_
			TREE SUR	RVEY SUMM	1ARY (2010) ORD.)			-
CLASSIFICATION	TOTAL TREES (#)	TOTAL TREES (IN)	REQUIRED PRESERVATION (%)	REQUIRED PRESERVATION (IN)	20% MINIMUM PRESERVATION (IN)	TOTAL TREES REMOVED (IN)	TOTAL PRESERVED TREES (IN)	REQUIRED MITIGATION (IN)	
SIGNIFICANT	8	93.0	35%	32.6	18.6	61 (65.6%)	32 (34.4%)	0.6 (1 TO 1)	1
HERITAGE	0	0.0	100%	0.0	0 (20%)	0 (0%)	0 (0%)	0 (3 TO 1)	1


ZE ASS	LOCATION CLASS	CONDITION
ficant	Non-Exempt	Removed
ficant	Exempt	Removed
ficant	Exempt	Removed
ficant	Off—Site*	Saved
ficant	Non-Exempt	Removed
ficant	Non-Exempt	Removed
ficant	Exempt	Removed


POINTS									
POINT #	NORTHING	EASTING	SPECIES	SIZE	SIZE CLASS	LOCATION CLASS	CONDITION		
1001	13689441.66	2045531.52	нк	12	Significant	Non-Exempt	Removed		
1002	13688065.87	2045335.28	RET	8	Significant	Exempt	Removed		
1002	13688065.87	2045335.28	RET	8	Significant	Exempt	Removed		
1003	13687625.24	2044867.64	МК	11	Significant	Off–Site*	Saved		
1004	13689316.65	2043967.28	МК	16	Significant	Non-Exempt	Removed		
1005	13689461.35	2045559.19	НК	13	Significant	Non-Exempt	Removed		
2001	13687780.10	2046075.79	ΗU	10	Significant	Exempt	Removed		
2002	13687675.61	2044600.30	нк	11	Significant	Non-Exempt	Saved		
2003	13687806.45	2044386.31	МК	10	Significant	Exempt	Removed		
2003	13687806.45	2044386.31	МК	10	Significant	Exempt	Removed		
2004	13687857.49	2044266.13	МК	10	Significant	Non-Exempt	Removed		
2005	13687811.97	2044235.32	ΗU	10	Significant	Exempt	Removed		
2006	13688363.50	2043979.08	МК	10	Significant	Non—Exempt	Removed		
2007	13690411.76	2044203.94	НК	10	Significant	Off–Site*	Saved		
3001	13687718.31	2045029.89	МК	10	Significant	Non-Exempt	Saved		
3002	13688800.81	2043898.26	ΗU	11	Significant	Non-Exempt	Saved		
3003	13690377.44	2044315.49	WIL	8	Significant	Off-Site [*]	Saved		
ADECITE TREES WERE NOT INCLUSED IN ANY TREE RECERVATION ON SUBJECTION									

TREE PLANTING TOTAL LOTS WITHIN THE TREE PERMIT AREA REQUIRED TREES PLANTED PER LOT PER UDC WITHIN ALL UNITS (NOT

(COUNTED TOWARD MITIGATION & FINAL CANOPY REQUIREMENTS)


50' ALONG COLLECTOR ROAD)





PROPERTY LINE ·

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery @ 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.



COSA GENERAL NOTES

1. ALL THE TREES WITH A DIAMETER GREATER THAN 3 INCHES AFFECTED BY CONSTRUCTION SHALL HAVE THE LIMBS AND ROOTS TRIMMED AND PRUNED ACCORDING TO ITEM No. 802. TREE PRUNING, SOIL AMENDING AND FERTILIZATION, UNLESS SPECIFIED TREES SHALL RECEIVE LEVEL 2 PROTECTION AS PER ITEM No. 802. TREES TO RECEIVE LEVEL 1 PROTECTION AS PER ITEM No. 802 ARE SHOWN ON TREE PROTECTION TABLE ON THIS SHEET.

2. ALL TREES SHALL REMAIN UNLESS NOTED ON THE PLANS. 3. NO SITE PREPARATION WORK SHALL BEGIN IN AREAS WHERE TREE PRESERVATION AND TREATMENT MEASURES HAVE NOT BEEN COMPLETED AND APPROVED.

4. TREE PROTECTION FENCING SHALL BE REQUIRED. TREE PROTECTION FENCING SHALL BE INSTALLED, MAINTAINED AND REPAIRED BY THE CONTRACTOR DURING SITE CONSTRUCTION.

5. THE CONTRACTOR SHALL AVOID CUTTING ROOTS LARGER THAN THREE INCHES IN DIAMETER WHEN EXCAVATING NEAR EXISTING TREES. EXCAVATION IN THE VICINITY OF TREES SHALL PROCEED WITH CAUTION. THE CONTRACTOR SHALL CONTACT THE CITY INSPECTOR. 6. THE ROOT PROTECTION ZONE IS THAT AREA SURROUNDING A TREE, AS MEASURED BY A RADIUS FROM THE TREE TRUNK, IN WHICH NO EQUIPMENT, VEHICLES OR MATERIALS MAY OPERATE OR BE STORED. THE REQUIRED RADIUS LENGTH IS 1 FOOT PER DIAMETER INCH OF THE TREE. FOR EXAMPLE, A 10-INCH DIAMETER TREE WOULD HAVE A 5-FOOT

RADIUS ROOT PROTECTION ZONE AROUND THE TREE. ROOTS OR BRANCHES THAT ARE IN CONFLICT WITH THE CONSTRUCTION SHALL BE CUT CLEANLY ACCORDING TO PROPER PRUNING METHODS. LIVE OAK WOUNDS SHALL BE PAINTED OVER, WITHIN 20 MINUTES TO PREVENT OAK WII T

7. ACCESS TO FENCED AREAS WILL BE PERMITTED ONLY WITH THE APPROVAL OF THE ENGINEER OR CITY INSPECTOR. 8. GRADING, IF REQUIRED, SHALL BE LIMITED TO A 3 INCH CUT OR FILL WITHIN THE FENCED ROOT ZONE AREAS.

9. TREES, SHRUBS OR BUSHES TO BE CLEARED FROM PROTECTED ROOT ZONE AREAS SHALL BE REMOVED BY HAND AS DIRECTED BY THE PROJECT MANAGER OR CITY INSPECTOR.

10. TREES DAMAGED OR LOST DUE TO CONTRACTOR'S NEGLIGENCE DURING CONSTRUCTION SHALL BE MITIGATED TO THE ENGINEER'S SATISFACTION.

11. EXPOSED ROOTS SHALL BE COVERED AT THE END OF EACH DAY USING TECHNIQUES SUCH AS COVERING WITH SOIL, MULCH OR WET BURLAP.

12. ANY TREE REMOVAL SHALL BE APPROVED BY THE CITY ARBORIST PRIOR TO ITS REMOVAL.



