
BLOSSOM RANCH UNIT 1A

SAN ANTONIO, TEXAS

CIVIL CONSTRUCTION PLANS

SHEET INDEX

Sheet Description	Sheet No.
COVER SHEET	C0.00
OVERALL DRAINAGE PLAN & CALCULATIONS	C1.00
DRAIN PLAN & PROFILE (DRAIN A)	C1.01
DRAIN PLAN & PROFILE (DRAIN B)	C1.02
DRAIN PLAN & PROFILE (DRAIN C)	C1.03
DRAIN DETAILS (PRIVATE DRAINS)	C1.10
DRAIN DETAILS (MISC)	C1.11
DRAIN DETAILS (SBC)	C1.12
DRAIN DETAILS (CURLEX)	C1.13
STREET PLAN & PROFILE (FLUSS RIVER)	C2.00
STREET PLAN & PROFILE (FLUSS RIVER)	C2.01
STREET PLAN & PROFILE (BODEN GLEN)	C2.02
STREET PLAN & PROFILE (BERG HILLS)	
STREET PLAN & PROFILE (BLATT POINT)	
STREET PLAN & PROFILE (HIMMEL CREST)	C2.03
STREET PLAN & PROFILE (VOGEL FIELDS)	
TURN LANE PLAN	C2.04
STREET DETAILS	C2.10
STREET DETAILS	C2.11
STREET DETAILS	C2.12
OVERALL SIGNAGE PLAN	C3.00
OVERALL SIGNAGE PLAN	C3.01
SIGNAGE DETAILS SHEET 1 OF 3	C3.10
SIGNAGE DETAILS SHEET 2 OF 3	C3.11
SIGNAGE DETAILS SHEET 3 OF 3	C3.12
OVERALL WATER DISTRIBUTION PLAN	C4.00
OVERALL WATER DISTRIBUTION PLAN	C4.01
WATER DISTRIBUTION PLAN DETAILS	C4.10
WATER DISTRIBUTION PLAN NOTES	C4.11
OVERALL SANITARY SEWER	C5.00
OVERALL SANITARY SEWER PLAN	C5.01
OVERALL SANITARY SEWER PLAN	C5.02
SANITARY SEWER LINE A ~ STA. 1+00.00 TO END	C5.03
SANITARY SEWER LINE B ~ STA. 1+00.00 TO 12+00.00	C5.04
SANITARY SEWER LINE B ~ STA. 12+00.00 TO END	C5.05
SANITARY SEWER LINE C & D ~ STA. 1+00.00 TO END	C5.06
SANITARY SEWER DETAILS	C5.10
SANITARY SEWER NOTES	C5.11
OVERALL UTILITY PLAN	C6.00
OVERALL UTLITY PLAN	C6.01
OVERALL GRADING PLAN	C7.00
STORM WATER POLLUTION PREVENTION PLAN	C8.00
STORM WATER POLLUTION PREVENTION PLAN DETAILS	C8.10



PREPARED FOR:

LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD.

100 NE LOOP 410, SUITE 1155

SAN ANTONIO, TEXAS 78216

JANUARY 2025



TEXAS ENGINEERING FIRM #470 | TEXAS SURVEYING FIRM #10028800

SEWER UPPER MEDINA - SOUTH SEWERSHED - DOS RIOS/LEON CREEK

DEVELOPER'S NAME: LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD.

ADDRESS: 100 NE LOOP 410, SUITE 1155

CITY: SAN ANTONIO STATE: TEXAS ZIP: 78216

PHONE# (210) 889-5516 E-MAIL: RICHARD.MOTT@LENNAR.COM

SAWS BLOCK MAP# 082-546 TOTAL EDU'S 80 TOTAL ACREAGE 15.89

TOTAL LINEAR FOOTAGE OF PIPE: 8" 2,873 LF PLAT NO. 24-11800406

NUMBER OF LOTS 80 SAWS JOB NO. 24-1630

WATER (SAWS PRESSURE ZONE 4 (930 HGL))

DEVELOPER'S NAME: LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION. LTD
ADDRESS: 100 NE LOOP 410. SUITE 1155

CITY: SAN ANTONIO STATE: TEXAS ZIP: 78216

PHONE# (210) 889-5516 E-MAIL: RICHARD.MOTT@LENNAR.COM

SAWS BLOCK MAP# 082-546 TOTAL EDU'S 81.5 TOTAL ACREAGE 15.8


2" 688 LF


TOTAL LINEAR FOOTAGE OF PIPE: 8" 1.357 LF PLAT NO. 24-11800406

NUMBER OF LOTS 80 SAWS JOB NO. XX-XXXX


SHEET CO.OO

HYDROLOGY SUMMARY TABLE OVERLAND FLOW SHALLOW CHANNEL FLOW (6 FPS) INTENSITY TIME OF TOTAL AREA | COMPOSITE TRAVEL CONCENTRATION POINT STRUCTURE WATERSHED **POINT** (ACRES) C VALUE | LENGTH | TIME | LENGTH | TIME | LENGTH | TRAVEL TIME Q_{25} Q₁₀₀ FEET MINUTES FEET MINUTES FEET MINUTES IN/HR IN/HR CFS **MINUTES** IN/HR **CFS** 0.71 3.74 6.32 CULVERT A1 1.06 0.0 413 5.0 6.79 8.40 5.11 0.52 0.78 5.0 305 5.0 10.48 13.63 3.18 4.25 5.53 CHANNEL A2 40 7.84 REFERENCE STORM WATER MANAGEMENT REPORT FOR HYDRAULIC CALCULATIONS 1.58 5.93 7.39 A1 + A2CHANNEL 13.31 1.0 115 1.0 16.77 1.22 1.73 2.18 **SWALE** SUB AREA B 0.20 0.65 65 9.38 6.42 STREET B1 9.01 0.65 100 10.0 1205 11.0 4.70 7.95 27.54 37.61 46.54 STREET 1.95 0.65 100 10.0 215 2.0 12 5.81 7.97 9.86 7.37 10.10 12.50 10.96 REFERENCE STORM WATER MANAGEMENT REPORT FOR HYDRAULIC CALCULATIONS 30.62 **41.82** 51.75 SIDEWALK BOX B1 + B2 2.58 0.37 0.65 138 1.0 6.32 8.65 10.73 1.52 2.08 **SWALE** 100 10.0 **SWALE** D1 0.12 0.65 7.0 108 1.0 9.36 11.67 0.53 0.73 0.91 65 6.79 5.23 0.65 6.79 23.07 STREET D2 100 10.0 805 7.0 8.40 16.89 28.54 16.89 **23.07** 28.54 8 SIDEWALK BOX D1+ D2 5.35 REFERENCE STORM WATER MANAGEMENT REPORT FOR HYDRAULIC CALCULATIONS






LOCATION MAP NOT-TO-SCALE



DRAINAGE LEGEND




JON D. ADAME

1-24-25


LNN SOM RANCH SAN ANTONIO, TEX BL

PLAT NO. 24-11800406 JOB NO. 13055-20 DESIGNER CHECKED AS DRAWN CB C1.00

(DOC. NO. 20240132079 O.P.R.)



NO. REVISION DAT



SAN ANTONIO, TX 78213 | 210.375.9000 M #470 | TEXAS SURVEYING FIRM #10028800

O, TEXAS

DRAIN "A" ~ STA. 1+00.00 TO E DRAIN PLAN & PROFILE

PLAT NO. 24-11800406

JOB NO. 13055-20

DATE JANUARY 2025

DESIGNER CB

CHECKED AS DRAWN CB

C1.01

DRAINAGE & GRADING NOTES: 1. A BEXAR COUNTY ROW PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED.

TO REPAIR, AT HIS EXPENSE.

- 2. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY
- 3. ALL CONCRETE FOR TXDOT DRAINAGE STRUCTURES SHALL MEET TXDOT SPECIFICATIONS. ALL OTHER CONCRETE SHALL BE CLASS "A" 3000 PSI CYLINDER STRENGTH IN 28 DAYS.
- 4. REFERENCE DRAINAGE DETAILS FOR PIPE TRENCH DETAILS, BOX CULVERT, HEADWALL, AND WINGWALL CONSTRUCTION DETAILS, AND BOX CULVERT BEDDING AND EXCAVATION LIMITS.
- 5. CONTRACTOR SHALL GROUT ALL CURB INLETS AND JUNCTION BOXES TO PROVIDE FOR POSITIVE DRAINAGE.
- 6. EARTHEN CHANNELS WILL BE VEGETATED BY SEEDING OR SODDING. 85% OF THE CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT.
- 7. CONTRACTOR SHALL MATCH TOP OF CHANNEL TO NATURAL GROUND AND MAINTAIN A MINIMUM CHANNEL DEPTH OF "D" AS SHOWN IN THE

HYDRAULIC CALCULATIONS

SIDEWALK BOXES

DRAIN "B"

 $C \times h^{3/2}$

41.82 CFS

 $(3.087)(0.79 \text{ FT})^{3/2}$

Lcal = USE (4)-5 FT SIDEWALK BOXES

 $Bw = C X L X h^{3}(3/2) (WIER EQ.)$

Q25 = 41.82 CFS

C = 3.087

L =

h = 0.79 FT


L = 19.29 FT

TRENCH EXCAVATION SAFETY PROTECTION:

CONTRACTOR AND / OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

CAUTION!!

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON




SECTION "A-A"

EARTHEN TRAP. CHANNEL


NOT-TO-SCALE

STA. 1+12.40 TO 2+31.51



NOT-TO-SCALE

STA. 2+36.51 TO 2+41.67



R49'-

(FOC)

VERTICAL SCALE: 1" = 5'

HORIZONTAL SCALE: 1" = 20'

HIMMEL CREST

(50' ROW)

CAUTION!!!

CROSSING

-(4)-5' SIDEWALK BOXES

W\ARMOR CURB

L20 LF ~ PIPE RAILING


(SEE SHEET C1.02)

WATER/DRAIN

STA: 2+42.00

-PROPOSED

MANHOLE




SCALE: 1"= 20'


EXISTING STORM DRAIN FLOW ARROW

KEY LEGEND:


- (A) 13' ELEC., GAS, TELE, & CA. T.V. EASEMENT
- (B) VARIABLE WIDTH DRAINAGE EASEMENT (BY SEPARATE INSTRUMENT)
- (E) 4' SIDEWALK
- (F) 4' DEVELOPER SIDEWALK
- © 15' CLEARING AND GRADING BUFFER EASEMENT (DOC. NO. 20240132079 O.P.R.)

			HYDRAULIC			HYDRAULIC
		(CALCULATIONS		(CALCULATIONS
	EAF	RTF	IEN TRAP. CHANNEL	<u> </u>	OC	K TRAP. CHANNEL
		STA	(SECTION A-A) . 1+12.40 TO 2+31.51		STA	(SECTION A-A) 2+31.51 TO 2+36.51
	Q25	5 =	41.82 CFS	Q2	5 =	41.82 CFS
	Bw	=	10'	Bw	=	21.5'
	n	=	0.035	n	=	0.035
_	s	=	0.60%	S	=	0.60%
	D	=	1.60'	D	=	1.60'
	dn	=	1.08'	dn	=	0.72'
	\ \	=	2.92 fps	\ \ \	=	2.45 fps
	$ au_{\sf d}$	=	0.32 < 1.0 OK (CLASS 'C' VEGETATION)	$ au_{\sf d}$	=	0.26 < 2.5 OK (ROCK, D50=6IN)





THESE PLANS OR NOT.




TW 659.05


BW 659.05


901 TW 659.05 · FL 657.12


C.L. STA: 2+36.35—

OFFSET 12.00' LT.










UNPLATTED


TRACT 1 276.657 ACRES ANDIRON MULTISTATE 1 LLC

(DOC. NO. 20240217198 O.P.R.)






SIDEWALK BOX SECTION C-C NOT-TO-SCALE




CURB ARMOR DETAIL

NOT-TO-SCALE



SIDEWALK BOX DETAIL SECTION "D-D" NOT-TO-SCALE



DRAIN "B" ~ STA. 1+12.40 TO END

PLAT NO. 24-11800406 13055-20 DESIGNER CHECKED AS DRAWN CB C1.02

+12.40 TO PROFILE

IN "B" ~ DRAIN

SOM RANCH SAN ANTONIO, TEX

JON D. ADAME

DRAINAGE & GRADING NOTES:


- 1. A BEXAR COUNTY ROW PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED.
- 2. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
- 3. ALL CONCRETE FOR TXDOT DRAINAGE STRUCTURES SHALL MEET TXDOT SPECIFICATIONS. ALL OTHER CONCRETE SHALL BE CLASS "A" 3000 PSI CYLINDER STRENGTH IN 28 DAYS.
- 4. REFERENCE DRAINAGE DETAILS FOR PIPE TRENCH DETAILS, BOX CULVERT, HEADWALL, AND WINGWALL CONSTRUCTION DETAILS, AND BOX CULVERT BEDDING AND EXCAVATION LIMITS.
- 5. CONTRACTOR SHALL GROUT ALL CURB INLETS AND JUNCTION BOXES TO PROVIDE FOR POSITIVE DRAINAGE.
- 6. EARTHEN CHANNELS WILL BE VEGETATED BY SEEDING OR SODDING. 85% OF THE CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT.
- 7. CONTRACTOR SHALL MATCH TOP OF CHANNEL TO NATURAL GROUND AND MAINTAIN A MINIMUM CHANNEL DEPTH OF "D" AS SHOWN IN THE

TRENCH EXCAVATION SAFETY PROTECTION:

CONTRACTOR AND / OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.


CAUTION!!

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.



SECTION "A-A" EARTHEN TRAP. CHANNEL NOT-TO-SCALE

STA. 1+78.44 TO 1+90.76



SECTION "B-B" DETAIL **CONCRETE U-CHANNE**

> NOT-TO-SCALE STA. 1+90.76 TO 1+98.20

> > EXISTING STORM DRAIN FLOW ARROW


PROJECT LIMITS

EXISTING CONTOUR

PROPOSED WATER

PROPOSED SEWER

PROPOSED STORM DRAIN



KEY LEGEND:

(A) 13' ELEC., GAS, TELE, & CA. T.V. EASEMENT

DRAINAGE LEGEND

PROPOSED 100 YR FLOODPLAIN

EXISTING 100 YR FLOODPLAIN

SCALE: 1"= 20'


(B) VARIABLE WIDTH DRAINAGE EASEMENT (BY SEPARATE INSTRUMENT)


(E) 4' SIDEWALK

(F) 4' DEVELOPER SIDEWALK

EXISTING 1% A.C. (100-YR) FEMA DFIRM G FLOODPLAIN (FIRM PANEL 48029C0530 EFFECTIVE SEPT. 29, 2010)

H 15' CLEARING AND GRADING BUFFER EASEMENT (DOC NO 20240132079 OPR)








dn = 0.40'

131 CB 4319 276.657 ACRES ANDIRON MULTISTATE 1 LLC (DOC. NO. 20240217198 O.P.R.) —17 LF ∼ PIPE RAILING (SEE SHEET C2.10) **VOGEL FIELDS** CAUTION!!! WATER/DRAIN (50' ROW) STA: 1+98.20 1+00 -PROPOSED MANHOLE (3)-5' SIDEWALK BOXES \W\ARMOR CURB SOIL RETENTION -BLANKET AND 6"-8" ROCK RUBBLE AT 12" SEE THIS SHEET-FOR DRAIN "C"


RIPRAP DETAIL







NOT-TO-SCALE




CURB ARMOR DETAIL NOT-TO-SCALE

PLAT NO. 24-11800406 JOB NO. 13055-20 DESIGNER CHECKED CB DRAWN B C1.03


SOM RANCH UNIT V = 3.60 fpsS

RAIN "C" ~ STA. 1+10.00 TO DRAIN PLAN & PROFILE 四四

Z H



NO. REVISION DATE



FAPE-DAMSON

ENGINEERS

2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000

TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800

LOSSOM RANCH UNIT 1A
SAN ANTONIO, TEXAS
DRAIN DETAILS (PRIVATE DRAINS)

PLAT NO. 24-11800406


JOB NO. 13055-20

DATE JANUARY 2025

DESIGNER CB

CHECKED AS DRAWN CB

SHEET C1.10







TABLE OF ESTIMATED



PAPE-DAWSON

ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800

BLOSSOM RANCH UNIT 1 SAN ANTONIO, TEXAS

PLAT NO. 24-11800406

JOB NO. 13055-20


DATE JANUARY 2025


DESIGNER AD


CHECKED AS DRAWN AD

SHEET <u>C1.11</u>

Oate: Jan Circles Circ







PLAT NO. 24-11800406

13055-20 JANUARY 2025 DESIGNER CHECKED AS DRAWN AD C1.12

American Excelsion Company® **Earth Science Division**





PRODUCT DATA SHEET CURLEX® ENFORCER®

DESCRIPTION

Curlex Enforcer a biocomposite Turf Reinforcement Mat (TRM) that consists of a specific cut of naturally seed free Great Lakes Aspen curled wood excelsior with 80% six-inch fibers or greater fiber length. It is of consistent thickness with fibers evenly distributed throughout the entire area of the blanket. The top and bottom of each blanket is covered with extra heavy duty black net. Curlex Enforcer is also available as QuickGRASS (green pigment). Curlex Enforcer shall be manufactured in the U.S.A.

Curlex Enforcer has a design soil loss ratio (event-based RUSLE C factor) of .022 and is typically suitable for slopes up to .5H:1V. Curlex Enforcer is rated for channel flows up to 11 ft/s (3.4 m/s); 3.25 lb/ft² (156 Pa) shear stress unvegetated or 17 ft/s (5.2 m/s); 10.0 lb/ft² (480 Pa) shear stress vegetated.

PHYSICAL PROPERTIES

I II I DI CILE I ACOI EILI AED			
Curlex Enforcer measurements at time of manufacturing			
Width 8.0 ft (2.4 m)			
Length	67.5 ft (20.6 m)		
Area	$60.0 \text{ yd}^2 (50.2 \text{ m}^2)$		
Weight ^a	75.0 lb (34.1 kg)		
Fiber Count	\approx 12,000 per yd ²		
Fiber Count	$(\approx 14,400 \text{ per m}^2)$		
Fiber Length (80% min.)	≥6.0 in (≥15.2 cm)		
Mass per Unit Area	1.25 lb/yd ²		
(± 10%)	(0.68 kg/m^2)		
Net Openings	0.75 in x 1.0 in		
Met Openings	(19.1 mm x 25.4 mm)		

TYPICAL INDEX VALUES		
Index Property	Test Method	Value
Thickness	ASTM D 6525	0.419 in (10.64 mm)
Light Penetration	ASTM D 6567	12.7%
Resiliency	ASTM D 1777/ECTC	55%
Mass per Unit Area	ASTM D 6475	$0.98 \text{ lb/yd}^2 (0.532 \text{ kg/m}^2)$
MD-Tensile Strength Max.	ASTM D 6818	612.0 lb/ft (8.93 kN/m)
TD-Tensile Strength Max.	ASTM D 6818	460.8 lb/ft (6.72 kN/m)
MD-Elongation	ASTM D 6818	19.5%
TD-Elongation	ASTM D 6818	27.3%
Swell	ECTC Procedure	33%
Water Absorption	ASTM D 1117/ECTC	170%
UV Stability	ASTM D 4355 (1,000 hr)	90% minimum
Bench-Scale Rain Splash	ASTM D 7101	$SLR = 10.24 @ 2 in/hr_{hc}^{b,c}$
Bench-Scale Rain Splash	ASTM D 7101	$SLR = 10.51 \ \text{@} 4 \text{ in/hr}^{6,c}$
Bench-Scale Rain Splash	ASTM D 7101	$SLR = 10.86 \ \text{@ 6 in/hr}^{6,c}$
Bench-Scale Shear	ASTM D 7207	SLR = 10.51 @ 4 in/hr b,c SLR = 10.86 @ 6 in/hr b,c 3.55 lb/ft ² @ 0.5 in soil loss ^c
Germination Improvement	ASTM D 7322	486%

^a Weight is based on a dry fiber weight basis at time of manufacture. Baseline moisture content of Great Lakes Aspen excelsior is

^b SLR is the Soil Loss Ratio, as reported by NTPEP/AASHTO. ° Bench-scale index values should not be used for design purposes.



850 Avenue H East | Arlington, Texas 76011 Phone 1-800-777-SOIL | Fax 817-385-3585 | www.Curlex.com

W0516R1116



Heavy Duty Excelsior Erosion Control Blankets

SUGGESTED SPECIFICATIONS

Choosing the Right Heavy Duty Curlex Product

Heavy Duty Excelsior Blankets are available in various fiber weights and netting combinations to match the appropriate job site requirements. Eighty percent of the Curlex fibers are six-inches or longer with consistent thickness and are evenly distributed over its entire area. Both the top and bottom side of the blankets are covered with black, extruded plastic mesh designed to provide strength beyond the service life of standard blankets. Curlex Excelsior blankets are naturally seed free and do not contain any chemical additives or foreign matter.

Curlex				ons	
Recon	nmen	dec	d Use:		Slope
	E177*				Shea

es to 1H.1V, channel bottom applications, ar stress 120 Pa (2.5 lb/ft²) (unvegetated) Roll Sizes: 40 yd²(4' x90'), 80 yd²(8' x90'), 160 yd²(16' x90') 0.98 lb/yd² Weight*: Black or FibreNet™, top and bottom Netting: Natural Aspen or QuickGRASS Green

Curlex Enforcer Specifications Recommended Use:

Slopes to .5H:1V, channel bottom applications, Shear stress 156 Pa (3.25 lb/ft²) (unvegetated), 480 Pa (10.0 lb/ft²) (vegetated) Roll Sizes: 60 yd²(8'x 67.5')

Weight*: 1.25 lb/yd² Netting: Extra Heavy Duty Black, top and bottom

Natural Aspen or QuickGRASS Green Color: **Curlex HV Specifications**

Shear stress 156 Pa (3.25 lb/ft²) (unvegetated), Roll Sizes: 44.4 yd²(8' x 50')

Weight*: 1.62 lb/yd² Heavy Duty Black or FibreNet™, top and bottom

*Weight is based on a dry fiber weight basis at time of manufacture. Baseline moisture content of Great Lakes Aspen Excelsior is 22%.

Installation

Recommended Use:

Before installing Curlex blankets, the seedbed shall be inspected by the Owner's Representative to ensure it has been properly compacted and fine graded to remove any existing rills. It shall be free of obstructions, such as tree roots, projections such as stones, and other foreign objects. Grass seed shall match soil conditions to allow for maximum germination, dense vegetation, and a structural root system. Contractor shall proceed when satisfactory conditions are present. After the area has been properly shaped, seeded, fertilized, and compacted, locate the start of the roll, making sure the roll is facing toward the area to be covered, and then roll out the blanket. Blankets shall be rolled out flat, even, and smooth without stretching the material then anchored to the subgrade. Slopes: It is recommended that the blankets be installed in the same direction as the water flow; however, on short slopes it may be more practical to install horizontally across the width of the application. If more than one width is required, simply abut the edges together and secure the blankets with a common row of biodegradable staples, steel staples, or stakes. Overlapping of Curlex excelsion blankets is not required or recommended. An exception is waterway slopes.

Slopes to .75H:1V, channel bottom applications,

Channels: Curlex blankets shall be centered to offset a seam in the middle of the waterway. They shall be installed in the same direction as the water flow. The adjoining blankets shall be installed away from the center of channel and concentrated water flow. They shall be secured by a common row of staples. It is usually not necessary to overlap Curlex blankets; however, a 2" shingle type installation shall be used in waterway slopes applications. Curlex blanket installation should continue up the side slopes 3' above the anticipated high water elevation. Flanks exposed to runoff, or sheet flow, must be protected by a check slot or trenched. Curlex blankets shall be trenched at the start of the channel and anchored using a staggered staple pattern at end of roll overlaps and end of roll terminations.

Disclaimer: Curlex III, Curlex Enforcer, and Curlex HV is a system for erosion control and re-vegetation on slopes and channels. American Excelsior Company (AEC) believes that the information contained herein to be reliable and accurate for use in erosion control and re-vegetation applications. However, since physical conditions vary from job site to job site and even within a given job site, AEC makes no performance guarantees and assumes no obligation or liability for the reliability or accuracy of information containe herein for the results, safety, or suitability of using Curlex, or for damages occurring in connection with the installation of any erosion control product whether or not made by AEC or its affiliates, except as separately and specifically made in writing by AEC. These specifications are subject to change without notice.



If you would like to receive more information or consult with one of our Customer Care Center Specialists, please call us toll free at (888-352-9582) PDF download specifications available in the Technical Support Library at www.curlex.com



Curlex Blankets

Heavy Duty Excelsior Erosion Control Blankets

Heavy Duty Curlex Blankets, for long-term protection against wind and water erosion, are a natural choice in place of stone or riprap in swales, ditch bottoms, and on long, steep slopes.

Curlex III

0.98 lb/yd2 of Great Lakes Aspen Excelsior Wood Fibers and two layers of netting designed to provide protection for grass seed and topsoil from wind and water erosion for up to 36 months, while simultaneously promoting ideal growing conditions.

Curlex Enforcer 1.25 lb/yd2 of Great Lakes Aspen Excelsior Wood Fibers and two layers of extra heavy duty UV stabilized netting designed to provide permanent service life and reinforcement between established vegetation and root systems on slopes and in channel bottoms. Curlex Enforcer is a biocomposite turf reinforcement mat (TRM).

Curlex High Velocity

1.62 lb/yd2 of Great Lakes Aspen Excelsior Wood Fibers and two layers of heavy duty netting designed to provide extended protection for grass seed and topsoil from wind and water erosion for approximately 36+ months, while simultaneously promoting ideal growing conditions on steep, long slopes and/or in channel applications.

Curlex heavy duty excelsior blankets are available individually wrapped or in master packs to allow for mechanical unloading and stacking.

PERFORMANCE CAPABILITIES

Curlex heavy duty blankets can handle wind and water shear even on steep slopes. These heavy duty blankets provide long-term protection in critical areas where vegetation requires additional time and protection to develop.

Curlex III Channels Shear Stress: 120 Pa (2.5 lb/ft²) (unvegetated) Slopes Grade: up to 1H:1V

Curlex Enforcer

Channels Shear Stress: 156 Pa (3.25 lb/ft²) (unvegetated) 480 Pa (10.0 lb/ft²) (vegetated)

Slopes

Curlex HV Shear Stress: 156 Pa (3.25 lb/ft²) (unvegetated) Channels

Slopes Grade: up to .75H:1V

TYPICAL APPLICATIONS

Channel bottoms, swales, steep slopes, let down structures, drop structures, and other areas associated with concentrated water flow exceeding the performance capability and service life of a standard biodegradable blanket.

up to .50H:1V









UNI S

PLAT NO. 24-11800406 JOB NO. 13055-20 JANUARY 2025 ESIGNER

HECKED AS DRAWN AD C1.13

DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.





KEY LEGEND:

- (A) 10' ELEC., GAS, TELE, & CA. T.V. EASEMENT
- © 14' ELEC., GAS, TELE, & CA. T.V. EASEMENT
- (D) 6' DEVELOPER SIDEWALK
- E 4' SIDEWALK
- F 4' DEVELOPER SIDEWALK
- © 12' PRIVATE DRAINAGE EASEMENT
- (H) VARIABLE WIDTH SANITARY SEWER EASEMENT
- J 6' SIDEWALK
- 6" DOUBLE SOLID YELLOW LINE (THERMOPLASTIC) (470 LF)
 W/ TYPE II—AA REFLECTIVE PAVEMENT MARKERS

K 1' VEHICLE NON-ACCESS EASEMENT

- M VARIABLE WIDTH CLEAR VISION EASEMENT
- (1) 13' ELEC., GAS, TELE, & CA. T.V. EASEMENT
- Q VARIABLE WIDTH (MIN. 14') ELEC., GAS, TELE, & CA. T.V. EASEMENT

STREET LEGEND

DRIVEWAY

STREET LEGEN	<u>D</u>
PROJECT LIMITS	
MAINTAIN GUTTER	\longrightarrow — \rightarrow
EXISTING CONTOUR	
WHEELCHAIR RAMP	•
CENTERLINE	CL
RADIUS POINT	RP
POINT OF CURVATURE	PC
POINT OF TANGENCY	PT
RETURN	RET
DRAINAGE FLOW ARROW	→
TOP OF CURB SPOT ELEVATION	857.30
PAVEMENT ELEVATION	857.00(P) ×
WASHOUT CROWN SECTION	

SIDEWALK (HOMEOWNER'S RESPONSIBILITY) SIDEWALK (DEVELOPER'S RESPONSIBILITY)

JON D. ADAME

IND H

1+00. AN &

A PL

SIDEWALK NOTE:

THE CONSTRUCTION OF SIDEWALKS ADJACENT TO ALL 900 SERIES LOTS WILL BE THE RESPONSIBILITY OF THE DEVELOPER AS SHOWN ON THE OVERALL SIGNAGE PLAN (SHEET C3.00 - C3.01). REFER TO SHEET C3.00 -C3.01 FOR LOCATIONS OF SIDEWALK CONSTRUCTION WHERE SIDEWALKS ARE NOT SHOWN

STREET SELECT FILL NOTE:

FILL MATERIAL SHOULD BE NATIVE ON-SITE MATERIAL, FREE OF DELETERIOUS MATERIAL WITH A MINIMUM CBR VALUE OF 2.5 AND A PI MAXIMUM OF 40. THE GRAVEL SIZE SHOULD NOT EXCEED 3 INCHES IN DIAMETER. LIME APPLICATION RATE SHOULD BE RE-EVALUATED FOR THE FILL MATERIAL. THE MATERIAL SHOULD BE PLACED AS PER APPLICABLE CITY OR COUNTY GUIDELINES.

WHEEL CHAIR NOTE:


WHEEL CHAIR RAMPS (WCR) TO BE CENTERED ON STATION NOTED BELOW. ELEVATION SHOWN ARE TOP OF CURB AND NOT GUTTER


STREET NOTES:

- 1. A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING I BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS
- 2. CONTRACTOR SHALL MATCH EXISTING PAVEMENT AT TIE-IN. IF EXISTING PAVEMENT ELEVATION DIFFERS SIGNIFICANTLY, CONTRACTOR SHALL NOTIFY THE ENGINEER PRIOR TO CONTINUING WORK.
- 3. SIDEWALKS SHALL BE CONSTRUCTED 3—FT FROM THE BACK OF CURB FOR ALL LOCATIONS WHERE THE SIDEWALK IS SHOWN OFFSET. REFER TO STREET DETAIL SHEET FOR SIDEWALK AND RAMP DETAILS.
- 4. NO PERMANENT STRUCTURES HIGHER THAN 3 FEET, AND LOWER THAN 8 FEET ABOVE THE PAVEMENT, INCLUDING STRUCTURES, WALLS, FENCES, AND VEGETATION, SHALL BE CONSTRUCTED OR ALLOWED WITHIN THI CLEAR VISION EASEMENT. CONTRACTOR SHALL GRADE AREAS WITHIN CLEAR VISION EASEMENTS SUCH THAT THE ELEVATION WITHIN THE CLEAR VISION EASEMENT IS NOT HIGHER THAN 3 FEET ABOVE THE ADJACENT TOP OF PAVEMENT.
- 5. DRIVEWAYS SHOWN ON THIS PLAN ARE FOR THE SOLE PURPOSE OF INDICATING A POTENTIAL CONFLICT WITH CURB RAMP, DRAINAGE INFRASTRUCTURE, OR OTHER CONFLICT. DRIVEWAY LOCATION IS SUBJECT TO CHANGE BASED ON HOME SELECTION AND FINAL LOT DESIGN.
- 6. CHANGES IN THE SIDEWALK LOCATION FOR A MAXIMUM LINEAR DISTANCE OF TWO HUNDRED (200) FEET ARE PERMITTED TO BE APPROVED BY THE FIELD INSPECTOR WITHOUT AMENDING THE STREET PLAN OF UTILITY LAYOUT PER UDC SECTION 35-506 (Q)(6).

T NO 24-11800406 13055-20 JANUARY 2025

DESIGNER HECKED AS DRAWN CB






STREET LEGEND

PROJECT LIMITS		
MAINTAIN GUTTER	$\longrightarrow \longrightarrow -$	$- \rightarrow$
EXISTING CONTOUR	97	·0 - — — —
WHEELCHAIR RAMP	0)
CENTERLINE	С	L
RADIUS POINT	R	Р
POINT OF CURVATURE	P	С
POINT OF TANGENCY	Р	Т
RETURN	RE	Τ
DRAINAGE FLOW ARROW	_	>
TOP OF CURB SPOT ELEVATION	857	.30
PAVEMENT ELEVATION	857.0	00(P) ×
WASHOUT CROWN SECTION		
SIDEWALK (HOMEOWNER'S RESPONSIB	LITY)	
SIDEWALK (DEVELOPER'S RESPONSIBIL	ITY)	
DRIVEWAY		

KEY LEGEND:

- (A) 10' ELEC., GAS, TELE, & CA. T.V. EASEMENT
- B 15' CLEARING AND GRADING BUFFER EASEMENT (DOC. NO. 20240132079 O.P.R.)
- (C) 14' ELEC., GAS, TELE, & CA. T.V. EASEMENT
- (D) 6' DEVELOPER SIDEWALK
- € 4' SIDEWALK
- F 4' DEVELOPER SIDEWALK
- © 10' PRIVATE DRAINAGE EASEMENT
- H EXISTING 100' SANITARY SEWER EASEMENT

 (J) 6' SIDEWALK
- (L) 5'X5' ADA PASSING SPACE
- 13' ELEC., GAS, TELE, & CA. T.V. EASEMENT
- P 14' ELEC., GAS, TELE, & CA. T.V. EASEMENT



SIDEWALK NOTE:

THE CONSTRUCTION OF SIDEWALKS ADJACENT TO ALL 900 SERIES LOTS WILL BE THE RESPONSIBILITY OF THE DEVELOPER AS SHOWN ON THE OVERALL SIGNAGE PLAN (SHEET C3.00—C3.01). REFER TO SHEET C3.00—C3.01 FOR LOCATIONS OF SIDEWALK CONSTRUCTION WHERE SIDEWALKS ARE NOT SHOWN

STREET SELECT FILL NOTE:

FILL MATERIAL SHOULD BE NATIVE ON—SITE MATERIAL, FREE OF DELETERIOUS MATERIAL WITH A MINIMUM CBR VALUE OF 2.5 AND A PI MAXIMUM OF 40. THE GRAVEL SIZE SHOULD NOT EXCEED 3 INCHES IN DIAMETER. LIME APPLICATION RATE SHOULD BE RE—EVALUATED FOR THE FILL MATERIAL. THE MATERIAL SHOULD BE PLACED AS PER APPLICABLE CITY OR COUNTY GUIDELINES.

WHEEL CHAIR NOTE:

WHEEL CHAIR RAMPS (WCR) TO BE CENTERED ON STATION NOTED BELOW. ELEVATION SHOWN ARE TOP OF CURB AND NOT GUTTER

STREET NOTES:

- 1. A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED.
- 2. CONTRACTOR SHALL MATCH EXISTING PAVEMENT AT TIE—IN. IF EXISTING PAVEMENT ELEVATION DIFFERS SIGNIFICANTLY, CONTRACTOR SHALL NOTIFY THE ENGINEER PRIOR TO CONTINUING WORK.
- 3. SIDEWALKS SHALL BE CONSTRUCTED 3—FT FROM THE BACK OF CURB FOR ALL LOCATIONS WHERE THE SIDEWALK IS SHOWN OFFSET. REFER TO STREET DETAIL SHEET FOR SIDEWALK AND RAMP DETAILS.
- 4. NO PERMANENT STRUCTURES HIGHER THAN 3 FEET, AND LOWER THAN 8 FEET ABOVE THE PAVEMENT, INCLUDING STRUCTURES, WALLS, FENCES, AND VEGETATION, SHALL BE CONSTRUCTED OR ALLOWED WITHIN THE CLEAR VISION EASEMENT. CONTRACTOR SHALL GRADE AREAS WITHIN CLEAR VISION EASEMENTS SUCH THAT THE ELEVATION WITHIN THE CLEAR VISION EASEMENT IS NOT HIGHER THAN 3 FEET ABOVE THE ADJACENT TOP OF PAVEMENT.
- 5. DRIVEWAYS SHOWN ON THIS PLAN ARE FOR THE SOLE PURPOSE OF INDICATING A POTENTIAL CONFLICT WITH CURB RAMP, DRAINAGE INFRASTRUCTURE, OR OTHER CONFLICT. DRIVEWAY LOCATION IS SUBJECT TO CHANGE BASED ON HOME SELECTION AND FINAL LOT DESIGN.
- 6. CHANGES IN THE SIDEWALK LOCATION FOR A MAXIMUM LINEAR DISTANCE OF TWO HUNDRED (200) FEET ARE PERMITTED TO BE APPROVED BY THE FIELD INSPECTOR WITHOUT AMENDING THE STREET PLAN OR UTILITY LAYOUT PER UDC SECTION 35-506 (Q)(6).

BLOSSOM RANCH L

ග් ∞


PLAT NO. 24-11800406

JOB NO. 13055-20

DATE JANUARY 2025

DESIGNER CB


HECKED AS DRAWN CB





DRIVEWAY

PROJECT LIMITS MAINTAIN GUTTER EXISTING CONTOUR WHEELCHAIR RAMP CENTERLINE RADIUS POINT POINT OF CURVATURE POINT OF TANGENCY RET RETURN DRAINAGE FLOW ARROW 857.30 TOP OF CURB SPOT ELEVATION PAVEMENT ELEVATION 857.00(P) × WASHOUT CROWN SECTION SIDEWALK (HOMEOWNER'S RESPONSIBILITY) SIDEWALK (DEVELOPER'S RESPONSIBILITY)



SIDEWALK NOTE:

THE CONSTRUCTION OF SIDEWALKS ADJACENT TO ALL 900 SERIES LOTS WILL BE THE RESPONSIBILITY OF THE DEVELOPER AS SHOWN ON THE OVERALL SIGNAGE PLAN (SHEET C3.00—C3.01). REFER TO SHEET C3.00—C3.01 FOR LOCATIONS OF SIDEWALK CONSTRUCTION WHERE SIDEWALKS ARE NOT SHOWN

STREET SELECT FILL NOTE:

FILL MATERIAL SHOULD BE NATIVE ON—SITE MATERIAL, FREE OF DELETERIOUS MATERIAL WITH A MINIMUM CBR VALUE OF 2.5 AND A PI MAXIMUM OF 40. THE GRAVEL SIZE SHOULD NOT EXCEED 3 INCHES IN DIAMETER. LIME APPLICATION RATE SHOULD BE RE—EVALUATED FOR THE FILL MATERIAL. THE MATERIAL SHOULD BE PLACED AS PER APPLICABLE CITY OR COUNTY GUIDELINES.

WHEEL CHAIR NOTE:

WHEEL CHAIR RAMPS (WCR) TO BE CENTERED ON STATION NOTED BELOW. ELEVATION SHOWN ARE TOP OF CURB AND NOT GUTTER

STREET NOTES:

- 1. A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED.
- CONTRACTOR SHALL MATCH EXISTING PAVEMENT AT TIE—IN. IF EXISTING PAVEMENT ELEVATION DIFFERS SIGNIFICANTLY, CONTRACTOR SHALL NOTIFY THE ENGINEER PRIOR TO CONTINUING WORK.
- 3. SIDEWALKS SHALL BE CONSTRUCTED 3—FT FROM THE BACK OF CURB FOR ALL LOCATIONS WHERE THE SIDEWALK IS SHOWN OFFSET. REFER TO STREET DETAIL SHEET FOR SIDEWALK AND RAMP DETAILS.
- 4. NO PERMANENT STRUCTURES HIGHER THAN 3 FEET, AND LOWER THAN 8 FEET ABOVE THE PAVEMENT, INCLUDING STRUCTURES, WALLS, FENCES, AND VEGETATION, SHALL BE CONSTRUCTED OR ALLOWED WITHIN THE CLEAR VISION EASEMENT. CONTRACTOR SHALL GRADE AREAS WITHIN CLEAR VISION EASEMENTS SUCH THAT THE ELEVATION WITHIN THE CLEAR VISION EASEMENT IS NOT HIGHER THAN 3 FEET ABOVE THE ADJACENT TOP OF PAVEMENT.
- 5. DRIVEWAYS SHOWN ON THIS PLAN ARE FOR THE SOLE PURPOSE OF INDICATING A POTENTIAL CONFLICT WITH CURB RAMP, DRAINAGE INFRASTRUCTURE, OR OTHER CONFLICT. DRIVEWAY LOCATION IS SUBJECT TO CHANGE BASED ON HOME SELECTION AND FINAL LOT DESIGN.
- 6. CHANGES IN THE SIDEWALK LOCATION FOR A MAXIMUM LINEAR DISTANCE OF TWO HUNDRED (200) FEET ARE PERMITTED TO BE APPROVED BY THE FIELD INSPECTOR WITHOUT AMENDING THE STREET PLAN OR UTILITY LAYOUT PER UDC SECTION 35-506 (Q)(6).

BODEN GLEN ~ STA. 1+00.00 TO STA. BERG HILLS ~ STA. 3+13.35 TO STA. 7


JON D. ADAME


PAPE-DAWS ENGINEERS

24-11800406
DB NO. 13055-20
ATE JANUARY 2025

DESIGNER CB

CHECKED AS DRAWN CB





STREET LEGEND

PROJECT LIMITS MAINTAIN GUTTER EXISTING CONTOUR WHEELCHAIR RAMP CENTERLINE RADIUS POINT POINT OF CURVATURE POINT OF TANGENCY RET DRAINAGE FLOW ARROW TOP OF CURB SPOT ELEVATION PAVEMENT ELEVATION 857.00(P) × WASHOUT CROWN SECTION SIDEWALK (HOMEOWNER'S RESPONSIBILITY) SIDEWALK (DEVELOPER'S RESPONSIBILITY)

KEY LEGEND:

- (A) 10' ELEC., GAS, TELE, & CA. T.V. EASEMENT
- B 15' CLEARING AND GRADING BUFFER EASEMENT (DOC. NO. 20240132079 O.P.R.)
- (D) 4' SIDEWALK
- (E) 4' DEVELOPER SIDEWALK
- (F) 6' SIDEWALK
- (G) 12' PRIVATE DRAINAGE EASEMENT
- H 5'X5' ADA PASSING SPACE
- PROPOSED SIDEWALK BOX (SEE SHEET C1.10)
- K 1% ANNUAL CHANCE (100-YR) FUTURE CONDITIONS FLOODPLAIN
- (L) 10' PRIVATE DRAINAGE EASEMENT
- (0) 13' ELEC., GAS, TELE, & CA. T.V. EASEMENT
- P VARIABLE WIDTH DRAINAGE EASEMENT (BY SEPARATE INSTRUMENT)

SIDEWALK NOTE:

THE CONSTRUCTION OF SIDEWALKS ADJACENT TO ALL 900 SERIES LOT WILL BE THE RESPONSIBILITY OF THE DEVELOPER AS SHOWN ON TH OVERALL SIGNAGE PLAN (SHEET C3.00-C3.01). REFER TO SHEE C3.00-C3.01 FOR LOCATIONS OF SIDEWALK CONSTRUCTION WHERE SIDEWALKS ARE NOT SHOWN

STREET SELECT FILL NOTE:

FILL MATERIAL SHOULD BE NATIVE ON-SITE MATERIAL, FREE OF DELETERIOUS MATERIAL WITH A MINIMUM CBR VALUE OF 2.5 AND A PI MAXIMUM OF 40. THE GRAVEL SIZE SHOULD NOT EXCEED 3 INCHES IN DIAMETER. LIME APPLICATION RATE SHOULD BE RE-EVALUATED FOR THE FILL MATERIAL. THE MATERIAL SHOULD BE PLACED AS PER APPLICABLE CITY OR COUNTY GUIDELINES.

WHEEL CHAIR NOTE:

WHEEL CHAIR RAMPS (WCR) TO BE CENTERED ON STATION NOTED BELOW. ELEVATION SHOWN ARE TOP OF CURB AND NOT GUTTER


STREET NOTES:


- 1. A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED.
- 2. CONTRACTOR SHALL MATCH EXISTING PAVEMENT AT TIE-IN. IF EXISTING PAVEMENT ELEVATION DIFFERS SIGNIFICANTLY, CONTRACTOR SHALL NOTIFY THE ENGINEER PRIOR TO CONTINUING WORK.
- 3. SIDEWALKS SHALL BE CONSTRUCTED 3-FT FROM THE BACK OF CURB FOR ALL LOCATIONS WHERE THE SIDEWALK IS SHOWN OFFSET. REFER TO STREET DETAIL SHEET FOR SIDEWALK AND RAMP DETAILS.
- 4. NO PERMANENT STRUCTURES HIGHER THAN 3 FEET, AND LOWER THAN 8 FEET ABOVE THE PAVEMENT, INCLUDING STRUCTURES, WALLS, FENCES, AND VEGETATION, SHALL BE CONSTRUCTED OR ALLOWED WITHIN THI CLEAR VISION EASEMENT. CONTRACTOR SHALL GRADE AREAS WITHIN CLEAR VISION EASEMENTS SUCH THAT THE ELEVATION WITHIN TH CLEAR VISION EASEMENT IS NOT HIGHER THAN 3 FEET ABOVE THE ADJACENT TOP OF PAVEMENT.
- 5. DRIVEWAYS SHOWN ON THIS PLAN ARE FOR THE SOLE PURPOSE OF INDICATING A POTENTIAL CONFLICT WITH CURB RAMP, DRAINAGE INFRASTRUCTURE, OR OTHER CONFLICT. DRIVEWAY LOCATION IS SUBJECT TO CHANGE BASED ON HOME SELECTION AND FINAL LOT DESIGN.
- 6. CHANGES IN THE SIDEWALK LOCATION FOR A MAXIMUM LINEAR DISTANCE OF TWO HUNDRED (200) FEET ARE PERMITTED TO BE APPROVED BY THE FIELD INSPECTOR WITHOUT AMENDING THE STREET PLAN OF UTILITY LAYOUT PER UDC SECTION 35-506 (Q)(6).

JON D. ADAME

- NO 24-11800406 13055-20

DESIGNER HECKED AS DRAWN CB






STRIPING IMPROVEMENTS - LUCKEY RIVER

SCALE 1" = 20'

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.





SCALE: 1"- 20"

	:	SCALE:	1 =	20		
0'		20'		40'	60'	

	SYMBOL	ITEM NUMBER
$\langle A \rangle$	WHITE ARROW & WORD "ONLY" STANDARD PAVING MARKING-THERMOPLASTIC	
B	125 LF ~ WHITE 8" SOLID LINE — THERMOPLASTIC WITH TYPE I—C RPM	
©	175 LF ~ DOUBLE YELLOW 6" SOLID LINE— THERMOPLASTIC WITH TYPE II—A—A RPMS	
D	24" WIDE SOLID WHITE STRIPE (STOP BAR)	
	R3-8 30"X30"	531.14

OSSOM RANCH UNIT SAN ANTONIO, TEXAS BL

GENERAL NOTES

- ALL DISTANCES ARE MEASURED FROM FACE OF CURB.
 ALL PAVEMENT MARKINGS SHALL BE THERMOPLASTIC MATERIAL
- ACCORDING TO THE COSA/TXDOT STANDARDS. 3. ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL CONFORM TO APPLICABLE TXDOT STANDARD SPECIFICATIONS AND CITY OF SAN ANTONIO STANDARD
- SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION. 4. CONTRACTOR SHALL NOTIFY COSA/BEXAR COUNTY AT LEAST 48 HOURS PRIOR TO STARTING CONSTRUCTION.
- 5. CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUIRING ALL NECESSARY PERMITS BEFORE BEGINNING CONSTRUCTION.
- 6. CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER OF ANY QUESTIONS THAT MAY ARISE CONCERNING THE INTENT, ALIGNMENT, PLACEMENT, LIMITS, DIMENSIONS OR GRADES NECESSARY FOR
- CONSTRUCTION OF THIS PROJECT. 7. REFER TO PROJECT SPECIFICATIONS FOR ADDITIONAL SPECIFICATIONS AND CONTRACT INFORMATION. 8. CONTRACTOR SHALL NOTIFY BEXAR COUNTY PRIOR TO CONSTRUCTION
- IN ACCORDANCE WITH THE DRIVEWAY PERMIT. 9. REFERENCE DETAIL SHEET C3.11&C3.12 FOR STRIPING DETAILS 10. CONTRACTOR SHALL MAINTAIN POSITIVE DRAINAGE ON TURN LANE

WITH MAXIMUM 2.00% CROSS SLOPE. ROW PERMIT NOTE:

A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY RIGHTS-OF-WAY.

_{- NO.} 24-11800406 13055-20 ESIGNER HECKED AS DRAWN AD

*STREET TRANSITIONS FROM STREET CLASSIFICATIONS OF DIFFERING PAVEMENT WIDTHS SHALL BE CONSTRUCTED WITH PAVEMENT SECTION OF STREET CLASSIFICATION WITH WIDER PAVEMENT SECTION

SUBGRADE NOTES (*):

- 1. CUT AND FILL DATA ARE NOT AVAILABLE AT THIS TIME
- 2. FILL USED TO RAISE THE GRADE
 - APPROVED FILL MATERIAL FREE SHOULD HAVE A MINIMUM CBR VALUE OF 2.5 AND A MAXIMUM PLASTICITY INDEX VALUE OF 40 (ON SITE MATERIAL). LIME APPLICATION RATE SHOULD BE RE-EVALUATED AND TESTED FOR SULFATE CONTENT PRIOR TO USE OF THE FILL MATERIAL
 - •THE FILL MATERIAL SHOULD BE APPROVED BY THE GEOTECHNICAL ENGINEER, FREE OF DELETERIOUS MATERIAL, AND THE GRAVEL SIZE SHOULD NOT EXCEED 3 INCHES IN SIZE. THE MATERIAL SHOULD BE PLACED AND COMPACTED AS PER APPLICABLE CITY/COUNCIL GUIDELINES.
- BASED ON THE THICKNESS OF THE CLAYS ENCOUNTERED IN THE BORINGS, WE ANTICIPATE THE FINAL PAVEMENT SUBGRADE PLASTICITY INDEX VALUE TO BE GREATER THAN 20.
- 4. IF THE SUBGRADE PLASTICITY INDEX VALUES ARE LESS THAN OR EQUAL TO 20, AS PER CITY OF SAN ANTONIO OR BEXAR COUNTY REQUIREMENTS, SUBGRADE STABILIZATION IS NOT NEEDED.
- SUBGRADE SHOULD BE STABILIZED USING LIME OR CEMENT. LIME APPLICATION RATE ARE PRESENTED HERE. PLEASE CONTACT INTEC FOR CEMENT APPLICATION RATES:
- •STABILIZED TO A DEPTH OF 6 OR 8 INCHES USING 6 $\frac{1}{2}$ PERCENT LIME CONTENT.
- THE SUBGRADE SOILS SHOULD BE TESTED FOR SOIL SULFATE CONTENT PRIOR TO STABILIZATION. IF THE SOIL SULFATE CONTENT IS HIGHER THAN 3000 PPM, AN ALTERNATE PROCEDURE WILL BE NEEDED.
- •LIME APPLICATION RATE OF 31 LBS PER SQ YARD FOR 6-INCH DEPTH OF STABILIZATION IS
- •LIME APPLICATION RATE OF 41 LBS PER SQ YARD FOR 8-INCH DEPTH OF STABILIZATION IS RECOMMENDED.
- CEMENT MAY BE USED IN LIEU OF LIME. CEMENT APPLICATION RATE SHOULD BE DETERMINED AT THE TIME OF CONSTRUCTION.

GENERAL NOTES:


- CONTRACTOR SHALL REFERENCE THE PROJECT PAVEMENT DESIGN REPORT NO. XXXXXXX PREPARED BY INTEC
- PAVEMENT SECTION RECOMMENDATION ARE BASED ON A SUBGRADE CBR VALUE OF 2.5. THE PAVEMENT RECOMMENDATIONS ARE NOT BASED ON THE SHRINK/SWELL CHARACTERISTICS OF THE UNDERLYING SOILS. THE PAVEMENT CAN EXPERIENCE CRACKING AND DEFORMATION DUE TO SHRINKAGE AND SWELLING CHARACTERISTICS OF THE SOILS AS DESCRIBED IN THE VERTICAL MOVEMENTS SECTION OF THIS REPORT. USE OF GEOGRID HELPS REDUCE SHRINK/SWELL RELATED PAVEMENT DISTRESS.
- SIGNIFICANT PAVEMENT DISTRESS HAS BEEN OBSERVED DURING CONSTRUCTION PHASE WITH THE COMBINATION OF CONSTRUCTION TRAFFIC AND IRRIGATION WATER/RAIN WATER GETTING UNDERNEATH THE
- IF WATER IS ALLOWED TO GET UNDERNEATH THE ASPHALT/CONCRETE OR IF MOISTURE CONTENT OF THE BASE OR SUBGRADE CHANGES SIGNIFICANTLY, THEN PAVEMENT DISTRESS WILL OCCUR. MOISTURE PENETRATION UNDERNEATH THE ASPHALT PAVEMENT SURFACE SHOULD BE REDUCED. ONE OF THE FOLLOWING METHODS SHOULD BE USED:
- DEEPER CURBS: SUCH AS CURBS EXTENDING A MINIMUM OF 3 INCHES INTO SUBGRADE.
- COMPACTED CLAYS BACKFILLED AGAINST THE CURBS.
- IN ADDITION, WATER SHOULD NOT BE ALLOWED TO GET UNDERNEATH THE PAVEMENT SECTION AT THE TIME OF HOME CONSTRUCTION.
- 6. CONTRACTOR SHALL RETAIN A GEOTECHNICAL ENGINEER TO VERIFY THE SUB GRADE CONDITION PRIOR TO PLACING ANY BASE MATERIAL. GEOTECHNICAL ENGINEER SHALL DETERMINE THE SUB GRADE CONDITION AND IF LIME STABILIZATION IS REQUIRED.
- GEOTECHNICAL ENGINEER SHOULD VERIFY THE STREET SUBGRADE AT THE TIME OF CONSTRUCTION PRIOR TO PLACEMENT OF AGGREGATE BASE.
- THE FLEXIBLE BASE COURSE SHOULD BE CRUSHED LIMESTONE CONFORMING TO TXDOT STANDARD SPECIFICATIONS, ITEM 247, TYPE A, GRADES 1 OR 2.
- THE MOISTURE CONTENT OF THE FILL SHOULD BE MAINTAINED WITHIN THE RANGE OF OPTIMUM WATER CONTENT TO 3 PERCENTAGE POINTS ABOVE THE OPTIMUM WATER CONTENT UNTIL PERMANENTLY COVERED.
- 10. IN THE EVENT THAT THE CLAY FILL USED IS DIFFERENT THAN THE EXISTING SUBGRADE, THE RECOMMENDATIONS IN THE GEOTECHNICAL REPORT COULD BE INVALIDATED AND THE DESIGN ENGINEER MUST BE CONSULTED TO DETERMINE IF ADDITIONAL CBR TESTING AND THICKER PAVEMENT SECTIONS ARE
- . WHERE PAVEMENT SUBGRADE IS LOCATED WITHIN 2-FEET OF THE EXISTING GROUND SURFACE (STRATUM 1 CLAYS), MOISTURE CONDITIONED SUBGRADE WILL BE REQUIRED. GEOTECHNICAL ENGINEER SHOULD VERIFY THE STREET SUBGRADE AT THE TIME OF CONSTRUCTION PRIOR TO PLACEMENT OF AGGREGATE BASE TO DETERMINE WHERE THE MOISTURE CONDITIONED SUBGRADE IS NEEDED. REFERENCE GEOTECHNICAL


LIME NOTES:

- FOR LIME STABILIZATION CONSTRUCTION VERIFICATION THE FOLLOWING SHALL BE CONDUCTED ON THE FIELD: AFTER INITIAL MIXING THE SOIL-LIME MIXTURE SHALL MELLOW FOR A PERIOD OF TWO TO THREE (2-3) DAYS. MAINTAIN MOISTURE DURING MELLOWING.
- AFTER MELLOWING AND FINAL MIXING, THE PULVERIZATION SHALL BE CHECKED USING THE FOLLOWING CRITERIA (REMOVE NON-SLAKING AGGREGATES RETAINED ON THE 3/4 INCH SIEVE FROM THE SAMPLE): MINIMUM PASSING 1¾ SIEVE
- MINIMUM PASSING ¾ SIEVE MINIMUM PASSING NO. 4 SIEVE


ENGINEERING REPORT FOR MORE INFORMATION.


- SAMPLE SOIL-LIME MIXTURE FOR DETERMINATION OF MAXIMUM DRY DENSITY (MDD). IN THE LABORATORY, MOLD SPECIMENS TO 95% OF MDD AT OPTIMUM MOISTURE CONTENT AND VERIFY UCS TO BE AT LEAST 160 PSI IN ACCORDANCE WITH PROCEDURE OUTLINED IN THE BEXAR COUNTY FLEXIBLE PAVEMENT DESIGN CRITERIA GUIDE FOR MIXTURE DESIGN.
- 4. COMPACT AND CHECK FIELD DENSITY (MINIMUM OF 95% OF MDD REQUIRED).
- CURE FOR AN ADDITIONAL 2 TO 5 DAYS (TOTAL MELLOWING AND CURING TIME SHOULD TOTAL AT LEAST
- 6. VERIFY DEPTH OF LIME STABILIZED LAYER TO DEPTH AS NOTED ON PLAN TO WITHIN ± 1.0 INCH.






LOCAL TYPE B STREET SECTION NOT-TO-SCALE






ASPHALT/ASPHALT JUNCTURE DETAIL


NOT-TO-SCALE




CONCRETE/ASPHALT JUNCTURE DETAIL NOT-TO-SCALE




HEADER CURB DETAIL NOT-TO-SCALE








WELDING ELBOW NOT-TO-SCALE




THE CITY OF SAN ANTONIO STANDARD SPECIFICATIONS FOR PUBLIC


PIPE RAILING DETAIL NOT-TO-SCALE




CONCRETE CURB DETAIL NOT-TO-SCALE



CURB TRANSITION DETAIL (FROM HEADER CURB TO STANDARD CURB



CURB TRANSITION DETAIL (FROM PAVEMENT TO STANDARD CURB)





 \Box


JON D. ADAME 82567

PLAT NO 24-11800406 JOB NO. 13055-20 JANUARY 2025 DESIGNER CHECKED AS DRAWN CB


FOR STREET DESIGN HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.









THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.







PAPE-DAWSON

ENGINEERING FIRM #470 | TEXAS SHEVENING FIRM #10038800

BLOSSOM RANCH UNIT 1A SAN ANTONIO, TEXAS


PLAT NO. 24-11800406


JOB NO. 13055-20

DATE JANUARY 2025


DESIGNER AD

CHECKED AS DRAWN AI
CHEET C2.11







THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.



LUG CURB DETAIL NOT-TO-SCALE





S B


JON D. ADAME

82567


0


E-DAW


_{- NO.} 24-11800406 JOB NO. 13055-20 JANUARY 2025 ESIGNER HECKED AS DRAWN AD





THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGL® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.













DRIVEWAYS SHOWN ON THIS PLAN ARE FOR THE SOLE PURPOSE OF INDICATING A POTENTIAL CONFLICT WITH CURB RAMP, DRAINAGE INFRASTRUCTURE, OR OTHER CONFLICT. DRIVEWAY LOCATION IS SUBJECT TO

CHANGE BASED ON HOME SELECTION AND FINAL LOT DESIGN. TRENCH EXCAVATION SAFETY PROTECTION: CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYE

A BEXAR COUNTY ROW PERMIT MUST BE OBTAINED BEFORE WORKING II BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE

BEXAR COUNTY ROW NOTES:

CONSTRUCTED.

DRIVEWAY NOTE:


OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN TH PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OF PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN


ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AN ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

NO 24-11800406 JOB NO. 13055-20

C3.00

HECKED AS DRAWN GP







BLOCK 133 CB 4319

UNPLATTED PHASE II TRACT 111.266 ACRES OWNER: LGI HOMES-TEXAS, LLC

(DOC. NO. 20200090153 O.P.R.)





35' SANITARY SEWER

-VARIABLE WIDTH ACCESS, SANITARY SEWER,

UNPLATTED TRACT 1

276.657 ACRES

ANDIRON MULTISTATE 1 LLC (DOC. NO. 20240217198 O.P.R.)

STREET RIGHT-OF-WAY

WATER, GAS, ELECTRIC EASEMENT TO EXPIRE UPON INCORPORATION INTO FUTURE PLATTED PUBLIC


EASEMENT


- HEADER CURB &


EASEMENT

BARRICADE POSTS

-END OF ROAD MARKER OM4-3











DRIVEWAY NOTE:

A BEXAR COUNTY ROW PERMIT MUST BE OBTAINED BEFORE WORKING I BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE

CONSTRUCTED.

BEXAR COUNTY ROW NOTES:

DRIVEWAYS SHOWN ON THIS PLAN ARE FOR THE SOLE PURPOSE OF INDICATING A POTENTIAL CONFLICT WITH CURB RAMP, DRAINAGE INFRASTRUCTURE, OR OTHER CONFLICT. DRIVEWAY LOCATION IS SUBJECT TO CHANGE BASED ON HOME SELECTION AND FINAL LOT DESIGN.

TRENCH EXCAVATION SAFETY PROTECTION: CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYE

OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN TH PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OF PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AN ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

NO 24-11800406

HECKED AS DRAWN AD

C3.01


THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.


(NO SEPARATE PAY ITEM) 10' GETCTV dead en FLUSS RIVER <= EASEMENT FLUSS RIVER 10' GETCTV 7 (VARIABLE WIDTH R.O.W.) 4' SIDEWALK / 13' GETCTV **EASEMENT** VOGEL FIELDS EASEMENT 6' SIDEWALK -13' GETCTV 4' SIDEWALK EASEMENT (DEVELOPER 10' PRIVATE -RESPONSIBILITY) 10' GETCTV -DRAINAGE EASEMENT EASEMENT 4' SIDEWALK DEAD EN EASEMENT FLUSS RIVER ' SIDEWALK (DEVELOPER HIMMEL CREST RESPONSIBILITY) -12' PRIVATE DRAINAGE EASEMENT EASEMENT TYPE II BLUE RAISED PAVEMENT MARKER AT FIRE HYDRANT (NO SEPARATE PAY ITEM) __13' GETCTV EASEMENT 4' SIDEWALK (DEVELOPER -RESPONSIBILITY)


4' SIDEWALK -

TYPE II BLUE RAISED -PAVEMENT MARKER AT FIRE HYDRANT


13' GETCTV TEASEMENT







HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.





JON D. ADAME


24-11800406 13055-20 JANUARY 2025


ESIGNER HECKED AS DRAWN GF

C3.10









1. FRP sign supports for a single type sign support may be used for signs up to and including 16 square feet. Dual post installation may be used for signs up to and including 32 square feet. II nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." 3. See the Traffic Operations Division website for detailed drawings of sign

http://www.txdot.gov/publications/traffic.htm

1. Materials shall conform to the requirements of Departmental Material Specification DMS-4410 and will be furnished in a yellow or gray color as specified elsewhere in the plans. hickness of FRP sign support is 0.125" + 0.031", - 0.0". 3. FRP sign supports are pregualified by the Traffic Operations Division. requalification procedures are obtained by writing: Texas Department of Transportation

UNIVERSAL ANCHOR SYSTEM INSTALLATION PROCEDURES

foundation shall be a minimum depth of 18". When solid rock is encountered below ground level, the foundation shall extend in the solid rock a minimum depth of 18" or provide a minimum foundation depth of 30". If solid rock is encountered, the socket/stub may be reduced in length as required to a minimum length of 18°. Any material removed from the socket/stub shall be from the bottom and the clearance requirements given on SMD(GEN) must be followed. The inner surfaces of the socket/stub must remain free of concrete

2. The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A. 3. Insert base post in foundation hale to depths shown and fill hale with

concrete. Cut base post from bottom and ensure a minimum of 18" embedment if installed in solid rock. 4. Level and plumb the base post with coupler using a torpedo level and let concrete set a minimum of 4 days, unless otherwise directed by Engineer. Bottom of base post slots shall be above the concrete footing.

6. Insert sign post into base post. Lower until the post comes to rest on the 7. Use hammer to ensure the coupler is firmly seated. Top of coupler should be level with top of base post in most instances.

8. Check sign to ensure there is no twist. If loose, increase the tightening of coupler.

. Position base plate with coupler on existing concrete.


2. Drill holes into concrete and insert the $5/8^{\circ}$ diameter bolts with wedge anchors, and tighten nuts.

3. Attach sign to FRP post. Insert bottom of sign post into pipe stub.


i. Use hammer to ensure the coupler is firmly seated. Top of coupler should be level with top of base post in most instances. 6. Check sign to ensure there is no twist. If loose, increase the tightening of


Texas Department of Transportation SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS UNIVERSAL ANCHOR SYSTEM WITH FRP POST SMD (FRP) -08


24-1180040 13055-20 JANUARY 2025 ESIGNER HECKED AS DRAWN GF C3.11




HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.








THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.





PAPE-DAWSON

ENGINEERING FIRM #470 | TEXAS SIRVENING FIRM #40008800

BLOSSOM RANCH UNIT 1A SAN ANTONIO, TEXAS

PLAT NO. 24-11800406


JOB NO. 13055-20

DATE JANUARY 2025

DESIGNER AD

CHECKED AS DRAWN GP

SHEET C3.12




FIRE FLOW NOTE:


IN AN EFFORT TO MEET THE CITY OF SAN ANTONIO'S FIRE FLOW REQUIREMENTS FOR THE PROPOSED RESIDENTIAL DEVELOPMENT, THE PUBLIC WATER MAIN SYSTEM HAS BEEN DESIGNED FOR A MINIMUM FIRE FLOW DEMAND OF 1500 GPM AT 25 PSI RESIDUAL PRESSURE. THE FIRE FLOW REQUIREMENTS FOR INDIVIDUAL STRUCTURES WILL BE REVIEWED DURING THE BUILDING PERMIT PROCESS IN ACCORDANCE WITH THE PROCEDURES SET FORTH BY THE CITY OF SAN ANTONIO DIRECTOR OF DEVELOPMENT SERVICES DEPARTMENT AND THE SAN ANTONIO FIRE DEPARTMENT FIRE MARSHAL.

ROW PERMIT NOTE:


A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY RIGHTS-OF-WAY.








WATER LEGEND





PRESSURE REDUCING VALVE NOTE:

PRESSURE REDUCING VALVE TO BE INSTALLED ON CUSTOMER'S SIDE OF METER BY HOMEBUILDER.

PRESSURE NOTE:

CONTRACTOR TO VERIFY THAT NO PORTION OF THE TRACT IS BELOW GROUND ELEVATION OF 745 FEET WHERE THE STATIC PRESSURE WILL NORMALLY EXCEED 80 PSI. AT ALL SUCH LOCATIONS WHERE THE GROUND LEVEL IS BELOW 745 FEET, THE DEVELOPER OR BUILDER SHALL INSTALL AT EACH LOT, ON THE CUSTOMER'S SIDE OF THE METER, AN APPROVED TYPE PRESSURE REGULATOR IN CONFORMANCE WITH THE PLUMBING CODE OF THE CITY OF SAN ANTONIO. NO DUAL SERVICES ALLOWED FOR ANY LOT(S) IF *PRV IS/ARE REQUIRED FOR SUCH LOT(S), ONLY SINGLE SERVICE CONNECTIONS SHALL BE ALLOWED.

*NOTE: A PRESSURE REGULATOR IS ALSO KNOWN AS A PRESSURE REDUCING VALVE (PRV).

JOINT RESTRAINT NOTE:

CONTRACTOR SHALL INSTALL RETAINER GLANDS AT ALL FITTINGS AND PROVIDE JOINT RESTRAINING HARNESSES OR FIELD LOCK GASKETS AT ALL JOINTS WITHIN THE LENGTH SHOWN. CONTRACTOR SHALL INSURE THAT ALL TEES, BENDS, VALVES, ETC. HAVE A MINIMUM OF 5 FT OF PIPE WITH NO JOINTS ON EACH SIDE OF THE FITTING. JOINT RESTRAINTS AND RETAINER GLANDS SHALL BE CALCULATED BY SAWS APPROVED PROGRAMS. THERE WILL BE NO SEPARATE PAY ITEM FOR RETAINER GLANDS AND OTHER JOINT RESTRAINING HARNESSES AND GASKETS, BUT SHALL BE SUBSIDIARY TO THE UNIT COST PER LINEAL FOOT OF PIPE INSTALLED.

TRENCH EXCAVATION SAFETY PROTECTION:

CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

WATER (SAWS PRESSURE ZONE 4 (930 HGL))

DEVELOPER'S NAME: LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD

ADDRESS: 100 NE LOOP 410, SUITE 1155

CITY: SAN ANTONIO STATE: TEXAS ZIP: 78216

PHONE# (210) 889-5516 E-MAIL: RICHARD.MOTT@LENNAR.COM

SAWS BLOCK MAP# 082-546 TOTAL EDU'S 81.5 TOTAL ACREAGE 15.89

TOTAL LINEAR FOOTAGE OF PIPE:8" 1.357 LF PLAT NO. 24-11800406

NUMBER OF LOTS 80 SAWS JOB NO. XX-XXXX

PLAT NO. 24-11800406

JOB NO. 13055-20

DATE JANUARY 2025

DESIGNER AS


CHECKED AS DRAWN AD

 $\mathbf{\Omega}$

JON D. ADAME

 $_{\text{EET}}$ C4.00

IIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGL® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthormagery Program, USDA Farm Service Agency.




HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.


IN AN EFFORT TO MEET THE CITY OF SAN ANTONIO'S FIRE FLOW REQUIREMENTS FOR THE PROPOSED RESIDENTIAL DEVELOPMENT, THE PUBLIC WATER MAIN SYSTEM HAS BEEN DESIGNED FOR A MINIMUM FIRE FLOW DEMAND OF 1500 GPM AT 25 PSI RESIDUAL PRESSURE. THE FIRE FLOW REQUIREMENTS FOR INDIVIDUAL STRUCTURES WILL BE REVIEWED DURING THE BUILDING PERMIT PROCESS IN ACCORDANCE WITH THE PROCEDURES SET FORTH BY THE CITY OF SAN ANTONIO DIRECTOR OF DEVELOPMENT SERVICES DEPARTMENT AND THE SAN ANTONIO FIRE DEPARTMENT FIRE MARSHAL.

ROW PERMIT NOTE:


A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR








WATER LEGEND





(SEE SAWS SPEC ITEM 812) TYPICAL SANITARY SEWER/WATER CROSSING DETAIL NOT-TO-SCALE

PRESSURE REDUCING VALVE NOTE:

PRESSURE REDUCING VALVE TO BE INSTALLED ON CUSTOMER'S SIDE OF METER BY HOMEBUILDER.

PRESSURE NOTE:

CONTRACTOR TO VERIFY THAT NO PORTION OF THE TRACT IS BELOW GROUND ELEVATION OF 745 FEET WHERE THE STATIC PRESSURE WILL NORMALLY EXCEED 80 PSI. AT ALL SUCH LOCATIONS WHERE THE GROUND LEVEL IS BELOW 745 FEET, THE DEVELOPER OR BUILDER SHALL INSTALL AT EACH LOT, ON THE CUSTOMER'S SIDE OF THE METER, AN APPROVED TYPE PRESSURE REGULATOR IN CONFORMANCE WITH THE PLUMBING CODE OF THE CITY OF SAN ANTONIO. NO DUAL SERVICES ALLOWED FOR ANY LOT(S) IF *PRV IS/ARE REQUIRED FOR SUCH LOT(S), ONLY SINGLE SERVICE CONNECTIONS SHALL BE ALLOWED. *NOTE: A PRESSURE REGULATOR IS ALSO KNOWN AS A PRESSURE REDUCING VALVE (PRV).

JOINT RESTRAINT NOTE:

CONTRACTOR SHALL INSTALL RETAINER GLANDS AT ALL FITTINGS AN PROVIDE JOINT RESTRAINING HARNESSES OR FIELD LOCK GASKETS AT ALI JOINTS WITHIN THE LENGTH SHOWN. CONTRACTOR SHALL INSURE THAT AL TEES, BENDS, VALVES, ETC. HAVE A MINIMUM OF 5 FT OF PIPE WITH N JOINTS ON EACH SIDE OF THE FITTING. JOINT RESTRAINTS AND RETAINER GLANDS SHALL BE CALCULATED BY SAWS APPROVED PROGRAMS. THER WILL BE NO SEPARATE PAY ITEM FOR RETAINER GLANDS AND OTHER JOINT RESTRAINING HARNESSES AND GASKETS, BUT SHALL BE SUBSIDIARY TO UNIT COST PER LINEAL FOOT OF PIPE INSTALLED.

TRENCH EXCAVATION SAFETY PROTECTION:

CONTRACTOR AND / OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYI OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCI EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OI PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/O CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AN ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. WATER (SAWS PRESSURE ZONE 4 (930 HGL))

DEVELOPER'S NAME: LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD ADDRESS: 100 NE LOOP 410, SUITE 1155 CITY: SAN ANTONIO STATE: TEXAS ZIP: 78216


PHONE# (210) 889-5516 E-MAIL: RICHARD.MOTT@LENNAR.COM SAWS BLOCK MAP# 082-546 TOTAL EDU'S 81.5 TOTAL ACREAGE 15.89 2" 688 LF

TOTAL LINEAR FOOTAGE OF PIPE:8" 1.357 LF

NUMBER OF LOTS 80 SAWS JOB NO. XX-XXXX

NO 24-11800406 13055-20 JANUARY 2025 DESIGNER CHECKED AS DRAWN AI

JON D. ADAME



WATER (SAWS PRESSURE ZONE 4 (930 HGL))

DEVELOPER'S NAME: LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD. ADDRESS: 100 NE LOOP 410, SUITE 1155 CITY: SAN ANTONIO STATE: TEXAS ZIP: 78216 PHONE# (210) 889-5516 E-MAIL: RICHARD.MOTT@LENNAR.COM SAWS BLOCK MAP# 082-546 TOTAL EDU'S 81.5 TOTAL ACREAGE 15.89

2" 688 LF

TOTAL LINEAR FOOTAGE OF PIPE: 8" 1,357 LF

PLAT NO. 24-11800406

12" 1,631 LF

NUMBER OF LOTS 80 SAWS JOB NO. XX-XXXX

NO 24-11800406 13055-20 JANUARY 2025 DESIGNER CHECKED AS DRAWN AD

LNN

SOM RANCH I

B

JON D. ADAME 82567

TYPICAL UTILITY/WATER CROSSING DETAIL NOT-TO-SCALE THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGL® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.

ALL JOINTS ARE FULLY RESTRAINED IN

ACCORDANCE WITH SAWS SPECIFICATION

1-1/8 BEND-

└WATER MAIN

-MISC. UTILITY (I.E.: RCP/BOX CULVERT, GAS OR ELECTRICAL

V—WATER MAIN

TABLE DD-839-06.

-1-1/8 BEND

DUCTBANK)

FINISHED GRADE

-1-1/8 BEND

WATER MAIN→

-MISC. UTILITY (I.E.: RCP/BOX

DUCTBANK)

CULVERT, GAS OR ELECTRICAL

-WATER MAIN

FINISHED GRADE

1-1/8 BEND-

WATER MAIN-

1-1/8 BEND-

	<u>S</u>
	 3.
	4 .
	6.
	7. 8.
	9.
	11.
	13

IS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.

SAWS CONSTRUCTION NOTES

(LAST REVISED JANUARY 2022)

SAWS GENERAL SECTION

- 1. ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL BE APPROVED BY THE SAN ANTONIO WATER SYSTEM (SAWS) AND COMPLY WITH THE PLANS, SPECIFICATIONS, GENERAL CONDITIONS AND WITH THE FOLLOWING AS APPLICABLE:
 - A.CURRENT TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) 'DESIGN CRITERIA FOR DOMESTIC WASTEWATER SYSTEM", TEXAS ADMINISTRATIVE CODE (TAC) TITLE 30 PART 1 CHAPTER 217 AND "PUBLIC DRINKING WATER", TAC TITLE 30 PART 1 CHAPTER 290.
- B.CURRENT TXDOT "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS AND DRAINAGE" C.CURRENT "SAN ANTONIO WATER SYSTEM STANDARD SPECIFICATIONS FOR WATER AND SANITARY SEWER CONSTRUCTION".
- D.CURRENT CITY OF SAN ANTONIO "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION". E. CURRENT CITY OF SAN ANTONIO "UTILITY EXCAVATION CRITERIA MANUAL" (UECM).
- 2. THE CONTRACTOR SHALL NOT PROCEED WITH ANY PIPE INSTALLATION WORK UNTIL THEY OBTAIN A COPY OF THE APPROVED COUNTER PERMIT OR GENERAL CONSTRUCTION PERMIT (GCP) FROM THE CONSULTANT AND HAS BEEN NOTIFIED BY SAWS CONSTRUCTION INSPECTION DIVISION TO PROCEED WITH THE WORK AND HAS ARRANGED A MEETING WITH THE INSPECTOR AND CONSULTANT FOR THE WORK REQUIREMENTS. WORK COMPLETED BY THE CONTRACTOR WITHOUT AN APPROVED COUNTER PERMIT AND/OR A GCP WILL BE SUBJECT TO REMOVAL AND REPLACEMENT AT THE EXPENSE OF THE CONTRACTORS AND/OR THE DEVELOPER.
- 3. THE CONTRACTOR SHALL OBTAIN THE SAWS STANDARD DETAILS FROM THE SAWS WEBSITE, HTTP: //WWW.SAWS.ORG/BUSINESS_CENTER/SPECS. UNLESS OTHERWISE NOTED WITHIN THE DESIGN PLANS.
- 4. THE CONTRACTOR IS TO MAKE ARRANGEMENTS WITH THE SAWS CONSTRUCTION (210) 233-2973, ON NOTIFICATION PROCEDURES THAT WILL BE USED TO NOTIFY AFFECTED HOME RESIDENTS AND/OR PROPERTY OWNERS 48 HOURS PRIOR TO BEGINNING ANY WORK.
- 5. LOCATION AND DEPTH OF EXISTING UTILITIES AND SERVICE LATERALS SHOWN ON IHE PLANS ARE UNDERSTOOD TO BE APPROXIMATE. ACTUAL LOCATIONS AND DEPTHS MUST BE FIELD VERIFIED BY THE CONTRACTOR AT LEAST 1 WEEK PRIOR TO CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO LOCATE UTILITY SERVICE LINES AS REQUIRED FOR CONSTRUCTION AND TO PROTECT THEM DURING CONSTRUCTION AT NO COST TO SAWS.
- 6. THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF UNDERGROUND UTILITIES AND DRAINAGE STRUCTURES AT LEAST 1-2 WEEKS PRIOR TO CONSTRUCTION WHETHER SHOWN ON PLANS OR NOT. PLEASE ALLOW UP TO 7 BUSINESS DAYS FOR LOCATES REQUESTING PIPE LOCATION MARKERS ON SAWS FACILITIES. THE FOLLOWING CONTACT INFORMATION ARE SUPPLIED FOR VERIFICATION PURPOSES:
 - SAWS UTILITY LOCATES: HTTP://WWW.SAWS.ORG/SERVICE/LOCATES
- COSA DRAINAGE (210) 207-0724 OR (210) 207-6026 COSA TRAFFIC SIGNAL OPERATIONS (210) 206-8480
- COSA TRAFFIC SIGNAL DAMAGES (210) 207-3951 ■ TEXAS STATE WIDE ONE CALL LOCATOR 1-800-545-6005 OR 811
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING EXISTING FENCES, CURBS, STREETS, DRIVEWAYS, SIDEWALKS, LANDSCAPING AND STRUCTURES TO ITS ORIGINAL OR BETTER CONDITION IF DAMAGES ARE MADE AS A RESULT OF THE PROJECT'S CONSTRUCTION.
- 8. ALL WORK IN TEXAS DEPARTMENT OF TRANSPORTATION (TXDOT) AND/OR BEXAR COUNTY RIGHT-OF-WAY SHALL BE DONE IN ACCORDANCE WITH RESPECTIVE CONSTRUCTION SPECIFICATIONS AND PERMIT REQUIREMENTS.
- 9. THE CONTRACTOR SHALL COMPLY WITH CITY OF SAN ANTONIO OR OTHER GOVERNING MUNICIPALITY'S TREE ORDINANCES WHEN EXCAVATING NEAR TREES.
- 10. THE CONTRACTOR SHALL NOT PLACE ANY WASTE MATERIALS IN THE 100-YEAR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN PERMIT.
- HOLIDAY WORK: CONTRACTORS WILL NOT BE ALLOWED TO PERFORM SAWS WORK ON SAWS RECOGNIZED HOLIDAYS. REQUEST SHOULD BE SENT CONSTWORKREQ@SAWS.ORG.
- WEEKEND WORK: CONTRACTORS ARE REQUIRED TO NOTIFY THE SAWS INSPECTION CONSTRUCTION DEPARTMENT 48 HOURS IN ADVANCE TO REQUEST WEEKEND WORK REQUEST SHOULD BE SENT TO CONSTWORKREQ@SAWS.ORG.
- 11. ANY AND ALL SAWS UTILITY WORK INSTALLED WITHOUT HOLIDAY/WEEKEND APPROVAL WILL BE SUBJECT TO BE UNCOVERED FOR PROPER INSPECTION.
- 12. COMPACTION NOTE (ITEM 804): THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEETING THE COMPACTION REQUIREMENTS ON ALL TRENCH BACKFILL AND FOR PAYING FOR THE TESTS PERFORMED BY A THIRD PARTY, COMPACTION TESTS WILL BE DONE AT ONE LOCATION POINT RANDOMLY SELECTED. OR AS INDICATED BY THE SAWS INSPECTOR AND/OR THE TEST ADMINISTRATOR, PER EACH 12-INCH LOOSE LIFT PER 400 LINEAR FEET AT A MINIMUM. THIS PROJECT WILL NOT BE ACCEPTED AND FINALIZED BY SAWS WITHOUT THIS REQUIREMENT BEING MET AND VERIFIED BY PROVIDING ALL NECESSARY DOCUMENTED TEST RESULTS.
- 13. A COPY OF ALL TESTING REPORTS SHALL BE FORWARDED TO SAWS CONSTRUCTION INSPECTION DIVISION.

SAWS WATER NOTES

- PRIOR TO TIE-INS, ANY SHUTDOWNS OF EXISTING MAINS OF ANY SIZE MUST BE COORDINATED WITH THE SAWS CONSTRUCTION INSPECTION DIVISION AT LEAST ONE WEEK IN ADVANCE OF THE SHUTDOWN. THE CONTRACTOR MUST ALSO PROVIDE A SEQUENCE OF WORK AS RELATED TO THE TIE-INS; THIS IS AT NO ADDITIONAL COST TO SAWS OR THE PROJECT AND IT IS THE ACCORDINGLY.
 - FOR WATER MAINS 12" OR HIGHER: SAWS EMERGENCY OPERATIONS CENTER (210) 233-2014
- ASBESTOS CEMENT (AC) PIPE, ALSO KNOWN AS TRANSITE PIPE WHICH IS KNOWN TO CONTAIN ASBESTOS- CONTAINING MATERIAL (ACM). MAY BE LOCATED WITHIN THE PROJECT LIMITS. SPECIAL WASTE MANAGEMENT PROCEDURES AND HEALTH AND SAFETY REQUIREMENTS WILL BE APPLICABLE WHEN REMOVAL AND/OR DISTURBANCE OF THIS PIPE OCCURS. SUCH WORK IS TO BE MADE UNDER SPECIAL SPECIFICATION ITEM NO. 3000, "SPECIAL SPECIFICATION FOR HANDLING ASBESTOS CEMENT PIPE".
- VALVE REMOVAL: WHERE THE CONTRACTOR IS TO ABANDON A WATER MAIN. THE CONTROL VALVE LOCATED ON THE ABANDONING BRANCH WILL BE REMOVED AND REPLACED WITH A CAP/PLUG. (NSPI)
- SUITABLE ANCHORAGE/THRUST BLOCKING OR JOINT RESTRAINT SHALL BE PROVIDED AT ALL OF THE FOLLOWING MAIN LOCATIONS: DEAD ENDS, PLUGS, CAPS, TEES, CROSSES, VALVES, AND BENDS, IN ACCORDANCE WITH THE STANDARD DRAWINGS DD-839 SERIES AND ITEM NO. 839, IN THE SAWS STANDARD SPECIFICATIONS FOR CONSTRUCTION.
- 5. ALL VALVES SHALL READ "OPEN RIGHT".
- IS BELOW GROUND ELEVATION OF 745 FEET WHERE THE STATIC PRESSURE WILL NORMALLY EXCEED 80 PSI. AT ALL SUCH LOCATIONS WHERE THE GROUND LEVEL IS BELOW 745 FEET, THE DEVELOPER OR BUILDER SHALL INSTALL AT EACH LOT, ON THE CUSTOMER'S SIDE OF THE METER, AN APPROVED TYPE PRESSURE REGULATOR IN CONFORMANCE WITH THE PLUMBING CODE OF THE CITY OF SAN ANTONIO. NO DUAL SERVICES ALLOWED FOR ANY LOT(S) IF *PRV IS/ARE REQUIRED FOR SUCH LOT(S), ONLY SINGLE SERVICE CONNECTIONS SHALL BE ALLOWED. *NOTE: A PRESSURE REGULATOR IS ALSO KNOWN AS A PRESSURE REDUCING VALVE

6. PRVS REQUIRED: CONTRACTOR TO VERIFY THAT NO PORTION OF THE TRACT

- PIPE DISINFECTION WITH DRY HTH FOR PROJECTS LESS THAN 800 LINEAR (ITEM NO. 847.3): MAINS SHALL BE DISINFECTED WITH DRY HTH WHERE SHOWN IN THE CONTRACT DOCUMENTS OR AS DIRECTED BY THE INSPECTOR, AND SHALL NOT EXCEED A TOTAL LENGTH OF 800 FEET. THIS METHOD OF DISINFECTION WILL ALSO BE FOLLOWED FOR MAIN REPAIRS. TH CONTRACTOR SHALL UTILIZE ALL APPROPRIATE SAFETY MEASURE TO PROTECT HIS PERSONNEL DURING DISINFECTION OPERATIONS.
- 8. BACKFLOW PREVENTION DEVICES:
- ALL IRRIGATION SERVICES WITHIN RESIDENTIAL AREAS ARE REQUIRED TO HAVE BACKFLOW PREVENTION DEVICES. ALL COMMERCIAL BACKFLOW PREVENTION DEVICES MUST BE APPROVED BY SAWS PRIOR TO INSTALLATION.
- FINAL CONNECTION TO THE EXISTING WATER MAIN SHALL NOT BE MADE | 14. SAWS REQUIRES LEAD FREE (< 0.25%) FIRE HYDRANTS. UNTIL THE WATER MAIN HAS BEEN PRESSURE TESTED, CHLORINATED, AND SAWS HAS RELEASED THE MAIN FOR TIE-IN AND USE.
- 10. DIVISION VALVES: DIVISION VALVES SHOWN ON PLANS OR NOT SHOWN ON PLANS BUT FOUND IN THE FIELD SHALL ONLY BE OPERATED BY SAWS DISTRIBUTION AND COLLECTION STAFF AND ONLY WITH PRIOR WRITTEN APPROVAL OF THE SAWS DIRECTOR OF PRODUCTION AND OPERATIONS AND PROPER COORDINATION WITH ALL SAWS DEPARTMENTS. CONTRACTOR SHALL PROVIDE WRITTEN NOTIFICATION TO THE INSPECTOR A MINIMUM OF TWO WEEKS IN ADVANCE TO START THE COORDINATION PROCESS AND WILL BE INFORMED BY THE INSPECTOR WHEN THE DIVISION VALVE WILL BE OPERATED BY THE SAWS DISTRIBUTION AND COLLECTION STAFF. THE DIVISION VALVE CAN ONLY BE OPERATED BY SAWS DISTRIBUTION AND COLLECTION STAFF MEMBER NOT THE INSPECTOR OR THE CONTRACTOR. OPERATION OF A DIVISION VALVE WITHOUT THE EXPRESS PRIOR WRITTEN APPROVAL OF THE SAWS DISTRIBUTION AND COLLECTION STAFF WILL CONSTITUTE A MATERIAL BREACH OF ANY WRITTEN SAWS CONTRACT OR PERMIT IN ADDITION TO SUBJECTING THE CONTRACTOR TO LIABILITY FOR ANY AND ALL FINES. FEES. OR OTHER DAMAGES, DIRECT OR CONSEQUENTIAL, THAT MAY ARISE FROM OR BE CAUSED BY THE OPERATION OF THE VALVE WITHOUT PRIOR WRITTEN PERMISSION. PLEASE BE INFORMED THAT THE APPROVAL OF THE OPERATION OR OPENING OR CLOSING OF A DIVISION VALVE CAN TAKE SEVERAL WEEKS FOR APPROVAL. DIVISION VALVES WILL ALSO HAVE A VALVE LID LABELED DIVISION VALVE AND A LOCKING MECHANISM INSTALLED WITH A KEY. THE LOCK AND KEY MECHANISM WILL BE PAID FOR BY THE CONTRACTOR BUT WILL BE INSTALLED BY SAWS DISTRIBUTION AND COLLECTION STAFF.


PROJECT WATER NOTES

MACHINE CHLORINATION BY THE S.A.W.S.

PROVIDED FOR IN THE SPECIAL CONDITIONS.

- ALL 8", 12" AND 16" PIPE SHALL BE P.V.C. C-900 CLASS 235 DR 18.
- RESPONSIBILITY OF THE CONTRACTOR TO SEQUENCE THE WORK | 3. ALL MAINS SHALL BE HYDROSTATICALLY TESTED BY THE CONTRACTOR, AS
 - THE WATER LINES WILL BE SET FROM THE STREET HUBS BEFORE THIS CONTRACT BEGINS. STREET CUT SHEETS WILL BE SUPPLIED TO THE CONTRACTOR. THERE SHOULD BE NO ADDITIONAL STAKES REQUIRED. AND I SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO INSPECT THE SITE AND VERIFY THAT ALL STAKES REQUIRED FOR HIS WORK ARE IN PLACE AT THE TIME THE CONSTRUCTION BEGINS. IF ANY STAKES ARE MISSING THE ENGINEER SHOULD BE NOTIFIED IMMEDIATELY. AFTER CONSTRUCTION BEGINS, ALL CONSTRUCTION STAKES, MARKS, ETC., SHALL BE CAREFULLY PRESERVED BY THE CONTRACTOR, AND IN CASE OF DESTRUCTION OR REMOVAL BY THE CONTRACTOR, HIS EMPLOYEE OR ANY OTHER MEANS, SUCH STAKES, MARKS, ETC., SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
 - THE CONTRACTOR SHALL FURNISH THE ENGINEER WITH ALL THE FINAL MEASUREMENTS, TAPS AND LENGTH OF SERVICE CONNECTIONS.
 - THE LOT CORNERS WILL BE SET BY THE ENGINEER FOR INSTALLATION OF ALL WATER SERVICES. THESE LOT CORNERS SHALL BE CAREFULLY PRESERVED BY THE CONTRACTOR SO THE METER BOXES CAN BE SET IN PHASE II. ANY LOT CORNER DESTROYED OR REMOVED BY THE CONTRACTOR, HIS EMPLOYEES, OR BY ANY OTHER MEANS SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
 - STREETS WILL HAVE BEEN EXCAVATED DOWN TO SUBGRADE AND THE PARKWAY WILL BE CUT DOWN TO TOP OF CURB BY THE STREET CONTRACTOR. PRIOR TO CONSTRUCTION OF THE WATER MAINS. IT WILL BE THE UTILITY CONTRACTOR'S RESPONSIBILITY TO PROVIDE A PAD FOR HIS EQUIPMENT.
 - 8. WATER METER BOXES IF APPLICABLE SHALL BE INSTALLED NINE FEET FROM FACE OF CURB TO CENTER OF THE METER BOX.
 - 9. ALL GARBAGE OR SPOIL MATERIAL FROM THIS WORK SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR, AT HIS EXPENSE.
 -). FINAL CONNECTION TO THE EXISTING WATER MAIN SHALL NOT BE MADE UNTIL WATER MAIN HAS BEEN PRESSURE TESTED, CHLORINATED AND THE S.A.W.S. RELEASES THE MAIN FOR TIE-IN AND USE.
 - . UNIT PRICE BID FOR "STANDARD FIRE HYDRANT ASSEMBLY" SHALL INCLUDE FIRE HYDRANT, 6-INCH GATE VALVE AND 6-INCH VALVE BOX COMPLETE, ANCHOR BEND, AND ALL 6-INCH DI PIPE REQUIRED (DI PIPE REQUIRED SHALL INCLUDE ALL PIPE FROM THE TEE ON THE MAIN LINE TO THE FIRE HYDRANT).
 - 2. WHEN SEWER LINES ARE INSTALLED IN THE VICINITY OF WATER MAINS, SUCH INSTALLATION SHALL BE IN STRICT ACCORDANCE WITH THE TEXAS NATURAL RESOURCE CONSERVATION COMMISSION "RULES AND REGULATIONS FOR PUBLIC WATER SYSTEMS" (1988 OR ANY REVISIONS THERETO).
 - 13. A CLEAR SPACE SHALL BE PROVIDED AROUND ALL FIRE HYDRANTS. THIS AREA SHOULD HAVE A MINIMUM DIAMETER OF 3.0' AND BE CLEAN OF VERTICAL OBSTRUCTIONS, VALVES, AND METER BOXES.

 - I5. UNLESS OTHERWISE NOTED ALL SERVICES SHALL BE 3/4" WITH 5/8" METER.



WATER (SAWS PRESSURE ZONE 4 (930 HGL))

DEVELOPER'S NAME: LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD. ADDRESS: 100 NE LOOP 410, SUITE 1155

CITY: SAN ANTONIO STATE: TEXAS ZIP: 78216 PHONE# <u>(210) 889-5516</u> E-MAIL: <u>RICHARD.MOTT@LENNAR.COM</u>


CHECKED AS DRAWN AI


DESIGNER


24-1180040

13055-20


JANUARY 2025







SEWER LEGEND



PROPOSED WATER LINE

WHERE SEWER PIPE CROSSES
A WATER LINE, THE SEWER
SHALL BE 160 PSI AND MEET
THE REQUIREMENTS OF ASTM
D2241 WITH ONE 20' JOINT
TO COMPLY WITH 30 TAC

D2241 WITH ONE 20' JOINT

FINISHED GROUND/PAVEMENT

PROTECTION REQUIREMENTS
TO COMPLY WITH 30 TAC
217.53(d) AND 290.44(e)

PROPOSED SANITARY SEWER LINE

TYPICAL SANITARY
SEWER/WATER CROSSING DETAIL

CAUTION!!

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.

FINISHED FLOOR NOTES:

- 1. THE FINISHED FLOOR ELEVATIONS (FF) REPRESENT THE MINIMUM POSSIBLE FLOOR ELEVATION TO PROVIDE SANITARY SEWER SERVICE TO EACH LOT. ACTUAL FINISHED FLOOR ELEVATIONS FOR EACH LOT ARE TO BE DETERMINED BY THE BUILDER AND SHALL TAKE INTO CONSIDERATION AS-BUILT CONDITIONS FOR FOUND SEWER SERVICES AND ACTUAL LATERAL PLACEMENT. IT IS THE BUILDER'S SOLE RESPONSIBILITY TO DETERMINE ACTUAL FINISHED FLOOR ELEVATIONS FOR EACH LOT PRIOR TO THE START OF HOME FOUNDATION CONSTRUCTION TAKING INTO CONSIDERATION SITE DRAINAGE, STREET ACCESS AND SANITARY SEWER SERVICE ELEVATIONS.
- THE MINIMUM SANITARY SEWER LATERAL GRADES WERE BASED UPON THE MINIMUM FINISHED FLOOR ELEVATIONS FOR THE LOTS LOCATED ON THE DOWNHILL SIDES OF THE PROPOSED ROADWAYS.

ROW PERMIT NOTE:

A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY RIGHTS-OF-WAY.

TRENCH EXCAVATION SAFETY PROTECTION:

CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

SEWER UPPER MEDINA - SOUTH SEWERSHED - DOS RIOS/LEON CREEK

DEVELOPER'S NAME: LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD.

ADDRESS: 100 NE LOOP 410, SUITE 1155

CITY: SAN ANTONIO STATE: TEXAS ZIP: 78216

PHONE# (210) 889-5516 E-MAIL: RICHARD.MOTT@LENNAR.COM

SAWS BLOCK MAP# 082-546 TOTAL EDU'S 80 TOTAL ACREAGE 15.89

15" 40 LF

TOTAL LINEAR FOOTAGE OF PIPE: 8" 2,873 LF PLAT NO. 24-11800406

NUMBER OF LOTS 80 SAWS JOB NO. 24-1630

PLAT NO. 24-11800406

JOB NO. 13055-20

DATE JANUARY 2025


DESIGNER AD

CHECKED AS DRAWN AD


C5.00

HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.


te: Jan 24, 2025, 10:43pm User ID: adavila e: P:\130\55\20\Design\Civil\SI—1305520.dwg





HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.



JON D. ADAME







TYPICAL SANITARY SEWER/WATER CROSSING DETAIL NOT-TO-SCALE

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO TH ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO TH START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL E THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON

- 1. THE FINISHED FLOOR ELEVATIONS (FF) REPRESENT THE MINIMUM POSSIBLE FLOOR ELEVATION TO PROVIDE SANITARY SEWER SERVICE TO EACH LOT. ACTUAL FINISHED FLOOR ELEVATIONS FOR EACH LOT ARE T BE DETERMINED BY THE BUILDER AND SHALL TAKE INTO CONSIDERATION AS-BUILT CONDITIONS FOR FOUND SEWER SERVICES AND ACTUAL LATERAL PLACEMENT. IT IS THE BUILDER'S SOLE RESPONSIBILITY TO DETERMINE ACTUAL FINISHED FLOOR ELEVATIONS FOR EACH LOT PRIOR TO THE START OF HOME FOUNDATION CONSTRUCTION TAKING INTO CONSIDERATION SITE DRAINAGE, STREET ACCESS AND SANITARY SEWER
- 2. THE MINIMUM SANITARY SEWER LATERAL GRADES WERE BASED UPON THE MINIMUM FINISHED FLOOR ELEVATIONS FOR THE LOTS LOCATED ON THE DOWNHILL SIDES OF THE PROPOSED ROADWAYS.

A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR

TRENCH EXCAVATION SAFETY PROTECTION:

CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYER OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND


SEWER UPPER MEDINA - SOUTH SEWERSHED - DOS RIOS/LEON CREEK

DEVELOPER'S NAME: LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD. ADDRESS: 100 NE LOOP 410, SUITE 1155 CITY: SAN ANTONIO STATE: TEXAS ZIP: 78216 PHONE# (210) 889-5516 E-MAIL: RICHARD.MOTT@LENNAR.COM SAWS BLOCK MAP# 082-546 TOTAL EDU'S 80 TOTAL ACREAGE 15.89 TOTAL LINEAR FOOTAGE OF PIPE: 15" 40 LF PLAT NO. 24-11800406 _____ SAWS JOB NO. <u>24-1630</u>

NO 24-11800406 OB NO. 13055-20


DESIGNER CHECKED AS DRAWN AD


JANUARY 2025




BEXAR COUNTY -SAN ANTONIO ETJ BEXAR COUNTY -SAN ANTONIO ETJ

JON D. ADAME





FINISHED GROUND/PAVEMENT (TOP OF GRADE)



SHALL BE 160 PSI AND MEET THE REQUIREMENTS OF ASTM D2241 WITH ONE 20' JOINT CENTERED AT THE WATER CROSSING PROPOSED SANITARY SEWER LINE

TYPICAL SANITARY SEWER/WATER CROSSING DETAIL

NOT-TO-SCALE

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO TH START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL E THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL B AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON

FINISHED FLOOR NOTES:

1. THE FINISHED FLOOR ELEVATIONS (FF) REPRESENT THE MINIMUM POSSIBLE FLOOR ELEVATION TO PROVIDE SANITARY SEWER SERVICE TO EACH LOT. ACTUAL FINISHED FLOOR ELEVATIONS FOR EACH LOT ARE T BE DETERMINED BY THE BUILDER AND SHALL TAKE INTO CONSIDERATION AS-BUILT CONDITIONS FOR FOUND SEWER SERVICES AND ACTUAL LATERAL PLACEMENT. IT IS THE BUILDER'S SOLE RESPONSIBILITY TO DETERMINE ACTUAL FINISHED FLOOR ELEVATIONS FOR EACH LOT PRIOR TO THE START OF HOME FOUNDATION CONSTRUCTION TAKING INTO CONSIDERATION SITE DRAINAGE, STREET ACCESS AND SANITARY SEWER SERVICE ELEVATIONS.

2. THE MINIMUM SANITARY SEWER LATERAL GRADES WERE BASED UPON THE MINIMUM FINISHED FLOOR ELEVATIONS FOR THE LOTS LOCATED ON THE DOWNHILL SIDES OF THE PROPOSED ROADWAYS.

TRENCH EXCAVATION SAFETY PROTECTION:

OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.


SEWER UPPER MEDINA - SOUTH SEWERSHED - DOS RIOS/LEON CREEK

DEVELOPER'S NAME: LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD. ADDRESS: 100 NE LOOP 410, SUITE 1155 CITY: SAN ANTONIO STATE: TEXAS ZIP: 78216 PHONE# (210) 889-5516 E-MAIL: RICHARD.MOTT@LENNAR.COM SAWS BLOCK MAP# 082-546 TOTAL EDU'S 80 TOTAL ACREAGE 15.89 15", 40 LF TOTAL LINEAR FOOTAGE OF PIPE: 8" 2.873 LF PLAT NO. 24-11800406 _____ SAWS JOB NO. 24-1630


24-11800406 13055-20


JANUARY 2025 DESIGNER CHECKED AS DRAWN AD

C5.02



THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. IMagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.





1+00.00 PROFIL

; ∞

~ ☐

LINE A EWER I

SANITARY SEWER SANITARY S

FINISHED GROUND/PAVEMENT (TOP OF GRADE) PROPOSED WATER LINE -WHERE SEWER PIPE CROSSES A WATER LINE, THE SEWER SEPARATION DISTANCE AND SHALL BE 160 PSI AND MEET PROTECTION REQUIREMENTS THE REQUIREMENTS OF ASTM TO COMPLY WITH 30 TAC D2241 WITH ONE 20' JOINT 217.53(d) AND 290.44(e) CENTERED AT THE WATER CROSSING PROPOSED SANITARY SEWER LINE TYPICAL SANITARY SEWER/WATER CROSSING DETAIL NOT-TO-SCALE

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVAT UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES.
ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO T START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL B AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN THESE PLANS OR NOT.


TRENCH EXCAVATION SAFETY PROTECTION:


CONTRACTOR AND / OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTAN IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENC EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND / PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAM AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARD FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFET CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AN ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. SEWER UPPER MEDINA - SOUTH SEWERSHED - DOS RIOS/LEON CREEK


DEVELOPER'S NAME: LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD. ADDRESS: 100 NE LOOP 410. SUITE 1155 PHONE# <u>(210) 889-5516</u> E-MAIL: <u>RICHARD.MOTT**©**LENNAR.COM</u> __ SAWS JOB NO. <u>24-1630</u>

NO 24-1180040 13055-20 JANUARY 2025 ESIGNER CHECKED AS DRAWN AL

C5.03







 \sim

AN &

ST. PL/

₹ ⊈

E B

FINISHED GROUND/PAVEMENT (TOP OF GRADE) PROPOSED WATER LINE — WHERE SEWER PIPE CROSSES A WATER LINE, THE SEWER SHALL BE 160 PSI AND MEET SEPARATION DISTANCE AND PROTECTION REQUIREMENTS THE REQUIREMENTS OF ASTM TO COMPLY WITH 30 TAC D2241 WITH ONE 20' JOINT 217.53(d) AND 290.44(e) CENTERED AT THE WATER CROSSING PROPOSED SANITARY SEWER LINE TYPICAL SANITARY SEWER/WATER CROSSING DETAIL

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVAT UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO T START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL E AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN THESE PLANS OR NOT.

NOT-TO-SCALE


TRENCH EXCAVATION SAFETY PROTECTION:


CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTAN IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENC EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OF PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAM AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARD FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFET CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AN ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. SEWER UPPER MEDINA - SOUTH SEWERSHED - DOS RIOS/LEON CREEK

DEVELOPER'S NAME: LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD ADDRESS: 100 NE LOOP 410. SUITE 1155 PHONE# <u>(210) 889-5516</u> E-MAIL: <u>RICHARD.MOTT**©**LENNAR.COM</u> _ SAWS JOB NO. <u>24-1630</u>


24-1180040 13055-20 JANUARY 2025 ESIGNER CHECKED AS DRAWN AL


C5.04





HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.





4 12+00.00 8 PROFILE

~ STA. PLAN

ARY SEWER LINE SANITARY SEWE

13055-20

C5.05

FINISHED GROUND/PAVEMENT (TOP OF GRADE) PROPOSED WATER LINE — WHERE SEWER PIPE CROSSES A WATER LINE, THE SEWER SHALL BE 160 PSI AND MEET SEPARATION DISTANCE AND PROTECTION REQUIREMENTS THE REQUIREMENTS OF ASTM TO COMPLY WITH 30 TAC D2241 WITH ONE 20' JOINT 217.53(d) AND 290.44(e) CENTERED AT THE WATER CROSSING PROPOSED SANITARY SEWER LINE

TYPICAL SANITARY SEWER/WATER CROSSING DETAIL NOT-TO-SCALE

CAUTION!!

PROPOSED SEWER LATERAL


CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO TH START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN (THESE PLANS OR NOT.


TRENCH EXCAVATION SAFETY PROTECTION:


CONTRACTOR AND / OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENC EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND / PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AN ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. SEWER UPPER MEDINA - SOUTH SEWERSHED - DOS RIOS/LEON CREEK


DEVELOPER'S NAME: LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD. ADDRESS: 100 NE LOOP 410, SUITE 1155 CITY: SAN ANTONIO STATE: TEXAS ZIP: 78216 PHONE# <u>(210) 889-5516</u> E-MAIL: <u>RICHARD.MOTT@LENNAR.COM</u> SAWS BLOCK MAP# 082-546 TOTAL EDU'S 80 TOTAL ACREAGE 15.89 ___ SAWS JOB NO. <u>24-1630</u>

NO. 24-11800406 JANUARY 2025 DESIGNER CHECKED AS DRAWN AD









00

NO 24-11800406

JANUARY 2025

C5.06

CHECKED_AS_DRAWN AD

DESIGNER

13055-20

1+00.00 1+00.00 PROFIL

FINISHED GROUND/PAVEMENT (TOP OF GRADE) PROPOSED WATER LINE — WHERE SEWER PIPE CROSSES A WATER LINE, THE SEWER SHALL BE 160 PSI AND MEET SEPARATION DISTANCE AND PROTECTION REQUIREMENTS THE REQUIREMENTS OF ASTM TO COMPLY WITH 30 TAC -D2241 WITH ONE 20' JOINT 217.53(d) AND 290.44(e) CENTERED AT THE WATER CROSSING PROPOSED SANITARY SEWER LINE

> TYPICAL SANITARY SEWER/WATER CROSSING DETAIL NOT-TO-SCALE


CAUTION!

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES.
ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL B AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN THESE PLANS OR NOT.


TRENCH EXCAVATION SAFETY PROTECTION:


CONTRACTOR AND / OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN T PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENC EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND / PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAM AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARD FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFET CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AN ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. SEWER UPPER MEDINA - SOUTH SEWERSHED - DOS RIOS/LEON CREEK

DEVELOPER'S NAME: LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD. ADDRESS: 100 NE LOOP 410, SUITE 1155 PHONE# <u>(210) 889-5516</u> E-MAIL: <u>RICHARD.MOTT@LENNAR.COM</u>



HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.





THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.

NO 24-11800406 13055-20 JANUARY 2025

DESIGNER CHECKED AS DRAWN AD C5.10

	<u>s</u> ,
	SAWS GENE
	1. ALL MATERIALS CONTRACT SHALL COMPLY WITH TO FOLLOWING AS A
	A. CURRENT TE CRITERIA FO CODE (TAC) WATER", TAC B. CURRENT THIGHWAYS, S C. CURRENT S WATER AND D. CURRENT CI WORKS CONS E. CURRENT CI (UECM).
	2. THE CONTRACTOR THEY OBTAIN OF CONSTRUCTION PERMITS CONSTRUCTION PERMITS COUNTER PERMITS COU
	 THE CONTRACTOR WEBSITE, HTTP://NOTED WITHIN THE THE CONTRACTOR INSPECTION DIVISION (210) 233-2973 AFFECTED HOME BEGINNING ANY
	5. LOCATION AND I THE PLANS ARI DEPTHS MUST BE CONSTRUCTION. UTILITY SERVICE DURING CONSTRU
	6. THE CONTRACTOR AND DRAINAGE WHETHER SHOWN LOCATES REQUE FOLLOWING CONT SAWS UTILIT COSA DRAIN COSA TRAFF COSA TRAFF
	TEXAS STAT THE CONTRACTO CURBS, STREETS ORIGINAL OR BE PROJECT'S CONS
	8. ALL WORK IN TO COUNTY RIGHT—CONSTRUCTION S
	9. THE CONTRACTO
	10. THE CONTRACTO FLOOD PLAIN WIT11. HOLIDAY WORK:
	11. HOLIDAY WORK: SAWS RECOGNIZE CONSTWORKREQ@ WEEKEND WORK: CONSTRUCTION E REQUEST SHOULE
	ANY AND ALL SA APPROVAL WILL
	12. COMPACTION NO MEETING THE C PAYING FOR THE BE DONE AT ONI SAWS INSPECTOR LIFT PER 400 LII AND FINALIZED E PROVIDING ALL N
	AND FINALIZED E PROVIDING ALL N 13. A COPY OF ALL INSPECTION DIVIS

IS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.

SAWS CONSTRUCTION NOTES (LAST REVISED JANUARY 2022)

NERAL SECTION

- ALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS HALL BE APPROVED BY THE SAN ANTONIO WATER SYSTEM (SAWS) AND H THE PLANS, SPECIFICATIONS, GENERAL CONDITIONS AND WITH THE AS APPLICABLE:
- TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) DESIGN FOR DOMESTIC WASTEWATER SYSTEM", TEXAS ADMINISTRATIVE (TAC) TITLE 30 PART 1 CHAPTER 217 AND "PUBLIC DRINKING" TAC TITLE 30 PART 1 CHAPTER 290.
- TXDOT "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF YS. STREETS AND DRAINAGE". "SAN ANTONIO WATER SYSTEM STANDARD SPECIFICATIONS FOR AND SANITARY SEWER CONSTRUCTION".
- CITY OF SAN ANTONIO "STANDARD SPECIFICATIONS FOR PUBLIC CONSTRUCTION".
- T CITY OF SAN ANTONIO "UTILITY EXCAVATION CRITERIA MANUAL"
- ACTOR SHALL NOT PROCEED WITH ANY PIPE INSTALLATION WORK UNTIL IN A COPY OF THE APPROVED COUNTER PERMIT OR GENERAL ON PERMIT (GCP) FROM THE CONSULTANT AND HAS BEEN NOTIFIED BY TRUCTION INSPECTION DIVISION TO PROCEED WITH THE WORK AND HAS MEETING WITH THE INSPECTOR AND CONSULTANT FOR THE WORK TS. WORK COMPLETED BY THE CONTRACTOR WITHOUT AN APPROVED PERMIT AND/OR A GCP WILL BE SUBJECT TO REMOVAL AND IT AT THE EXPENSE OF THE CONTRACTORS AND/OR THE DEVELOPER.
- ACTOR SHALL OBTAIN THE SAWS STANDARD DETAILS FROM THE SAWS TTP://WWW.SAWS.ORG/BUSINESS_CENTER/SPECS. UNLESS OTHERWISE
- ACTOR IS TO MAKE ARRANGEMENTS WITH THE SAWS CONSTRUCTION 2973, ON NOTIFICATION PROCEDURES THAT WILL BE USED TO NOTIFY HOME RESIDENTS AND/OR PROPERTY OWNERS 48 HOURS PRIOR TO
- ND DEPTH OF EXISTING UTILITIES AND SERVICE LATERALS SHOWN ON ARE UNDERSTOOD TO BE APPROXIMATE. ACTUAL LOCATIONS AND ST BE FIELD VERIFIED BY THE CONTRACTOR AT LEAST 1 WEEK PRIOR TO ION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO LOCATE RVICE LINES AS REQUIRED FOR CONSTRUCTION AND TO PROTECT THEM STRUCTION AT NO COST TO SAWS.
- ACTOR SHALL VERIFY THE EXACT LOCATION OF UNDERGROUND UTILITIES AGE STRUCTURES AT LEAST 1-2 WEEKS PRIOR TO CONSTRUCTION IOWN ON PLANS OR NOT. PLEASE ALLOW UP TO 7 BUSINESS DAYS FOR REQUESTING PIPE LOCATION MARKERS ON SAWS FACILITIES. TH CONTACT INFORMATION ARE SUPPLIED FOR VERIFICATION PURPOSES:
 - JTILITY LOCATES: HTTP://WWW.SAWS.ORG/SERVICE/LOCATES PRAINAGE (210) 207-0724 OR (210) 207-6026
 - RAFFIC SIGNAL OPERATIONS (210) 206-8480 RAFFIC SIGNAL DAMAGES (210) 207-3951
 - STATE WIDE ONE CALL LOCATOR 1-800-545-6005 OR 811
- ACTOR SHALL BE RESPONSIBLE FOR RESTORING EXISTING FENCES, EETS, DRIVEWAYS, SIDEWALKS, LANDSCAPING AND STRUCTURES TO ITS BETTER CONDITION IF DAMAGES ARE MADE AS A RESULT OF THE CONSTRUCTION.
- IN TEXAS DEPARTMENT OF TRANSPORTATION (TXDOT) AND/OR BEXAR SHT-OF-WAY SHALL BE DONE IN ACCORDANCE WITH RESPECTIVE ON SPECIFICATIONS AND PERMIT REQUIREMENTS.
- ACTOR SHALL COMPLY WITH CITY OF SAN ANTONIO OR OTHER MUNICIPALITY'S TREE ORDINANCES WHEN EXCAVATING NEAR TREES.
- ACTOR SHALL NOT PLACE ANY WASTE MATERIALS IN THE 100-YEAR WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN PERMIT.
- RK: CONTRACTORS WILL NOT BE ALLOWED TO PERFORM SAWS WORK ON PROJECT SEWER NOTES GNIZED HOLIDAYS. REQUEST SHOULD BE SENT TO REQ@SAWS.ORG.

ORK: CONTRACTORS ARE REQUIRED TO NOTIFY THE SAWS INSPECTION IN DEPARTMENT 48 HOURS IN ADVANCE TO REQUEST WEEKEND WORK. IOULD BE SENT TO CONSTWORKREQ@SAWS.ORG.

SAWS UTILITY WORK INSTALLED WITHOUT HOLIDAY/WEEKEND WILL BE SUBJECT TO BE UNCOVERED FOR PROPER INSPECTION.

- NOTE (ITEM 804): THE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPÀCTION RÉQUIREMENTS ON ALL TRENCH BACKFILL AND FOR THE TESTS PERFORMED BY A THIRD PARTY. COMPACTION TESTS WILL ONE LOCATION POINT RANDOMLY SELECTED, OR AS INDICATED BY THE CTOR AND/OR THE TEST ADMINISTRATOR, PER EACH 12-INCH LOOSE DO LINEAR FEET AT A MINIMUM. THIS PROJECT WILL NOT BE ACCEPTED ZED BY SAWS WITHOUT THIS REQUIREMENT BEING MET AND VERIFIED BY ALL NECESSARY DOCUMENTED TEST RESULTS.
- ALL TESTING REPORTS SHALL BE FORWARDED TO SAWS CONSTRUCTION

SAWS SEWER NOTES

- THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT NO SANITARY SEWER OVERFLOW (SSO) OCCURS AS A RESULT OF THEIR WORK. ALL CONTRACTOR PERSONNEL RESPONSIBLE FOR SSO PREVENTION AND CONTROL SHALL BE TRAINED ON PROPER RESPONSE. SHOULD AN SSO OCCUR, THE CONTRACTOR SHALL:
 - A. IDENTIFY THE SOURCE OF THE SSO AND NOTIFY SAWS EMERGENCY OPERATIONS CENTER (EOC) IMMEDIATELY AT (210) 233-2014. PROVIDE THE ADDRESS OF THE SPILL AND AN ESTIMATED VOLUME OR FLOW.
 - B.ATTEMPT TO ELIMINATE THE SOURCE OF THE SSO. C.CONTAIN SEWAGE FROM THE SSO TO THE EXTENT OF PREVENTING A
 - POSSIBLE CONTAMINATION OF WATERWAYS. D.CLEAN UP SPILL SITE (RETURN CONTAINED SEWAGE TO THE
 - COLLECTION SYSTEM IF POSSIBLE) AND PROPERLY DISPOSE OF CONTAMINATED SOIL/MATERIALS.
- E.CLEAN THE AFFECTED SEWER MAINS AND REMOVE ANY DEBRIS. F.MEET ALL POST-SSO REQUIREMENTS AS PER THE EPA CONSENT DECREE, INCLUDING LINE CLEANING AND TELEVISING THE AFFECTED SEWER MAINS (AT SAWS DIRECTION) WITHIN 24 HOURS.

SHOULD THE CONTRACTOR FAIL TO ADDRESS AN SSO IMMEDIATELY AND TO SAWS SATISFACTION, THEY WILL BE RESPONSIBLE FOR ALL COSTS INCURRED BY SAWS, INCLUDING ANY FINES FROM EPA, TCEQ AND/OR ANY OTHER FEDERAL, STATE OR LOCAL AGENCIES.

NO SEPARATE MEASUREMENT OR PAYMENT SHALL BE MADE FOR THIS WORK. ALL WORK SHALL BE DONE ACCORDING TO GUIDELINES SET BY THE TCEQ

2. IF BYPASS PUMPING IS REQUIRED, THE CONTRACTOR SHALL PERFORM SUCH WORK IN ACCORDANCE WITH SAWS STANDARD SPECIFICATION FOR WATER AND SANITARY SEWER CONSTRUCTION, ITEM NO. 864, "BYPASS PUMPING".

PRIOR TO TIE-INS, ANY SHUTDOWNS OF EXISTING FORCE MAINS OF ANY SIZE MUST BE COORDINATED WITH THE SAWS CONSTRUCTION INSPECTION DIVISION AT (210) 233-2973 AT LEAST ONE WEEK IN ADVANCE OF THE SHUTDOWN. THE CONTRACTOR MUST ALSO PROVIDE A SEQUENCE OF WORK AS RELATED TO THE TIE-INS: THIS IS AT NO ADDITIONAL COST TO SAWS OR THE PROJECT AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SEQUENCE THE WORK ACCORDINGLY.

SEWER PIPE WHERE WATER LINE CROSSES SHALL BE 160 PSI AND MEET THE REQUIREMENTS OF ASTM D2241, TAC 217.53 AND TCEQ 290.44(E)(4)(B). CONTRACTOR SHALL CENTER A 20' JOINT OF 160 PSI PRESSURÉ RATED PVC AT THE PROPOSED WATER CROSSING.

- ELEVATIONS POSTED FOR TOP OF MANHOLES ARE FOR REFERENCE ONLY: IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO MAKE ALLOWANCES AND ADJUSTMENTS FOR TOP OF MANHOLES TO MATCH THE FINISHED GRADE OF THE PROJECT'S IMPROVEMENTS. (NSPI)
- 6. SPILLS, OVERFLOWS, OR DISCHARGES OF WASTEWATER: ALL SPILLS, OVERFLOWS, OR DISCHARGES OF WASTEWATER, RECYCLED WATER, PETROLEUM PRODUCTS, OR CHEMICALS MUST BE REPORTED IMMEDIATELY TO THE SAWS INSPECTOR ASSIGNED TO THE COUNTER PERMIT OR GENERAL CONSTRUCTION PERMIT (GCP). THIS REQUIREMENT APPLIES TO EVERY SPILL, OVERFLOW, OR DISCHARGE RÉGARDLESS OF SIZE.
- MANHOLE AND ALL PIPE TESTING (INCLUDING THE TV INSPECTION) MUST BE PERFORMED AND PASSED PRIOR TO FINAL FIELD ACCEPTANCE BY SAWS CONSTRUCTION INSPECTION DIVISION, AS PER THE SAWS SPECIFICATIONS FOR WATER AND SANITARY SEWER CONSTRUCTION.
- . ALL PVC PIPE OVER 14 FEET OF COVER SHALL BE EXTRA STRENGTH WITH MINIMUM PIPE STIFFNESS OF 115 PSI.

VICINITY OF WATER MAINS.

- ALL RESIDENTIAL SEWER SERVICE LATERALS ARE 6" DIA. AND SHALL BE EXTENDED TO 10' PAST THE PROPERTY LINE AND CAPPED AND SEALED. CONTRACTOR SHALL INSTALL A 2" X 4" STAKE, FOUR (4) FEET LONG, TWO 2) FEET DEEP INTO THE GROUND AT THE END OF EACH SERVICE. NO SEPARATE PAY ITEM.
- CONTRACTOR TO INSTALL CLEANOUTS AT THE END OF ALL SEWER LATERALS, PER LATERAL DETAIL SHEET C5.10.
- NO VERTICAL STACKS ALLOWED FOR ANY LOTS UNLESS OTHERWISE
- SPECIFIED BY THE ENGINEER. ALL 6" SEWER LATERALS WILL BE SET AT 2% GRADE FROM THE MAIN TO
- THE PROPERTY LINE. WHEN HORIZONTAL DISTANCE BETWEEN SEWER PIPES AND WATER MAIN IS LESS THAN 9 FOOT OF SEPARATION, SEWER MAIN SHALL BE INSTALLED WITH 160 PSI (MIN) PRESSURE PIPE AND FITTINGS IN ACCORDANCE WITH SAWS CONSTRUCTION CRITERIA FOR CONSTRUCTION OF SEWER MAINS IN THE
- . CONTRACTOR SHALL ENSURE THAT MANHOLES OUTSIDE OF PAVED AREAS ARE SET WITH TOP ELEVATIONS 6" ABOVE FINISHED GRADE WITH CONCRETE RING ENCASEMENT.
- 7. ALL SEWER PIPES SHALL BE 8" PVC (SDR 26), UNLESS OTHERWISE NOTED.
- 8. CONTRACTOR IS TO VERIFY EXISTING INVERT OF EXISTING SANITARY SEWER MAINS AND ALERT ENGINEER IMMEDIATELY OF ANY DIFFERENCE FROM INVERT SHOWN ON PLANS.
- 9. CONTRACTOR SHALL PROTECT ALL EXISTING FENCES. ANY FENCE DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT THEIR
- 10. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
- I. CONCRETE RING ENCASEMENT TO BE INSTALLED ON ALL MANHOLES AND, WITHIN LIMITS OF PAVEMENT, BE INSTALLED TO THE TOP OF THE BASE LAYER WITH A MINIMUM OF 2" OF ASPHALT ON TOP OF THE RING ENCASEMENT.
- 12. MANHOLE OPENING INCREASED TO 30" AS PER TAC CHAPTER 217.55.
- 13. ALL SEWER PIPE LATERALS SHALL BE SDR 26 (CLASS 160) PVC PIPE.
- 14. IF THE GIVEN TOP OF MANHOLE ELEVATION DOES NOT AGREE ON ACTUAL GROUND SURFACE OR FINISH PAVEMENT, THE CONTRACTOR SHALL ADJUST ELEVATIONS SUCH THAT THE TOP OF MANHOLE SHALL BE 0.5' ABOVE EXISTING GROUND, OR FLUSH TO FINISH ASPHALT PAVEMENT.
- 15. ALL MANHOLES CONSTRUCTED OVER THE EDWARDS AQUIFER RECHARGE ZONE SHOULD BE WATERTIGHT.

SEWER UPPER MEDINA - SOUTH SEWERSHED - DOS RIOS/LEON CREEK

NUMBER OF LOTS 80 SAWS JOB NO. 24-1630

ADDRESS: 100 NE LOOP 410, SUITE 1155 CITY: SAN ANTONIO STATE: TEXAS ZIP: 78216 PHONE# (210) 889-5516 E-MAIL: RICHARD.MOTT@LENNAR.COM SAWS BLOCK MAP# 082-546 TOTAL EDU'S 80 TOTAL ACREAGE 15.89 15", 40 LF TOTAL LINEAR FOOTAGE OF PIPE: 8" 2.873 LF PLAT NO. 24-11800406

DEVELOPER'S NAME: LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD.

DESIGNER CHECKED AS DRAWN AD

OB NO. 13055-20


NO 24-11800406

JANUARY 2025


C5.11


JON D. ADAME

82567



HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.





UTILITY LEGEND

PROJECT LIMITS

EXISTING WATER

EXISTING SEWER

PROPOSED SEWER

PROPOSED WATER

PROPOSED WATER

PROPOSED WYE & LATERAL

SINGLE WATER SERVICE

DUAL WATER SERVICE

STREET LIGHTS

PAPE-DAW

BEXAR COUNTY ROW NOTES:

A BEXAR COUNTY ROW PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED.

CONDUIT NOTES:

- CONTRACTOR SHALL INSTALL PERMANENT MARKERS IN PROPOSED CURB WHERE CONDUITS CROSS THE ROADWAY (BOTH SIDES).
- CONDUITS SHALL BE PVC WITH MINIMUM BURY OF 36 INCHES BELOW PROPOSED FINISHED GRADE. SCHEDULE 80 TO BE USED FOR CPS CONDUITS, ALL OTHER CONDUITS ARE SCHEDULE 40.
- 3. ALL CONDUITS SHALL BE EXTENDED BEHIND CURBS OR PROPOSED SIDEWALKS A MINIMUM OF 3 FEET AND CAPPED FOR FUTURE USE.
- 4. ALL CONDUIT SLEEVES TO BE USED FOR ELECTRIC, GAS, OR TELECOMMUNICATION UTILITY CROSSINGS SHALL BE INSTALLED TO MEET OR EXCEED DESIGN REQUIREMENTS FOR THE UTILITY AGENCY WHICH THEY ARE SERVING, INCLUDING BUT NOT LIMITED TO THE DEPTH, TRENCH PLACEMENT, AND PROXIMITY TO OTHER UTILITIES. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR VERIFYING AND INSTALLING THE CONDUIT SLEEVES TO MEET THESE SPECIFICATIONS INCLUDING COORDINATING WITH THE UTILITY AGENCY FOR ANY REQUIRED INSPECTIONS

TRENCH EXCAVATION SAFETY PROTECTION:

CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

CAUTION

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.

PLAT NO. 24-11800406


JOB NO. 13055-20


DATE JANUARY 2025


DESIGNER AD

CHECKED AS DRAWN AD


_т <u>C6.00</u>







UTILITY LEGEND



BEXAR COUNTY ROW NOTES:

A BEXAR COUNTY ROW PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED.

CONDUIT NOTES:

- 1. CONTRACTOR SHALL INSTALL PERMANENT MARKERS IN PROPOSED CURB WHERE CONDUITS CROSS THE ROADWAY (BOTH SIDES).
- 2. CONDUITS SHALL BE PVC WITH MINIMUM BURY OF 36 INCHES BELOW PROPOSED FINISHED GRADE. SCHEDULE 80 TO BE USED FOR CPS CONDUITS, ALL OTHER CONDUITS ARE SCHEDULE 40.
- 3. ALL CONDUITS SHALL BE EXTENDED BEHIND CURBS OR PROPOSED SIDEWALKS A MINIMUM OF 3 FEET AND CAPPED FOR FUTURE USE.
- 4. ALL CONDUIT SLEEVES TO BE USED FOR ELECTRIC, GAS, OF TELECOMMUNICATION UTILITY CROSSINGS SHALL BE INSTALLED TO MEET OR EXCEED DESIGN REQUIREMENTS FOR THE UTILITY AGENCY WHICH THEY ARE SERVING, INCLUDING BUT NOT LIMITED TO THE DEPTH, TRENCH PLACEMENT, AND PROXIMITY TO OTHER UTILITIES. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR VERIFYING AND INSTALLING THE CONDUIT SLEEVES TO MEET THESE SPECIFICATIONS INCLUDING COORDINATING WITH THE UTILITY AGENCY FOR ANY REQUIRED

TRENCH EXCAVATION SAFETY PROTECTION:


CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO TH ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO TH START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL I THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.

NO 24-11800406 JOB NO. 13055-20 JANUARY 2025 DESIGNER

C6.01

HECKED AS DRAWN AD



AREAS, EMBANKMENT SLOPES, ETC. WILL BE STABILIZED PER APPLICABLE 9. BEST MANAGEMENT PRACTICES MAY BE INSTALLED IN STAGES TO COINCIDE WITH THE DISTURBANCE OF UPGRADIENT AREAS. 10. BEST MANAGEMENT PRACTICES MAY BE REMOVED IN STAGES ONCE THE WATERSHED FOR THAT PORTION CONTROLLED BY THE BEST MANAGEMENT

PRACTICES HAS BEEN STABILIZED IN ACCORDANCE WITH TPDES REQUIREMENTS. 11. UPON COMPLETION OF THE PROJECT, INCLUDING SITE STABILIZATION, AND BEFORE FINAL PAYMENT IS ISSUED, CONTRACTOR SHALL REMOVE ALL SEDIMENT AND EROSION CONTROL MEASURES, PAYING SPECIAL ATTENTION

TO ROCK BERMS IN DRAINAGE FEATURES.

SIGNATURE

12. WHERE VEGETATED FILTER STRIPS ARE INDICATED, CONTRACTOR SHALL VERIFY THAT SUFFICIENT VEGETATION EXISTS, OTHERWISE CONTRACTOR SHALL PLACE SILT FENCING IN LIEU OF VEGETATED FILTER STRIP.

13. SHADED AREA DENOTES LIMITS OF DISTURBED AREAS. OTHER AREAS WITHIN THE PROJECT LIMITS, WITH THE EXCEPTION OF A CONSTRUCTION EQUIPMENT AND MATERIAL STORAGE YARD, ARE NOT A AND WILL NOT BE DISTURBED BY CIVIL CONSTRUCTION ACTIVITIES. HOUSÉ CONSTRUCTION ACTIVITIES WILL REQUIRE A SEPARATE STORM WATER POLLUTION PREVENTION PLAN.


14. PRIOR TO BEGINNING CONSTRUCTION, CONTRACTOR SHALL COORDINATE PLACEMENT OF TEMPORARY BEST MANAGEMENT PRACTICES WITHIN TXDOT


15. CPS ENERGY WILL FUNCTION AS A SECONDARY OPERATOR ON THIS PROJECT AND WILL BE INSTALLING ELECTRIC UTILITIES FOR ON—SITE CONSTRUCTION AND OFF-SITE FEED TO THE PROJECT.

16. A BEXAR COUNTY ROW PERMIT MUST BE OBTAINED BEFORE WORKING IN ANY BEXAR COUNTY ROW.


SWP3 MODIFICATIONS

DESCRIPTION





JON D. ADAME



SWPPP LEGEND

PROJECT LIMITS EXISTING CONTOUR PROPOSED CONTOUR FLOW ARROW (EXISTING) FLOW ARROW (PROPOSED) -//-//-//-//-SILT FENCE (STAGE I) SILT FENCE (STAGE II) ******* ROCK BERM

GRAVEL FILTER BAGS

EARTHEN BERM W/POLYLINER AND SPILLWAY (BERMS ARE TO SPAN ACROSS PROPOSED STREET SECTION APPROX. 30 FEET WIDE FROM CURB TO CURB)

LIMITS OF DISTURBED AREA

STABILIZED CONSTRUCTION ENTRANCE/EXIT (FIELD LOCATE) CONSTRUCTION EQUIPMENT, VEHICLE &

MATERIALS STORAGE AREA (FIELD LOCATE) CONCRETE TRUCK WASH-OUT PIT (FIELD LOCATE)

AREA TO BE REVEGETATED PER TPDES PERMIT REQUIREMENTS (PERMANENT) AREA TO BE REVEGETATED PER TPDES PERMIT REQUIREMENTS (TEMPORARY)

V V V V

 $\nabla\nabla\nabla$

+ + + + + # # #

Ш

THIS SHEET HAS BEEN PREPARED FOR PURPOSES OF THE SWP3 ONLY. ALL OTHER CIVIL ENGINEERING RELATED INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SHEET IN THE CIVIL IMPROVEMENT PLANS.

EXHIBIT 2

THE ENGINEERING SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR THE PURPOSE OF DEMONSTRATING COMPLIANCE WITH THE TPDES—STORM WATER POLLUTION PREVENTION PLAN (SWP3) REGULATIONS.

HECKED AS DRAWN AD C8.00

ESIGNER

_{I NO} 24-11800406

OB NO. 13055-20 ATE JANUARY 2025

SCHEMATIC OF TEMPORARY CONSTRUCTION ENTRANCE/EXIT

MATERIALS

8-INCHES.

DRAINAGE

LAY SOD IN A STAGGERED PATTERN. BUTT

THE STRIPS TIGHTLY AGAINST EACH OTHER.

DO NOT LEAVE SPACES AND DO NOT

OVERLAP. A SHARPENED MASON'S TROWEL

IS A HANDY TOOL FOR TUCKING DOWN THE

AUTOMATIC SOD CUTTER MUST BE MATCHED

ANGLED ENDS CAUSED BY THE

ENDS AND TRIMMING PIECES.

LAY SOD ACROSS THE

DIRECTION OF FLOW

MATERIALS

OF 36 HOURS.

SHOOT GROWTH AND THATCH.

SITE PREPARATION

TIGHTLY (SEE FIGURE ABOVE).

TORN OR UNEVEN PADS SHOULD NOT BE ACCEPTABLE.

SUSPENDED FROM A FIRM GRASP ON ONE END OF THE SECTION.

TO FINAL GRADE IN ACCORDANCE WITH THE APPROVED PLAN.

INSTALLATION IN CHANNELS

INTERFERE WITH PLANTING, FERTILIZING OR MAINTENANCE OPERATIONS.

THE AGGREGATE SHOULD CONSIST OF 4-INCH TO 8-INCH WASHED STONE OVER A STABLE FOUNDATION AS SPECIFIED IN THE PLAN. 2. THE AGGREGATE SHOULD BE PLACED WITH A MINIMUM THICKNESS OF

3. THE GEOTEXTILE FABRIC SHOULD BE DESIGNED SPECIFICALLY FOR USE AS A SOIL FILTRATION MEDIA WITH AN APPROXIMATE WEIGHT OF 6 OZ/YD2, A MULLEN BURST RATING OF 140 LB/IN2, AND AN EQUIVALENT OPENING SIZE GREATER THAN A NUMBER 50 SIEVE.

4. IF A WASHING FACILITY IS REQUIRED, A LEVEL AREA WITH A MINIMUM OF 4-INCH DIAMETER WASHED STONE OR COMMERCIAL ROCK SHOULD BE INCLUDED IN THE PLANS. DIVERT WASTEWATER TO A SEDIMENT TRAP OF

INSTALLATION

AVOID CURVES ON PUBLIC ROADS AND STEEP SLOPES. REMOVE VEGETATION AND OTHER OBJECTIONABLE MATERIAL FROM THE FOUNDATION AREA. GRADE CROWN FOUNDATION FOR POSITIVE DRAINAGE.

. THE MINIMUM WIDTH OF THE ENTRANCE/EXIT SHOULD BE 12 FEET OR THE FULL WIDTH OF EXIT ROADWAY, WHICHEVER IS GREATER.

3. THE CONSTRUCTION ENTRANCE SHOULD BE AT LEAST 50 FEET LONG 4. IF THE SLOPE TOWARD THE ROAD EXCEEDS 2%, CONSTRUCT A RIDGE 6-INCHES TO 8-INCHES HIGH WITH 3:1 (H: V) SIDE SLOPES, ACROSS THE FOUNDATION APPROXIMATELY 15 FEET FROM THE ENTRANCE TO DIVERT RUNOFF AWAY FROM THE PUBLIC ROAD.

5. PLACE GEOTEXTILE FABRIC AND GRADE FOUNDATION TO IMPROVE STABILITY, ESPECIALLY WHERE WET CONDITIONS ARE ANTICIPATED.

6. PLACE STONE TO DIMENSIONS AND GRADE SHOWN ON PLANS. LEAVE SURFACE SMOOTH AND SLOPE FOR DRAINAGE.

8. INSTALL PIPE UNDER PAD AS NEEDED TO MAINTAIN PROPER PUBLIC ROAD

7. DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM THE STONE PAD TO A SEDIMENT TRAP OR BASIN.

STABILIZE FOUNDATION SECTION "A-A" OF A

GEOTEXTILE FABRIC TO

CONSTRUCTION ENTRANCE/EXIT

COMMON TROUBLE POINTS

1. INADEQUATE RUNOFF CONTROL-SEDIMENT WASHES ONTO PUBLIC ROAD. . STONE TOO SMALL OR GEOTEXTILE FABRIC ABSENT, RESULTS IN MUDDY

CONDITION AS STONE IS PRESSED INTO SOIL. PAD TOO SHORT FOR HEAVY CONSTRUCTION TRAFFIC-EXTEND PAD BEYOND THE MINIMUM 50-FOOT LENGTH AS NECESSARY. 4. PAD NOT FLARED SUFFICIENTLY AT ROAD SURFACE, RESULTS IN MUD BEING TRACKED ON TO ROAD AND POSSIBLE DAMAGE TO ROAD.

5. UNSTABLE FOUNDATION - USE GEOTEXTILE FABRIC UNDER PAD AND/OR IMPROVE FOUNDATION DRAINAGE.

INSPECTION AND MAINTENANCE GUIDELINES

THE ENTRANCE SHOULD BE MAINTAINED IN A CONDITION. WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT

2. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY SHOULD BE REMOVED IMMEDIATELY BY CONTRACTOR. 3. WHEN NECESSARY, WHEELS SHOULD BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY.

4. WHEN WASHING IS REQUIRED, IT SHOULD BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR

5. ALL SEDIMENT SHOULD BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATER COURSE BY USING APPROVED METHODS.

WOVEN WIRE SHEATHING

ISOMETRIC PLAN VIEW

ROCK BERMS

THE PURPOSE OF A ROCK BERM IS TO SERVE AS A CHECK DAM IN AREAS OF CONCENTRATED FLOW, TO INTERCEPT SEDIMENT-LADEN RUNOFF, DETAIN THE SEDIMENT AND RELEASE THE WATER IN SHEET FLOW. THE ROCK BERM SHOULD BE USED WHEN THE CONTRIBUTING DRAINAGE AREA IS LESS THAN 5 ACRES. ROCK BERMS ARE USED IN AREAS WHERE THE VOLUME OF RUNOFF IS TOO GREAT FOR A SILT FENCE TO CONTAIN. THEY ARE LESS EFFECTIVE FOR SEDIMENT REMOVAL THAN SILT FENCES, PARTICULARLY FOR FINE PARTICLES, BUT ARE ABLE TO WITHSTAND HIGHER FLOWS THAN A SILT FENCE. AS SUCH, ROCK BERMS ARE OFTEN USED IN AREAS OF CHANNEL FLOWS (DITCHES, GULLIES, ETC.). ROCK BERMS ARE MOST EFFECTIVE AT REDUCING BED LOAD IN CHANNELS AND SHOULD NOT BE SUBSTITUTED FOR OTHER EROSION AND SEDIMENT CONTROL MEASURES FARTHER UP THE WATERSHED.

INSPECTION AND MAINTENANCE GUIDELINES

. INSPECTION SHOULD BE MADE WEEKLY BY THE RESPONSIBLE PARTY. FOR INSTALLATIONS IN STREAMBEDS, ADDITIONAL DAILY INSPECTIONS SHOULD BE

REMOVE SEDIMENT AND OTHER DEBRIS WHEN BUILDUP REACHES 6 INCHES AND DISPOSE OF THE ACCUMULATED SILT IN AN APPROVED MANNER THAT WILL NOT CAUSE ANY ADDITIONAL SILTATION.

3. REPAIR ANY LOOSE WIRE SHEATHING.

4. THE BERM SHOULD BE RESHAPED AS NEEDED DURING INSPECTION

THE BERM SHOULD BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED DUE TO SILT ACCUMULATION AMONG THE ROCKS WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC.

6. THE ROCK BERM SHOULD BE LEFT IN PLACE UNTIL ALL UPSTREAM AREAS ARE STABILIZED AND ACCUMULATED SILT REMOVED.

WOVEN WIRE SHEATHING **SECTION "A-A**

THE BERM STRUCTURE SHOULD BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM OPENING OF 1 INCH AND A MINIMUM WIRE DIAMETER OF 20 GAUGE GALVANIZED AND SHOULD BE SECURED WITH SHOAT

2. CLEAN, OPEN GRADED 3-INCH TO 5-INCH DIAMETER ROCK SHOULD BE USED, EXCEPT IN AREAS WHERE HIGH VELOCITIES OR LARGE VOLUMES OF FLOW ARE EXPECTED, WHERE 5-INCH TO 8-INCH DIAMETER ROCKS MAY BE

INSTALLATION

I. LAY OUT THE WOVEN WIRE SHEATHING PERPENDICULAR TO THE FLOW LINE. THE SHEATHING SHOULD BE 20 GAUGE WOVEN WIRE MESH WITH 1 INCH

2. BERM SHOULD HAVE A TOP WIDTH OF 2 FEET MINIMUM WITH SIDE SLOPES BEING 2:1 (H:V) OR FLATTER. 3. PLACE THE ROCK ALONG THE SHEATHING AS SHOWN IN THE DIAGRAM TO

A HEIGHT NOT LESS THAN 18" 4. WRAP THE WIRE SHEATHING AROUND THE ROCK AND SECURE WITH TIE WIRE SO THAT THE ENDS OF THE SHEATHING OVERLAP AT LEAST 2 INCHES,

AND THE BERM RETAINS ITS SHAPE WHEN WALKED UPON.

5. BERM SHOULD BE BUILT ALONG THE CONTOUR AT ZERO PERCENT GRADE OR AS NEAR AS POSSIBLE 6. THE ENDS OF THE BERM SHOULD BE TIED INTO EXISTING UPSLOPE GRADE

AND THE BERM SHOULD BE BURIED IN A TRENCH APPROXIMATELY 3 TO 4 INCHES DEEP TO PREVENT FAILURE OF THE CONTROL. COMMON TROUBLE POINTS

INSUFFICIENT BERM HEIGHT OR LENGTH (RUNOFF QUICKLY ESCAPES OVER THE TOP OR AROUND THE SIDES OF BERM).

2. BERM NOT INSTALLED PERPENDICULAR TO FLOW LINE (RUNOFF ESCAPING AROUND ONE SIDE).

NOT-TO-SCALE

STEEL FENCE POST SILT FENCE MAX. 8' SPACING(**) MIN. HEIGHT 24" ABOVE EXISTING \M IN. EMBEDMENT = 1 GROUND) WIRE MESH BACKING COMPACTED EARTH OR ROCK BACKFILL - ALLOWABLE TYPICAL CHAIN LINK FENCE FABRIC IS ACCEPTABLE

EMBEDDED A MINIMUM OF 1-FOOT DEEP AND SPACED NOT MORE THAN 8 FEET O CENTER. WHERE WATER CONCENTRATES THE MAXIMUM SPACING SHOULD BE 6 4X4~W1.4xW1.4 MIN. FEET. (RG-348, SECTION 1.4.3)

**STEEL POSTS, WHICH SUPPORT THE SILT

SLIGHT ANGLE TOWARD THE ANTICIPATED

FENCE, SHOULD BE INSTALLED ON A

RUNOFF SOURCE. POST MUST BE

ROCK BERM DETAIL

GRASS SHOULD BE GREEN AND HEALTHY: MOWED AT A 2"-3"- THATCH- GRASS CLIPPINGS AND CORRECT DEAD LEAVES, UP TO 1/2" THICK. ROOT ZONE - SOIL AND ROOTS. SHOULD BE 1/2"-3/4" THICK, WITH DENSE ROOT MAT FOR STRENGTH. INCORRECT 1. ROLL SOD IMMEDIATELY TO ACHIEVE FIRM CONTACT WITH THE SOD INSTALLATION 3. MOW WHEN THE SOD IS ESTABLISHED - IN 2-3 WEEKS. SET

USE PEGS OR STAPLES TO FASTEN SOD

FIRMLY - AT THE ENDS OF STRIPS AND

THE STRIPS ARE LONG. WHEN READY TO

MOW, DRIVE PEGS OR STAPLES FLUSH

IN THE CENTER, OR EVERY 3-4 FEET IF

2. WATER TO A DEPTH OF 4" AS NEEDED. WATER WELL AS

STABILIZED CONSTRUCTION ENTRANCE/EXIT DETAIL

NOT-TO-SCALE

APPEARANCE OF GOOD SOD

SOON AS THE SOD IS LAID.

THE MOWER HIGH (2"-3").

SEDIMENT BASIN.

SHOOTS OR GRASS BLADES.

CUTTING HEIGHT.

1. SOD SHOULD BE MACHINE CUT AT A UNIFORM SOIL THICKNESS OF 3/4" INCH

(± 1/4" INCH) AT THE TIME OF CUTTING. THIS THICKNESS SHOULD EXCLUDE

2. PIECES OF SOD SHOULD BE CUT TO THE SUPPLIER'S STANDARD WIDTH AND

STANDARD SIZE SECTIONS OF SOD SHOULD BE STRONG ENOUGH TO

SUPPORT THEIR OWN WEIGHT AND RETAIN THEIR SIZE AND SHAPE WHEN

4. SOD SHOULD BE HARVESTED, DELIVERED, AND INSTALLED WITHIN A PERIOD

PRIOR TO SOIL PREPARATION, AREAS TO BE SODDED SHOULD BE BROUGHT

THE SURFACE SHOULD BE CLEARED OF ALL TRASH, DEBRIS AND OF ALL

FERTILIZE ACCORDING TO SOIL TESTS. FERTILIZER NEEDS CAN BE

DETERMINED BY A SOIL TESTING LABORATORY OR REGIONAL RECOMMENDATIONS CAN BE MADE BY COUNTY AGRICULTURAL EXTENSION AGENTS. FERTILIZER

SHOULD BE WORKED INTO THE SOIL TO A DEPTH OF 3 INCHES WITH A DISC,

FINAL HARROWING OR DISCING OPERATION SHOULD BE ON THE CONTOUR.

SPRINGTOOTH HARROW OR OTHER SUITABLE EQUIPMENT. ON SLOPING LAND, THE

SOD STRIPS IN WATERWAYS SHOULD BE LAID PERPENDICULAR TO THE

AFTER ROLLING OR TAMPING, SOD SHOULD BE PEGGED OR STAPLED TO

RESIST WASHOUT DURING THE ESTABLISHMENT PERIOD. MESH OR OTHER

NETTING MAY BE PEGGED OVER THE SOD FOR EXTRA PROTECTION IN CRITICAL

DIRECTION OF FLOW. CARE SHOULD BE TAKEN TO BUTT ENDS OF STRIPS

SOIL.

IN CRITICAL AREAS, SECURE SOD WITH NETTING. USE STAPLES.

GENERAL INSTALLATION (VA. DEPT. OF CONSERVATION, 1992)

REDUCE ROOT BURNING AND DIEBACK.

(SEE FIGURE ABOVE).

SOD SHOULD NOT BE CUT OR LAID IN EXCESSIVELY WET OR DRY WEATHER. SOD ALSO SHOULD NOT BE LAID ON SOIL SURFACES THAT ARE FROZEN. 2. DURING PERIODS OF HIGH TEMPERATURE, THE SOIL SHOULD BE LIGHTLY LENGTH, WITH A MAXIMUM ALLOWABLE DEVIATION IN ANY DIMENSION OF 5%. IRRIGATED IMMEDIATELY PRIOR TO LAYING THE SOD, TO COOL THE SOIL AND

WITH THE GROUND.

THE FIRST ROW OF SOD SHOULD BE LAID IN A STRAIGHT LINE WITH SUBSEQUENT ROWS PLACED PARALLEL TO AND BUTTING TIGHTLY AGAINST EACH OTHER. LATERAL JOINTS SHOULD BE STAGGERED TO PROMOTE MORE UNIFORM GROWTH AND STRENGTH. CARE SHOULD BE EXERCISED TO ENSURE THAT SOD IS NOT STRETCHED OR OVERLAPPED AND THAT ALL JOINTS ARE BUTTED TIGHT IN ORDER TO PREVENT VOIDS WHICH WOULD CAUSE DRYING OF THE ROOTS

4. ON SLOPES 3:1 OR GREATER, OR WHEREVER EROSION MAY BE A PROBLEM, SOD SHOULD BE LAID WITH STAGGERED JOINTS AND SECURED BY STAPLING OR OTHER APPROVED METHODS. SOD SHOULD BE INSTALLED WITH THE LENGTH PERPENDICULAR TO THE SLOPE (ON CONTOUR).

5. AS SODDING OF CLEARLY DEFINED AREAS IS COMPLETED, SOD SHOULD BE ROOTS, BRUSH, WIRE, GRADE STAKES AND OTHER OBJECTS THAT WOULD ROLLED OR TAMPED TO PROVIDE FIRM CONTACT BETWEEN ROOTS AND SOIL. . AFTER ROLLING, SOD SHOULD BE IRRIGATED TO A DEPTH SUFFICIENT THAT THE UNDERSIDE OF THE SOD PAD AND THE SOIL 4 INCHES BELOW THE SOD IS

> UNTIL SUCH TIME A GOOD ROOT SYSTEM BECOMES DEVELOPED, IN THE ABSENCE OF ADEQUATE RAINFALL, WATERING SHOULD BE PERFORMED AS OFTEN AS NECESSARY TO MAINTAIN MOIST SOIL TO A DEPTH OF AT LEAST 4

> 8. THE FIRST MOWING SHOULD NOT BE ATTEMPTED UNTIL THE SOD IS FIRMLY ROOTED, USUALLY 2-3 WEEKS. NOT MORE THAN ONE THIRD OF THE GRASS LEAF SHOULD BE REMOVED AT ANY ONE CUTTING.

NSPECTION AND MAINTENANCE GUIDELINES SOD SHOULD BE INSPECTED WEEKLY AND AFTER EACH RAIN EVENT TO LOCATE AND REPAIR ANY DAMAGE.

IIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.

. DAMAGE FROM STORMS OR NORMAL CONSTRUCTION ACTIVITIES SUCH AS TIRE RUTS OR DISTURBANCE OF SWALE STABILIZATION SHOULD BE REPAIRED AS

SOD INSTALLATION DETAIL

SOON AS PRACTICAL.

TRENCH-ISOMETRIC PLAN VIEW

SILT FENCE

A SILT FENCE IS A BARRIER CONSISTING OF GEOTEXTILE FABRIC SUPPORTED BY METAL POSTS TO PREVENT SOIL AND SEDIMENT LOSS FROM A SITE. WHEN PROPERLY USED, SILT FENCES CAN BE HIGHLY EFFECTIVE AT CONTROLLING SEDIMENT FROM DISTURBED AREAS. THEY CAUSE RUNOFF TO POND, ALLOWING HEAVIER SOLIDS TO SETTLE OUT. IF NOT PROPERLY INSTALLED, SILT FENCES ARE NOT LIKELY TO BE EFFECTIVE.

THE PURPOSE OF A SILT FENCE IS TO INTERCEPT AND DETAIN WATER-BORN SEDIMENT FROM UNPROTECTED AREAS OF A LIMITED EXTENT. SILT FENCE IS USED DURING THE PERIOD OF CONSTRUCTION NEAR THE PERIMETER OF A DISTURBED AREA TO INTERCEPT SEDIMENT WHILE ALLOWING WATER TO PERCOLATE THROUGH. THIS FENCE SHOULD REMAIN IN PLACE UNTIL THE DISTURBED AREA IS PERMANENTLY STABILIZED. SILT FENCE SHOULD NOT BE USED WHERE THERE IS A CONCENTRATION OF WATER IN A CHANNEL OR DRAINAGE WAY. IF CONCENTRATED FLOW OCCURS AFTER INSTALLATION, CORRECTIVE ACTION MUST BE TAKEN SUCH AS PLACING A ROCK BERM IN THE AREAS OF CONCENTRATED FLOW.

SILT FENCING WITHIN THE SITE MAY BE TEMPORARILY MOVED DURING THE DAY TO ALLOW CONSTRUCTION ACTIVITY PROVIDED IT IS REPLACED AND PROPERLY ANCHORED TO THE GROUND AT THE END OF THE DAY. SILT FENCES ON THE PERIMETER OF THE SITE OR AROUND DRAINAGE WAYS SHOULD NOT BE MOVED AT ANY TIME.

SILT FENCE MATERIAL SHOULD BE POLYPROPYLENE, POLYETHYLENE, OR POLYAMIDE WOVEN OR NONWOVEN FABRIC. THE FABRIC SHOULD BE 36 INCHES, WITH A MINIMUM UNIT WEIGHT OF 4.5 OZ/YD, MULLEN BURST STRENGTH EXCEEDING 190 LB/IN2, ULTRAVIOLET STABILITY EXCEEDING 70%, AND MINIMUM APPARENT OPENING SIZE OF U.S. SIEVE NUMBER 30.

FENCE POSTS SHOULD BE MADE OF HOT ROLLED STEEL, AT LEAST 4 FEET LONG WITH TEE OR Y-BAR CROSS SECTION, SURFACE PAINTED OR GALVANIZED, MINIMUM WEIGHT 1.25 LB/FT, AND BRINDELL HARDNESS

3. WOVEN WIRE BACKING TO SUPPORT THE FABRIC SHOULD BE GALVANIZED 2" X 4" WELDED WIRE, 12 GAUGE MINIMUM.

INSTALLATION

. STEEL POSTS, WHICH SUPPORT THE SILT FENCE, SHOULD BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POSTS MUST BE EMBEDDED A MINIMUM OF 1-FOOT DEEP AND SPACED NOT MORE THAN 8 FEET ON CENTER. WHERE WATER CONCENTRATES, THE MAXIMUM SPACING SHOULD BE 6 FEET.

2. LAY OUT FENCING DOWN-SLOPE OF DISTURBED AREA, FOLLOWING THE CONTOUR AS CLOSELY AS POSSIBLE. THE FENCE SHOULD BE SITED SO THAT THE MAXIMUM DRAINAGE AREA IS 1/4 ACRE/100 FEET OF FENCE.

3. THE TOE OF THE SILT FENCE SHOULD BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWN-SLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. WHERE FENCE CANNOT BE TRENCHED IN (E.G., PAVEMENT OR ROCK OUTCROP), WEIGHT FABRIC FLAP WITH 3 INCHES OF PEA GRAVEL ON UPHILL SIDE TO PREVENT FLOW FROM SEEPING UNDER FENCE.

4. THE TRENCH MUST BE A MINIMUM OF 6 INCHES DEEP AND 6 INCHES WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL. 5. SILT FENCE SHOULD BE SECURELY FASTENED TO EACH STEEL SUPPORT POST OR TO WOVEN WIRE, WHICH IS IN TURN ATTACHED TO THE STEEL FENCE POST. THERE SHOULD BE A 3-FOOT OVERLAP, SECURELY FASTENED WHERE

6. SILT FENCE SHOULD BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.

COMMON TROUBLE POINTS FENCE NOT INSTALLED ALONG THE CONTOUR CAUSING WATER TO

ENDS OF FABRIC MEET

CONCENTRATE AND FLOW OVER THE FENCE. 2. FABRIC NOT SEATED SECURELY TO GROUND (RUNOFF PASSING UNDER FENCE).

3. FENCE NOT INSTALLED PERPENDICULAR TO FLOW LINE (RUNOFF ESCAPING 4. FENCE TREATING TOO LARGE AN AREA, OR EXCESSIVE CHANNEL FLOW (RUNOFF OVERTOPS OR COLLAPSES FENCE).


INSPECTION AND MAINTENANCE GUIDELINES 1. INSPECT ALL FENCING WEEKLY.

REMOVE SEDIMENT WHEN BUILDUP APPROACHES 6 INCHES, BUT NOT TO EXCEED 50% OF HEIGHT. 3. REPLACE TORN FABRIC OR INSTALL A SECOND LINE OF FENCING PARALLEL

TO THE TORN SECTION. 4. REPLACE OR REPAIR SECTIONS CRUSHED OR COLLAPSED IN THE COURSE OF CONSTRUCTION ACTIVITY. IF A SECTION OF FENCE IS OBSTRUCTING VEHICULAR ACCESS, CONSIDER RELOCATING IT TO A SPOT WHERE IT WILL PROVIDE EQUAL PROTECTION, BUT WILL NOT OBSTRUCT VEHICLES. A TRIANGULAR FILTER DIKE MAY BE PREFERABLE TO A SILT FENCE AT COMMON VEHICLE ACCESS POINTS.

WHEN CONSTRUCTION IS COMPLETE, THE SEDIMENT SHOULD BE DISPOSED OF IN A MANNER THAT WILL NOT CAUSE ADDITIONAL SILTATION AND THE PRIOR LOCATION OF THE SILT FENCE SHOULD BE REVEGETATED. THE FENCE ITSELF SHOULD BE DISPOSED OF IN AN APPROVED LANDFILL.

SILT FENCE DETAIL



A MANNER THAT IT WILL NOT ERODE.

. CONTRACTOR TO INSTALL 2"x4"-W1.4xW1.4 WIRE MESH SUPPORTING FILTER FABRIC OVER THE INLET OPENING. FABRIC MUST BE SECURED TO WIRE BACKING WITH CLIPS OR WIRE TIES AT THIS LOCATION. SAND BAGS FILLED WITH WASHED PEA GRAVEL SHOULD BE PLACED ON TOP OF WIRE MESH ON TOP OF THE INLET AS SHOWN ON THIS DETAIL TO HOLD WIRE MESH IN PLACE. SANDBAGS FILLED WITH WASHED PEA GRAVEL SHOULD ALSO BE PLACED ALONG THE GUTTER AS SHOWN ON THIS DETAIL TO HOLD WIRE MESH IN PLACE. SAND BAGS TO BE STACKED TO FORM A CONTINUOUS BARRIER AROUND INLETS.

2. THE BAGS SHOULD BE TIGHTLY ABUTTED AGAINST EACH OTHER TO PREVENT RUNOFF FROM FLOWING BETWEEN THE BAGS.

INSPECTION AND MAINTENANCE GUIDELINES . INSPECTION SHOULD BE MADE WEEKLY. REPAIR OR REPLACEMENT SHOULD


BE MADE PROMPTLY AS NEEDED BY THE CONTRACTOR. 2. REMOVE SEDIMENT WHEN BUILDUP REACHES A DEPTH OF 3 INCHES. REMOVED SEDIMENT SHOULD BE DEPOSITED IN A SUITABLE AREA AND IN SUCH

3. CHECK PLACEMENT OF DEVICE TO PREVENT GAPS BETWEEN DEVICE AND

4. INSPECT FILTER FABRIC AND PATCH OR REPLACE IF TORN OR MISSING. . STRUCTURES SHOULD BE REMOVED AND THE AREA STABILIZED ONLY AFTER THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

BAGGED GRAVEL CURB INLET PROTECTION DETAIL

NOT-TO-SCALE



MIN. 10 MIL PLASTIC LINING SAND BAGS (TYP.) -SAND BAGS (TYP.)

GENERAL NOTES

DETAIL ABOVE ILLUSTRATES MINIMUM DIMENSIONS. PIT CAN BE INCREASED IN SIZE DEPENDING ON EXPECTED FREQUENCY OF USE. 2. WASHOUT PIT SHALL BE LOCATED IN AN AREA EASILY ACCESSIBLE TO CONSTRUCTION TRAFFIC.

SECTION "A-A"

3. WASHOUT PIT SHALL NOT BE LOCATED IN AREAS SUBJECT TO INUNDATION FROM STORM WATER RUNOFF.

4. LOCATE WASHOUT AREA AT LEAST 50 FEET FROM SENSITIVE FEATURES, STORM DRAINS, OPEN DITCHES OR WATER BODIES. 5. TEMPORARY CONCRETE WASHOUT FACILITY SHOULD BE CONSTRUCTED WITH SUFFICIENT QUANTITY AND VOLUME TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS.

MATERIALS

PLASTIC LINING MATERIAL SHOULD BE A MINIMUM OF 10 MIL IN POLYETHYLENE SHEETING AND SHOULD BE FREE OF HOLES, TEARS, OR OTHER DEFECTS THAT COMPROMISE THE IMPERMEABILITY OF THE MATERIAL.

MAINTENANCE


WHEN TEMPORARY CONCRETE WASHOUT FACILITIES ARE NO LONGER REQUIRED FOR THE WORK, THE HARDENED CONCRETE SHOULD BE REMOVED AND DISPOSED OF. . MATERIALS USED TO CONSTRUCT TEMPORARY CONCRETE WASHOUT

. HOLES, DEPRESSIONS OR OTHER GROUND DISTURBANCES CAUSED BY THE REMOVAL OF THE TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE BACKFILLED AND REPAIRED.

NOT-TO-SCALE

FACILITIES SHOULD BE REMOVED FROM THE SITE OF THE WORK AND DISPOSED

CONCRETE TRUCK WASHOUT PIT DETAIL



OF LOT

82567

JON D. ADAME

PROPER1 **LEGEND**

THESE DETAILS AND LOCATED ON THE DOWNGRADIENT SIDE OF EACH LOT LINE —" -" -" — SILT FENCE OR LIMITS OF CLEARING AS GENERALLY → DRAINAGE FLOW SHOWN ON THE OVERALL SITE PLAN.

DRIVE WAY

SECTION "A-A"

TYPICAL HOUSE LOT LAYOUTS NOT-TO-SCALE


LOT TYPE-C

NOTE: SILT FENCE TO BE INSTALLED PER

PLAN VIEW

LOT TYPE-E

HOUSE PAD




THE FILTER BAG MATERIAL SHALL BE MADE OF POLYPROPYLENE POLYETHYLENE OR POLYAMIDE WOVEN FABRIC, MIN. UNIT WEIGHT OF 4 OUNCES/SY, HAVE A MULLEN BURST STRENGTH EXCEEDING 300 PSI AND ULTRAVIOLET STABILITY EXCEEDING 70%.

THE FILTER BAG SHALL BE FILLED WITH CLEAN, MEDIUM WASHED PEA GRAVEL TO COARSE GRAVEL (0.31 TO 0.75 INCH DIAMETER). 3. SAND SHALL <u>NOT</u> BE USED TO FILL THE FILTER BAGS.

GRAVEL FILTER BAG DETAIL

NOT-TO-SCALE



CONSTRUCTION STAGING AREA

THE ENGINEERING SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR THE PURPOSE OF DEMONSTRATING COMPLIANCE WITH THE TPDES-STORM WATER POLLUTION PREVENTION PLAN (SWP3) REGULATIONS.

NOT-TO-SCALE

THIS SHEET HAS BEEN PREPARED FOI PURPOSES OF THE SWP3 ONLY. ALL OTHER CIVIL FNGINFFRING RFLATFD INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SHEET IN THE CIVIL IMPROVEMENT PLANS.

EXHIBIT 1 OF 2

13055-20 JANUARY 2025 ESIGNER HECKED AS DRAWN A C8.10

NO 24-1180040

NOT-TO-SCALE