

# BRIGGS RANCH NORTH SEWER UPSIZING

# BEXAR COUNTY, TEXAS SAWS JOB NO. 23-1643

## 100% SUBMITTAL





**LOCATION MAP** 

PREPARED FOR:

CHESMAR HOMES 211 N. LOOP 1604 E, SUITE 175 SAN ANTONIO, TEXAS 78232

FEBRUARY 2024





#### SHEET INDEX

Sheet Description	Sheet No.
COVER SHEET	C0.00
GENERAL NOTES AND QUANTITIES	C1.00
OVERALL SANITARY SEWER PLAN	C2.00
ABANDONMENT PLAN	C2.30
SUGGESTED BYPASS AND SEQUENCING PLAN	C2.40
SANITARY SEWER LINE PLAN AND PROFILE	C3.00
SANITARY SEWER LINE PLAN AND PROFILE	C3.01
SANITARY SEWER DETAILS	C4.00
TREE PRESERVATION PLAN AND DETAILS	C6.00
STORMWATER POLLUTION PREVENTION PLAN	C7.00
STORMWATER POLLUTION PREVENTION PLAN DETAILS	C7.01

UPPER MEDINA - SOUTH SEWERSHED - DOS RIOS/LEON CREEK

브	BRIGGS RANCH NORTH SEWER UPSIZING					
	Developer's Name: <u>CHESMAR HOMES</u> Address: 211 N. LOOP 1604 E, SUITE 175					
	City: SAN ANTONIO State: TEXAS ZIP: 78232					
	Phone# <u>(210) 957–3395</u> FAX <u># N/A</u>					
	SAWS Block Map# 080560, 080562Total Acreage 1.45					
	Total Linear Footage of Pipe <u>1,785 LF ~ 21" PVC SEWER</u> Plat No <u>.N/A</u>					
IJ	Number of Lots N/A TOTAL EDU'S N/A SAWS JOB NO. 23-1643					

- A. CURRENT TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) "DESIGN CRITERIA FOR DOMESTIC WASTEWATER SYSTEM", TEXAS ADMINISTRATIVE CODE (TAC) TITLE 30 PART 1 CHAPTER 217 AND "PUBLIC DRINKING WATER", TAC TITLE 30 PART 1 CHAPTER 290. B. CURRENT TXDOT "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS
- AND DRAINAGE."

  C. CURRENT "SAN ANTONIO WATER SYSTEM STANDARD SPECIFICATIONS FOR WATER AND
- C. CURRENT "SAN ANTONIO WATER SYSTEM STANDARD SPECIFICATIONS FOR WATER AND SANITARY SEWER CONSTRUCTION."
- D. CURRENT CITY OF SAN ANTONIO "STANDARD SPECIFICATIONS FOR CONSTRUCTION."
- CURRENT CITY OF SAN ANTONIO "UTILITY EXCAVATION CRITERIA MANUAL" (UECM)
- 2. THE CONTRACTOR SHALL OBTAIN SAWS STANDARD DETAILS FROM THE SAWS WEBSITE, HTTPS://APPS.SAWS.ORG/BUSINESS\_CENTER/SPECS/CONSTSPECS/ UNLESS OTHERWISE NOTED WITHIN THE DESIGN PLANS.
- 3. THE CONTRACTOR IS TO NOTIFY AND MAKE ARRANGEMENTS WITH THE SAWS CONSTRUCTION INSPECTION DIVISION AT 210-233-3500 (DURING REGULAR SAWS WORKING HOURS) AND PROVIDE NOTIFICATION PROCEDURES THE CONTRACTOR WILL USE TO NOTIFY AFFECTED HOME RESIDENTS AND/OR PROPERTY OWNERS TWO (2) WEEKS PRIOR TO EXCAVATION. OUTSIDE OF REGULAR SAWS WORKING HOURS THE SAWS EOC SHOULD BE CONTACTED AT 210-704-7297.
- 4. IF NECESSARY, CONTRACTOR WILL COORDINATE USE OF SAWS PREMISES AT NO ADDITIONAL COST TO SAWS. SUCH EFFORTS INCLUDE, BUT ARE NOT LIMITED TO, OBTAINING SECURITY IDENTIFICATION BADGES REQUIRED FOR ACCESS TO SAWS FACILITIES.
- 5. LOCATIONS AND DEPTHS OF EXISTING UTILITIES AND SERVICE LATERALS SHOWN ON THE PLANS ARE UNDERSTOOD TO BE APPROXIMATE. ACTUAL LOCATIONS AND DEPTHS MUST BE FIELD VERIFIED BY THE CONTRACTOR'S RESPONSIBILITY TO LOCATE UTILITY SERVICE LINES AS REQUIRED FOR CONSTRUCTION AND TO PROTECT THEM DURING CONSTRUCTION AT NO COST TO SAWS.
- 6. THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF UNDERGROUND UTILITIES AND DRAINAGE STRUCTURES PRIOR TO CONSTRUCTION WHETHER SHOWN ON PLANS OR NOT. AS—BUILTS FOR SAWS INFRASTRUCTURE CAN BE OBTAINED AT WEBSITE BELOW. CONTRACTOR SHALL COORDINATE PHYSICAL LOCATES FOR SAWS INFRASTRUCTURE THROUGH THE SAWS INSPECTOR. PLEASE ALLOW UP TO 7 BUSINESS DAYS FOR LOCATES REQUESTING PIPE LOCATION MARKERS ON SAWS INFRASTRUCTURE. THE FOLLOWING CONTACT INFORMATION ARE SUPPLIED FOR VERIFICATION PURPOSES:

SAN ANTONIO WATER SYSTEM:
REQUEST AS-BUILTS: HTTPS://WWW.SAWS.ORG/SERVICE/LOCATES-SERVICE/
COSA DRAINAGE 210-206-8433
COSA TRAFFIC SIGNAL OPERATIONS 210-207-7720

TEXAS STATEWIDE ONE CALL LOCATOR 1-800-545-6005 OR 811

- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING EXISTING FENCES, CURBS, STREETS, DRIVEWAYS, SIDEWALKS, LANDSCAPING, AND STRUCTURES TO ITS ORIGINAL OR BETTER CONDITION AS A RESULT OF DAMAGES DONE BY THE PROJECT'S CONSTRUCTION.
- 8. CONTRACTOR SHALL NOT MAKE USE OF DUMPSTERS OR WASTE BINS THAT ARE INTENDED TO SERVE RESIDENTS AND/OR BUSINESSES.
- 9. ALL WORK IN TEXAS DEPARTMENT OF TRANSPORTATION AND BEXAR COUNTY RIGHT—OF—WAY SHALL BE DONE IN ACCORDANCE WITH RESPECTIVE CONSTRUCTION SPECIFICATIONS AND PERMIT.
- 10. THE CONTRACTOR SHALL COMPLY WITH CITY OF SAN ANTONIO OR OTHER GOVERNING MUNICIPALITY'S TREE ORDINANCES WHEN EXCAVATING NEAR TREES.
- 11. ALL WORK WITHIN THE 100—YEAR FLOODPLAIN SHALL BE DONE IN ACCORDANCE WITH FLOODPLAIN DEVELOPMENT PERMIT.
- 12. ANY WORK COMPLETED WITHOUT PRIOR WRITTEN AUTHORIZATION WHICH IS NOT INCLUDED IN THESE PLANS AND SPECIFICATIONS WILL NOT BE COMPENSATED BY THE SAN ANTONIO WATER SYSTEM.
- 13. HOLIDAY WORK: CONTRACTORS WILL NOT BE ALLOWED TO PERFORM SAWS WORK ON SAWS RECOGNIZED HOLIDAYS.

WEEKEND WORK: CONTRACTORS ARE REQUIRED TO SUBMIT REQUEST TO THE SAWS INSPECTION CONSTRUCTION DEPARTMENT BY 12:00 PM ON THE WEDNESDAY PRIOR TO THE WEEKEND BEING REQUESTED. REQUEST SHOULD BE SENT TO CONSTWORKREQ@SAWS.ORG

ANY AND ALL SAWS UTILITY WORK INSTALLED WITHOUT WEEKEND APPROVAL WILL BE SUBJECT TO BE UNCOVERED FOR PROPER INSPECTION AT NO COST TO SAWS.

- 14. PRE-CON SITE VIDEO: BEFORE THE START OF ANY CONSTRUCTION. THE SITE MUST BE VIDEO RECORDED BY THE CONTRACTOR WITH ONE COPY SUBMITTED TO SAWS INSPECTIONS. A PRE-SITE VIDEO WILL PROVIDE ACCURATE DOCUMENTATION OF THE EXISTING CONDITIONS (NSPI).
- 15. POWER POLE BRACING: CONTRACTORS SHOULD BE ADVISED THAT THERE ARE EXISTING OVERHEAD UTILITY POLES ALONG THE PROJECT CORRIDOR. CONTRACTORS SHOULD FURTHER BE ADVISED THAT IF THE DISTANCE FROM THE OUTSIDE FACE OF A UTILITY TRENCH TO THE FACE OF A UTILITY POLE IS LESS THAN 5 FEET, SAID UTILITY POLE IS SUBJECT TO BRACING, BASED ON A DETERMINATION MADE BY UTILITY POLE OWNER. IT IS ADVISABLE FOR THE CONTRACTOR TO REVIEW THE CONSTRUCTION DOCUMENTS AND VISIT THE CONSTRUCTION SITE TO DETERMINE POTENTIAL IMPACTS.
- 16. CONSTRUCTION SEQUENCING: IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO SCHEDULE SEQUENCING FOR REMOVAL AND INSTALLATION OF EXISTING AND PROPOSED SAWS UTILITIES IN CONJUNCTION WITH GENERAL PROJECT CONSTRUCTION. SEQUENCE OF CONSTRUCTION ACTIVITIES SHALL BE CONSIDERED IN ORDER TO MINIMIZE THE EXTENT AND DURATION OF DISTURBANCES.
- 17. CONTRACTOR SHALL COMPLY WITH APPLICABLE REGULATIONS INCLUDING, BUT NOT LIMITED TO, THOSE OVERSEEN BY THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA). OSHA INFORMATION AND RELATED MATERIALS MAY BE OBTAINED AT HTTPS://WWW.OSHA.GOV/ OR AT THE OSHA SAN ANTONIO OFFICE LOCATED AT FOUNTAINHEAD TOWER, SUITE 605 8200 W. INTERSTATE 10 SAN ANTONIO, TX 78230 WHICH IS ALSO REACHABLE BY PHONE AT (210) 472-5040.

18. TRENCH EXCAVATION SAFETY PROTECTION: CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREAS IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF THE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLIES WITH, AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

#### SEWER SECTION

23. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT NO SANITARY SEWER OVERFLOW (SSO) OCCURS AS A RESULT OF THEIR WORK. ALL CONTRACTOR PERSONNEL RESPONSIBLE FOR SSO PREVENTION AND CONTROL SHALL BE TRAINED ON PROPER RESPONSE. SHOULD AN SSO OCCUR, THE CONTRACTOR SHALL:

A. IDENTIFY THE SOURCE OF THE SSO AND NOTIFY SAWS EMERGENCY OPERATIONS CENTER (EOC) IMMEDIATELY AT 210-704-SAWS (210-704-7297). PROVIDE THE ADDRESS OF THE SPILL AND AN ESTIMATED VOLUME OR FLOW.

B. ATTEMPT TO ELIMINATE THE SOURCE OF THE SSO. C. CONTAIN SEWAGE FROM THE SSO TO THE EXTENT OF PREVENTING A POSSIBLE CONTAMINATION OF WATERWAYS.

D. CLEAN UP SPILL SITE (RETURN CONTAINED SEWAGE TO THE COLLECTION SYSTEM IF POSSIBLE) AND PROPERLY DISPOSE OF CONTAMINATED SOIL/MATERIALS.

E. CLEAN THE AFFECTED SEWER MAINS AND REMOVE ANY DEBRIS.

F. MEET ALL POST—SSO REQUIREMENTS AS PER THE EPA CONSENT DECREE, INCLUDING LINE CLEANING AND TELEVISING THE AFFECTED SEWER MAINS (AT SAWS DIRECTION) WITHIN 24 HOURS.

SHOULD THE CONTRACTOR FAIL TO ADDRESS AN SSO IMMEDIATELY AND TO SAWS SATISFACTION, THEY WILL BE RESPONSIBLE FOR ALL COSTS INCURRED BY SAWS, INCLUDING ANY FINES FROM EPA.

NO SEPARATE MEASUREMENT OR PAYMENT SHALL BE MADE FOR THIS WORK. ALL WORK SHALL BE DONE ACCORDING TO GUIDELINES SET BY THE TCEQ AND SAWS.

- 24. THE CONTRACTOR SHALL PROVIDE BYPASS PUMPING OF SEWAGE AROUND EACH SEGMENT OF PIPE TO BE REPLACED, IN ACCORDANCE WITH SAWS STANDARD SPECIFICATION ITEM NO. 865, "BYPASS PUMPING SMALL DIAMETER SANITARY SEWER MAINS" AND STANDARD SPECIFICATION ITEM NO. 864, "BYPASS PUMPING LARGE DIAMETER SANITARY SEWER MAINS" AS APPLICABLE. PAYMENT FOR SUCH WORK WILL BE MADE UNDER THE APPROPRIATE BID ITEM ASSOCIATED WITH SANITARY SEWER BYPASS PUMPING IN ACCORDANCE WITH SAWS STANDARD SPECIFICATIONS 865 AND 864.
- 25. PRIOR TO TIE-INS, ANY SHUTDOWNS OF EXISTING FORCE MAINS OF ANY SIZE MUST BE COORDINATED WITH THE SAWS CONSTRUCTION INSPECTION DIVISION AT 210-233-3500 AND/OR SAWS PRODUCTION GROUPS AT LEAST TWO WEEKS OR MORE IN ADVANCE OF THE SHUTDOWN. THE CONTRACTOR MUST ALSO PROVIDE A SEQUENCE OF WORK AS RELATED TO THE TIE-INS; THIS IS AT NO ADDITIONAL COST TO SAWS OR THE PROJECT AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SEQUENCE THE WORK ACCORDINGLY.
- 26. ELEVATIONS POSTED FOR TOP OF MANHOLES ARE FOR REFERENCE ONLY: IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO MAKE ALLOWANCES AND ADJUSTMENTS FOR TOP OF MANHOLES TO MATCH THE FINISHED GRADE OF THE PROJECT'S IMPROVEMENTS. (NSPI)
- 27. MANHOLE REMOVAL: WHERE EXISTING MANHOLES ARE TO BE REPLACED BY THE CONTRACTOR, THE EXISTING MANHOLES SHALL BE REMOVED. (NSPI)
- 28. SMART MANHOLE COVERS: THE CONTRACTOR SHALL NOTIFY SAWS EOC AT 210-704-SAWS (210-233-7297) AND EITHER AMERICA ESPINOZA AT 210-233-2934 OR JOSE A. MARTINEZ AT 210-233-3071 A MINIMUM OF 72 HOURS, NOT COUNTING WEEKENDS OR SAWS HOLIDAYS, BEFORE WORKING ON THE PIPE OR MANHOLE, IN ORDER TO HAVE SAWS REMOVE THE SMART COVER. ANY DAMAGE DONE TO THE SMART COVER WILL BE CHARGED TO THE CONTRACTOR THROUGH A CHANGE ORDER.
- 29. FLOW METER IN MANHOLES: THE CONTRACTOR SHALL NOTIFY BOBBY JOHNSON AT 210-233-3493 OR ABEL BORUNDA AT 210-233-3704 A MINIMUM OF 72 HOURS, NOT COUNTING WEEKEND OR SAWS HOLIDAYS, BEFORE WORKING ON THE PIPE OR MANHOLE, IN ORDER TO HAVE SAWS REMOVE THE FLOW METER IN THE MANHOLE. ANY DAMAGE DONE TO THE FLOW METER WILL BE CHARGED TO THE CONTRACTOR THROUGH A CHANGE ORDER.

#### **EXISTING IMPROVEMENTS**

ALL EXISTING IMPROVEMENTS WITHIN THE PROJECT AREA, WHICH ARE NOT COVERED UNDER THE UNIT PRICE BID PROPOSAL, SHALL BE PROTECTED OR REMOVED AND REPLACED TO EXISTING CONDITION OR BETTER AT NO ADDITIONAL COST TO THE OWNER.

#### HAULING AND STORAGE

HAULING AND/OR TEMPORARY STORAGE OF EQUIPMENT AND MATERIALS MAY BE NECESSARY, INCLUDING EXCAVATED MATERIAL AND SPOILS. CONTRACTOR SHALL INCLUDE IN HIS BID PRICE ALL COSTS ASSOCIATED WITH HAULING AND OFF-SITE STORAGE OF ALL MATERIALS AND/OR EQUIPMENT. ALSO REFER TO THE PROJECT SPECIFICATIONS.

#### TREE PROTECTION NOTES

- 1. CONTRACTOR TO PROTECT ALL TREES WHEREVER POSSIBLE. DAMAGE TO TREES IDENTIFIED TO BE PROTECTED WILL BE MITIGATED AT THE CONTRACTOR'S SOLE EXPENSE.
- PROTECT EXISTING TREES SIX INCH (6") DIAMETER AND LARGER. ALL TREES TO BE PRESERVED AS PART OF THE PROJECT SHALL BE PROTECTED AGAINST INJURY OR DAMAGE, INCLUDING CUTTING, SOIL COMPACTION, BREAKING OR SKINNING OF ROOTS, TRUNKS, OR BRANCHES DURING CONSTRUCTION OPERATIONS BY FENCING AS DESCRIBED BELOW. THE TREE PROTECTION SHALL BE PLACED BEFORE ANY EXCAVATION OR GRADING IS BEGUN AND MAINTAINED FOR THE DURATION OF THE CONSTRUCTION WORK. PROTECTION WILL ENCOMPASS THE ROOT PROTECTION ZONE WHICH WILL BE AT MINIMUM ONE FOOT (1.0') RADIUS PER INCH DIAMETER OF THE TREE TRUNK AT 4.5' ABOVE GROUND. NO MATERIAL SHALL BE STORED OR CONSTRUCTION OPERATION SHALL BE CARRIED ON WITHIN THE TREE PROTECTION FENCING, UNLESS AUTHORIZED BY THE OWNER. THE PROTECTION SHALL REMAIN UNTIL ALL WORK IS COMPLETED.

- 3. NO CONSTRUCTION ACTIVITIES SHALL BE PERFORMED WITHIN 5' FROM THE TRUNK OF A TREE THAT IS PROTECTED. TRENCH SHORING WILL BE REQUIRED INSIDE OF A ROOT PROTECTION ZONE. THE ROOT PROTECTION ZONE IS CALCULATED AS A RADIUS FROM THE TREE TRUNK EQUAL TO ONE FOOT PER DIAMETER INCH OF THE TREE.
- 4. THIS PROJECT IS SUBJECT TO REGULATIONS ESTABLISHED BY THE CITY OF SAN ANTONIO TREE ORDINANCE.

#### STORM WATER PROTECTION AND EROSION CONTROL NOTES

- 1. CONTRACTOR SHALL INSTALL STORM WATER POLLUTION PREVENTION STRUCTURES INCLUDING BUT NOT LIMITED TO, SILT FENCING AND/OR ROCK BERMS IN ALL AREA TO BE IMPACTED BY CURRENT AND ONGOING CONSTRUCTION AND MAINTAIN SUCH STRUCTURES UNTIL SUITABLE GROUNDCOVER/REVEGETATION IS ACCEPTED. ALL STORM WATER POLLUTION PREVENTION STRUCTURES SHALL BE CONSTRUCTED WITHIN THE WATER LINE EASEMENTS. ANY FEATURES SHOWN OUTSIDE THESE AREAS ARE SHOWN FOR VISUAL CLARITY ONLY.
- 2. THE LOCATION OF ANY BEST MANAGEMENT PRACTICES (B.M.P.'S) SUCH AS SILT FENCING, ROCK BERMS, STABILIZED CONSTRUCTION ENTRANCE/EXIT, ETC. THAT MAY BE SHOWN ON THESE PLANS ARE SUBJECT TO FIELD VERIFICATION. CONTRACTOR SHALL ADJUST THE LOCATIONS OF B.M.P.'S TO BEST ACCOMMODATE THE CONDITIONS AND TOPOGRAPHY ENCOUNTERED DURING CONSTRUCTION. QUESTIONS REGARDING THE PLACEMENT AND/OR CHANGES CONCERNING B.M.P.'S SHALL BE REFERRED TO THE OWNER AND THE COUNTY. THE CONTRACTOR IS TO ENSURE THAT SEDIMENTATION AND EROSION WILL BE CONTAINED WITHIN THE PROJECT WORK AREAS AND KEPT OFF ROADWAYS AND ADJACENT PROPERTIES AND OUT OF DRAINAGE CHANNELS AND WATER COURSES.

#### **CPS ENERGY NOTES**

1. CONTRACTOR TO EXERCISE EXTREME CAUTION WHEN WORKING UNDER "HIGH VOLTAGE TRANSMISSION LINES". A WORKING HEIGHT OF 30' FROM GROUND ELEVATION WILL BE OBSERVED WHEN WORKING UNDER THE HIGH VOLTAGE LINE. COORDINATE ALL WORK WITH CPS ENERGY.

#### BEXAR COUNTY FLOODPLAIN GENERAL CONSTRUCTION NOTE

- 1. CONTRACTOR IS TO MAINTAIN UNRESTRICTED DRAINAGE OF THE PROJECT SITE AND ADJACENT AREAS DURING CONSTRUCTION.
- 2. NO CONSTRUCTION AND/OR WASTE MATERIAL SHALL BE PLACED IN EXISTING LOWS THAT WILL BLOCK OR ALTER FLOW LIMITS OF EXISTING NATURAL DRAINAGE OR PLACED WITHIN THE LIMITS OF EXISTING FLOODPLAIN.


#### TXDOT GENERAL CONSTRUCTION NOTES

- 1. WITHIN TXDOT ROW, THE CONTRACTOR SHALL ADHERE TO THE TXDOT UTILITY PERMIT AND SPECIAL CONDITIONS. CONTRACTOR SHALL NOTIFY SAWS 60 DAYS PRIOR TO WORK IN TXDOT ROW.
- 2. ANY DAMAGE TO EXISTING IMPROVEMENTS WITHIN THE TXDOT ROW CAUSED BY THE CONTRACTOR SHALL BE REPLACED TO ORIGINAL OR BETTER CONDITION (AT NO ADDITIONAL COST TO SAWS OR TXDOT) PER TXDOT SPECIFICATIONS.

OVERALL QUANTITY TABLE					
ITEM NO	ITEM DESCRIPTION	UNIT	QUANTITY		
502.1	BARRICADES, SIGNS AND TRAFFIC HANDLING (TXDOT SPEC)	LS	1		
540	SWPPP	LS	1		
550	TRENCH EXCAVATION PROTECTION	LF	1813		
848	21" PVC SANITARY SEWER MAIN (OPEN CUT) (5'-10' DEPTH)	LF	1813		
852	REMOVE EXISTING MANHOLE AND REPLACE WITH 6' DIAMETER FRP MANHOLE, MITER WITH STANDARD WATERTIGHT RING AND COVER	EA	2		
852	4' DIAMETER VENTED FRP MANHOLE WITH STANDARD WATERTIGHT RING AND COVER	EA	1		
852	4' DIAMETER FRP MANHOLE, MITER WITH STANDARD WATERTIGHT RING AND COVER	EA	1		
852	4' DIAMETER FRP DROP MANHOLE, MITER WITH STANDARD WATERTIGHT RING AND COVER	EA	1		
852	4' DIAMETER FRP MANHOLE WITH STANDARD WATERTIGHT RING AND COVER	EA	1		
858	CONCRETE ENCASEMENT	CY	20		
862	ABANDONMENT OF SANITARY SEWER MAINS (OVER 15")	LF	1808		
862	ABANDONMENT OF SANITARY SEWER MANHOLES	EA	5		
864	BYPASS PUMPING LARGE DIAMETER SANITARY SEWER MAINS	LS	1		
865	BYPASS PUMPING SMALL DIAMETER SANITARY SEWER MAINS	LS	1		
866	SEWER MAIN TV INSPECTION, POST (ALL SIZES)	LF	1,813		
100	MOBILIZATION (MAX 10% OF ITEMS 1-14)	LS	1		
101	PREPARATION OF RIGHT-OF-WAY (MAX 5% OF ITEMS 1-14)	LS	1		

UPPER MEDINA - SOUTH SEWERSHED - DOS RIOS/LEON CREEK

Address: 211 N. LOOP 1604	E, SUITE 175	
City: SAN ANTONIO	State: TEXAS	ZIP <u>: 78232</u>
Phone# <u>(210)</u> 957-3395	FAX <u>#_N/A</u>	
SAWS Block Map# 080560, 0	080562	Total Acreage_1.4
Total Linear Footage of Pipe	1,785 LF ~ 21" PVC SEWER	Plat No. <u>N</u>



JASON T. DIAMOND

96532

96532

CENS
ONAL

0006:94

PAPE-DAWSO

ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #

ANCH NORTH SEWER UPSI BEXAR COUNTY, TEXAS

BRIG

PLAT NO.


JOB NO. 12719-07

DATE JANUARY 2024

DESIGNER CD

CHECKED MP DRAWN RJ

SHEET



FROM MANHOLE	TO MANHOLE	SIZE OF PIPE (INCH)	LENGTH OF PIPE (LF
453910	453882	15	59
453882	453883	15	250
453883	453884	15	501
453884	453885	15	501
453885	453886	15	355
453886	453887	15	142


	EXISTING MANHOLES TO BE ABANDONED		
	453882		
453883			
453884			
	453885		
	453886		
	REMOVE RING AND COVER, CUT AND PLUG ALL SIDES IN ACCORDANCE WITH SAWS SPECIFICATION 862		

#### SEWER ABANDONMENT NOTES

- 1. LINES 15" OR GREATER IN DIAMETER AND INDICATED AS "ABANDONED" SHALL BE FILLED WITH GROUT FOR THE ENTIRE LENGTH OF THE PIPE IN ACCORDANCE WITH SAWS SPECIFICATION NO. 862.
- 2. GROUT SHALL CONFORM TO SAWS SPECIFICATION ITEM NO. 862. THE GROUT MIX DESIGN SHALL BE SUBMITTED BY THE CONTRACTOR TO THE ENGINEER FOR REVIEW.
- 3. MANHOLES SHOWN PROPOSED FOR ABANDONMENT SHALL BE REMOVED TO A MINIMUM OF 2 FEET BELOW GRADE AND BACKFILLED IN ACCORDANCE WITH SAWS SPECIFICATION NO. 862.
- 4. ABANDONING OF SANITARY SEWER LINES AND MANHOLES SHALL NOT OCCUR UNTIL ALL EXISTING SANITARY SEWER SERVICES HAVE BEEN TRANSFERRED TO PROPOSED LINE AS DIRECTED BY THE INSPECTOR.


#### EXISTING LINES ABANDONMENT NOTES

 ALL EXISTING SANITARY SEWER LINES TO BE ABANDONED MUST BE CCTV INSPECTED PRIOR TO GROUTING FOR POSSIBLE, EXISTING UNKNOWN SERVICE LATERAL(S). ALL SERVICE LATERALS MUST BE TIED TO NEW LINES PRIOR TO ABANDONMENT. CONTRACTOR SHALL NOTIFY SAWS IMMEDIATELY IF UNKNOWN ACTIVE LATERAL CONNECTIONS ARE ENCOUNTERED.









#### **LEGEND**

16' PERMANENT SEWER EASEMENT-(VOL. 12521, PG. 593 O.P.R.)

MERIDIAN AT BLUE SKIES HOMEOWNERS ASSOCIATION INC 3.9541 ACRES (DOC ID NO. 20210259047)

REMOVE AND REPLACE -

MANHOLE ID 453887

(SAWS JOB NO. 06-1777)

ABANDON EXISTING SANITARY -

SEWER MANHOLE ID 453886

(SAWS JOB NO. 06-1777) REMOVE RING AND COVER

ABANDON ±143 LF EXISTING 15" —
PVC SANITARY SEWER MAIN

(SAWS JOB NO. 06-1777)

<u> </u>	PROPOSED SANITARY SEWER
21"SS 21"SS	EXISTING SANITARY SEWER
	PERMANENT SEWER EASEMENT
	TEMPORARY CONSTRUCTION EASEMENT
	EXISTING MINOR CONTOUR
	EXISTING MAJOR CONTOUR
- $ -$	100 YR FLOODPLAIN LIMITS
	PARCEL BOUNDARY
	SANITARY SEWER ABANDONMENT

	QUANTITY TABLE		
ITEM	DESCRIPTION	UNIT	QTY
862	ABANDONMENT OF SANITARY SEWER MAINS (OVER 15")	LF	1,808
862	ABANDONMENT OF SANITARY SEWER MANHOLES	EA	5

**UPSI** SEWEI , TEXAS


RANCH NORTH BEXAR COUNTY RIG

UPPER I

GGS RANCH NORTH SEWER UPSIZING	1
eveloper's Name: <u>CHESMAR HOMES</u> ddress: 211 N. LOOP 1604 E, SUITE 175	
ity: <u>SAN ANTONIO</u> State <u>: TEXAS</u> ZIP <u>: 78232</u>	
hone# <u>(210) 957-3395</u> FAX <u># N/A</u>	
AWS Block Map# 080560, 080562 Total Acreage 1.45	
otal Linear Footage of Pipe <u>1,785 LF ~ 21" PVC SEWER</u> Plat No. <u>N/A</u>	
umber of Lots N/A TOTAL EDU'S N/A SAWS JOB NO. 23-1643	

	$ \overline{\mathbf{a}} $
MEDINA - SOUTH SEWERSHED - DOS RIOS/LEON CREEK	
er's Name: CHESMAR HOMES	PLAT NO.
State: TEXAS ZIP: 78232	JOB NO. 12719-07
(210) 957-3395 FAX# N/A  Block Map# 080560, 080562 Total Acreage 1.45	DATE JANUARY 2024  DESIGNER CD
near Footage of Pipe <u>1,785 LF ~ 21" PVC SEWER</u> Plat No <u>.N/A</u>	CHECKED MP DRAWN RJ
of Lots N/A TOTAL EDU'S N/A SAWS JOB NO. 23-1643	SHEET <b>C2.30</b>

EXISTING MANHOLES TO BE ABANDONED				
453882				
453883 453884 453885 453886				
				REMOVE RING AND COVER, CUT AND PLUG ALL SIDES IN ACCORDANCE WITH SAWS SPECIFICATION 862



MAIN (SAWS JOB NO. DJ-1106) — ABANDON ±250 LF EXISTING 15" PVC SANITARY SEWER MAIN

(SAWS JOB NO. 06-1777) 16' PERMANENT SEWER EASEMENT — (VOL. 12521, PG. 593 O.P.R.) - ABANDON EXISTING SANITARY SEWER MANHOLE ID 453882 (SAWS JOB NO. 06-1777) REMOVE RING AND COVER

- ABANDON EXISTING SANITARY SEWER MANHOLE ID 453884

(SAWS JOB NO. 06-1777) REMOVE RING AND COVER

8' PERMANENT SEWER EASEMENT (DOC ID NO. 20230154380)

ABANDON ±354 LF EXISTING 15" —

PVC SANITARY SEWER MAIN

(SAWS JOB NO. 06-1777)

REMAINING PORTION OF A CALLED 304.044 ACRE TRACT AIR FORCE VILLAGE II (VOL. 6179, PG. 967 OPR)

HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.

100% SUBMITTAL

PROPOSED MH-A3

EXISTING SANITARY SEWER

- 1. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT NO SANITARY SEWER OVERFLOW (SSO) OCCURS AS A RESULT OF THEIR WORK. ALL CONTRACTOR PERSONNEL RESPONSIBLE FOR SSO PREVENTION AND CONTROL SHALL BE TRAINED ON PROPER RESPONSE. SHOULD AN SSO OCCUR, THE
- A. IDENTIFY THE SOURCE OF THE SSO AND NOTIFY SAWS EMERGENCY OPERATIONS CENTER (EOC) IMMEDIATELY AT 210-704-SAWS (210-704-7297). PROVIDE THE ADDRESS OF THE SPILL AND AN ESTIMATED VOLUME OR FLOW.
- B. ATTEMPT TO ELIMINATE THE SOURCE OF THE SSO. C. CONTAIN SEWAGE FROM THE SSO TO THE EXTENT OF PREVENTING A POSSIBLE CONTAMINATION OF
- WATERWAYS. D. CLEAN UP SPILL SITE (RETURN CONTAINED SEWAGE TO THE COLLECTION SYSTEM IF POSSIBLE) AND PROPERLY DISPOSE OF CONTAMINATED SOIL/MATERIALS. E. CLEAN THE AFFECTED SEWER MAINS AND REMOVE ANY DEBRIS.
- F. MEET ALL POST-SSO REQUIREMENTS AS PER THE EPA CONSENT DECREE, INCLUDING LINE CLEANING AND TELEVISING THE AFFECTED SEWER MAINS (AT SAWS DIRECTION) WITHIN 24 HOURS.
- SHOULD THE CONTRACTOR FAIL TO ADDRESS AN SSO IMMEDIATELY AND TO SAWS SATISFACTION, THEY WILL BE RESPONSIBLE FOR ALL COSTS INCURRED BY SAWS, INCLUDING ANY FINES FROM EPA.
- NO SEPARATE MEASUREMENT OR PAYMENT SHALL BE MADE FOR THIS WORK. ALL WORK SHALL BE DONE ACCORDING TO GUIDELINE SET BY THE TCEQ AND SAWS.
- 2. THE CONTRACTOR SHALL PROVIDE BYPASS PUMPING AND FLOW MANAGEMENT AS NECESSARY OF SEWAGE AROUND EACH SEGMENT OF PIPE TO BE REPLACED IN ACCORDANCE WITH SAWS STANDARD
- 3. THE BYPASS PUMPING PLAN SHOWN ON THE DRAWING IS ONLY SUGGESTED FOR THE CONTRACTOR'S CONSIDERATION. CONTRACTOR SHALL SUBMIT BYPASS AND PHASING PLAN IN ACCORDANCE WITH SAWS STANDARD SPECIFICATIONS 864 & 865 TO SAWS FOR REVIEW AND APPROVAL PRIOR TO COMMENCEMENT OF THE CONSTRUCTION.
- 4. SEWER WORK AND CLEAN UP SHALL BE IN ACCORDANCE WITH GUIDELINES SET FORTH BY TCEQ AND SAWS. CONTRACTOR SHALL IDENTIFY AND TRAIN PERSONNEL RESPONSIBLE FOR SPILLAGE PREVENTION AND CONTROL. CONTRACTOR SHALL DOCUMENT AND EDUCATE EMPLOYEES IN ADVANCE OF WORK ABOUT THE WORK ENVIRONMENT INCLUDING WHAT TO DO WHEN THERE ARE SEWER LEAKS AND HOW TO WORK SAFELY AROUND RAW SEWAGE.
- 5. ANY SMART COVERS AND/OR FLOW METERS PRESENT NEED TO BE REMOVED BY SAWS PRIOR TO CONSTRUCTION TO AVOID DAMAGE TO EQUIPMENT.
- 6. BYPASS PIPE ALIGNMENTS SHOWN HEREIN ARE FOR GENERAL ALIGNMENT ROUTING ONLY. THE CONTRACTOR SHALL INSTALL ALL BYPASS PIPING DURING CONSTRUCTION WITHIN EXISTING OR PROPOSED SANITARY SEWER EASEMENTS OR PUBLIC RIGHT OF WAY.
- 7. ANY ADDITIONAL STRUCTURES OR MANHOLES (DOGHOUSE, TEMPORARY, OR PERMANENT) REQUIRED TO INSTALL THE CONTRACTOR'S DESIGNED BYPASS PUMPING PLAN SHOULD BE INCLUDED IN THE BID PRICE FOR THE BYPASS PUMPING.

BRIGGS RANCH NORTH SEWER UPSIZING ESTIMATED FLOWS					
US MH	DS MH	DIA. (IN)	ESTIMATED DESIGN FLOW (GPM)		
1189048	453887	8	344*		
453888	453887	15	1839*		
453882	453910	15	2183*		
75872	453910	27	10146*		
*ESTIMATED DESIGN FLOW (FULL FLOW CAPACITY OF EXISTING PIPE) WAS CALCULATED AT					

MANHOLES WHERE FLOW DATA WAS NOT AVAILABLE. PER THE SAWS SPECIFICATIONS 864 & 865 THE CONTRACTOR IS RESPONSIBLE TO CONFIRM THE DESIGN FLOWS AND DESIGN A BYPASS PUMPING ACCORDINGLY.

PROPOSED 21" PVC SANITARY SEWER

#### SUGGESTED CONSTRUCTION SEQUENCING

- PHASE 1: INSTALL SANITARY SEWER MAIN

  1. MOBILIZE AND PREPARE SITE

  2. INSTALL SANITARY SEWER MAIN FROM MH-A2 TO MH-A5 TEST MANHOLES AND PIPELINE

#### PHASE 2: REMOVE AND REPLACE MANHOLE ID 453910 1. MOBILIZE AND PREPARE SITE WITHIN TXDOT ROW

- 2. SET UP BYPASS #1 PER CONTRACTOR'S SUBMITTED AND APPROVED
- BYPASS PUMPING"PLAN 3. INSTALL PLUG ON INCOMING 27" LINE DJ-1106 AT EXISTING MH 75872 4. INSTALL PLUG ON INCOMING 15" LINE 06-1777 AT EXISTING MH 453882
- 5. REMOVE EXISTING MANHOLE ID 453910, REPLACE WITH MH-A1, INSTALL SANITARY SEWER FROM MH-A1 TO MH-A2, INSTALL MH-A2
- 6. TEST MANHOLES AND PIPELINE 7. INTRODUCE FLOWS FROM EXISTING 27" PVC SANITARY SEWER MAIN (SAWS JOB NO. DJ-1106) TO MH-A1

#### PHASE 3: REMOVE AND REPLACE MANHOLE ID 453887 1. MOBILIZE AND PREPARE SITE

- 2. SET UP BYPASS #2 PER CONTRACTOR'S SUBMITTED AND APPROVED
- BYPASS PUMPING"PLAN 3. INSTALL PLUG ON INCOMING 15" LINE 06-1777 AT EXISTING MH 453912
- 4. INSTALL PLUG ON INCOMING 8" LINE 19-1541 AT EXISTING MH 1189048 5. REMOVE EXISTING MANHOLE ID 453887, REPLACE WITH MH-A6, INSTALL SANITARY SEWER MAIN FROM MH-A5 TO MH-A6
- TEST MANHOLES AND PIPELINE INTRODUCE FLOWS TO INSTALLED SANITARY SEWER MAIN

#### PHASE 4: ABANDON EXISTING SEWER MAIN

- 1. CONTRACTOR TO CCTV (PRE-ABANDONMENT) THE EXISTING 15" SANITARY SEWER MAIN (SAWS JOB NO. 06-1777) TO VERIFY ALL CONNECTIONS HAVE BEEN ACCOUNTED FOR
- 2. CONTRACTOR TO ABANDON EXISTING 15" SANITARY SEWER MAIN (SAWS JOB NO. 06-1777) PER SAWS SPEC 862: ABANDONMENT OF SANITARY SEWER MAINS (OVER 15")

SUGGESTED BYPASS SETUP 2

(UPSTREAM TIE IN)

REMAINING PORTION OF A CALLED 331.9 ACRE TRACT CONVERGENCE BRASS, LLC (VOL. 17108, PG. 282 OPR)

EXISTING SANITARY SEWER MANHOLE ID 453885


REMAINING PORTION OF A CALLED 304.044 ACRE TRACT AIR FORCE VILLAGE II (VOL. 6179, PG. 967 OPR)

EXISTING 15" PVC SANITARY SEWER-

MAIN (SAWS JOB NO. 06-1777

#### SUGGESTED BYPASS SETUP 1

(DOWNSTREAM TIE IN)



EXISTING 15" PVC SANITARY SEWER MAIN (SAWS JOB NO. 06-1777

PROPOSED MH-A5

EXISTING SANITARY SEWER MANHOLE ID 453887 BE REMOVED AND REPLACED)

EXISTING 8" PVC SANITARY SEWER MAIN (SAWS JOB NO. 19-1541)

> EXISTING SANITARY SEWER MANHOLE ID 1189048

EXISTING SANITARY SEWER

MANHOLE ID 453886

PROPOSED MH-A4

16' PERMANENT SEWER EASEMENT (VOL. 12521, PG. 593 O.P.R.)

EXISTING SANITARY SEWER
MANHOLE ID 453888


PROPOSED MH-A6


# **BEXAR** COUNTY **LOCATION MAP**

NOT-TO-SCALE


JASON T. DIAMON







	QUANTITY TABLE		
ITEM	DESCRIPTION	UNIT	QTY
864	BYPASS PUMPING LARGE DIAMETER SANITARY SEWER MAINS	LS	1
865	BYPASS PUMPING SMALL DIAMETER SANITARY SEWER MAINS	LS	1



PROPOSED SANITARY SEWER
EXISTING SANITARY SEWER
PERMANENT SEWER EASEMENT
TEMPORARY CONSTRUCTION EASEM
EXISTING MINOR CONTOUR
EXISTING MAJOR CONTOUR
100 YR FLOODPLAIN LIMITS
PROPOSED BYPASS LINE
PROPOSED SANITARY SEWER WORK
FUTURE R.O.W.
EXIST R.O.W.
EXIST PARCEL BOUNDARY

	QUANTITY TABLE		
ITEM	DESCRIPTION	UNIT	QTY
864	BYPASS PUMPING LARGE DIAMETER SANITARY SEWER MAINS	LS	1
865	BYPASS PUMPING SMALL DIAMETER SANITARY SEWER MAINS	LS	1

## UPPER MEDINA - SOUTH SEWERSHED - DOS RIOS/LEON CREEK

Developer's Name: <u>CHESMAR</u>		
Address: 211 N. LOOP 1604	4 E, SUITE 175	
City: SAN ANTONIO	State: TEXAS	ZIP <u>: 78232</u>
Phone# <u>(210) 957-3395</u>	FAX <u>#_N/</u>	'A
SAWS Block Map <u># 080560, (</u>	080562	Total Acreage_1.45
Total Linear Footage of Pipe	e 1,785 LF ~ 21" PVC SEWER	Plat No. <u>N</u> ,

30' TEMPORARY CONSTRUCTION EASEMENT (DOC ID NO. 20230154380

B' PERMANENT SEWER EASEMENT

(DOC ID NO. 20230154380)


100% SUBMITTAL

BRIG

ESIGNER

OB NO. 12719-07


HECKED<u>MP</u> DRAWN<u>R</u>




SANITARY SEWER LINE "A"

STA. 1+00.00 TO 10+00.00


VERTICAL SCALE: 1" = 5'
HORIZONTAL SCALE: 1" = 50'











#### <u>LEGEND</u>

<b>──</b> \$\$	PROPOSED SANITARY SEWER
21"SS 21"SS	EXISTING SANITARY SEWER
	PERMANENT SEWER EASEMENT
	TEMPORARY CONSTRUCTION EASEMENT
	EXISTING MINOR CONTOUR
	EXISTING MAJOR CONTOUR
- $ -$	100 YR FLOODPLAIN LIMITS
	PARCEL BOUNDARY

	QUANTITY TABLE		
ITEM	DESCRIPTION	UNIT	QTY
550	TRENCH EXCAVATION PROTECTION	LF	900
848	21" PVC SANITARY SEWER MAIN (OPEN CUT) (5'-10' DEPTH)	LF	900
852	REMOVE EXISTING MANHOLE AND REPLACE WITH 4' DIAMETER FRP MANHOLE, MITER WITH STANDARD WATERTIGHT RING AND COVER	EA	1
852	4' DIAMETER FRP MANHOLE, MITER WITH STANDARD WATERTIGHT RING AND COVER	EA	1
852	4' DIAMETER VENTED FRP MANHOLE WITH STANDARD WATERTIGHT RING AND COVER	EA	1
858	CONCRETE ENCASEMENT	CY	10
866	SEWER MAIN TV INSPECTION, POST (ALL SIZES)	LF	900

#### **CONTRACTOR NOTE**

EXISTING 15" SEWER MAIN (SAWS JOB NO. 06-1777) SHOULD REMAIN IN SERVICE DURING CONSTRUCTION OF THE NEW 21" SEWER MAIN. THE ABANDONMENT OF THE EXISTING 15" SEWER MAIN (SAWS JOB NO. 06-1777) SHOULD NOT OCCUR UNTIL IT IS VERIFIED THAT ALL FLOWS HAVE BEEN TRANSFERRED TO THE NEW MAIN.

UPPER MEDINA - SOUTH SEWERSHED - DOS RIOS/LEON CREEK BRIGGS RANCH NORTH SEWER UPSIZING

veloper's Name: <u>CHESMAR HOMES</u>				
ddress: 211 N. LOOP 1604 E, SUITE 175				
ty: SAN ANTONIO State: TEXAS	ZIP <u>: 78232</u>			
none# <u>(210) 957–3395</u> FAX <u># N/A</u>				
NWS Block Map#_080560, 080562	Total Acreage <u>1.45</u>			
tal Linear Footage of Pipe 1,785 LF ~ 21" PVC SEWER	Plat No. <u>N/A</u>			
umber of Lots N/A TOTAL EDU'S N/A SAWS	JOB NO. <u>23–1643</u>			

PLAT NO.

JOB NO. 12719-07

DATE JANUARY 2024

DESIGNER CD

CHECKED MP DRAWN RJ


SHEET C3.00


ANITARY SEWER LINE PLAN AND STA. 1+00 TO STA. 10+00

ANCH NORTH BEXAR COUNTY


BRIGG

JASON T. DIAMON






THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.









#### <u>LEGEND</u>

<b>──</b> \$\$	PROPOSED SANITARY SEWER
21"SS 21"SS	EXISTING SANITARY SEWER
	PERMANENT SEWER EASEMENT
	TEMPORARY CONSTRUCTION EASEMENT
	EXISTING MINOR CONTOUR
	EXISTING MAJOR CONTOUR
- $ -$	100 YR FLOODPLAIN LIMITS
	PARCEL BOUNDARY

	QUANTITY TABLE			
ITEM	DESCRIPTION	UNIT	QTY	
550	TRENCH EXCAVATION PROTECTION	LF	913	
848	21" PVC SANITARY SEWER MAIN (OPEN CUT) (5'-10' DEPTH)	LF	913	
852	REMOVE EXISTING MANHOLE AND REPLACE WITH 4' DIAMETER FRP MANHOLE, MITER WITH STANDARD WATERTIGHT RING AND COVER	EA	1	
852	4' DIAMETER FRP DROP MANHOLE, MITER WITH STANDARD WATERTIGHT RING AND COVER	EA	1	
852	4' DIAMETER FRP MANHOLE WITH STANDARD WATERTIGHT RING AND COVER	EA	1	
858	CONCRETE ENCASEMENT	CY	10	
866	SEWER MAIN TV INSPECTION, POST (ALL SIZES)	LF	913	

# BRIGGS RANCH NORTH BEXAR COUNTY,

SIZING

SEWER , TEXAS

UPPER MEDINA - SOUTH SEWERSHED - DOS RIOS/LEON CREEK BRIGGS RANCH NORTH SEWER UPSIZING

RIGGS RANCH NORTH SEWER C	JI SIZINO	
Developer's Name: <u>CHESMAR HOME</u>	5	
Address: 211 N. LOOP 1604 E, SU	ITE 175	
City: SAN ANTONIO	State: TEXAS	ZIP: 78232
Phone# <u>(210)</u> 957-3395	FAX <u>#_N/A</u>	
SAWS Block Map <u># 080560, 080562</u>		Total Acreage <u>1.45</u>
Total Linear Footage of Pipe <u>1,785</u>	LF ~ 21" PVC SEWER	Plat No. <u>N/A</u>
Number of Lots <u>N/A</u> TOTAL	EDU'S <u>N/A</u> SAWS	JOB NO. <u>23–1643</u>

PLAT NO.

JOB NO. 12719-07


DATE JANUARY 2024


DESIGNER CD


CHECKED MP DRAWN RJ

SHEET C3.01

ANITARY SEWER LINE PLAN AND PROFIL STA. 10+00 TO STA. 19+12.61













RANCH NORTH SEWER
BEXAR COUNTY, TEXAS

BRIG










#### TREE PRESERVATION GENERAL NOTES


- 1. ALL TREES SHALL REMAIN UNLESS NOTED ON THE CITY OF SAN ANTONIO APPROVED PLANS.
- 2. NO UTILITY EXCAVATION WORK SHALL BEGIN IN AREAS WHERE TREE PRESERVATION AND TREATMENT MEASURES HAVE NOT BEEN COMPLETED AND APPROVED.
- 3. THE CONTRACTOR SHALL AVOID CUTTING ROOTS LARGER THAN ONE INCH IN DIAMETER WHEN EXCAVATING NEAR EXISTING TREES. EXCAVATION IN VICINITY OF TREES SHALL PROCEED WITH CAUTION. THE CONTRACTOR SHALL CONTACT THE CITY INSPECTOR FOR GUIDANCE.
- 4. EXPOSED ROOTS SHALL BE COVERED AT THE END OF THE DAY USING TECHNIQUES SUCH AS COVERING WITH SOIL, MULCH OR WET BURLAP.
- 5. NO EQUIPMENT, VEHICLES OR MATERIALS SHALL OPERATE OR BE STORED WITHIN THE ROOT PROTECTION ZONE OF ANY TREE NEAR THE PROJECT. ROOT PROTECTION ZONE IS ONE FOOT RADIUS PER DIAMETER INCH OF THE TRUNK OF THE TREE. A TEN INCH TREE SHALL REQUIRE A TEN FOOT ROOT PROTECTION ZONE. ROOTS OR BRANCHES IN CONFLICT WITH THE CONSTRUCTION SHALL BE CUT CLEANLY ACCORDING TO PROPER PRUNING METHODS. ALL WOUNDS TO OAK TREES SHALL BE PAINTED WITHIN 20 MINUTES TO PREVENT THE SPREAD OF OAK WILT.
- 6. THE CITY ARBORIST, 207-0278, SHALL APPROVE ANY TREE REMOVED.
- 7. TREES, TREE LIMBS, BUSHES AND SHRUBS LOCATED IN THE PERMANENT EASEMENTS WHICH INTERFERE WITH PROPOSED CONSTRUCTION ACTIVITIES MAY BE NEATLY TRIMMED BY THE CONTRACTOR ONLY AFTER APPROVAL FROM THE CITY INSPECTOR.
- 8. TREES THAT ARE DAMAGED OR LOST DUE TO THE CONTRACTOR'S NEGLIGENCE DURING CONSTRUCTION SHALL BE MITIGATED TO THE CITY'S SATISFACTION.
- 9. SAPLINGS, SHRUBS OR BUSHES TO BE REMOVED FROM THE PROTECTED ROOT ZONE AREA OF PROTECTED TREES SHALL BE REMOVED BY HAND AS DESIGNATED BY THE INSPECTOR.
- 10. ALL DEBRIS GENERATED BY THE PRUNING OR TRIMMING OF THE TREES AND/OR BUSHES SHALL BECOME PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF PROPERLY.
- 11. TREES MUST BE MAINTAINED IN GOOD HEALTH THROUGHOUT THE CONSTRUCTION PROCESS. MAINTENANCE MAY INCLUDE WATERING THE ROOT PROTECTION ZONE AND/OR WASHING FOLIAGE.
- 12. NO WIRES, NAILS OR OTHER MATERIALS MAY BE ATTACHED TO PROTECTED TREES.
- 13. PRIOR TO START OF WORK, CALL 207-1111 TO SCHEDULE A PRE-CONSTRUCTION & FENCING INSPECTION (PER SECTION 35-477 OF THE UDC, SUBSECTION TREE PERMITS (5)(C)).
- 14. FAILURE TO SCHEDULE A FENCING INSPECTION PRIOR TO START OF WORK MAY RESULT IN A STOP WORK ORDER OR A PENALTY OF \$2,000 OR BOTH (PER SECTION 35-523 OF THE UDC, SUBSECTION (K)(2), THE BARRIER SHALL BE IN PLACE BEFORE ANY SITE WORK IS INITIATED AND MAINTAINED THROUGHOUT THE CONSTRUCTION PROCESS).
- 15. TREE PLANTING AND MAINTENANCE: ALL PRESERVED AND PLANTED TREES SHALL BE MAINTAINED IN A HEALTHY CONDITION AT ALL TIMES. THIS INCLUDES IRRIGATING, FERTILIZING, PRUNING, AND OTHER MAINTENANCE AS NEEDED. TREES THAT DIE WITHIN TWELVE MONTHS SHALL BE REPLACED WITH A TREE OF COMPARABLE SIZE AND SPECIES. REGUARDING REPLACEMENT OF PRESERVED TREES, SIGNIFICANT TREES SHALL BE REPLACED WITH A 1:1 RATIO (OR INCH-FOR-INCH) AND HERITAGE TREES SHALL BE REPLACED AT A 3:1 RATIO (OR THREE-TO-ONE INCH).



#### TREE PRESERVATION NOTES

- 1. ALL TREES TO REMAIN ON SITE REQUIRE PROTECTIVE FENCING, PRUNING, WATERING, AND FERTILIZATION AS DIRECTED BY A QUALIFIED ARBORIST.
- 2. PROTECTIVE FENCING CONSISTS OF 4'-0" HIGH FENCE.
- 3. FENCE TO EXTEND FROM TRUNK ONE FOOT FOR EVERY CALIPER INCH OF TREE (MINIMUM). THE OPTIMUM DISTANCE IS TO INSTALL FENCE DIRECTLY BENEATH DRIPLINE OF TREE TO REMAIN AS SHOWN.
- 4. DURING CONSTRUCTION, NO EXCESS SOIL, FILL MATERIAL, EQUIPMENT, LIQUIDS, OR CONSTRUCTION DEBRIS SHALL BE PLACED WITHIN THE PROTECTIVE FENCING, NOR SHALL ANY SOIL BE REMOVED FROM WITHIN THE FENCING.
- 5. ALL TREE PROTECTION MUST BE IN PLACE BEFORE CONSTRUCTION
- 6. INSTALL 4" MINIMUM DEPTH OF SHREDDED MULCH BENEATH THE DRIPLINE OF THE TREE.

#### TREE PROTECTION DETAIL **EXISTING TREES**




NOTE: DO NOT CUT FROM D TO E


- A. FIRST CUT TO PREVENT THE BARK FROM BEING PEELED WHEN THE BRANCH FALLS.
- B. <u>SECOND CUT</u> TO REDUCE THE WEIGHT OF BRANCH.
- C. <u>FINAL CUT</u> ALLOW FOR HEALING COLLAR BUT NO
- D. <u>BRANCH RIDGES</u> INDENT PROPERLY BRANCH RIDGES WHICH ARE SITE FOR DECAY.
- FOR OAKS ONLY: PAINT ALL WOUNDS OR CUTS WITH PRUNING PAINT WITHIN 20 MIN. TO PREVENT THE SPREAD OF OAK WILT.


#### TREE PRUNING DETAIL


#### TREE PLAN NOTE

PLEASE REFERENCE MASTER TREE PLAN TRE-APP-APP22-38802001 FOR TOTAL TREE CANOPY REMOVAL AND PRESERVATION PROPOSED WITH BRIGGS RANCH NORTH DEVELOPMENT. SEWER UPSIZING PROJECT WILL BE MITIGATED UNDER MASTER TREE PLAN TRE-APP-APP22-38802001.









PLAT NO.

DESIGNER

JOB NO. 12719-07


CHECKED MP DRAWN RU

JANUARY 2024


C6.00

LIDDER MEDINA SOLITH SEWERSHED DOS BIOS/LEON CREEK


BRIGGS RANCH NORTH SEWER		THOS/LLON CHLLK
Developer's Name: <u>CHESMAR HOM</u> Address: 211 N. LOOP 1604 E, S		
	State: TEXAS	ZIP <u>: 78232</u>
Phone# <u>(210)</u> 957-3395	FAX <u>#_N/A</u>	
SAWS Block Map# <u>080560, 08056</u>	52	Total Acreage <u>1.45</u>
Total Linear Footage of Pipe 1,78	85 LF ~ 21" PVC SEWER	Plat No. <u>N/A</u>
Number of Lots N/A TOT	FAL EDU'S <u>N/A</u> SAWS	S JOB NO. <u>23–1643</u>



HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.



NOT-TO-SCALE



#### **SWPPP LEGEND**

PROJECT LIMITS EXISTING CONTOUR PROPOSED CONTOUR FLOW ARROW (EXISTING) FLOW ARROW (PROPOSED) SILT FENCE **\*\*\*** GRAVEL FILTER BAGS GRATE INLET PROTECTION SEDIMENT CONTROL ROLLS LIMITS OF DISTURBED AREA AQUATIC FEATURE

**GENERAL NOTES** 

1. DO NOT DISTURB VEGETATED AREAS (TREES, GRASS, WEEDS, BRUSH, ETC.) ANY MORE THAN NECESSARY FOR CONSTRUCTION.

2. CONSTRUCTION ENTRANCE/EXIT LOCATION, CONCRETE WASH-OUT PI AND CONSTRUCTION EQUIPMENT AND MATERIAL STORAGE YARD TO BE DETERMINED IN THE FIELD.

3. STORM WATER POLLUTION PREVENTION CONTROLS MAY NEED TO MODIFIED IN THE FIELD TO ACCOMPLISH THE DESIRED EFFECT. MODIFICATIONS ARE TO BE NOTED ON THIS EXHIBIT AND SIGNED AND DATED BY THE RESPONSIBLE PARTY.

4. RESTRICT ENTRY/EXIT TO THE PROJECT SITE TO DESIGNATED LOCATIONS BY USE OF ADEQUATE FENCING, IF NECESSARY. 5. ALL STORM WATER POLLUTION PREVENTION CONTROLS ARE TO BE

MAINTAINED AND IN WORKING CONDITIONS AT ALL TIMES. 6. FOR A COMPLETE LISTING OF TEMPORARY STORM WATER POLLUTION PREVENTION CONTROLS REFER TO THE TPDES STORM WATER POLLUTION PREVENTION PLAN.

7. STORM WATER POLLUTION PREVENTION STRUCTURES SHOULD CONSTRUCTED WITHIN THE SITE BOUNDARIES. SOME OF THESE FEATURES MAY BE SHOWN OUTSIDE THE SITE BOUNDARIES ON THIS PLAN FOR VISUAL

8. AS SOON AS PRACTICAL, ALL DISTURBED SOIL THAT WILL NOT BE COVERED BY IMPERVIOUS COVER SUCH AS PARKWAY AREAS, EASEMENT AREAS, EMBANKMENT SLOPES, ETC. WILL BE STABILIZED PER APPLICABLE PROJECT SPECIFICATIONS.

9. BEST MANAGEMENT PRACTICES MAY BE INSTALLED IN STAGES TO COINCIDE WITH THE DISTURBANCE OF UPGRADIENT AREAS. 10. BEST MANAGEMENT PRACTICES MAY BE REMOVED IN STAGES ONCE TH WATERSHED FOR THAT PORTION CONTROLLED BY THE BEST MANAGEMENT PRACTICES HAS BEEN STABILIZED IN ACCORDANCE WITH TPDES

11. UPON COMPLETION OF THE PROJECT, INCLUDING SITE STABILIZATION AND BEFORE FINAL PAYMENT IS ISSUED, CONTRACTOR SHALL REMOVE ALL SEDIMENT AND EROSION CONTROL MEASURES, PAYING SPECIAL ATTENTION TO ROCK BERMS IN DRAINAGE FEATURES.

12. WHERE VEGETATED FILTER STRIPS ARE INDICATED, CONTRACTOR SHAL VERIFY THAT SUFFICIENT VEGETATION EXISTS, OTHERWISE CONTRACTOR SHALL PLACE SILT FENCING IN LIEU OF VEGETATED FILTER STRIP.

13. SHADED AREA DENOTES LIMITS OF DISTURBED AREAS. OTHE AREAS WITHIN THE PROJECT LIMITS, WITH THE EXCEPTION OF CONSTRUCTION EQUIPMENT AND MATERIAL STORAGE YARD, ARE NOT PART OF THIS TPDES STORM WATER POLLUTION PREVENTION PLAN (SWP3) AND WILL NOT BE DISTURBED BY CIVIL CONSTRUCTION ACTIVITIES. HOUSÉ CONSTRUCTION ACTIVITIES WILL REQUIRE A SEPARATE STORM WATER POLLUTION PREVENTION PLAN.

14. PRIOR TO BEGINNING CONSTRUCTION, CONTRACTOR SHALL COORDINATE PLACEMENT OF TEMPORARY BEST MANAGEMENT PRACTICES WITHIN TXDOT RIGHT-OF-WAY WITH TXDOT.

15. CPS ENERGY WILL FUNCTION AS A SECONDARY OPERATOR ON TH PROJECT AND WILL BE INSTALLING ELECTRIC UTILITIES FOR ON-SITE CONSTRUCTION AND OFF-SITE FEED TO THE PROJECT.

THE ENGINEERING SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR TH PURPOSE OF DEMONSTRATING COMPLIANCE WITH THE TPDES-STORM WATER POLLUTION PREVENTION PLAN (SWP3) REGULATIONS.

THIS SHEET HAS BEEN PREPARED FOR PURPOSES OF THE SWP3 ONLY. ALL OTHER CIVIL ENGINEERING RELATED INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SHEET IN THE CIVIL IMPROVEMENT PLANS.

JOB NO. 12719-07 JANUARY 2024 ESIGNER

HECKED MP DRAWN RU

C7.00

CH EX

SCHEMATIC OF TEMPORARY CONSTRUCTION ENTRANCE/EXIT

#### **MATERIALS**

THE AGGREGATE SHOULD CONSIST OF 4-INCH TO 8-INCH WASHED STONE OVER A STABLE FOUNDATION AS SPECIFIED IN THE PLAN. 2. THE AGGREGATE SHOULD BE PLACED WITH A MINIMUM THICKNESS OF 8-INCHES.

3. THE GEOTEXTILE FABRIC SHOULD BE DESIGNED SPECIFICALLY FOR USE AS A SOIL FILTRATION MEDIA WITH AN APPROXIMATE WEIGHT OF 6 OZ/YD2, A MULLEN BURST RATING OF 140 LB/IN2, AND AN EQUIVALENT OPENING SIZE GREATER THAN A NUMBER 50 SIEVE.

4. IF A WASHING FACILITY IS REQUIRED, A LEVEL AREA WITH A MINIMUM OF 4-INCH DIAMETER WASHED STONE OR COMMERCIAL ROCK SHOULD BE INCLUDED IN THE PLANS. DIVERT WASTEWATER TO A SEDIMENT TRAP OF

DRAINAGE

 AVOID CURVES ON PUBLIC ROADS AND STEEP SLOPES. REMOVE VEGETATION AND OTHER OBJECTIONABLE MATERIAL FROM THE FOUNDATION AREA. GRADE CROWN FOUNDATION FOR POSITIVE DRAINAGE.

2. THE MINIMUM WIDTH OF THE ENTRANCE/EXIT SHOULD BE 12 FEET OR THE FULL WIDTH OF EXIT ROADWAY, WHICHEVER IS GREATER.

3. THE CONSTRUCTION ENTRANCE SHOULD BE AT LEAST 50 FEET LONG. THE SLOPE TOWARD THE ROAD EXCEEDS 2%, CONSTRUCT A RIDGE 6-INCHES TO 8-INCHES HIGH WITH 3:1 (H: V) SIDE SLOPES, ACROSS THE FOUNDATION APPROXIMATELY 15 FEET FROM THE ENTRANCE TO DIVERT RUNOFF AWAY FROM THE PUBLIC ROAD.

5. PLACE GEOTEXTILE FABRIC AND GRADE FOUNDATION TO IMPROVE STABILITY, ESPECIALLY WHERE WET CONDITIONS ARE ANTICIPATED.

6. PLACE STONE TO DIMENSIONS AND GRADE SHOWN ON PLANS. LEAVE SURFACE SMOOTH AND SLOPE FOR DRAINAGE.

7. DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM THE STONE PAD TO A SEDIMENT TRAP OR BASIN.

1. SOD SHOULD BE MACHINE CUT AT A UNIFORM SOIL THICKNESS OF 3/4" INCH

(± 1/4" INCH) AT THE TIME OF CUTTING. THIS THICKNESS SHOULD EXCLUDE

2. PIECES OF SOD SHOULD BE CUT TO THE SUPPLIER'S STANDARD WIDTH AND

LENGTH, WITH A MAXIMUM ALLOWABLE DEVIATION IN ANY DIMENSION OF 5%.

3. STANDARD SIZE SECTIONS OF SOD SHOULD BE STRONG ENOUGH TO SUPPORT THEIR OWN WEIGHT AND RETAIN THEIR SIZE AND SHAPE WHEN

4. SOD SHOULD BE HARVESTED, DELIVERED, AND INSTALLED WITHIN A PERIOD

PRIOR TO SOIL PREPARATION, AREAS TO BE SODDED SHOULD BE BROUGHT

THE SURFACE SHOULD BE CLEARED OF ALL TRASH, DEBRIS AND OF ALL

FERTILIZE ACCORDING TO SOIL TESTS. FERTILIZER NEEDS CAN BE

DETERMINED BY A SOIL TESTING LABORATORY OR REGIONAL RECOMMENDATIONS

SPRINGTOOTH HARROW OR OTHER SUITABLE EQUIPMENT. ON SLOPING LAND, THE

SOD STRIPS IN WATERWAYS SHOULD BE LAID PERPENDICULAR TO THE

. AFTER ROLLING OR TAMPING, SOD SHOULD BE PEGGED OR STAPLED TO

RESIST WASHOUT DURING THE ESTABLISHMENT PERIOD. MESH OR OTHER

NETTING MAY BE PEGGED OVER THE SOD FOR EXTRA PROTECTION IN CRITICAL

DIRECTION OF FLOW. CARE SHOULD BE TAKEN TO BUTT ENDS OF STRIPS

CAN BE MADE BY COUNTY AGRICULTURAL EXTENSION AGENTS. FERTILIZE

SHOULD BE WORKED INTO THE SOIL TO A DEPTH OF 3 INCHES WITH A DISC,

FINAL HARROWING OR DISCING OPERATION SHOULD BE ON THE CONTOUR.

## GEOTEXTILE FABRIC TO STABILIZE FOUNDATION

**ROCK BERMS** 

INSPECTIONS SHOULD BE MADE.

WILL NOT CAUSE ANY ADDITIONAL SILTATION.

WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC.

ARE STABILIZED AND ACCUMULATED SILT REMOVED.

3. REPAIR ANY LOOSE WIRE SHEATHING.

#### ISOMETRIC PLAN VIEW

THE PURPOSE OF A ROCK BERM IS TO SERVE AS A CHECK DAM IN AREAS

OF CONCENTRATED FLOW. TO INTERCEPT SEDIMENT-LADEN RUNOFF, DETAIN

THE SEDIMENT AND RELEASE THE WATER IN SHEET FLOW. THE ROCK BERM

SHOULD BE USED WHEN THE CONTRIBUTING DRAINAGE AREA IS LESS THAN 5

ACRES. ROCK BERMS ARE USED IN AREAS WHERE THE VOLUME OF RUNOFF

IS TOO GREAT FOR A SILT FENCE TO CONTAIN. THEY ARE LESS EFFECTIVE

FOR SEDIMENT REMOVAL THAN SILT FENCES. PARTICULARLY FOR FINE

PARTICLES, BUT ARE ABLE TO WITHSTAND HIGHER FLOWS THAN A SILT FENCE.

AS SUCH, ROCK BERMS ARE OFTEN USED IN AREAS OF CHANNEL FLOWS

(DITCHES, GULLIES, ETC.). ROCK BERMS ARE MOST EFFECTIVE AT REDUCING

BED LOAD IN CHANNELS AND SHOULD NOT BE SUBSTITUTED FOR OTHER

INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL BY THE

REMOVE SEDIMENT AND OTHER DEBRIS WHEN BUILDUP REACHES 6 INCHES

AND DISPOSE OF THE ACCUMULATED SILT IN AN APPROVED MANNER THAT

4. THE BERM SHOULD BE RESHAPED AS NEEDED DURING INSPECTION

5. THE BERM SHOULD BE REPLACED WHEN THE STRUCTURE CEASES TO

FUNCTION AS INTENDED DUE TO SILT ACCUMULATION AMONG THE ROCKS,

6. THE ROCK BERM SHOULD BE LEFT IN PLACE UNTIL ALL UPSTREAM AREAS

A SILT FENCE IS A BARRIER CONSISTING OF GEOTEXTILE FABRIC SUPPORTED

BY METAL POSTS TO PREVENT SOIL AND SEDIMENT LOSS FROM A SITE.

WHEN PROPERLY USED, SILT FENCES CAN BE HIGHLY EFFECTIVE AT

CONTROLLING SEDIMENT FROM DISTURBED AREAS. THEY CAUSE RUNOFF TO

POND, ALLOWING HEAVIER SOLIDS TO SETTLE OUT. IF NOT PROPERLY

THE PURPOSE OF A SILT FENCE IS TO INTERCEPT AND DETAIN WATER-BORN

SEDIMENT FROM UNPROTECTED AREAS OF A LIMITED EXTENT. SILT FENCE IS

USED DURING THE PERIOD OF CONSTRUCTION NEAR THE PERIMETER OF A

DISTURBED AREA TO INTERCEPT SEDIMENT WHILE ALLOWING WATER TO

PERCOLATE THROUGH. THIS FENCE SHOULD REMAIN IN PLACE UNTIL THE

DISTURBED AREA IS PERMANENTLY STABILIZED. SILT FENCE SHOULD NOT BE

USED WHERE THERE IS A CONCENTRATION OF WATER IN A CHANNEL OF

DRAINAGE WAY. IF CONCENTRATED FLOW OCCURS AFTER INSTALLATION,

CORRECTIVE ACTION MUST BE TAKEN SUCH AS PLACING A ROCK BERM IN THE

SILT FENCING WITHIN THE SITE MAY BE TEMPORARILY MOVED DURING THE DAY

TO ALLOW CONSTRUCTION ACTIVITY PROVIDED IT IS REPLACED AND PROPERLY

SILT FENCE MATERIAL SHOULD BE POLYPROPYLENE, POLYETHYLENE, OR

POLYAMIDE WOVEN OR NONWOVEN FABRIC. THE FABRIC SHOULD BE 36

INCHES, WITH A MINIMUM UNIT WEIGHT OF 4.5 OZ/YD, MULLEN BURST

STRENGTH EXCEEDING 190 LB/IN2, ULTRAVIOLET STABILITY EXCEEDING 70%,

FENCE POSTS SHOULD BE MADE OF HOT ROLLED STEEL, AT LEAST 4 FEET

LONG WITH TEE OR Y-BAR CROSS SECTION, SURFACE PAINTED OR

GALVANIZED, MINIMUM WEIGHT 1.25 LB/FT, AND BRINDELL HARDNESS

3. WOVEN WIRE BACKING TO SUPPORT THE FABRIC SHOULD BE GALVANIZED

1. STEEL POSTS, WHICH SUPPORT THE SILT FENCE, SHOULD BE INSTALLED ON

A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POSTS MUST

BE EMBEDDED A MINIMUM OF 1-FOOT DEEP AND SPACED NOT MORE THAN 8

FEET ON CENTER. WHERE WATER CONCENTRATES, THE MAXIMUM SPACING

LAY OUT FENCING DOWN-SLOPE OF DISTURBED AREA, FOLLOWING THE

CONTOUR AS CLOSELY AS POSSIBLE. THE FENCE SHOULD BE SITED SO THAT

THE MAXIMUM DRAINAGE AREA IS 1/4 ACRE/100 FEET OF FENCE.

AND MINIMUM APPARENT OPENING SIZE OF U.S. SIEVE NUMBER 30.

ANCHORED TO THE GROUND AT THE END OF THE DAY. SILT FENCES ON THE

PERIMETER OF THE SITE OR AROUND DRAINAGE WAYS SHOULD NOT BE MOVED

INSTALLED, SILT FENCES ARE NOT LIKELY TO BE EFFECTIVE.

RESPONSIBLE PARTY. FOR INSTALLATIONS IN STREAMBEDS, ADDITIONAL DAILY

EROSION AND SEDIMENT CONTROL MEASURES FARTHER UP THE WATERSHED.

INSPECTION AND MAINTENANCE GUIDELINES

WOVEN WIRE SHEATHING

# WOVEN WIRE SHEATHING

#### **MATERIALS**

THE BERM STRUCTURE SHOULD BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM OPENING OF 1 INCH AND A MINIMUM WIRE DIAMETER OF 20 GAUGE GALVANIZED AND SHOULD BE SECURED WITH SHOAT

**SECTION "A-A"** 

2. CLEAN, OPEN GRADED 3-INCH TO 5-INCH DIAMETER ROCK SHOULD BE USED, EXCEPT IN AREAS WHERE HIGH VELOCITIES OR LARGE VOLUMES OF FLOW ARE EXPECTED, WHERE 5-INCH TO 8-INCH DIAMETER ROCKS MAY BE

#### INSTALLATION

1. LAY OUT THE WOVEN WIRE SHEATHING PERPENDICULAR TO THE FLOW LINE. THE SHEATHING SHOULD BE 20 GAUGE WOVEN WIRE MESH WITH 1 INCH

2. BERM SHOULD HAVE A TOP WIDTH OF 2 FEET MINIMUM WITH SIDE SLOPES BEING 2:1 (H: V) OR FLATTER.

3. PLACE THE ROCK ALONG THE SHEATHING AS SHOWN IN THE DIAGRAM TO A HEIGHT NOT LESS THAN 18". 4. WRAP THE WIRE SHEATHING AROUND THE ROCK AND SECURE WITH TIE

WIRE SO THAT THE ENDS OF THE SHEATHING OVERLAP AT LEAST 2 INCHES,

AND THE BERM RETAINS ITS SHAPE WHEN WALKED UPON. 5. BERM SHOULD BE BUILT ALONG THE CONTOUR AT ZERO PERCENT GRADE OR AS NEAR AS POSSIBLE 6. THE ENDS OF THE BERM SHOULD BE TIED INTO EXISTING UPSLOPE GRADE AND THE BERM SHOULD BE BURIED IN A TRENCH APPROXIMATELY 3 TO 4

#### COMMON TROUBLE POINTS

INCHES DEEP TO PREVENT FAILURE OF THE CONTROL.

. INSUFFICIENT BERM HEIGHT OR LENGTH (RUNOFF QUICKLY ESCAPES OVER THE TOP OR AROUND THE SIDES OF BERM).

2. BERM NOT INSTALLED PERPENDICULAR TO FLOW LINE (RUNOFF ESCAPING AROUND ONE SIDE).

3. THE TOE OF THE SILT FENCE SHOULD BE TRENCHED IN WITH A SPADE OR

MECHANICAL TRENCHER, SO THAT THE DOWN-SLOPE FACE OF THE TRENCH IS

FLAT AND PERPENDICULAR TO THE LINE OF FLOW. WHERE FENCE CANNOT BE

TRENCHED IN (E.G., PAVEMENT OR ROCK OUTCROP), WEIGHT FABRIC FLAP

WITH 3 INCHES OF PEA GRAVEL ON UPHILL SIDE TO PREVENT FLOW FROM

4. THE TRENCH MUST BE A MINIMUM OF 6 INCHES DEEP AND 6 INCHES WIDE

TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND

5. SILT FENCE SHOULD BE SECURELY FASTENED TO EACH STEEL SUPPORT

POST OR TO WOVEN WIRE, WHICH IS IN TURN ATTACHED TO THE STEEL FENCE

POST. THERE SHOULD BE A 3-FOOT OVERLAP, SECURELY FASTENED WHERE

6. SILT FENCE SHOULD BE REMOVED WHEN THE SITE IS COMPLETELY

FENCE NOT INSTALLED ALONG THE CONTOUR CAUSING WATER TO

2. FABRIC NOT SEATED SECURELY TO GROUND (RUNOFF PASSING UNDER

3. FENCE NOT INSTALLED PERPENDICULAR TO FLOW LINE (RUNOFF ESCAPING

4. FENCE TREATING TOO LARGE AN AREA, OR EXCESSIVE CHANNEL FLOW

3. REPLACE TORN FABRIC OR INSTALL A SECOND LINE OF FENCING PARALLEL

4. REPLACE OR REPAIR SECTIONS CRUSHED OR COLLAPSED IN THE COURSE OF CONSTRUCTION ACTIVITY. IF A SECTION OF FENCE IS OBSTRUCTING

VEHICULAR ACCESS, CONSIDER RELOCATING IT TO A SPOT WHERE IT WILL

PROVIDE EQUAL PROTECTION, BUT WILL NOT OBSTRUCT VEHICLES. A

OF IN A MANNER THAT WILL NOT CAUSE ADDITIONAL SILTATION AND THE

PRIOR LOCATION OF THE SILT FENCE SHOULD BE REVEGETATED. THE FENCE


TRIANGULAR FILTER DIKE MAY BE PREFERABLE TO A SILT FENCE AT COMMON

WHEN CONSTRUCTION IS COMPLETE, THE SEDIMENT SHOULD BE DISPOSED

INSPECTION AND MAINTENANCE GUIDELINES

STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.

#### **ROCK BERM DETAIL**



ISOMETRIC PLAN VIEW

SEEPING UNDER FENCE.

ENDS OF FABRIC MEET.

TO THE TORN SECTION.

VEHICLE ACCESS POINTS.

FENCE).

BACKFILLED WITH COMPACTED MATERIAL.

COMMON TROUBLE POINTS

CONCENTRATE AND FLOW OVER THE FENCE.

(RUNOFF OVERTOPS OR COLLAPSES FENCE).

1. INSPECT ALL FENCING WEEKLY, AND AFTER RAINFALL.

2. REMOVE SEDIMENT WHEN BUILDUP REACHES 6 INCHES.

ITSELF SHOULD BE DISPOSED OF IN AN APPROVED LANDFILL.

#### 8. INSTALL PIPE UNDER PAD AS NEEDED TO MAINTAIN PROPER PUBLIC ROAD STABILIZED CONSTRUCTION ENTRANCE/EXIT DETAIL

NOT-TO-SCALE

LAY SOD IN A STAGGERED PATTERN. BUTT THE STRIPS TIGHTLY AGAINST EACH OTHER. DO NOT LEAVE SPACES AND DO NOT

IS A HANDY TOOL FOR TUCKING DOWN THE ENDS AND TRIMMING PIECES. ANGLED ENDS CAUSED BY THE

OVERLAP. A SHARPENED MASON'S TROWEL

AUTOMATIC SOD CUTTER MUST BE MATCHED CORRECTLY.

LAY SOD ACROSS THE DIRECTION OF FLOW

**MATERIALS** 

OF 36 HOURS.

SHOOT GROWTH AND THATCH.

SITE PREPARATION

TIGHTLY (SEE FIGURE ABOVE).


TORN OR UNEVEN PADS SHOULD NOT BE ACCEPTABLE.

SUSPENDED FROM A FIRM GRASP ON ONE END OF THE SECTION.

TO FINAL GRADE IN ACCORDANCE WITH THE APPROVED PLAN.

INSTALLATION IN CHANNELS

INTERFERE WITH PLANTING, FERTILIZING OR MAINTENANCE OPERATIONS.



APPEARANCE OF GOOD SOD

SOON AS THE SOD IS LAID.

SOIL.

1. ROLL SOD IMMEDIATELY TO ACHIEVE FIRM CONTACT WITH THE

2. WATER TO A DEPTH OF 4" AS NEEDED. WATER WELL AS

IN CRITICAL AREAS, SECURE SOD WITH NETTING. USE STAPLES.

GENERAL INSTALLATION (VA. DEPT. OF

SOD SHOULD NOT BE CUT OR LAID IN EXCESSIVELY WET OR DRY WEATHER. SOD ALSO SHOULD NOT BE LAID ON SOIL SURFACES THAT ARE FROZEN. 2. DURING PERIODS OF HIGH TEMPERATURE, THE SOIL SHOULD BE LIGHTLY IRRIGATED IMMEDIATELY PRIOR TO LAYING THE SOD, TO COOL THE SOIL AND REDUCE ROOT BURNING AND DIEBACK.

SECTION "A-A" OF A

CONSTRUCTION ENTRANCE/EXIT

. STONE TOO SMALL OR GEOTEXTILE FABRIC ABSENT, RESULTS IN MUDDY

PAD TOO SHORT FOR HEAVY CONSTRUCTION TRAFFIC-EXTEND PAD BEYOND

4. PAD NOT FLARED SUFFICIENTLY AT ROAD SURFACE, RESULTS IN MUD BEING

5. UNSTABLE FOUNDATION - USE GEOTEXTILE FABRIC UNDER PAD AND/OR

THE ENTRANCE SHOULD BE MAINTAINED IN A CONDITION, WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY.

THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS

CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES

2. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC

3. WHEN NECESSARY, WHEELS SHOULD BE CLEANED TO REMOVE SEDIMENT

4. WHEN WASHING IS REQUIRED, IT SHOULD BE DONE ON AN AREA STABILIZED

WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR

5. ALL SEDIMENT SHOULD BE PREVENTED FROM ENTERING ANY STORM DRAIN,

RIGHTS-OF-WAY SHOULD BE REMOVED IMMEDIATELY BY CONTRACTOR.

INSPECTION AND MAINTENANCE GUIDELINES

1. INADEQUATE RUNOFF CONTROL-SEDIMENT WASHES ONTO PUBLIC ROAD.

COMMON TROUBLE POINTS

CONDITION AS STONE IS PRESSED INTO SOIL.

IMPROVE FOUNDATION DRAINAGE.

USED TO TRAP SEDIMENT

SHOOTS OR GRASS BLADES.

HEALTHY; MOWED AT A 2"-3"

CUTTING HEIGHT.

GRASS SHOULD BE GREEN AND

-THATCH- GRASS CLIPPINGS AND

-ROOT ZONE - SOIL AND ROOTS.

DEAD LEAVES, UP TO 1/2" THICK.

SHOULD BE 1/2"-3/4" THICK, WITH

DENSE ROOT MAT FOR STRENGTH.

SEDIMENT BASIN

THE MINIMUM 50-FOOT LENGTH AS NECESSARY.

TRACKED ON TO ROAD AND POSSIBLE DAMAGE TO ROAD.

PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY.

DITCH OR WATER COURSE BY USING APPROVED METHODS.

FIRST ROW OF SOD SHOULD BE LAID IN A STRAIGHT LINE WITH SUBSEQUENT ROWS PLACED PARALLEL TO AND BUTTING TIGHTLY AGAINST EACH OTHER. LATERAL JOINTS SHOULD BE STAGGERED TO PROMOTE MORE UNIFORM GROWTH AND STRENGTH. CARE SHOULD BE EXERCISED TO ENSURE THAT SOD IS NOT STRETCHED OR OVERLAPPED AND THAT ALL JOINTS ARE BUTTED TIGHT IN ORDER TO PREVENT VOIDS WHICH WOULD CAUSE DRYING OF THE ROOTS

4. ON SLOPES 3:1 OR GREATER, OR WHEREVER EROSION MAY BE A PROBLEM, SOD SHOULD BE LAID WITH STAGGERED JOINTS AND SECURED BY STAPLING OR OTHER APPROVED METHODS. SOD SHOULD BE INSTALLED WITH THE LENGTH PERPENDICULAR TO THE SLOPE (ON CONTOUR).

5. AS SODDING OF CLEARLY DEFINED AREAS IS COMPLETED, SOD SHOULD BE ROOTS, BRUSH, WIRE, GRADE STAKES AND OTHER OBJECTS THAT WOULD ROLLED OR TAMPED TO PROVIDE FIRM CONTACT BETWEEN ROOTS AND SOIL. THE UNDERSIDE OF THE SOD PAD AND THE SOIL 4 INCHES BELOW THE SOD IS

> UNTIL SUCH TIME A GOOD ROOT SYSTEM BECOMES DEVELOPED, IN THE ABSENCE OF ADEQUATE RAINFALL, WATERING SHOULD BE PERFORMED AS OFTEN AS NECESSARY TO MAINTAIN MOIST SOIL TO A DEPTH OF AT LEAST 4

> 8. THE FIRST MOWING SHOULD NOT BE ATTEMPTED UNTIL THE SOD IS FIRMLY ROOTED, USUALLY 2-3 WEEKS. NOT MORE THAN ONE THIRD OF THE GRASS LEAF SHOULD BE REMOVED AT ANY ONE CUTTING.

NSPECTION AND MAINTENANCE GUIDELINES

#### SOD INSTALLATION DETAIL

AREAS OF CONCENTRATED FLOW.

2" X 4" WELDED WIRE, 12 GAUGE MINIMUM.

INSTALLATION

SHOULD BE 6 FEET.

AT ANY TIME.

SILT FENCE

USE PEGS OR STAPLES TO FASTEN SOD FIRMLY - AT THE ENDS OF STRIPS AND IN THE CENTER, OR EVERY 3-4 FEET IF THE STRIPS ARE LONG. WHEN READY TO MOW, DRIVE PEGS OR STAPLES FLUSH WITH THE GROUND.

CORRECT

INCORRECT

SOD INSTALLATION

## CONSERVATION, 1992)

(SEE FIGURE ABOVE).


AFTER ROLLING, SOD SHOULD BE IRRIGATED TO A DEPTH SUFFICIENT THAT

#### SOD SHOULD BE INSPECTED WEEKLY AND AFTER EACH RAIN EVENT TO LOCATE AND REPAIR ANY DAMAGE.

2. DAMAGE FROM STORMS OR NORMAL CONSTRUCTION ACTIVITIES SUCH AS TIRE RUTS OR DISTURBANCE OF SWALE STABILIZATION SHOULD BE REPAIRED AS SOON AS PRACTICAL.

#### SILT FENCE DETAIL

NOT-TO-SCALE



. THE FILTER BAG MATERIAL SHALL BE MADE OF POLYPROPYLENE POLYETHYLENE OR POLYAMIDE WOVEN FABRIC, MIN. UNIT WEIGHT OF 4 OUNCES/SY, HAVE A MULLEN BURST STRENGTH EXCEEDING 300 PSI AND ULTRAVIOLET STABILITY EXCEEDING 70%.

2. THE FILTER BAG SHALL BE FILLED WITH CLEAN, MEDIUM WASHED PEA GRAVEL TO COARSE GRAVEL (0.31 TO 0.75 INCH DIAMETER). 3. SAND SHALL NOT BE USED TO FILL THE FILTER BAGS.

#### GRAVEL FILTER BAG DETAIL

NOT-TO-SCALE

ONSTRUCTIO **EQUIPMENT &** VFHICL F STORAGE AN MAINTENANCE AREA FIELD OFFICE **ENTRANCE** CONSTRUCTION

### CONSTRUCTION STAGING AREA

**LEGEND** 


-\\-\\- SILT FENCE

→ FLOW ARROWS


NOT-TO-SCALE

AND WASTE MATERIA

STORAGE AREA



**PLAN VIEW** 



#### SECTION "A-A'

GENERAL NOTES DETAIL ABOVE ILLUSTRATES MINIMUM DIMENSIONS. PIT CAN BE INCREASED IN SIZE DEPENDING ON EXPECTED FREQUENCY OF USE.

2. WASHOUT PIT SHALL BE LOCATED IN AN AREA EASILY ACCESSIBLE TO CONSTRUCTION TRAFFIC. 3. WASHOUT PIT SHALL NOT BE LOCATED IN AREAS SUBJECT TO INUNDATION

FROM STORM WATER RUNOFF. 4. LOCATE WASHOUT AREA AT LEAST 50 FEET FROM SENSITIVE FEATURES, STORM DRAINS, OPEN DITCHES OR WATER BODIES. . TEMPORARY CONCRETE WASHOUT FACILITY SHOULD BE CONSTRUCTED WITH SUFFICIENT QUANTITY AND VOLUME TO CONTAIN ALL LIQUID AND CONCRETE

#### MATERIALS

PLASTIC LINING MATERIAL SHOULD BE A MINIMUM OF 10 MIL IN POLYETHYLENE SHEETING AND SHOULD BE FREE OF HOLES, TEARS, OR OTHER DEFECTS THAT COMPROMISE THE IMPERMEABILITY OF THE MATERIAL

#### MAINTENANCE WHEN TEMPORARY CONCRETE WASHOUT FACILITIES ARE NO LONGER


WASTE GENERATED BY WASHOUT OPERATIONS.

REQUIRED FOR THE WORK, THE HARDENED CONCRETE SHOULD BE REMOVED AND DISPOSED OF. MATERIALS USED TO CONSTRUCT TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE REMOVED FROM THE SITE OF THE WORK AND DISPOSED

HOLES, DEPRESSIONS OR OTHER GROUND DISTURBANCES CAUSED BY THE REMOVAL OF THE TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE BACKFILLED AND REPAIRED.

#### CONCRETE TRUCK WASHOUT PIT DETAIL

NOT-TO-SCALE



**LOCATION MAP** NOT-TO-SCALE

JASON T. DIAMON

THE ENGINEERING SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR THE PURPOSE OF DEMONSTRATING COMPLIANCE WITH THE TPDES-STORM WATER POLLUTION PREVENTION PLAN (SWP3) REGULATIONS.

THIS SHEET HAS BEEN PREPARED FOR PURPOSES OF THE SWP3 ONLY. ALL OTHER CIVIL ENGINEERING RELATED INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE

SHEET IN THE CIVIL IMPROVEMENT PLANS.

SIGNER ECKED MP DRAWN R C7.01

OB NO. 12719-07

JANUARY 2024