

BROOK STONE CREEK-UNIT 2E
Bexar County, TX

ITEM NO.	BID ITEM	UNIT	QUANTITY	UNIT PRICE	BID TOTAL
DEMOLITION, EARTHWORK, CLEARING, AND SWPPP					
	Remove Header Curb and Barricade Posts	LF	28		
	Remove Temporary Turnaround	EA	3		
	Street Excavation	CY	9,957		
	Street Embankment	CY	7,123		
	Lot Excavation	CY	8,496		
	Lot Embankment	CY	43,266		
	Basin Excavation	CY	18		
	Basin Embankment	CY	1,314		
	Import	CY	33,232		
	TPDES	LS	1		
	Clearing (Streets)	AC	6.3		
	Clearing (Lots/Offsite Easements)	AC	22.1		
	Retaining Wall	SF	2,451		
	Wooden Fence	LF	676		
	12' Wide Access Gate	EA	2		
	SUB-TOTAL				
SANITARY SEWER					
	8" Sanitary Sewer Pipe (6'-10' Deep) (SDR-26)	LF	2,310		
	8" Sanitary Sewer Pipe (10'-14' Deep) (SDR-26)	LF	833		
	8" Sanitary Sewer Pipe (14'-18' Deep) (SDR-26)	LF	425		
	8" Sanitary Sewer Pipe (18'-22' Deep) (SDR-26)	LF	1,737		
	8" Sanitary Sewer Pipe (22'-26' Deep) (SDR-26)	LF	201		
	6" Sanitary Sewer Lateral (SDR-26)	LF	5,830		
	Standard Manhole	EA	20		
	Drop Manhole	EA	4		
	Manhole Ring Encasement	EA	24		
	Adjust Existing Manhole	EA	1		
	Tie to Existing Manhole	EA	1		
	Manhole Extra Depth	VF	168.2		
	Vertical Stacks	VF	589.8		
	8" x 6" Wye	EA	158		
	Trench Excavation Protection	LF	5,506		
	Sewer Revegetation	SY	2,375		
	Camera Testing	LF	5,506		
	SUB-TOTAL				
ONSITE DRAINAGE					
	24" RCP (Class III)	LF	1,054		
	24" CMP	LF	41		
	30" RCP (Class III)	LF	146		
	36" RCP (Class III)	LF	254		
	36" UFCMP	LF	246		
	42" UFCMP	LF	347		
	5' Type CI Curb Inlet	EA	5		
	5' Type CII Curb Inlet	EA	4		
	10' Type CI Curb Inlet	EA	2		
	10' Type CII Curb Inlet	EA	3		
	15' Type C Curb Inlet	EA	1		
	Concrete Collars	CY	10.6		
	Baffle Blocks	CY	0.8		
	Concrete Headwall	CY	13.0		
	6" Concrete Rip-Rap	SY	49		
	Trench Excavation Protection	LF	2,087		
	SUB-TOTAL				
ONSITE DRAINAGE - BASIN					
	Water Quality Logic Controller and Water Quality Components	EA	1		
	4'x4' Junction Box with Vault Hatch	EA	1		
	4'x4' Grate Inlet	EA	1		
	24" UFCMP	LF	35		
	Baffle Blocks	CY	0.3		
	Concrete Headwall	CY	3.3		
	6" Concrete Rip-Rap	SY	8		
	6" Solid PVC	LF	59		
	6" Topsoil w/ Hydromulch	SY	676		
	12" Clay Liner	SY	676		
	Basin Fence (6' High Chain Link)	LF	410		
	12' Wide Access Gate	EA	1		
	Basin Access Road	LS	1		
	SUB-TOTAL				
WATER DISTRIBUTION					
	2' HDPE Class 200 DR9	LF	354		
	8" PVC C-900, Class 235, DR 18	LF	4,703		
	8" Gate Valve, M.J. with Valve Box	EA	11		
	12" PVC C-900, Class 235, DR 18	LF	446		
	12" Gate Valve, M.J. with Valve Box	EA	2		
	Standard Fire Hydrant Assembly	EA	8		
	Ductile Iron Fitting	Ton	5.4		
	2" Blow Off (Temporary)	EA	5		
	2" Blow Off (Permanent)	EA	2		
	Hydrostatic Testing	LS	1		
	Chlorination	LF	5,503		
	Trench Excavation Protection	LF	5,503		
	Joint Restraints	LS	1		
	3/4" Single Short Service w/ 5/8" meter	EA	91		
	3/4" Single Long Service w/ 5/8" meter	EA	67		
	Water Revegetation	SY	343		
	Plastic Meter Box with Lid	EA	158		
	SUB-TOTAL				
ONSITE STREETS					
	2" Type D HMAc	SY	17,876		
	8.5" Flex Base	SY	19,917		
	7" Concrete Curb	LF	10,276		
	4' Sidewalk	SY	264		
	Portland Cement Concrete Driveway - Commercial	SY	30		
	Header Curb	LF	28		
	Barricade Posts	EA	5		
	Signage and Striping	LS	1		
	SUB-TOTAL				
CONDUITS					
	1-6" SCH 80 & 2-4" SCH 40 Bundle	LF	240		
	2-6" SCH 80 & 2-4" SCH 40 Bundle	LF	90		
	3-6" SCH 80 & 2-4" SCH 40 Bundle	LF	30		
	SUB-TOTAL				
GRAND TOTAL					