



CONSTRUCTION PLANS

for

CHELSEA PARK II



OVERALL SITE
NOT TO SCALE




OWNER/DEVELOPER:
CHELSEA PARK FPRP
16607 BLANCO RD, SUITE 201
SAN ANTONIO, TEXAS 78232



PREPARED BY:
KCI TECHNOLOGIES, INC.
2806 WEST BITTERS RD, SUITE 218
SAN ANTONIO, TEXAS 78230-1037
PHONE: (210) 641-9999
FAX: (210) 641-6440
REGISTRATION #F-10573 / #101943-65


Sheet List Table	
Sheet Number	Sheet Title
0	COVER SHEET
1	CHANNEL A PLAN & PROFILE
2	CHANNEL A PLAN & PROFILE
3	GRADING PLAN
4	GRADING PLAN
5	SEDIMENTATION & EROSION CONTROL PLAN
6	SEDIMENTATION & EROSION CONTROL PLAN
7	SEDIMENTATION & EROSION CONTROL NARRATIVE
8	SEDIMENTATION & EROSION CONTROL DETAILS




CHELSEA PARK II
COVER SHEET



DRAFTING:	N.O.	CHECK:	C.P.
DESIGN:	C.P.	CHECK:	M.P.S.
SUBMITTAL PHASE:			
DATE:	6/27/2025		
KCI JOB #:	762305304		
SHEET:			

0



KCI TECHNOLOGIES, INC.
2806 W. BITTERS RD, SUITE 218
SAN ANTONIO, TEXAS 78248
PHONE: (210) 641-9999
FAX: (210) 641-6440
REGISTRATION #F-10573 / #101943-65





LEGEND

- | | |
|------------------------------|--|
| PROPOSED STORM DRAIN | |
| PROPOSED EARTHEN CHANNEL | |
| PROPOSED SANITARY SEWER MAIN | |
| DIRECTION OF FLOW | |
| EXISTING WATER MAIN | |
| PROPOSED WATER MAIN | |
| PROPOSED CONTOURS | |
| EXISTING CONTOURS | |
| 100-YR FLOOD PLAIN | |
| 500-YR FLOOD PLAIN | |

Line Table		
Line	Length	Direction
L1	201.44'	S04°32'47"W
L2	140.73'	S25°11'01"W
L3	221.26'	S27°18'35"W
L4	369.12'	S28°01'22"W
L5	459.18'	S30°09'01"W

Curve #	Length	Radius	Delta	Chord Direction	Chord Length
C1	43.22'	120.00'	020°38'14"	S14° 51' 54"W	42.99'
C2	393.28'	400.00'	056°19'57"	S0° 51' 24"E	377.63'





CHELSEA PARK II

CHANNEL A PLAN AND PROFILE

DRAFTING: N.O.	CHECK: C.P.
DESIGN: C.P.	CHECK: M.P.S.
SUBMITTAL PHASE:	
DATE:	6/27/2021
KCI JOB #:	76230530
SHEET:	

Date: Jun 27 2025 9:59am User ID: \\c:\development\proj 2023 kci\762305304 chelsen park iii-clomr-lomr\CADD\762305304 CHANNEL A PLAN & PROFILE.dwg

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARD COPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.





LEGEND

- PROPOSED STORM DRAIN
- PROPOSED EARTHEN CHANNEL
- PROPOSED SANITARY SEWER MAIN
- DIRECTION OF FLOW
- EXISTING WATER MAIN
- PROPOSED WATER MAIN
- PROPOSED CONTOURS
- EXISTING CONTOURS
- 100-YR FLOOD PLAN
- 500-YR FLOOD PLAN

Line Table		
Line	Length	Direction
L1	201.44'	S54°32'47"W
L2	140.73'	S25°11'01"W
L3	221.28'	S27°18'35"W
L4	369.12'	S29°01'22"E
L5	459.18'	S30°09'01"E

Curve Table					
Curve #	Length	Radius	Delta	Chord Direction	Chord Length
C1	43.22'	120.00'	020°38'14"	S14°51'54"W	42.99'
C2	393.28'	400.00'	056°19'50"	S0°51'24"E	377.63'



KCI TECHNOLOGIES, INC.

2806 W. BITTERS RD. SUITE 218
SAN ANTONIO, TEXAS 78248
PHONE: (210) 641-9999
FAX: (210) 641-6440
REGISTRATION #10573 / #101943-65



CHELSEA PARK II

CHANNEL A PLAN AND PROFILE


DRAFTING: N.O. / CHECK: C.P.
DESIGN: C.P. / CHECK: M.P.S.
SUBMITTAL PHASE:
DATE: 6/27/2025
KCI JOB #: 762305304
SHEET:



EXISTING CONTOUR - - - - - 740 - - - - -
PROPOSED CONTOUR - - - - - 740 - - - - -

GENERAL NOTES

1. FILL MATERIALS: MATERIALS SHALL CONSIST OF SOILS APPROVED BY THE ENGINEER FROM SOURCES IDENTIFIED AND APPROVED. THE SOIL SHALL BE FREE OF VEGETABLE MATTER AND OTHER DELERIOUS SUBSTANCE AND SHALL NOT CONTAIN ROCKS OR LUMPS HAVING A DIAMETER GREATER THAN SIX INCHES (6").
2. DENSITY AND MIXING OF FILL LAYERS: THE SELECTED FILL MATERIAL SHALL BE PLACED IN LEVEL, UNIFORM LAYERS WHICH, WHEN COMPACTIOND, SHALL HAVE A DENSITY CONFORMING TO REQUIRED AMOUNT OF COMPACTION. EACH LAYER SHALL BE THOROUGHLY BLADE MIXED DURING THE SPREADING TO INSURE UNIFORMITY OF MATERIAL. IN EACH LAYER, COMPACTIONED LAYER THICKNESS NORMALLY WILL BE SIX INCHES (6"). HOWEVER, BASED ON TWELVE INCHES (12") IF COMPACTION EQUIPMENT OF DEMONSTRATED CAPABILITY WILL BE USED.
3. ROCK: WHEN FILL MATERIAL INCLUDES ROCK, THE MAXIMUM ROCK SIZE ACCEPTABLE SHALL BE SIX INCHES (6"). NO LARGE ROCKS SHALL BE ALLOWED TO NEST AND ALL VOIDS MUST BE CAREFULLY FILLED WITH SMALL STONES OR EARTH, AND PROPERLY COMPACTIOND. NO LARGE ROCKS WILL BE ALLOWED WITHIN TWELVE INCHES (12") OF THE FINISHED SURFACE.
4. MOISTURE CONTENT: THE FILL MATERIAL SHALL BE COMPACTIOND AT THE APPROPRIATE MOISTURE CONTENT SPECIFIED FOR THE SOILS BEING USED AND IDENTIFIED IN SOIL AND LABORATORY REPORTS. MOISTURE CONTENT TOLERANCES SHALL BE PLUS OR MINUS 3% FROM OPTIMUM.
5. AMOUNT OF COMPACTION: AFTER EACH LAYER (LIFT) HAS BEEN PLACED, MIXED AND SPREAD EVENLY, IT SHALL BE COMPACTIOND TO THE SPECIFIED DENSITY. THE SPECIFIED DENSITY SHALL BE STATED AS A PERCENTAGE OF THE MAXIMUM DENSITY ATTAINABLE USING CURRENT ASTM D 698 TO 95 PERCENT DENSITY.
6. COMPACTION OF FILL LAYER: COMPACTION EQUIPMENT SHALL BE OF SUCH DESIGN THAT IT WILL COMPACT THE FILL TO THE APPROPRIATE SPECIFIED DENSITY AT THE OPTIMUM MOISTURE CONTENT. COMPACTION EFFORT SHALL BE CONTINUOUS OVER EACH LAYER UNTIL DENSITY HAS BEEN ACHIEVED.
7. DENSITY TESTS: FIELD DENSITY TESTS SHALL BE MADE BY THE SOILS ENGINEER AFTER THE COMPACTION OF EACH LAYER. WHEN TEST INDICATE THAT THE DENSITY OF ANY LAYER OR PORTION IS BELOW REQUIRED DENSITY, THEREFORE, REWORK AND RETESTS ARE REQUIRED. ALL FIELD DENSITY TESTS SHALL BE ESTABLISHED BY THE SOIL ENGINEER TO CERTIFY TO THE REQUIRED 792 LECTURE REQUIREMENTS.



CHELSEA PARK II GRADING PLAN

DRAFTING: N.O.	CHECK: C
DESIGN: C.P.	CHECK: M.
SUBMITTAL PHASE:	
DATE:	6/27/20
CCI JOB #:	762305
SHEET:	

3



EXISTING CONTOUR - - - - - 740 - - - - -
PROPOSED CONTOUR - - - - - 740 - - - - -

GENERAL NOTES

1. FILL MATERIALS: MATERIALS SHALL CONSIST OF SOILS APPROVED BY THE ENGINEER FROM SOURCES IDENTIFIED AND APPROVED. THE SOIL SHALL BE FREE OF VEGETABLE MATTER AND OTHER DELETERIOUS SUBSTANCE AND SHALL NOT CONTAIN ROCKS OR LUMPS HAVING A DIAMETER GREATER THAN SIX INCHES (6").
2. DEPTH AND MIXING OF FILL LAYERS: EACH SELECTED FILL MATERIAL SHALL BE PLACED IN LEVEL, UNIFORM LAYERS WHICH, WHEN COMPACTED, SHALL HAVE A DENSITY CORRESPONDING TO THE REQUIRED AMOUNT OF COMPACTION; EACH LAYER SHALL BE THOROUGHLY BLADE MIXED DURING THE SPREADING TO INSURE UNIFORMITY OF MATERIAL IN EACH LAYER. COMPACTED LAYER THICKNESS NORMALLY WILL BE SIX INCHES (6"); HOWEVER, IT MAY BE INCREASED TO TWELVE INCHES (12") IF COMPACTION EQUIPMENT OF DEMONSTRATED CAPABILITY WILL BE USED.
3. ROCK: WHEN FILL MATERIAL INCLUDES ROCK, THE MAXIMUM ROCK SIZE ACCEPTABLE SHALL BE SIX INCHES (6"). NO LARGE ROCKS OR LUMPS, OR NEST AND ALL JOINTS MUST BE CAREFULLY FILLED WITH SMALL STONES OR EARTH, AND PROPERLY COMPACTED. NO LARGE ROCKS WILL BE ALLOWED WITHIN TWELVE INCHES (12") OF THE FINISHED SURFACE.
4. MOISTURE CONTENT: THE FILL MATERIAL SHALL BE COMPACTED AT THE APPROPRIATE MOISTURE CONTENT SPECIFIED FOR THE SOILS BEING USED AND IDENTIFIED IN SOIL AND LABORATORY REPORTS. MOISTURE CONTENT TOLERANCES SHALL BE PLUS OR MINUS 3% FROM OPTIMUM.
5. AMOUNT OF COMPACTION: AFTER EACH LAYER (LIFT) HAS BEEN PLACED, MIXED AND SPREAD EVENLY, IT SHALL BE COMPACTED TO THE SPECIFIED DENSITY. THE SPECIFIED DENSITY SHALL BE STATED AS A PERCENTAGE OF THE MAXIMUM DENSITY ATTAINABLE USING CURRENT ASTM D 698 TO 95 PERCENT DENSITY.
6. COMPACTION OF FILL LAYER: COMPACTION EQUIPMENT SHALL BE OF SUCH DESIGN THAT IT WILL COMPACT THE FILL TO THE APPROPRIATE SPECIFIED DENSITY AT THE OPTIMUM MOISTURE CONTENT. COMPACTION EFFORT SHALL BE CONTINUOUS OVER EACH LAYER UNTIL DENSITY HAS BEEN ACHIEVED.
7. DENSITY TESTS: FIELD DENSITY TESTS SHALL BE MADE BY THE SOILS ENGINEER AFTER THE COMPACTION OF EACH LAYER. WHEN TEST INDICATE THAT THE DENSITY OF ANY LAYER OR PORTION IS BELOW REQUIRED DENSITY, THE AREA SHALL BE RECOMPACTED UNTIL DENSITY OBTAINED. THE NUMBER OF TESTS SHALL BE ESTABLISHED BY THE SOILS ENGINEER TO CERTIFY TO THE REQUIRED 795 LECTURE REQUIREMENTS.

MATCH LINE "A": SEE SHEET 7


DO NOT CLEAR
AREA SHOWN

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARD COPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

KCI TECHNOLOGIES, INC.

CHNOLOGIES,
W. BITTERS RD, SUITE 218

TECHNOLOGIES, INC.
2806 W. BITTERS RD, SUITE 218
SAN ANTONIO, TEXAS 78248
PHONE: (210) 641-9999
FAX: (210) 641-6440
REGISTRATION #F-10573 / #101943-65





CHELSEA PARK II GRADING PLAN

DRAFTING: N.O.	CHECK: C.P.
DESIGN: C.P.	CHECK: M.P.S.
SUBMITTAL PHASE:	
DATE:	6/27/2021
KCI JOB #:	76230530
SHEET:	

4

Date: Jun 27, 2025, 9:58am User ID: lance@proj-2023 kci\762305304 cheleen park iii-clomr-lamr\CANN\762305304 Grading Plan.dwg

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARD COPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.



LEGEND


TEMPORARY SEDIMENT CONTROL FENCE	---	SCF
TEMPORARY ROCK FILTER DAM	---	RFD
TYPE 1 CONSTRUCTION EXIT	---	
CONCRETE WASHOUT PIT	---	
GRAVEL FILTER BAGS	---	
LIMITS OF CONSTRUCTION	---	LOC
GRADING SLOPE ARROW	---	
PROPOSED STAGING AREA	---	
POST CONSTRUCTION SEDIMENT CONTROL FENCE (PHASE 2)	---	PSCF

NOTE:

CONTRACTOR TO ENSURE POSITIVE DRAINAGE
AT UPSTREAM & DOWNSTREAM ENDS OF
PROJECT AND THAT NO PONDING WILL OCCUR.


S.W.P.P. GENERAL NOTES

1. THE CONTROL MEASURES CONTAINED HEREON (AND AS FURTHER DESCRIBED BY THE STANDARD SPECIFICATIONS) SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE CONSTRUCTION CONTRACT TO ASSURE EFFECTIVE AND CONTINUOUS WATER POLLUTION CONTROL DURING CONSTRUCTION AND POST CONSTRUCTION PERIODS.
2. A RAIN GAUGE SHALL BE PROVIDED BY THE CONTRACTOR AND LOCATED AT THE PROJECT SITE. THE CONTRACTOR AND INSPECTOR WILL INSPECT THE ENTIRE PROJECT TO DETERMINE THE CONDITION OF THE CONTROL MEASURES. SEDIMENT WILL BE REMOVED AND DEVICES REPAIRED AS SOON AS PRACTICABLE BUT NO LATER THAN 7 DAYS AFTER THE SURROUNDING EXPOSED GROUND HAS DRIED SUFFICIENTLY TO PREVENT FURTHER DAMAGE BEING CAUSED BY REPAIR OPERATIONS.
3. THE CONTRACTOR SHALL CLEAN PAVED SURFACES (ADJACENT TO THE CONSTRUCTION AREAS) AS NECESSARY TO REMOVE SEDIMENT WHICH HAS ACCUMULATED ON THE ROADWAY DUE TO STORMWATER FLOWS AND VEHICULAR TRAFFIC THROUGH AND ACROSS THE CONSTRUCTION SITE.
4. IN CASE OF FAILURE ON THE PART OF THE CONTRACTOR TO PREVENT AND CONTROL SOIL EROSION, SEDIMENTATION AND WATER POLLUTION WHICH MAY DEGRADE RECEIVING WATERS, THE DEVELOPER/OWNER RESERVES THE RIGHT TO EMPLOY OUTSIDE ASSISTANCE OR USE OTHER FORCES TO PROVIDE THE NECESSARY CORRECTIVE MEASURES. ALL COST (INCLUDING ENGINEERING) COST WILL BE DEDUCTED FROM ANY MONEYS DUE TO OR TO BECOME DUE TO THE CONTRACTOR.
5. UPON COMPLETION OF CONSTRUCTION AND THE INSTALLATION OF PERMANENT EROSION CONTROL METHODS, A FINAL EROSION CONTROL INSPECTION WILL BE PERFORMED AS PART OF ACCEPTANCE OF THE PROJECT BY THE DEVELOPER/OWNER. IN THE EVENT THAT THE PERMANENT EROSION CONTROL IS INADEQUATE DUE TO IMPROPER DESIGN OR INSTALLATION, THE PERMANENT EROSION CONTROL MEASURES MUST BE CORRECTED OR REDESIGNED TO FUNCTION PROPERLY.
6. THE NOTICE OF INTENT (N.O.I.) SHALL BE SIGNED AND SUBMITTED BY THE CONTRACTOR AT LEAST 48 HOURS PRIOR TO THE CONTRACTOR MOVING ONTO THE SITE.
7. THE CONTRACTOR SHALL SUBMIT A SIGNED NOTICE OF TERMINATION (N.O.T.)



J-HOOK DETAIL
SCALE: NTS


KCI TECHNOLOGIES, INC.
2806 W. BITTERS RD. SUITE 218
SAN ANTONIO, TEXAS 78248
PHONE: (210) 641-9899
FAX: (210) 641-6440
REGISTRATION #F-10573 / #101943-65



CHELSEA PARK II SEDIMENTATION & EROSION CONTROL PLAN

DRAFTING:	N.O.	CHECK:	C.P.
DESIGN:	C.P.	CHECK:	M.P.S.
SUBMITTAL PHASE:			
DATE:	6/27/2025		
KCI JOB #:	762305304		
SHEET:			

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARD COPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.



LEGEND


TEMPORARY SEDIMENT CONTROL FENCE	SCF
TEMPORARY ROCK FILTER DAM	RFD
TYPE 1 CONSTRUCTION EXIT	
CONCRETE WASHOUT PIT	
GRAVEL FILTER BAGS	
LIMITS OF CONSTRUCTION	LOC
GRADING SLOPE ARROW	
PROPOSED STAGING AREA	
POST CONSTRUCTION SEDIMENT CONTROL FENCE (PHASE 2)	PSCF

NOTE:

CONTRACTOR TO ENSURE POSITIVE DRAINAGE AT UPSTREAM & DOWNSTREAM ENDS OF PROJECT AND THAT NO PONDING WILL OCCUR.


S.W.P.P. GENERAL NOTES

1. THE CONTROL MEASURES CONTAINED HEREON (AND AS FURTHER DESCRIBED BY THE STANDARD SPECIFICATIONS) SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE CONSTRUCTION CONTRACT TO ASSURE EFFECTIVE AND CONTINUOUS WATER POLLUTION CONTROL DURING CONSTRUCTION AND POST CONSTRUCTION PERIODS.
2. A RAIN GAUGE SHALL BE PROVIDED BY THE CONTRACTOR AND LOCATED AT THE PROJECT SITE. THE CONTRACTOR AND INSPECTOR WILL INSPECT THE ENTIRE PROJECT TO DETERMINE THE CONDITION OF THE CONTROL MEASURES. SEDIMENT WILL BE REMOVED AND DEVICES REPAIRED AS SOON AS PRACTICABLE BUT NO LATER THAN 7 DAYS AFTER THE SURROUNDING EXPOSED GROUND HAS DRIED SUFFICIENTLY TO PREVENT FURTHER DAMAGE BEING CAUSED BY REPAIR OPERATIONS.
3. THE CONTRACTOR SHALL CLEAN PAVED SURFACES (ADJACENT TO THE CONSTRUCTION AREAS) AS NECESSARY TO REMOVE SEDIMENT WHICH HAS ACCUMULATED ON THE ROADWAY DUE TO STORMWATER FLOWS AND VEHICULAR TRAFFIC THROUGH AND ACROSS THE CONSTRUCTION SITE.
4. IN CASE OF FAILURE ON THE PART OF THE CONTRACTOR TO PREVENT AND CONTROL SOIL EROSION, SEDIMENTATION AND WATER POLLUTION WHICH MAY DEGRADE RECEIVING WATERS, THE DEVELOPER/OWNER RESERVES THE RIGHT TO EMPLOY OUTSIDE ASSISTANCE OR USE OTHER FORCES TO PROVIDE THE NECESSARY CORRECTIVE MEASURES. ALL COST (INCLUDING ENGINEERING) COST WILL BE DEDUCTED FROM ANY MONEYS DUE TO OR TO BECOME DUE TO THE CONTRACTOR.
5. UPON COMPLETION OF CONSTRUCTION AND THE INSTALLATION OF PERMANENT EROSION CONTROL METHODS, A FINAL EROSION CONTROL INSPECTION WILL BE PERFORMED AS PART OF ACCEPTANCE OF THE PROJECT BY THE DEVELOPER/OWNER. IN THE EVENT THAT THE PERMANENT EROSION CONTROL IS INADEQUATE DUE TO IMPROPER DESIGN OR INSTALLATION, THE PERMANENT EROSION CONTROL MEASURES MUST BE CORRECTED OR REDESIGNED TO FUNCTION PROPERLY.
6. THE NOTICE OF INTENT (N.O.I.) SHALL BE SIGNED AND SUBMITTED BY THE CONTRACTOR AT LEAST 48 HOURS PRIOR TO THE CONTRACTOR MOVING ONTO THE SITE.
7. THE CONTRACTOR SHALL SUBMIT A SIGNED NOTICE OF TERMINATION (N.O.T.)



J-HOOK DETAIL
SCALE: NTS

KCI TECHNOLOGIES, INC.
2806 W. BITTERS RD. SUITE 218
SAN ANTONIO, TEXAS 78248
PHONE: (210) 641-9899
FAX: (210) 641-6440
REGISTRATION #10573 / #101943-65



CHELSEA PARK II
SEDIMENTATION & EROSION CONTROL PLAN

DRAFTING:	N.O.	CHECK:	C.P.
DESIGN:	C.P.	CHECK:	M.P.S.
SUBMITTAL PHASE:			
DATE:	6/27/2025		
KCI JOB #:	762305304		
SHEET:			

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARD COPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

SITE DESCRIPTION

PROJECT LIMITS: 32.06 acre unit located south-west of the Interstate 35 N, Selma, Texas.

LATITUDE 29°35'18.90"N LONGITUDE 98°17'36.85"W

PROJECT DESCRIPTION: Construction of flood plain improvements including: drainage improvements.

MAJOR SOIL DISTURBING ACTIVITIES: Soil disturbing activities will include preparing right-of-way clearing, and grubbing, grading, excavation. Erosion and sediment controls.

TOTAL PROJECT AREA: 32.06 AC

TOTAL AREA TO BE DISTURBED: 29.07 AC out of 32.06 AC (91%)

WEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION): 0.35

WEIGHTED RUNOFF COEFFICIENT (POST-CONSTRUCTION): 0.35

EXISTING CONDITION OF SOIL & VEGETATIVE COVER AND % OF EXISTING VEGETATIVE COVER: The existing topsoil is dark greyish-brown silty clay. Existing Vegetation is 60% covered with underbrush.

NAME OF RECEIVING WATERS: The storm water will flow into the Dietz Creek Watershed.

SOIL STABILIZATION PRACTICES:

- TEMPORARY SEEDING
- PERMANENT PLANTING, SODDING, OR SEEDING
- MULCHING
- SOIL RETENTION BLANKET
- BUFFER ZONES
- PRESERVATION OF NATURAL RESOURCES

OTHER: Disturbed areas on which construction activity has ceased (temporarily or permanently) shall be stabilized within 14 days unless activities are scheduled to resume and do within 21 days.

STRUCTURAL PRACTICES:

- SILT FENCES
- HAY BALES
- ROCK BERMS
- DIVERSION, INTERCEPTOR, OR PERIMETER DIKES
- DIVERSION, INTERCEPTOR, OR PERIMETER SWALES
- DIVERSION DIKE AND SWALE COMBINATIONS
- PIPE SLOPE DRAINS
- PAVED FLUMES
- ROCK BEDDING AT CONSTRUCTION EXIT
- TIMBER MATTING AT CONSTRUCTION EXIT
- CHANNEL LINERS
- SEDIMENT TRAPS
- SEDIMENT BASINS
- STORM INLET SEDIMENT TRAP
- STONE OUTLET STRUCTURES
- CURBS AND GUTTERS
- STORM SEWERS
- VELOCITY CONTROL DEVICES

OTHER:

NARRATIVE - SEQUENCE OF CONSTRUCTION (STORM WATER MANAGEMENT) ACTIVITIES:

The order of activities will be as follows:

1. Install temporary control, establish limits of construction, install silt fence, construction entrance/exit, and concrete wash out area.

2. Clear and grub.

3. Excavate and Embank for flood plain.

4. When all construction activity is complete and the site is stabilized and approved by the project engineer, remove all temporary structural controls and stabilize areas disturbed by their removal.

5. The contractor is responsible for implementing and maintaining the storm water pollution prevention plan.

STORM WATER MANAGEMENT: Storm water drainage will be conveyed by existing drainage structures.

NON-STORM WATER DISCHARGE: Any water discharged on the site for approved non-storm water discharges, shall be per permit conditions. The source of the non-storm water water is from the San Antonio Water System and should have no detrimental effect on the site or downstream from the site.

EROSION AND SEDIMENT CONTROLS

OTHER EROSION AND SEDIMENT CONTROLS:

MAINTENANCE: All erosion and sediment controls will be maintained in good working order. If a repair is necessary, it will be done at the earliest date possible, but no later than 7 calendar days after the surrounding exposed ground has dried sufficiently to prevent further damage from heavy equipment. The areas adjacent to creeks and drainage ways shall have priority followed by devices protecting storm sewer inlets.

INSPECTION: An inspection will be performed by a designated inspector every week as well as after every half inch or more of rain (as recorded on a non-freezing rain management regulations. All trash and construction debris from the site will be deposited in the dumpster. The dumpster will be emptied as necessary or as required by local gauge to be located at the Project Site). An inspection and Maintenance Report will be made per each inspection. Based on the inspection results, the controls shall be located at the Project Site). An inspection and Maintenance Report will be made per each revised per the inspection report.

WASTE MATERIALS: All waste materials will be collected and stored in a secured metal dumpster. The dumpster will meet all state and local city solid waste regulations and the trash will be hauled to a local dump. No construction waste material will be buried on site.

HAZARDOUS WASTE (INCLUDING SPILL REPORTING): At a minimum, any products in the following categories are considered to be hazardous: paints, acids for cleaning masonry surfaces, cleaning solvents, asphalt products, chemical additives for soil stabilization or concrete curing compounds and additives. In the event of a hazardous material spill, the spill coordinator shall be contacted immediately.

SANITARY WASTE: All sanitary waste will be collected from portable units as necessary, or as required by local regulations by a Licensed Sanitary Waste Management Contractor.

OFFSITE VEHICLE TRACKING:

- HAUL ROADS DAMPENED FOR DUST CONTROL
- LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
- EXCESS DIRT ON ROAD REMOVED DAILY
- STABILIZED CONSTRUCTION ENTRANCE

PERMITS:

REMARKS: Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving waters. Disposal areas shall not be located in any wetland, waterbody or streambed. Construction staging areas and vehicle maintenance areas shall be constructed by the Contractor in a manner to minimize the runoff of pollutants. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting, falsework, piling, debris or other obstructions placed during construction operations that are not a part of the finished work.

OWNERS CERTIFICATION

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.


SIGNATURE DATE

CONTRACTOR'S CERTIFICATION

I certify under penalty of law that I understand the terms and conditions of the general Texas Pollutant Discharge Elimination System (TPDES) permit that authorizes the storm water discharges associated with industrial activity from the construction site identified as part of this certification plan.

SIGNATURE (CONTRACTOR) DATE



KCI TECHNOLOGIES, INC.
2806 W. BITTERS RD. SUITE 218
SAN ANTONIO, TEXAS 78248
PHONE: (210) 641-9899
FAX: (210) 641-6440
REGISTRATION #F-10573 / #101943-65



CHELSEA PARK II

SEDIMENTATION & EROSION CONTROL NARRATIVE

DRAFTING: N.O. CHECK: C.P.
DESIGN: C.P. CHECK: M.P.S.
SUBMITTAL PHASE:
DATE: 6/27/2025
KCI JOB #: 762305304
SHEET:



06/27/2025

MARY P. STEWART

REGISTERED PROFESSIONAL ENGINEER

Mary P. Stewart

KCI TECHNOLOGIES, INC.

2806 W. BITTERS RD. SUITE 218

SAN ANTONIO, TEXAS 78248

PHONE: (210) 641-9889

FAX: (210) 641-6440

REGISTRATION #10573 / #101943-65

KCI TECHNOLOGIES

CHELSEA PARK II

SEDIMENTATION & EROSION

CONTROL DETAILS

DRAFTING: N.O./CHECK: C.P.

DESIGN: C.P./CHECK: M.P.S.

SUBMITTAL PHASE:

DATE: 6/27/2025

KCI JOB #: 762305304

SHEET: 8