

**UNIT PRICE LIST FOR
CIBOLO CANYONS UNIT 9C**

CIBOLO CANYONS UNIT 9C		BIDDER	
DESCRIPTION	UNIT	QTY	UNIT AMOUNT
STREET IMPROVEMENTS			
Mobilization	LS	1	
Clearing	AC	30	
Street Excavation (Up to ROW)	CY	15,706	
Street Embankment (Up to ROW)	CY	3,503	
8.5" Flexible Base (Local A)	SY	15,889	
17" Flexible Base (Local B)	SY	2,121	
2" Type D Asphalt (Local A)	SY	14,256	
3" Type D Asphalt (Local B)	SY	1,930	
7" Standard Curb	LF	9,099	
Remove Header Curb & Barricade Posts	LF	40	
Concrete Sidewalk (Developer Responsibility)(Includes ADA Ramps)	SY	240	
Signage and Striping	LS	1	
TPDES Erosion Control Measures	LS	1	
SUBTOTAL			
DRAINAGE IMPROVEMENTS			
Drain Excavation	CY	526	
Drain Embankment	CY	3,373	
Concrete Baffle Blocks	CY	3	
24" Reinforced Concrete Pipe	LF	436	
30" Reinforced Concrete Pipe	LF	30	
24" HDPE	LF	112	
36" HDPE	LF	242	
Concrete Collars	CY	12	
5'x5' Junction Box	EA	4	
10' Curb Inlet	EA	2	
15' Curb Inlet	EA	4	
25' Curb Inlet	EA	2	
5' Sidewalk Box	EA	3	
6" Concrete Rip-Rap	SY	176	
Hydromulch	SY	384	
Sidewalk Pipe Railing	LF	16	
9" Rock Rubble	SY	7	
18" Rock Rubble	SY	116	
Trench Excavation Protection	LF	820	
SUBTOTAL			
SEWER			
8" Sanitary Sewer Pipe (PVC), SDR-26 160 PSI Rated			
a. 0' - 6'	LF	78	
b. 6' - 10'	LF	2,506	
c. 10' - 14'	LF	1,616	
d. 14' - 18'	LF	320	
6" Sanitary Sewer Lateral (SDR-26)	LF	3,907	
8"x6" Wyes	EA	106	
Standard Sanitary Sewer Manhole w/ Ring Encasement	EA	15	
Tie into Existing Manhole	EA	1	
Vertical Stack	VF	95	
Manhole Extra Depth	VF	52	
Trench Excavation Protection	LF	8,427	
TV Video Sewer Line	LF	4,520	
SUBTOTAL			

WATER				
8" C-900 Class 235 PVC (DR18) Pipe CL 235	LF	3,299		
8" DI Pipe (CL 350)	LF	28		
12" C-900 Class 235 PVC (DR18) Pipe CL 235	LF	1,377		
12" DI pipe (CL 350)	LF	16		
2" HDPE (DR 9)	LF	339		
2" DI Pipe (CL 350)	LF	17		
3/4" Single Service, Short w/ 5/8" meter	EA	70		
3/4" Single Service, Long w/ 5/8" meter	EA	36		
Standard Fire Hydrant Assembly	EA	9		
8" Gate Valve, MJ w/ Valve Box	EA	10		
12" Gate Valve, MJ w/ Valve Box	EA	5		
2" Blowoff (Permanent)	EA	1		
2" Blowoff (Temporary)	EA	1		
3/4" Irrigation Service w/ 5/8" meter	EA	5		
Tie Into Existing Water Main	EA	1		
Hydrostatic Testing	LS	1		
Fittings	TON	3		
Trench Excavation Protection	LF	5,076		
Joint Restraint	LS	1		
Chlorination	LF	5,076		
Meter Box	EA	111		
SUBTOTAL				
PRIVATE IMPROVEMENTS				
Lot Excavation	CY	40,708		
Lot Embankment	CY	46,426		
Walls (must match existing walls on Madera/Monteverde subdivision)	FF	11,731		
Wall Over Excavation	CY	970		
Haul off (if needed)	CY	4,608		
Construction Staking	LS	1		
Conduit Bundle A (2~ 6" PVC Sch 80, 2~4" PVC Sch 40)(Under drains)	LF	60		
Conduit Bundle B (3~ 6" PVC Sch 80, 2~4" PVC Sch 40)(Under drains)	LF	30		
Conduit Bundle C (1~10" PVC Sch 80, 1~ 6" PVC Sch 80, 2~4" PVC Sch 40)(Under drains)	LF	40		
Conduit Bundle D (1~10" PVC Sch 80, 2~ 6" PVC Sch 80, 2~4" PVC Sch 40)(Under drains)	LF	20		
SUBTOTAL				
TOTAL CIBOLO CANYONS UNIT 9C (ENCLAVE) BID				