

**Clear Creek Subdivision
Unit 1
Bid Form**

Page 1

Street Items						
Item Number	Description	Quantity	Unit	Unit Price	Total Price	
100.1 (COSA)	Mobilization (1 unit)	1	LS			
101.1 (COSA)	Prep. Right-Of-Way (1 unit)	1	LS			
101.1 (COSA)	Clearing and Grubbing	14	AC			
104.1 (COSA)	Excavation	26460	CY			
107.1 (COSA)	Embankment	12898	CY			
	Haul Off	13562	CY			
200.1 (COSA)	Flexible Base (12") local	7670	SY			
200.1 (COSA)	Flexible Base (15") Collector	3217	SY			
202.1 (COSA)	Prime Coat	2177	GAL			
203.1 (COSA)	Tack Coat	1089	GAL			
205.4 (COSA)	Hotmix (Type D) (3") local	7315	SY			
205.4 (COSA)	Hotmix (Type D) (3") Collector	2730	SY			
234.1 (COSA)	Base Reinforcement - Geogrid TX-5	10887	SY			
500.3 (COSA)	Conc. Cross Valley Gutter	253	SY			
500.4 (COSA)	Conc Curb and Gutter	4606	LF			
500.4 (COSA)	Header Curb	50	LF			
500.4 (COSA)	ADA Ramps	19	EA			
502.1 (COSA)	Concrete Sidewalk	853	SY			
510.1 (COSA)	Timber Guard Post	10	EA			
531 (COSA)	Stop Sign (R1-1)	5	EA			
531 (COSA)	Street Name Sign (R1-1)	7	EA			
Street Subtotal						

Drainage Items						
Item Number	Description	Quantity	Unit	Unit Price	Total Price	
401.1 (COSA)	24" RCP Class IV	1030	LF			
401.1 (COSA)	30" RCP Class IV	36	LF			
401.1 (COSA)	42" RCP Class IV	651	LF			
401.1 (COSA)	60" RCP Class IV	281	LF			
04626003 (TXDOT)	3'X2' MBC	40	LF			
04626003 (TXDOT)	4'X3' MBC	100	LF			
04626003 (TXDOT)	6'X3' MBC	286	LF			
403.14 (COSA)	5' Curb Inlet Extension	6	EA			
403.8 (COSA)	10' Curb Inlet	10	EA			
403.1 (COSA)	4'x4' Junction Box	1	EA			
403.2 (COSA)	5'X5' Junction Box	6	EA			
403.3 (COSA)	6'X6' Junction Box	1	EA			
403.3 (COSA)	6'X8' Junction Box	3	EA			
403.3 (COSA)	8'X8' Junction Box	1	EA			
505.1 (COSA)	5" Concrete Rip Rap	550	SY			
	6"-8" Rock Rip Rap	50	CY			
520.1 (COSA)	Hydromulch	2,447	SY			
522.1 (COSA)	Sidewalk Pipe Railing	243	LF			
540.6 (COSA)	Construction Exits	150	SY			
540.9 (COSA)	Silt Fence	3,786	LF			
540.1 (COSA)	Rock Filter Dam (Install) Type II	12	CY			
540.9 (COSA)	Gravel Filter Bags	120	LF			
540.9 (COSA)	4ft Wide Curlex Blanket	1,940	LF			
522.1 (COSA)	Concrete Sidewalk Bridge	20	LF			
307.1 (COSA)	Concrete Structure (Storm Drain Line A Outfall)	50	CY			
Drainage Subtotal						

**Clear Creek Subdivision
Unit 1
Bid Form**

Page 2

Sewer Items					
Item Number	Description	Quantity	Unit	Unit Price	Total Price
	Connect to Existing Manhole	1	EA		
506.1 (WW)	New Manhole 4' dia.	10	EA		
509 (WW)	Trench Protection	2,200	LF		
510.1 (WW)	Pipe, 8" Dia (PVC SDR-26) All Depths) Including Excavation and Backfill	452	LF		
510.1 (WW)	Pipe, 12" Dia (PVC SDR-26) All Depths) Including Excavation and Backfill	1,440	LF		
510.1 (WW)	Pipe, 15" Dia (PVC SDR-26) All Depths) Including Excavation and Backfill	308	LF		
510 (WW)	6" Sanitray Sewer Laterals	50	EA		
Sewer Subtotal					

Water Items					
Item Number	Description	Quantity	Unit	Unit Price	Total Price
509 (W)	Trench Protection	2,040	LF		
510.1 (W)	6" Ductile Iron Fire Lead	40	LF		
510.1 (W)	8" PVC C-900 Pipe DR 18	2,038	LF		
510 (W)	24" Steel Pipe Casing	43	LF		
510 (W)	1" Short Unmetered Single Service (Landscape)	1	EA		
510 (W)	1" Long Unmetered Single Service (Landscape)	1	EA		
510 (W)	1" Short Unmetered Single Service	32	EA		
510 (W)	1" Long Unmetered Single Service	19	EA		
510 (W)	Meter Box	53	EA		
510.15 (W)	Ductile Iron Fittings	1.0	TON		
511.1 (W)	6" Gate Valves	4	EA		
511.1 (W)	8" Gate Valves	9	EA		
511.1 (W)	2" Blowoff	2	EA		
511.2 (W)	Fire Hydrant Assembly (Complete)	4	EA		
Water Subtotal					

Dry Utilities					
Item Number	Description	Quantity	Unit	Unit Price	Total Price
	**Dry Utilities	1	LS		
Dry Utility Subtotal					

Total