

**Clear Creek Subdivision
Unit 2
Bid Form**

Page 1

Street Items					
Item Number	Description	Quantity	Unit	Unit Price	Total Price
100.1 (COSA)	Mobilization (1 unit)	1	LS		
101.1 (COSA)	Prep. Right-Of-Way (1 unit)	1	LS		
101.1 (COSA)	Clearing and Grubbing	13	AC		
104.1 (COSA)	Excavation	22230	CY		
107.1 (COSA)	Embankment	3385	CY		
	Haul Off	18845	CY		
	Concrete Retaining Wall (Vertical Face Foot)	7647	SF		
200.1 (COSA)	Flexible Base (12") local	5738	SY		
202.1 (COSA)	Prime Coat	1148	GAL		
203.1 (COSA)	Tack Coat	574	GAL		
205.4 (COSA)	Hotmix (Type D) (3") local	4695	SY		
234.1 (COSA)	Base Reinforcement - Geogrid TX-5	5738	SY		
500.4 (COSA)	Conc Curb and Gutter	3130	LF		
500.4 (COSA)	ADA Ramps	6	EA		
502.1 (COSA)	Concrete Sidewalk	32	SY		
510.1 (COSA)	Timber Guard Post	4	EA		
531 (COSA)	Street Name Sign (R1-1)	2	EA		
531 (COSA)	Street Striping	1	LS		
Street Subtotal					

Drainage Items					
Item Number	Description	Quantity	Unit	Unit Price	Total Price
401.1 (COSA)	24" RCP Class IV	423	LF		
401.1 (COSA)	30" RCP Class IV	367	LF		
401.1 (COSA)	18" RCP Class IV	102	LF		
403.14 (COSA)	10' Curb Inlet Extension	6	EA		
403.8 (COSA)	10' Curb Inlet	6	EA		
403.1 (COSA)	3'x3' Junction Box	2	EA		
403.2 (COSA)	4'X4' Junction Box	3	EA		
505.1 (COSA)	5" Concrete Rip Rap	76	SY		
520.1 (COSA)	Hydromulch	2,788	SY		
522.1 (COSA)	Sidewalk Pipe Railing	47	LF		
540.6(COSA)	Construction Exits	150	SY		
540.9 (COSA)	Silt Fence	3,275	LF		
540.1 (COSA)	Rock Filter Dam (Install) Type II	22	LF		
540.9 (COSA)	Gravel Filter Bags	264	LF		
540.9 (COSA)	4ft Wide Curlex Blanket	3,055	LF		
522.1 (COSA)	Concrete Sidewalk Bridge	25	LF		
Drainage Subtotal					

Sewer Items					
Item Number	Description	Quantity	Unit	Unit Price	Total Price
	Connect to Existing Sewer - Doghouse Manhole	2	EA		
506.1 (WW)	New Manhole 4' dia.	5	EA		
509 (WW)	Trench Protection	1,517	LF		
510.1 (WW)	Pipe, 8" Dia (PVC SDR-26) All Depths) Including Excavation and Backfill	1,517	LF		
510 (WW)	6" Sanitray Sewer Laterals	63	EA		
	Manufactured Sand Backfill	1,517	LF		
Sewer Subtotal					

Clear Creek Subdivision
Unit 2
Bid Form

Page 2

Water Items					
Item Number	Description	Quantity	Unit	Unit Price	Total Price
509 (W)	Trench Protection	1,603	LF		
510.1 (W)	6" Ductile Iron Fire Lead	39	LF		
510.1 (W)	8" PVC C-900 Pipe DR 18	1,603	LF		
510 (W)	1" Long Unmetered Single Service (Landscape)	1	EA		
510 (W)	1" Short Unmetered Single Service	30	EA		
510 (W)	1" Long Unmetered Single Service	32	EA		
510 (W)	Meter Box	63	EA		
510.15 (W)	Ductile Iron Fittings	1.0	TON		
511.1 (W)	6" Gate Valves	3	EA		
511.1 (W)	8" Gate Valves	3	EA		
511.2 (W)	Fire Hydrant Assembly (Complete)	3	EA		
Water Subtotal					

Dry Utilities					
Item Number	Description	Quantity	Unit	Unit Price	Total Price
	**Dry Utilities - Underground Conduit	1	LF		
	**Dry Utilities - Street Lights	1	EA		
Dry Utility Subtotal					

Total

Alternate					
Item Number	Description	Quantity	Unit	Unit Price	Total Price
	1-1/8" Gravel Backfill for Sanitary Sewer	1,517	LF		
	Rock Milling - Utilities	1,603	LF		
	Rock Milling - Street	1,565	LF		