

PRESERVE AT CULEBRA-UNIT 7
BEXAR COUNTY, TX

ITEM NO.	BID ITEM			UNIT PRICE	BID TOTAL
		UNIT	QUANTITY		
24050	ONSITE STREETS				
	1.5" Type D HMA	SY	849		
	2" Type D HMA	SY	3,867		
	2.5" Type C HMA	SY	849		
	11" Flex Base	SY	4,294		
	18.5" Flex Base	SY	943		
	Lime Stabilized Subgrade (6" Compacted Depth)	SY	4,294		
	Lime Stabilized Subgrade (8" Compacted Depth)	SY	943		
	Lime	TON	83		
	Prime Coat	GAL	1,047		
	Tack Coat	GAL	524		
	7" Concrete Curb	LF	2,590		
	4' Sidewalk	SY	39		
	Remove Existing Pavement, Curb, and Sidewalk	SY	180		
	Sidewalk Ramps	EA	8		
	Barricade Posts	EA	7		
	Header Curb	LF	34		
	Remove Header Curb and Barricade Posts	LF	40		
	Signage & Striping	LS	1		
	SUB-TOTAL				
21000	SANITARY SEWER				
	8" Sanitary Sewer Pipe (6'-10' Deep) (SDR-26)	LF	1,191		
	8" Sanitary Sewer Pipe (10'-14' Deep) (SDR-26)	LF	1,043		
	Tie to Existing Manhole	EA	1		
	Standard Manhole	EA	7		
	Manhole Extra Depth	VF	29.0		
	Concrete Ring Encasement	EA	7		
	8" x 6" Wye	EA	54		
	6" Sanitary Sewer Lateral (SDR-26)	LF	2,147		
	Trench Excavation Protection	LF	2,234		
	Camera Testing	LF	2,234		
	SUB-TOTAL				
23000	WATER DISTRIBUTION				
	8" PVC C-900, Class 235, DR18	LF	1,241		
	8" Gate Valve, MJ w/ Valve Box	LF	4		
	Standard Fire Hydrant Assembly	EA	3		
	Ductile Iron Fitting	Ton	0.5		
	1" Dual Service w/ 5/8" Meter (Short)	EA	12		
	1" Dual Service w/ 5/8" Meter (Long)	EA	14		
	3/4" Single Service w/ 5/8" Meter (Short)	EA	4		
	3/4" Single Service w/ 5/8" Meter (Long)	EA	3		
	2" Blowoff (Temporary)	EA	2		
	2" Blowoff (Permanent)	EA	1		
	Service Relay	EA	1		
	Hydrostatic Testing	LS	1		
	Chlorination	LF	1,241		
	Trench Excavation Protection	LF	1,241		
	Joint Restraints	LS	1		
	Plastic Meter Box with Lid	EA	59		
	SUB-TOTAL				
20080	EARTHWORK, CLEARING, AND SWPPP				
	Street Excavation	CY	3,220		
	Street Embankment	CY	170		
	Lot Excavation	CY	1,252		
	Lot Embankment	CY	4,022		
	Stockpile and Stabilize Excess Dirt Adjacent to Site	CY	280		
	TPDES	LS	1		
	Clearing (Streets)	AC	1.5		
	Clearing (Lots/Offsite Easements)	AC	6.9		
	SUB-TOTAL				
22000	ONSITE DRAINAGE				
	Precast Reinforced Concrete Box Culverts (4'X2')	LF	86		
	10' Type CI Curb Inlet	EA	2		

	Concrete Headwall	CY	3.9		
	5" Concrete Rip-Rap	SY	5		
	6" Concrete Rip-Rap	SY	50		
	Trench Excavation Protection	LF	86		
	Concrete Collars	CY	1.8		
	Rock Rubble	SY	19		
	SUB-TOTAL				
25060	CONDUITS				
	1-6" SCH 80 & 2-4" SCH 40 Bundle	LF	900		
	2-6" SCH 80 & 2-4" SCH 40 Bundle	LF	60		
	SUB-TOTAL				
	Testing	LS			
	Construction Staking	LS			
	SUB-TOTAL				
22000	ONSITE DRAINAGE ALTERNATE				
	30" RCP (Class III)	LF	121		
	30" UFCMP	LF	27		
	SUB-TOTAL				
	GRAND TOTAL				