

**THE ENCLAVE AT HIDEAWAY VILLAGE  
BID QUANTITIES**

**SITE WORK**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Clearing and Grubbing	AC.	14.28	\$	-
2	Stabilized Construction Entrance/Exit	E.A.	1	\$	-
3	Silt Fence	L.F.	2,390	\$	-
4	Gravel Filter Bags	L.F.	54	\$	-
5	Rock Filter Dam - Type II	L.F.	38	\$	-
6	Construction Staging Area	E.A.	1	\$	-
7	Concrete Washout Pit	E.A.	1	\$	-
8	Lot Excavation	C.Y.	20,157	\$	-
9	Lot Embankment (79G requirement)	C.Y.	29,044	\$	-
10	Import Material	C.Y.	7009	\$	-
				<b>TOTAL COST</b>	<b>\$ -</b>

**SANITARY SEWER IMPROVEMENTS**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Tie into Existing Sanitary Sewer Main	EA.	1	\$	-
2	Trench Excavation Safety Protection	L.F.	1,913	\$	-
2	8" Sanitary Sewer Pipe, SDR-26 (0'-6')	L.F.	507	\$	-
3	8" Sanitary Sewer Pipe, SDR-26 (6'-10')	L.F.	1,406	\$	-
4	Standard Sanitary Sewer Manhole	EA.	12	\$	-
5	Reconstruct/Recoat Existing Manhole	EA.	1	\$	-
6	Extra Depth Manhole	V.F.	8.8	\$	-
7	6" Sanitary Sewer Laterals, SDR-26	L.F.	1,928	\$	-
8	8" Sewer Main Television Inspection	L.F.	1,913	\$	-
9	Vertical Stacks	V.F.	8.6	\$	-
				<b>TOTAL COST</b>	<b>\$ -</b>

**ON-SITE WATER MAIN IMPROVEMENTS**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Water Main Tie-In	EA.	2	\$	-
2	Trench Excavation Protection	L.F.	3,135	\$	-
3	8" Pipe, C900 DR 18 PVC Class 235 (Includes Joint Restraints)	L.F.	2,755	\$	-
4	2" Pipe, HDPE DR 9	L.F.	276	\$	-
5	8" DI Pipe	L.F.	104	\$	-
6	2" Permanent Blow-Offs	EA.	2	\$	-
7	2" Temporary Blow-Offs	EA.	2	\$	-
8	8" Gate Valve, M.J. (Complete with Restraints)	EA.	10	\$	-
9	Standard Fire Hydrant (Complete with Tee, Valve, Bends and Restraints)	EA.	4	\$	-
10	3/4" Single Service with 5/8" Meter : Short	EA.	28	\$	-
11	3/4" Single Service with 5/8" Meter : Long	EA.	22	\$	-
12	Irrigation Service with 3/4" Meter : Short	EA.	1	\$	-
13	D.I. Fittings (Restrained)	TON.	2.5	\$	-
14	Hydrostatic Testing	EA.	1	\$	-
15	Meter Boxes	EA.	51	\$	-
				<b>TOTAL COST</b>	<b>\$ -</b>

**STREET IMPROVEMENTS (ONSITE)**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Street/Excavation	C.Y.	4,992	\$	-
2	Street/Embankment	C.Y.	7,001	\$	-
3	Lime Stabilization (6") (includes lime)	S.Y.	7,508	\$	-
4	Lime Stabilization (8") (includes lime)	S.Y.	2,024	\$	-
5	Flexible Base (8" Compacted) (Local A)	S.Y.	7,508	\$	-
6	Flexible Base (18.5" Compacted) (Local B)	S.Y.	2,024	\$	-
6	Flexible Base (5" Compacted) (Local A Modified)	S.Y.	146	\$	-
7	Prime Coat	GAL.	2,145	\$	-
8	Tack Coat	GAL.	1,072	\$	-

9	HMAC - Type D (3" Pavement Thickness) (Local A)	S.Y.	6,718	\$	-
10	HMAC - Type D (2" Pavement Thickness) (Local A Modified)	S.Y.	130	\$	-
12	HMAC - Type D (1.5" Pavement Thickness) (Local B)	S.Y.	1,874	\$	-
11	HMAC - Type B (4" Pavement Thickness) (Local A Modified)	S.Y.	130	\$	-
13	HMAC - Type C (1.5" Pavement Thickness) (Local B)	S.Y.	1,874	\$	-
14	Machine Laid Curb	L.F.	5,145	\$	-
15	Concrete Sidewalk (By Developer)	S.Y.	485	\$	-
16	ADA Ramps (By Developer)	EA.	9	\$	-
17	Stop Sign	EA.	3	\$	-
18	Street Name Signs	EA.	6	\$	-
19	End of Road Markers	EA.	6	\$	-
20	Blue Raised Pavement Marker	EA.	4	\$	-
21	Header Curb	L.F.	60	\$	-
				<b>TOTAL COST</b>	<b>\$ -</b>

**DRAIN A**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	24" R.C.P.	LF	657	\$	-
2	15' Type C2 Curb Inlet	EA	1	\$	-
3	15' Type C1 Curb Inlet	EA	1	\$	-
4	Junction Box 4'X4'	EA	2	\$	-
5	Concrete Collars	CY	2	\$	-
				<b>TOTAL COST</b>	<b>\$ -</b>

**DRAIN B**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	6" Concrete Rip-rap	S.Y.	48	\$	-
2	2'X6' Precast SBCE	L.F.	76	\$	-
3	Headwalls/Wingwalls	CY	8	\$	-
4	Baffle Blocks	CY	1	\$	-
5	Pipe Railing	L.F.	50	\$	-
				<b>TOTAL COST</b>	<b>\$0.00</b>

**DRAIN C**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	6" Concrete Rip-rap	S.Y.	20	\$	-
2	24" R.C.P. Class IV	L.F.	165	\$	-
3	Headwall	E.A.	2.5	\$	-
4	Pipe Railing	L.F.	9	\$	-
				<b>TOTAL COST</b>	<b>\$0.00</b>

**CZP**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	8'x12' Jellyfish Filter	E.A.	1	\$	-
2	3'x3' Junction Box	E.A.	1	\$	-
3	24" PVC	L.F.	200	\$	-
4	6" Concrete Rip-rap	S.Y.	8	\$	-
				<b>TOTAL COST</b>	<b>\$0.00</b>

**ADDITIVE ITEM**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Conduit Bundle (2-6" PVC & 2-4" PVC)	L.F.	200	\$	-
2	Conduit Bundle (1-6" PVC & 2-4" PVC)	L.F.	300	\$	-

---

TOTAL COST \$0.00