
GATES SUBDIVISION UNIT 1

BEXAR COUNTY, TX

STREET, DRAINAGE, WATER, SANITARY SEWER, AND UTILITY IMPROVEMENTS

SHEET INDEX				
Sheet Title	Sheet Number			
COVER SHEET	0.0			
OVERALL UTILITY PLAN (SHEET 1 OF 2)	1.0			
OVERALL UTILITY PLAN (SHEET 2 OF 2)	1.1			
MASTER DRAINAGE PLAN	2.0			
OVERALL GRADING PLAN (SHEET 1 OF 2)	3.0			
OVERALL GRADING PLAN (SHEET 2 OF 2)	3.1			
PRIVATE DRAIN "A" PLAN & PROFILE	4.0			
PRIVATE DRAIN "B" PLAN & PROFILE	4.1			
PRIVATE DRAIN "C" PLAN & PROFILE (SHEET 1 OF 3)	4.2			
PRIVATE DRAIN "C" PLAN & PROFILE (SHEET 2 OF 3)	4.3			
PRIVATE DRAIN "C" PLAN & PROFILE (SHEET 3 OF 3)	4.4			
PRIVATE DRAIN "D" PLAN & PROFILE	4.5			
PRIVATE DRAIN "E" PLAN & PROFILE	4.6			
PRIVATE DRAIN "F" PLAN & PROFILE	4.7			
DRAIN DETAILS (SHEET 1 OF 4)	4.8			
DRAIN DETAILS (SHEET 2 OF 4)	4.9			
DRAIN DETAILS (SHEET 3 OF 4)	4.10			
DRAIN DETAILS (SHEET 4 OF 4)	4.11			
TEMPORARY INTERCEPTOR DRAIN "G" & "H" PLAN & PROFILE	4.12			
TEMPORARY INTERCEPTOR DRAIN "I" & "J" PLAN & PROFILE	4.13			
TEMPORARY INTERCEPTOR DRAIN "K" & "L" PLAN & PROFILE	4.14			
FIELDSTONE WAY PLAN & PROFILE (SHEET 1 OF 2)	5.0			
FIELDSTONE WAY PLAN & PROFILE (SHEET 2 OF 2)	5.1			
KAILORS COVE AND SUNRIDGE HTS PLAN & PROFILE	5.2			
INGRESS AVE PLAN & PROFILE	5.3			
INGRESS AVE CUL-DE-SAC DETAIL	5.4			
KINSLEY WAY PLAN & PROFILE	5.5			
FIREWEED CT PLAN & PROFILE	5.6			
TROJAN TRAIL & HASTINGS WAY PLAN & PROFILE	5.7			
KESTIS LN & HAWKWELL LN PLAN & PROFILE	5.8			
TYPICAL STREET DETAILS	5.9			
CONCRETE DRIVEWAY DETAILS	5.10			




LOCATION MAP NOT-TO-SCALE

OWNER INFORMATION
MEH HOLDING COMPANY LTD
5210 THOUSAND OAKS, STE. 1318
SAN ANTONIO, TX 78233

SHEE	I INDEX

Sheet Title	Sheet Number
WHEELCHAIR RAMP DETAILS	5.11
TXDOT PEDESTRIAN CURB RAMP DETAIL	5.12
TRAFFIC SIGNAGE & PEDESTRIAN ACCESSIBILITY PLAN (SHEET 1 OF 2)	5.13
TRAFFIC SIGNAGE & PEDESTRIAN ACCESSIBILITY PLAN (SHEET 2 OF 2)	5.14
TRAFFIC SIGNAGE DETAILS (SHEET 1 OF 2)	5.15
TRAFFIC SIGNAGE DETAILS (SHEET 2 OF 2)	5.16
PAVEMENT MARKING DETAILS (SHEET 1 OF 2)	5.17
PAVEMENT MARKING DETAILS (SHEET 2 OF 2)	5.18
SANITARY SEWER COVER SHEET	6.0
OVERALL SANITARY SEWER PLAN (SHEET 1 OF 2)	6.1
OVERALL SANITARY SEWER PLAN (SHEET 2 OF 2)	6.2
LINE "A" PLAN & PROFILE (SHEET 1 OF 2)	6.3
LINE "A" PLAN & PROFILE (SHEET 2 OF 2)	6.4
LINE "B" PLAN & PROFILE	6.5
LINE "C', "D" & "E" PLAN & PROFILE	6.6
LINE "F" & "G" PLAN & PROFILE	6.7
LINE "H', "I' & "K" PLAN & PROFILE	6.8
LINE "J" PLAN & PROFILE	6.9
WATER DISTRIBUTION COVER SHEET	7.0
WATER DISTRIBUTION PLAN (SHEET 1 OF 2)	7.1
WATER DISTRIBUTION PLAN (SHEET 2 OF 2)	7.2
WATER DISTRIBUTION DETAILS (SHEET 1 OF 5)	7.3
WATER DISTRIBUTION DETAILS (SHEET 2 OF 5)	7.4
WATER DISTRIBUTION DETAILS (SHEET 3 OF 5)	7.5
WATER DISTRIBUTION DETAILS (SHEET 4 OF 5)	7.6
WATER DISTRIBUTION DETAILS (SHEET 5 OF 5)	7.7
STORM WATER POLLUTION PREVENTION PLAN (SHEET 1 OF 2)	8.0
STORM WATER POLLUTION PREVENTION PLAN (SHEET 2 OF 2)	8.1
STORM WATER POLLUTION PREVENTION DETAILS	8.2







SHEET REVISION LOG


DATE SHEET REVISION NO. DESCRIPTION


4/18/2022 5.0 1 REVISED CURB RETURN STATIONS













LEGEND

STUDY POINT DRAINAGE AREA BOUNDARY

---- EXISTING CONTOURS

PROPOS

FLOW AF

	CLAYTON J. LINNEY		
NG CONTOURS	111543 CENSEO		
SED UNIT	Cayte hung		
ARROW	3/17/223		


Study Point		(Acres)	С	T _{ovrl} (min)	1	T _{sc} (min)	T. /min	T /min)	I (in/hr)	li /in/hel	l (in/hr	VO (5+3/5)	O (5+3/-)	0 15+31
J. 174.00							T _{ch} (min)	T _{tot} (min)						Q ₁₀₀ (ft ³ /s
1	A-1	4.22	0.75	9.00		3	1	13	5.61	7.82	9.76	17.76	24.75	30.89
2	A-2	3.59	0.75	9.00		3	1	13	5.61	7.82	9.76	15.11	21.05	26.28
3	A-3	3.09	0.75	9.00		4	0	13	5.61	7.82	9.76	13.01	18.12	22.62
	Control of the	Charles II		Ulatari	CARRYOVER			7	110		1.0	10.70		
4	PT. 3 + A-4	12.73	0.76	10.00	FROM PT. 3	3	1	14	5.42	7.53	9.39	52.56	72.94	91.00
	A-4	9.64	0.77					1-2 -1	1 The state				11. 7 =	
5	A-5	10.98	0.75	9.00		4	3	16	5.06	6.99	8.71	41.70	57.54	71.70
6	A-6	11.92	0.75	9.00		6	2	17	4.91	6.76	8.42	43.86	60.46	75.27
7	A-7	13.01	0.75	9.00		8	2	19	4.63	6.37	7.93	45.21	62.20	77.35
					CARRYOVER									
8	PT. 6 + A-8	14.94	0.75	10.00	FROM PT. 4	7	0	17	4.91	6.76	8.42	54.98	75.77	94.34
	A-8	3.02	0.75											
9	A-9	5.89	0.75	9.00		4	2	15	5.24	7.24	9.03	23.15	31.98	39.88
10	A-10	7.12	0.75	9.00		5	1	15	5.24	7.24	9.03	27.98	38.66	48.21
11	A-11	8.06	0.75	9.00		5	1	15	5.24	7.24	9.03	31.68	43.77	54.57
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	0.00	0.75	3.00	CARRYOVER			15	3.24	7.24	3.03	31.00	45.77	34.37
12	PT. 11 + A-12	10.04	0.75	10.00	FROM PT. 9	5	2	17	4.91	6.76	8.42	36.94	50.92	63.40
44	A-12	1.98	0.75	10.00	TROWIT 1. 5	-		17	4.31	0.70	0,42	30.94	30.92	05.40
	A-12	1.50	0.75	-		-								
					CARRYOVER				7 - 1	1000				
13	PT. 10+ PT. 11	17.16	0.75	10.00	FROM PT. 10	7	0	17	4.91	6.76	8.42	63.14	87.03	108.36
14	A-14	6.28	0.82	9.00	THOMIT II. 10	6	2	17	4.91	6.76	8.42	25.12	34.62	43.11
15	A-15	7.57	0.75	9.00		6	2	17	4.91	6.76	8.42	27.86	38.39	47.80
16	A-16	6.44	0.75	9.00		5	1	15	5.24	7.24	9.03			
17	A-17	9.00	0.75	9.00			-					25.31	34.97	43.60
1/	A-17	9.00	0.75	9.00	CARRYOVER	4	0	13	5.61	7.82	9.76	37.88	52.77	65.88
10	DT 14: DT 15: 4 10	24.42	0.77	40.00	CARRYOVER			25	20.00	100.05	22:	5:00	CYTE LA	1.65 %
18	PT. 14+ PT. 15 + A-18	21.42	0.77	10.00	FROM PT. 12	7	3	20	4.51	6.21	7.71	74.38	102.24	127.08
	A-18	7.57	0.75											
19	A-19	5.12	0.75	9.00		4	0	13	5.61	7.82	9.76	21.55	30.02	37.48
	PT. 17 + PT. 18 +				CARRYOVER									1.0
20	PT. 19 + A-20	40.29	0.75	10.00	FROM PT. 16	10	2	22	4.30	5.91	7.34	130.02	178.48	221.67
	A-20	4.75	0.75					100.00						i coc
21	A-21	3.96	0.75	9.00		4	1	14	5.42	7.53	9.39	16.11	22.35	27.89
22	A-22	4.40	0.75	9.00		4	1	14	5.42	7.53	9.39	17.89	24.83	30.98
23	A-23	4.21	0.75	9.00		4	1	14	5.42	7.53	9.39	17.12	23.76	29.65
				1	CARRYOVER									
24	PT. 16 + A-24	10.32	0.75	10.00	FROM PT. 14	5	2	17	4.91	6.76	8.42	37.98	52.34	65.17
	A-24	3.88	0.75						3752			01.50	02.0.	55117
					CARRYOVER									
25	PT. 23 + PT.24	14.53	0.75	10.00	FROM PT. 22	7	0	17	4.91	6.76	8.42	53.47	73.69	91.75
	11,25 111,24	14.55	0.73	10.00	CARRYOVER	,	0	1/	4.31	0.70	0.42	33.47	73.09	91.75
26	PT. 22 + PT. 25 + A-26	22.52	0.75	10.00		7	1	10	4.70	C FC	0.16	00.46	110.70	127.04
20				10.00	FROM PT. 23	/	1	18	4.76	6.56	8.16	80.46	110.78	137.84
27	A-26	3.59	0.75	0.00					1.40	2.22		122.12		
	A-27	9.11	0.75	9.00		5	3	17	4.91	6.76	8.42	33.52	46.20	57.53
28	A-28	8.13	0.75	9.00		4	2	15	5.24	7.24	9.03	31.95	44.15	55.04
29	A-29	1.61	0,91	14.00		2	0	16	5.06	6.99	8.71	7.42	10.24	12.76
30	A-30	9.92	0.75	9.00		6	1	16	5.06	6.99	8.71	37.68	51.99	64.78
31	PT.29 + A-31	5.04	0.87	9.00		3	2	14	5.42	7.53	9.39	23.77	32.98	41.15
	A-31	3.43	0.85											
				100	CARRYOVER									
32	PT. 30 +PT. 31	14.96	0.84	10.00	FROM PT. 29	6	1	17	4.91	6.76	8.42	61.65	84.97	105.79
33	A-33	9.17	0.75	9.00		4	1	14	5.42	7.53	9.39	37.29	51.76	64.57
					CARRYOVER							81.186		2 314.
34	PT. 32 + PT.34	19.29	0.78	10.00	FROM PT. 30	7	2	19	4.63	6.37	7.93	69.83	96.06	119.46
	A-34	4.33	0.75	10.00	111011111111	-	- 2	1.5	4.03	0.57	7.33	03.63	30.00	119.40
25				0.00		2	2	45	5.24	7.24	0.00	24.76	24.24	10.55
35	A-35	6.30	0.75	9.00		3	3	15	5.24	7.24	9.03	24.76	34.21	42.65
20	DT 22 DT 24		4 44	10000	CARRYOVER			77			Tetas -	100		
36	PT. 33 + PT. 34 + A-36	31.52	0.77	10.00	FROM PT. 32	9	1	20	4.51	6.21	7.71	109.44	150.44	186.99
	A-36	3.06	0.75			1 4 7						-26		1
37	A-37	6.62	0.75	9.00		6	1	16	5.06	6.99	8.71	25.14	34.69	43.23
38	A-38	5.49	0.75	9.00		3	1	13	5.61	7.82	9.76	23.11	32.19	40.19
39	A-40	69.37	0.80	19.00	plant and an arrangement	7	5	31	3.62	4.96	6.14	201.02	275.30	341.36


PLAT NO. 21-11800645 JOB NO.:205-43-04

SUBDIVISION UNIT BEXAR COUNTY, TX


GATE


- 1. ELEVATION SHOWN ON FOUNDATION IS FOR FINISHED FLOOR.
- 2. CONTRACTOR SHALL PROVIDE OWNER ALL NECESSARY DENSITY TESTS FOR FILL LOTS AS REQUIRED BY HUD SPECIFICATIONS.
- 3. HOME BUILDER SHALL REFER TO THE APPROVED SUBDIVISION PLAT TO CONFIRM ALL BUILDING SETBACKS PRIOR TO ANY
- 4. AS SOON AS PRACTICAL HOME BUILDER SHALL ESTABLISH VEGETATION (HYDROMULCH, SEEDING, SODDING, ETC...) TO PREVENT EROSION FROM OCCURRING.
- 5. CONTRACTOR SHALL CONTACT ENGINEER REGARDING ANY QUESTIONS ON THE INTENT OF THIS PLAN.
- 6. POSITIVE DRAINAGE SHALL BE MAINTAINED ON ALL SURFACE AREAS WITHIN THE SCOPE OF THIS PROJECT. DRAINAGE SHALL BE DIRECTED AWAY FROM ALL BUILDING FOUNDATIONS AND TOWARDS THE PROPER DRAINAGE EASEMENT OR STREET RIGHT OF WAY ACCORDING TO THE MASTER DRAINAGE PLAN FOR THE PROJECT. CONTRACTOR SHOULD TAKE PRECAUTIONS NOT TO ALLOW PONDING OF WATER.
- 7. ALL ELEVATIONS AND CONTOURS SHOWN ON THIS GRADING PLAN REFLECT FINISHED GRADES. THE THICKNESS OF PAVEMENT, CURBS, AND SIDEWALKS MUST BE SUBTRACTED TO OBTAIN SUBGRADE ELEVATIONS.
- 8. GRADING PLAN IS INTENDED FOR USE IN LOT GRADING ONLY. CONTRACTOR SHOULD REFER TO CONSTRUCTION DRAWINGS FOR ALL OTHER GRADES, INCLUDING, BUT NOT LIMITED TO, CHANNELS, ROADS, AND DETENTION PONDS.
- 9. CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE ALL SWALES.















FOUNDATION F.F.

TYPICAL SIDE YARD GRADING N.T.S.

FOUNDATION F.F







LOCATION MAP NOT-TO-SCALE

LEGEND


E, G, T, & TV. E. = GAS, ELECTRIC, TELEPHONE, CABLE T.V. EASEMENT





= LOT GRADE TYPE




= PROPOSED DRIVEWAY LOCATION








2



SUBDIVISION BEXAR COUNTY, TX

PLAT NO. 21-11800645 JOB NO.:205-43-04



PLAT NO. 21-11800645

JOB NO.:205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:CL

SHEET NUMBER:

MATCH PROPOSED -NOTE: GRADE 1. ALL CONCRETE SHALL DEVELOP A MINIMUM COMPRESSIVE STRENGTH OF NOT LESS THAN 3000 PSI IN 28 DAYS. 2. ANY DISTURBED AREAS WILL BE VEGETATED BY SEEDING OR SODDING. EIGHTY-FIVE PERCENT OF THE DISTURBED SURFACE AREA MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT. 1/4" PER FT. MIN. 2.0' MIN @ 2% MAX ② GRADE TO NATURAL GROUND. 3:1 SLOPE MAX. __6" CONC. RIP-RAP W/ #4 BARS 3 1/4" PER FT. MIN. 15' MIN @ 2% MAX @ 12" O.C.E.W. AND 2" MIN. GRAVEL CUSHION

> SECTION "A1-A1" STA. 1+46.40 - STA. 1+50.97 N.T.S.

5'-2" MINIMUM 12" X 12" TBAR

TYPICAL SIDEWALK BRIDGE &

SIDEWALK PIPE RAILING SECTION

N.T.S.

20.0 LINEAR FEET OF HAND RAIL. SEE THIS SHEET FOR DETAIL. TRANSITION SIDEWALK TO RAILING TRANSITION SIDEWALK TO MATCH TOP OF SIDEWALK MATCH TOP OF SIDEWALK ± 6' - 3" BOX @ 5% MAX 5 - #4 BARS FULL LENGTH SEE CURB ARMOR #4 BARS @ 12" O.C. 10 - #4 BARS 6' CONCRETE SIDEWALK **FULL LENGTH** 6' CONCRETE SIDEWALK (5" O.C.) #4 BARS @ 12" O.C. -#4 BARS @ 8" O.C. 6" #4 BARS @ 18" O.C.E.W. 618.06 618.08 NO. 4 BARS @ 18" O.C. DOWELED INTO SLAB SECTION "A2-A2" 6" CONC. RIP RAP N.T.S. SIDEWALK BOX DETAIL N.T.S. 24" TOE-DOWN 3/8" FILLET WELD &
GROUND SMOOTH— 2 1/2" DIA. -3" DIA. 90° ELBOW OR 4" DIA. 90° ELBOW 3" DIA, DOUBLE - EXTRA STRONG STANDARD POST OR 4" DIA. STANDARD STEEL PIPE DETAIL OF 90° WELDING ELBOWS N.T.S. * A NEAT END SECTION, SATISFACTORY TO THE ENGINEER, FROM SUBMITTED SHOP 4 - 5/8" DIA. DOWELS BARS BUTT WELDED TO BOTTOM OF PLATE DRAWINGS, MAY BE USED IN LIEU OF THE 90° WELDING ELBOW 90° WELDING ELBOWS -------


~----

FOR VERTICAL WALLS

TOTAL LENGTH OF BAR TO BE 30 DIAMETERS

PIPE ANCHORAGE DETAILS

N.T.S.



CLAYTON J. LINNEY 3 17 2023

PLAT NO. 21-11800645 JOB NO.:205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:CL

GA

SHEET NUMBER:

-GALVANIZED CURB

-1/2" HOLES @

5/16" X 1'-0 PLATE


CURB ARMOR DETAIL


N.T.S.


ARMOR 5/16" STEEL PLATE


1/2" DIA. X 3" STUD

ANCHOR 12" O.C.












CLAYTON J. LINNEY 3/11/2023


> 3 DRAIN


PLAT NO. 21-11800645 JOB NO.:205-43-04












THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL





SUBDIVISION GA


CLAYTON J. LINNEY

6/13/2023


PLAT NO. 21-11800645 JOB NO.:205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:CL SHEET NUMBER







THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAF





CLAYTON J. LINNEY

3. 111543

CENSED

ONAL ENGL

4 | 25 | 2522


GATES SUBDIVISION UNIT BEXAR COUNTY, TX 4


OF

S

S

PLAT NO. 21-11800645 JOB NO.:205-43-04





THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

ENGINEERS + SURVEYING
3421 Paesanos Pkwy, Suite 200, San Antonio, TX 78231
Phone #: (210) 979-8444 • Fax #: (210) 979-8441
TBPE Firm #: 9513 • TBPLS Firm #: 10122300



ES SUBDIVISION UNIT 1

O

3


SHI

7AIL

PLAT NO. 21-11800645 JOB NO.:205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:CL

DRAWN:OM CHECKED:CL
SHEET NUMBER:

4.10



THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

Product Data LANDLOK 300⁶

LANDLOK 300® turf reinforcement mat (TRM) is a three-dimensional, lofty, woven polypropylene geotextile that is available in green or tan which is specially designed for erosion control applications on steep slopes and vegetated waterways. The matrix is composed of polypropylene monofilament yarns featuring X3® technology woven into a uniform configuration of resilient pyramid-like projections. The material exhibits very high interlock and reinforcement capacity with both soil and root systems, demonstrates superior UV resistance, and enhances seedling emergence.

LANDLOK 300® conforms to the property values listed below¹ and is manufactured at a Propex facility having achieved ISO 9001:2000 certification. Propex performs internal Manufacturing Quality Control (MQC) tests that have been accredited by the Geosynthetic Accreditation Institute - Laboratory Accreditation Program (GAI-LAP). This product is NTPEP approved for AASHTO standards.

		M	IARV ²
PROPERTY	TEST METHOD	ENGLISH	METRIC
ORIGIN OF MATERIALS			
% U.S. Manufactured Inputs		100%	100%
% U.S. Manufactured		100%	100%
PHYSICAL			
Mass/Unit Area	ASTM D-6566	7.5 oz/yd ²	254.3 g/m ²
Thickness	ASTM D-6525	0.25 in	6.35 mm
Light Penetration (% Passing)	ASTM D-6567	50% (Max)	50%
Color	Visual	Gree	n or Tan
MECHANICAL			
Tensile Strength (Grab)	ASTM D-6818	2000 x 1800 lb/ft	29.2 x 26.3 kN/m
Elongation	ASTM D-6818	50% (max)	50% (max)
Resiliency	ASTM D-6524	70%	70%
Flexibility	ASTM D-6575	0.195 in-lb (avg)	225,000 mg-cm (avg
ENDURANCE			
UV Resistance % Retained 3000 hrs	ASTM D-4355	90%	90%
PERFORMANCE			
Velocity ³ (Vegetated)	Large Scale	20 ft/sec	6.10 m/sec
Shear Stress ³ (Vegetated)	Large Scale	12 lb/ft ²	575 Pa
Manning's "n" 4 (Unvegetated)	Calculated	0.030	0.030
Seedling Emergence ⁴	ECTC Draft Method #4	•	*
ROLL SIZES		8.5 ft x 106 ft	2.6 m x 32.3 m


- 1. The property values listed are effective 04/2011 and are subject to change without notice. 2. MARV indicates minimum average roll value calculated as the typical minus two standard deviations. Statistically, it yields a 97.7% degree of confidence that any sample taken
- during quality assurance testing will exceed the value reported. 3. Maximum permissible velocity and shear stress has been obtained through vegetated testing programs featuring specific soil types, vegetation classes, flow conditions, and
- failure criteria. These conditions may not be relevant to every project nor are they replicated by other manufacturers. Please contact Propex for further information. 4. Calculated as typical values from large-scale flexible channel lining test programs with a flow depth of 6 to 12 inches.



LANDLOK

TESTED, PROVEN, TRUSTED, www.geotextile.com

Propex Operating Company, LLC · 6025 Lee Highway, Suite 425 · PO Box 22788 · Chattanooga, TN 37422 ph 423 899 0444 · ph 800 621 1273 · fax 423 899 7619



PLAT NO. 21-11800645 JOB NO.:205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:CL SHEET NUMBER.

TRENCH EXCAVATION SAFETY PROTECTION CAUTION!!: CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL THE CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITED DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT. CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. REMAINING PORTION OF 257.33 ACRES (DOC #20190051458 O.P.R.) 50' x 50' ELEC., GAS, TELE., OWNER: MEH HOLDING COMPANY LTD CATV., WATER, SANITARY SEWER & DRAINAGE EASEMENT. OFF-LOT 35' PRIVATE MATCH EXISTING (ENTIRE EASEMENT TO 2.0' - 4.5' - 4.5' - 2.0' -DRAINAGE EASEMENT GROUND @ 3:1 MAX EXPIRE UPON INCORPORATION INTO PLATTED STREET R.O.W.) SECTION "G1-G1" STA. 1+34.57- STA. 2+45.53 -4' SIDEWALK MATCH EXISTING 2.0' - 4.5' - 4.5' - 2.0' -GROUND @ 3:1 MAX TEMPORARY INTERCEPTOR DRAIN "G" HORZ SCALE: 1"=20' STA: 1+30.00 - END VERT SCALE: 1"=5" STA. 1+34.57- STA. 2+43.51 PROPOSED TOP OF DRAIN -620 NATURAL GROUND RT — NATURAL GROUND CL 🕇 615 115.53 L.F. ~ EARTHEN "V" CHANNEL @ 0.50% 4.58 L.F. ~ EARTHEN "V" CHANNEL @ 33.33% 610 EARTHEN "V" CHANNEL STA. 1+30.00 TO STA. 2+45.53 HYDRAULIC CALCULATION 605 Q(25) = 2.49 CFSn = 0.035

Pw = 4.74 FT.

A = 1.69 S.F.

S = 0.50%

Dn = 0.75'

 $V = 1.48 \, fps$

VH = 0.03'

2+00

1+00

A. AT THE PRE-FINAL INSPECTION: THE ENGINEER MUST ISSUE CERTIFICATION TO THE CITY INSPECTOR THAT THE TURF REINFORCEMENT MAT (TRM) WAS INSTALLED IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS. THE CERTIFICATION MUST ALSO NOTE THAT THE MATERIAL AND INSTALLATION HAS MET CITY AND MANUFACTURER SPECIFICATIONS.

B. IMPROVED EARTHEN CHANNELS AND DETENTION PONDS WILL BE VEGETATED BY SEEDING OR SODDING. EIGHTY FIVE PERCENT (85%) OF THE CHANNEL SURFACE AREA MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT THE CHANNEL FOR MAINTENANCE.

MATCH EXISTING

N.T.S.

SECTION "H1-H1"

N.T.S.

600


595


590

2+60

GROUND @ 3:1 MAX

MATCH EXISTING






2+00

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL

2+60



8 SUBDIVISION I BEXAR COUNTY, TX Ð" D

N

GATE

PLAT NO. 21-11800645

TRENCH EXCAVATION SAFETY PROTECTION CAUTION!!: CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL THE CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITED DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE A. AT THE PRE-FINAL INSPECTION: THE ENGINEER MUST ISSUE CERTIFICATION TO THE CITY INSPECTOR THAT GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC. THE TURF REINFORCEMENT MAT (TRM) WAS INSTALLED IN ACCORDANCE WITH THE PLANS AND PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE SPECIFICATIONS. THE CERTIFICATION MUST ALSO NOTE THAT THE MATERIAL AND INSTALLATION HAS MET THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE CITY AND MANUFACTURER SPECIFICATIONS. CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR B. IMPROVED EARTHEN CHANNELS AND DETENTION PONDS WILL BE VEGETATED BY SEEDING OR SODDING. CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT. EIGHTY FIVE PERCENT (85%) OF THE CHANNEL SURFACE AREA MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT THE CHANNEL FOR MAINTENANCE. REMAINING PORTION OF 257.33 ACRES (DOC #20190051458 O.P.R.) OWNER: MEH HOLDING COMPANY LTD OFF-LOT 50' x 50' ELEC., GAS, TELE., CATV., WATER, SANITARY SEWER & DRAINAGE EASEMENT. (ENTIRE EASEMENT TO EXPIRE MATCH EXISTING UPON INCORPORATION INTO MATCH EXISTING GROUND @ 3:1 MAX 10' E.G.T.TV.E. OFF-LOT 20' PRIVATE PLATTED STREET R.O.W.) GROUND @ 3:1 MAX OFF-LOT 20' PRIVATE RAINAGE EASEMENT SECTION "I1-I1" OFF-LOT 50' x 50' ELEC., GAS, TELE., CATV., WATER, SANITARY STA. 1+29.52- STA. 2+40.35 REMAINING PORTION OF N.T.S. SEWER & DRAINAGE EASEMENT. 257.33 ACRES (DOC #20190051458 O.P.R.) 620 (ENTIRE EASEMENT TO EXPIRE UPON INCORPORATION INTO PLATTED STREET R.O.W.) OWNER: MEH HOLDING COMPANY LTD FACE OF CURB MATCH EXISTING MATCH EXISTING GROUND @ 3:1 MAX GROUND @ 3:1 MAX TEMPORARY INTERCEPTOR DRAIN "I" TEMPORARY INTERCEPTOR DRAIN "J" HORZ SCALE: 1"=20' STA: 1+24.95 - END VERT SCALE: 1"=5" STA: 1+25.08 - END SECTION "J1-J1" STA. 1+29.65- STA. 2+38.51 N.T.S. 625 NATURAL GROUND RT _ NATURAL GROUND CL | NATURAL GROUND LT | NATURAL GROUND CL 7 NATURAL GROUND RT 620 113.43 L.F. ~ EARTHEN "V" CHANNEL @ 0.50% "V" CHANNEL @ 0.50% 4.57 L.F. ~ EARTHEN "V" CHANNEL @ 33.33% EARTHEN "V" CHANNEL EARTHEN "V" CHANNEL STA. 1+24.95 TO STA. 2+40.35 STA. 1+25.08 TO STA. 2+38.51 HYDRAULIC CALCULATION HYDRAULIC CALCULATION 610 Q(25) = 2.08 CFSQ(25) = 2.35 CFSn = 0.035n = 0.035Pw = 4.43 FT.Pw = 4.62 FT.A = 1.47 S.F.A = 1.60 S.F.S = 0.50%S = 0.50%Dn = 0.70'605 Dn = 0.73'V = 1.41 fps $V = 1.47 \, fps$ VH = 0.03'VH = 0.03'595 595 617.94 617.94 618.51 618.51 2+00 2+60 1+00 2+00 THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL

CLAYTON J. LINNEY 623 2023

HORZ SCALE: 1"=20' VERT SCALE: 1"=5"

"V" CHANNEL @ 33.33%

2+60

SUBDIVISION (
BEXAR COUNTY, TX TE. GA

DRAIN

INTERCEPTOR

TEMPORARY

PLAT NO. 21-11800645 JOB NO.:205-43-04 DATE: OCTOBER 2021

DRAWN:OM CHECKED:CL

SHEET NUMBER:

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL
DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE
GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO
IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE
CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE
TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH
EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY

CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE

PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.


CAUTION!!:


THE CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITED TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.


NOTE:


A. AT THE PRE-FINAL INSPECTION: THE ENGINEER MUST ISSUE CERTIFICATION TO THE CITY INSPECTOR THAT THE TURF REINFORCEMENT MAT (TRM) WAS INSTALLED IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS. THE CERTIFICATION MUST ALSO NOTE THAT THE MATERIAL AND INSTALLATION HAS MET CITY AND MANUFACTURER SPECIFICATIONS.


B. IMPROVED EARTHEN CHANNELS AND DETENTION PONDS WILL BE VEGETATED BY SEEDING OR SODDING. EIGHTY FIVE PERCENT (85%) OF THE CHANNEL SURFACE AREA MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT THE CHANNEL FOR MAINTENANCE.














SECTION "L1-L1" STA. 1+29.57- STA. 2+39.13 N.T.S.





THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL






GATES SUBDIVISION UNIT 1


BEXAR COUNTY, TX


VTERCEPTOR DRAIN "K" & "L" PLAN & PROF

PLAT NO. 21-11800645 JOB NO.:205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:CL

SHEET NUMBER: **4.14**







ENGINEERS + SURVEYING
3421 Paesanos Pkwy, Suite 200, San Antonio, TX 782
Phone #: (210) 979-8444 • Fax #: (210) 979-8441
TBPE Firm #: 9513 • TBPLS Firm #: 10122300

REVISIONS IS:

CLAYTON J. LINNEY

SITTS 43

CLAYTON J. LINNEY

SITTS 43

CLAYTON J. LINNEY

SITTS 43

CLAYTON J. LINNEY

CL

Claythung 9/21/2023

BEXAR COUNTY, TX
COVE AND SUNRIDGE HTS PLAN & PRO

PLAT NO. 21-11800645 JOB NO.205-43-04


JOB NO.:205-43-04

DATE: OCTOBER 2021

DRAWN:OM CHECKED:CL

SHEET NUMBER:

5.2



TRENCH EXCAVATION SAFETY PROTECTION


CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM. OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH


CAUTION!!:

THE CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITED TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCT BANKS, LANDSCAPE IRRIGATION FACILITIES, AND BEXAR COUNTY R.O.W. GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.

BEXAR COUNTY R.O.W. NOTE

A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN





THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

*********** = SIDEWALK TO BE CONSTRUCTED

BY DEVELOPER

= SIDEWALK TO BE BUILT AT THE TIME


= HIGH POINT

= LOW POINT

= EDGE OF PAVEMENT

OF HOME CONSTRUCTION

= PROPOSED DRIVEWAY LOCATION



SUBDIVISION (
BEXAR COUNTY, TX

CUL-DE-

PLAT NO. 21-11800645 JOB NO.:205-43-04 DATE: OCTOBER 2021

DRAWN:OM CHECKED:CL SHEET NUMBER:


5.4

TRENCH EXCAVATION SAFETY PROTECTION CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH


EXCAVATION.


THE CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITED TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCT BANKS, LANDSCAPE IRRIGATION FACILITIES, AND BEXAR COUNTY R.O.W. GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.

BEXAR COUNTY R.O.W. NOTE A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN









R.O.W. = RIGHT OF WAY

G.E.T.TV.E. = GAS, ELECTRIC, TELEPHONE &

= FLOW ARROW

= WASHOUT CROWN

SEE SHEET 5.11

SEE SHEET 5.11

 SINGLE DIRECTIONAL WHEELCHAIR RAMP = DUAL DIRECTIONAL WHEELCHAIR RAMP

= WHEELCHAIR RAMP TYPE II

= WHEELCHAIR RAMP TYPE I

CABLE EASEMENT

LEGEND

*//////// = SIDEWALK TO BE CONSTRUCTED

= HIGH POINT

E.O.P. = EDGE OF PAVEMENT


L.P. = LOW POINT

BY DEVELOPER

= SIDEWALK TO BE BUILT AT THE TIME


OF HOME CONSTRUCTION

PROPOSED DRIVEWAY LOCATION













N





PLAT NO. 21-11800645 JOB NO.:205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:CL SHEET NUMBER.

LEGEND TRENCH EXCAVATION SAFETY PROTECTION CAUTION!!: BEXAR COUNTY R.O.W. NOTE R.O.W. = RIGHT OF WAY *********** = SIDEWALK TO BE CONSTRUCTED A BEXAR COUNTY PERMIT MUST BE CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL THE CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING G.E.T.TV.E. = GAS, ELECTRIC, TELEPHONE & BY DEVELOPER DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND BUT NOT LIMITED TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, OBTAINED BEFORE WORKING IN CABLE EASEMENT BEXAR COUNTY R.O.W. AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCT BANKS, LANDSCAPE IRRIGATION FACILITIES, AND = SIDEWALK TO BE BUILT AT THE TIME FLOW ARROW PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER OF HOME CONSTRUCTION PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION WASHOUT CROWN PROPOSED DRIVEWAY LOCATION SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT. = WHEELCHAIR RAMP TYPE II = HIGH POINT CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS SEE SHEET 5.11 GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH = WHEELCHAIR RAMP TYPE I L.P. = LOW POINTEXCAVATION. SEE SHEET 5.11 E.O.P. = EDGE OF PAVEMENT = SINGLE DIRECTIONAL WHEELCHAIR RAMP = DUAL DIRECTIONAL WHEELCHALR RAM 21 22 BLOCK 5 24 10' E. G. T. TV. E 20 20 - 10' E. G. T. TV. E R.O.W. LINE 10' E. G. T. TV. E 10' E. G. T. TV. E 7 PROP. 4' SIDEWALK FACE OF CURB FIREWEED CT (50' R.O.W.) R.O.W. LINE 10' E. G. T. TV. E PROP. 4' SIDEWALK FACE OF CURB -FACE OF CURB 10' E. G. T. TV. E -PROP. 4' SIDEWALK BLOCK 5 L R.O.W. LINE 18 BLOCK 5 16 FIREWEED CT 17 HORZ SCALE: 1"=50" STA: 1+00.00 - END VERT SCALE: 1"=5" HORZ SCALE: 1"=30' 635 CUL-DE-SAC DETAIL VERT SCALE: 1"=5" 630 635 625 630 -27.59' + 22.16' + 25.13' +620 625 615 A.D. = -3.75 K = 10.00 37.46' V.C. 620 NATURAL GROUND RT NATURAL GROUND CL NATURAL GROUND LT 610 615 2.00% (RT)-NATURAL GROUND CL FILL TO BE COMPACTED AT 605 605 95% PROCTOR DENSITY PROPOSED RT & LT PROPOSED RT & LT →3.00% (LT) TOP OF CURB 600 TOP OF CURB-FILL TO BE COMPACTED AT 95% PROCTOR DENSITY 595 595 590 590 595 590 605.28 605.48 605.75 1+00 2+00 3+00

CLAYTON J. LINNEY

317/2023

635

630

625

620

610

600

595

590

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

PROFILE SUBDIVISION UNIT BEXAR COUNTY, TX 8 AN PL CTFIREWEED


TE

GA

PLAT NO. 21-11800645

JOB NO.:205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:CL SHEET NUMBER:


5.6



LEGEND TRENCH EXCAVATION SAFETY PROTECTION BEXAR COUNTY R.O.W. NOTE R.O.W. = RIGHT OF WAY THE CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITED TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, ************ = SIDEWALK TO BE CONSTRUCTED CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL A BEXAR COUNTY PERMIT MUST BE G.E.T.TV.E. = GAS, ELECTRIC, TELEPHONE & BY DEVELOPER DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND OBTAINED BEFORE WORKING IN CABLE EASEMENT AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCT BANKS, LANDSCAPE IRRIGATION FACILITIES, AND = SIDEWALK TO BE BUILT AT THE TIME PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER FLOW ARROW OF HOME CONSTRUCTION PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING = WASHOUT CROWN PROPOSED DRIVEWAY LOCATION SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT. = WHEELCHAIR RAMP TYPE II CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS = HIGH POINT SEE SHEET 5.11 GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH L.P. = LOW POINT = WHEELCHAIR RAMP TYPE I SEE SHEET 5.11 E.O.P. = EDGE OF PAVEMENT = SINGLE DIRECTIONAL WHEELCHAIR RAMP DDW = DUAL DIRECTIONAL WHEELCHAIR RAMPU **TEMPORARY** INTERCEPTOR DRAIN "L" SEE SHEET 4.14 BLOCK 8 **TEMPORARY** PROP. 4' SIDEWALK OFF-LOT 35' PRIVATE INTERCEPTOR DRAINAGE EASEMENT. FACE OF CURB DRAIN "J" SEE SHEET 4.13 (5) TIMBER GUARD POSTS 10' E. G. T. TV. E OFF-LOT 20' PRIVATE 50' x 50' ELEC., GAS, TELE., CATV., WATER. DRAINAGE EASEMENT. SANITARY SEWER & DRAINAGE EASEMENT. - 5'X5' ADA PASSING SPACE (ENTIRE EASEMENT TO EXPIRE UPON (5) TIMBER GUARD POSTS 10' E. G. T. TV. E INCORPORATION INTO PLATTED STREET R.O.W.) SEE SHEET 5.9 5'X5' ADA PASSING SPACE FACE OF CURB -OFF-LOT 20' PRIVATE PROP. 4' SIDEWALK -DRAINAGE EASEMENT. OFF-LOT 50' x 50' ELEC., GAS, TELE., CATV., WATER, R.O.W. LINE -SANITARY SEWER & DRAINAGE EASEMENT. 27 (ENTIRE EASEMENT TO EXPIRE UPON INCORPORATION INTO PLATTED STREET R.O.W.) BLOCK 7 TEMPORARY PROP. 4' SIDEWALK CLAYTON J. LINNEY - 5'X5' ADA PASSING SPACE INTERCEPTOR OFF-LOT 20' PRIVATE DRAIN "K" DRAINAGE EASEMENT. -∆=017°47'34" 45 SEE SHEET 4.14 R=150.00' BLOCK 6 10' E. G. T. TV. E -TEMPORARY INTERCEPTOR DRAIN "I" SEE SHEET 4.13 KESTIS LN HAWKWELL LN HORZ SCALE: 1"=50" HORZ SCALE: 1"=50" STA: 1+00.00 - END STA: 1+00.00 - END VERT SCALE: 1"=5" VERT SCALE: 1"=5" 645 645 640 SUBDIVISION UNIT BEXAR COUNTY, TX 635 635 635 HAWKWELL LN 630 630 625 PROPOSED RT & LT TOP OF CURB TIE TO EXISTING GROUND TIE TO EXISTING GROUND NATURAL GROUND RT -NATURAL GROUND CL NATURAL GROUND LT -620 GATES 8 KESTIS LN 615 605 600 600 600 616.40 PLAT NO. 21-11800645 IOB NO.:205-43-04 2+00 2+50 615.87 615.87 616.11 617.2 DRAWN:OM CHECKED:CL

SHEET NUMBER:

1+00 2+00



11' PARKWAY

4' CONC. SIDEWALK

ITEM 502-1

1"/FT MAX

2% SLOPE

CLAYTON J. LINNEY


6/13/202.

1. PAVEMENT DESIGN THICKNESS BASED ON GEOTECHNICAL REPORT BY INTEC, LLC. PROJECT NO.

2. REFERENCE PROJECT GEOTECHNICAL REPORT AND PROJECT SPECIFICATION FOR ADDITIONAL

3. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING MATERIAL TESTING. TESTING TO BE


4. CONTRACTOR MAY LEAVE VERTICAL CUT BANKS AT R.O.W. LINE AND MEDIANS PROVIDED



HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SE


SIO

PLAT NO. 21-11800645 OB NO.:205-43-04 DATE: OCTOBER 2021 RAWN:OM CHECKED:CL SHEET NUMBER:




TYPICAL RESIDENTIAL DRIVEWAY SECTION

WITH SIDEWALK ABUTTING CURB ITEM 503.1



TYPICAL RESIDENTIAL DRIVEWAY SECTION

WHERE PROPERTY IS LOWER THAN STREET & SIDEWALK IS ABUTTING CURB ITEM 503.1



TYPICAL COMMERCIAL DRIVEWAY SECTION


WITH SIDEWALK ABUTTING CURB ITEM 503.2

CONCRETE DRIVEWAY NOTES

- 1. DRIVEWAY PENETRATION REFERS TO A PORTION OF THE DRIVEWAY THAT MAY BE NECESSARY TO RECONSTRUCT WITHIN PRIVATE PROPERTY TO COMPLY WITH A MAXIMUM DRIVEWAY SLOPE. THIS PORTION OF THE DRIVEWAY SHALL BE PAID FOR UNDER THE FOLLOWING ITEMS AS MAY APPLY: A.) CONCRETE DRIVEWAY PAID FOR UNDER ITEM NO. 503.1 OR 503.2.
- B.) ASPHALTIC CONCRETE DRIVEWAY PAID FOR UNDER ITEM NO. 503.4 AND SHALL INCLUDE A MINIMUM OF 1" ASPHALT TYPE 'D' & 6" FLEXIBLE BASE C.) GRAVEL DRIVEWAY PAID FOR UNDER ITEM NO. 503.5 AND SHALL INCLUDE A MINIMUM OF 6" FLEXIBLE BASE
- 2. 7" MINIMUM HEIGHT WILL NOT NECESSARILY OCCUR AT THE PROPERTY LINE. IT MAY OCCUR WITHIN THE RIGHT OF WAY OR WITHIN THE DRIVEWAY PENETRATION ON PRIVATE PROPERTY.
- 3. THE PROPOSED DRIVEWAY SHOULD MATCH THE EXISTING WIDTH AT THE PROPERTY LINE BUT UNLESS AUTHORIZED BY THE CITY TRAFFIC ENGINEER, THE WIDTH SHALL BE WITHIN THE FOLLOWING VALUES:


TYPE	MINIMUM	MAXIMUM
RESIDENTIAL	10'	20'
COMMERCIAL - ONE WAY	12'	20'
COMMERCIAL - TWO WAY	24'	30'

- 4. FOR LOCAL TYPE "A" STREETS, SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 4' AND IF SEPARATED FROM THE CURB, THE SIDEWALK SHALL BE LOCATED A MINIMUM OF 3' FROM THE BACK OF CURB.
- 5. FOR OTHER THAN LOCAL TYPE "A" STREETS, THE SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 4' AND SEPARATED A MINIMUM OF 3' FROM THE BACK OF CURB OR, AS AN OPTION, THE SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 6' WHEN LOCATED AT THE BACK OF CURB.
- 6. DUMMY JOINTS PARALLEL TO THE CURB SHALL BE PLACED WHERE THE SIDEWALK MEETS THE DRIVEWAY. DUMMY JOINTS PERPENDICULAR TO THE CURB, AND WITHIN THE BOUNDARIES OF THE PARALLEL DUMMY JOINTS, SHALL BE PLACED AT INTERVALS EQUAL TO THE WIDTH OF THE SIDEWALK.
- 7. A MINIMUM OF TWO ROUND AND SMOOTH DOWEL BARS 3/8" IN DIAMETER AND 18" IN LENGTH SHALL BE SPACED 18" APART AT EACH EXPANSION JOINT.
- 8. SIDEWALK RAMP LENGTHS SHALL BE OF SUFFICIENT LENGTH TO MAINTAIN 8.33% (1:12) MAXIMUM SLOPE. WHERE SIDEWALKS CROSS DRIVEWAYS, SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2%.
- 9. SIDEWALK RAMP SURFACE SHALL BE BRUSH FINISHED.



TYPICAL RESIDENTIAL DRIVEWAY SECTION


WITH SIDEWALK SEPARATED FROM CURB ITEM 503.1



2 THE ALGEBRAIC DIFFERENCE OF G1 & G2 SHALL BE 14% OR LESS


TYPICAL RESIDENTIAL DRIVEWAY SECTION

WHERE PROPERTY IS LOWER THAN STREET & SIDEWALK IS SEPARATED FROM CURB



TYPICAL COMMERCIAL DRIVEWAY SECTION

WITH SIDEWALK SEPARATED FROM CURB ITEM 503.2




1. COST OF REINFORCEMENT TO BE INCLUDED IN UNIT COST OF ITEM 307.1. 2. CONCRETE RETAINING WALL COMBINATION TYPE SHALL BE USED FOR

CONCRETE DRIVEWAYS.

DRIVEWAY - CONCRETE RETAINING WALL


ON COMPACTED SUBGRADE ITEM 307.1



② RESIDENTIAL : 2' MAXIMUM; COMMERCIAL: SEE PLAN VIEW


CURB PROFILE AT DRIVEWAY

WITH SIDEWALK ABUTTING CURB



TYPICAL DRIVEWAY PLAN VIEW


WITH SIDEWALK ABUTTING CURB



② RESIDENTIAL : 2' MAXIMUM; COMMERCIAL: SEE PLAN VIEW

CURB PROFILE AT DRIVEWAY

WITH SIDEWALK SEPARATED FROM CURB



IS 4' OR GREATER. ② 45 FOR COMMERCIAL DRIVEWAY

TYPICAL DRIVEWAY PLAN VIEW

WITH SIDEWALK SEPARATED FROM CURB

MAY 2009

CITY OF SAN ANTONIO

CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

CONCRETE DRIVEWAY STANDARDS

% SUBMITTAL	PROJECT NO.:		DATE:
DRWN. BY: <u>V. VASQUEZ</u>	DSGN. BY:	CHKD. BY: R.S. HOSSEINI, P.E.	SHEET NO.:C

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL

PLAT NO. 21-11800645

JOB NO.:205-43-04


CLAYTON J. LINNE 111543


lightrum


RIVEWA


D


SUBDIVISI











THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

ENGINEERS + SURVEYING
3421 Paesanos Pkwy, Suite 200, San Antonio, TX 78231
Phone #: (210) 979-8444 • Fax #: (210) 979-8441
TBPE Firm #: 9513 • TBPLS Firm #: 10122300

CLAYTON J. LINNEY

111543

CENSE

Claythury

Llaythury

GATES SUBDIVISION UNIT 1 SAN ANTONIO. TX

CURB

TRIAN

D


1XDO

PLAT NO. 21-11800645 JOB NO.:205-43-04 DATE: OCTOBER 2021

DATE: OCTOBER 2021 DRAWN:OM CHECKED:CL SHEET NUMBER

5.12

Date: Apr 19, 2022, 9:25am User ID: omeiners



TRENCH EXCAVATION SAFETY PROTECTION
CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE


CLAYTON J. LINNEY C/29/2023


SUBD SIGNA

> PLAT NO. 21-11800645

JOB NO.:205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:CL SHEET NUMBER:

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL








White Prismatic Background

Green Overlay Film

Hwy C lettering








THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL








GATES SUBDIVISION UNIT 1
SAN ANTONIO. TX
FFIC SIGNAGE DETAILS (SHEET 1 OF 2)


PLAT NO. 21-11800645 JOB NO.:205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:CL

SHEET NUMBER:









THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.



CLAYTON J. LINNEY

111543

111543

CLAYTON J. LINNEY

25/2022

GATES SUBDIVISION UNIT 1


SAN ANTONIO. TX


=FIC SIGNAGE DETAILS (SHEET 2 OF 2)


PLAT NO. 21-11800645 JOB NO.:205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:CL


5.16

SHEET NUMBER:









THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL

ENGINEERS + SURVEYING
3421 Paesanos Pkwy, Suite 200, San Antonio, TX 78237
Phone #: (210) 979-8444
TBPE Firm #: 9513 • TBPLS Firm #: 10122300

CLAYTON J. LINNEY

111543

CENSE

Claythuy


4/cs/2022


2

0

GATES SUBDIVISION UNIT 1 SAN ANTONIO. TX

PLAT NO. 21-11800645 JOB NO.205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:CL SHEET NUMBER:






THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

ENGINEERS + SURVEYING
3421 Paesanos Pkwy, Suite 200, San Antonio, TX 78;
Phone #: (210) 979-8444 • Fax #: (210) 979-8441
TBPE Firm #: 9513 • TBPLS Firm #: 10122300

REVISIONS ISSUED



2

OF

2

(SHE

M

DE

RKING

GATES SUBDIVISION UNIT 1 SAN ANTONIO. TX

> PLAT NO. 21-11800645 B NO.:205-43-04

JOB NO.:205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:CL SHEET NUMBER:

1. All materials and construction procedures within the scope of this contract shall be approved by the San Antonio Water System (SAWS) and comply with the Plans, Specifications, General Conditions and with the following as applicable:

GENERAL SEWER NOTES (REVISED JULY 2017)

- A. Current Texas Commission on Environmental Quality (TCEQ) "Design Criteria for Domestic Waste water System", Texas Administrative Code (TAC) Title 30 Part 1 Chapter 217 and "Public Drinking Water". TAC Title 30 Part 1 Chapter 290.
- B. Current TXDOT "Standard Specifications for Construction of Highways, Streets and Drainage". C. Current "San Antonio Water System Standard Specifications for Water and Sanitary Sewer
- D. Current City of San Antonio "Standard Specifications for Public Works Construction".

2. The contractor shall not proceed with any pipe installation work until they obtain a copy of the approved Counter Permit or General Construction Permit (GCP) from the consultant and has been notified by SAWS Construction I nspection Division to proceed with the work and has arranged a meeting with the inspector and consultant for the work requirements. Work completed by the contractor without an approved Counter Permit and/or a GCP will be subject to removal and replacement at the expense of the contractors and/or the developer.

3. The Contractor shall obtain the SAWS Standard Details from the SAWS website, http://www.saws.org/business_center/specs. Unless otherwise noted within the design plans.

E. Current City of San Antonio "Utility Excavation Criteria Manual" (UECM).

4. The Contractor is to make arrangements with the SAWS Construction Inspection Division at (210) 233-2973, on notification procedures that will be used to notify affected home residents and/or property owners 48 hours prior

5. Location and depth of existing utilities and service laterals shown on the plans are understood to be approximate. Actual locations and depths must be field verified by the Contractor at least 1 week prior to construction. It shall be the Contractor's responsibility to locate utility service lines as required for construction and to protect them during

6. The Contractor shall verify the exact location of underground utilities and drainage structures at least 1-2 weeks prior to construction whether shown on plans or not. Please allow up to 7 business days for locates requesting pipe location markers on SAWS facilities. The following contact information are supplied for verification purposes:

- SAWS Utility Locates: http://www.saws.org/Service/Locates
- COSA Drainage (210) 207-0724 or (210) 207-6026 COSA Traffic Signal Operations (210) 206-8480
- COSA Traffic Signal Damages (210) 207-3951
- Texas State Wide One Call Locator 1-800-545-6005 or 811

7. The Contractor shall be responsible for restoring existing fences, curbs, streets, driveways, sidewalks, landscaping and structures to its original or better condition if damages are made as a result of the project's construction.

8. All work in Texas Department of Transportation (TxDOT) and/or Bexar County right-of-way shall be done in accordance with respective construction specifications and permit requirements.

9. The Contractor shall comply with City of San Antonio or other governing municipality's tree ordinances when

10. The Contractor shall not place any waste materials in the 100-year Flood Plain without first obtaining an

11. Holiday Work: Contractors will not be allowed to perform SAWS work on SAWS recognized holidays. Request should be sent to constworkreq@saws.org. Weekend Work: Contractors are required to notify the SAWS Inspection Construction Department 48 hours in advance to request weekend work. Request should be sent to constworkreq@saws.org. Any and all SAWS utility work installed without holiday/weekend approval will be subject

12. Compaction note (Item 804): The contractor shall be responsible for meeting the compaction requirements on all trench backfill and for paying for the tests performed by a third party. Compaction tests will be done at one location point randomly selected, or as indicated by the SAWS Inspector and/or the test administrator, per each 12-inch loose lift per 400 linear feet at a minimum. This project will not be accepted and finalized by SAWS without this requirement being met and verified by providing all necessary documented test results.

13. A copy of all testing reports shall be forwarded to SAWS Construction Inspection Division.

1. The Contractor is responsible for ensuring that no Sanitary Sewer Overflow (SSO) occurs as a result of their work. All contractor personnel responsible for SSO prevention and control shall be trained on proper response. Should an SSO occur, the contractor shall:

- A. Identify the soruce of the SSO and notify SAWS Emergency Operations Center (EOC) immediately at (210) 233-2014. Provide the address of the spill and en estimated volume or flow.
- B. Attempt to eliminate the source of the SSO C. Contain sewage from the SSO to the extent of preventing a possible contamination of waterways.
- D. Clean up spill site (return contained sewage to the collection system if possible) and properly dispose of contaminated soil/materials.
- E. Clean the affected sewer mains and remove any debris. F. Meet all post-SSO requirements as per the EPA Consent Decree, including line cleaning and
- televising the affected sewer mains (at SAWS direction) within 24 hours.

cost incurred by SAWS, including any fines from EPA, TCEQ and/or any other Federal, State or Local Agencies. No separate measurement or payment shall be made for this work. All work shall be done according to guidelines

Should the Contractor fail to address an SSO immediately and to SAWS satisfaction, they will be responsible for all

set by TCEQ and SAWS.

2. If bypass pumping is required, the Contractor shall perform such work in accordance with SAWS Standard Specification for Water and Sanitary Sewer Construction, Item No. 864, "Bypass Pumping".

3. Prior to tie-ins, any shutdowns of existing force mains of any size must be coordinated with the SAWS Construction Inspection Division at (210) 233-2973 at least one week in advance of the shutdown. The Contractor must also provide a sequence of work as related to the tie-ins: this is at no additional cost to SAWS or the project and it is the responsibility of the Contractor sequence the work accordingly.

4. Sewer pipe where water line crosses shall be 160 psi and meet the requirements of ASTM D2241, TAC 217.53 and TCEQ 290.44(Ee)(4)(B). Contractor shall center a 20' joint of 160 psi pressure rated PVC at the proposed

5. ELEVATIONS POSTED FOR TOP OF MANHOLES ARE FOR REFERENCE ONLY: It shall be the responsibility of the Contractor to make allowances and adjustments for top of manholes to match the finished grade of the

6. Spills, Overflows, or Discharges of Wastewater: All Spills, overflows, or discharges of wastewater, recycled water, petroleum products, or chemicals must be reported immediately to the SAWS Inspector assigned to the Counter Permit or GEneral Construction Permit (GCP). This requirement applies to every spill, overflow, or

7. Manhole and all pipe testing (including the TV inspection) must be performed and passed prior to Final Field Acceptance by SAWS Construction Inspection Division, as per SAWS Specifications For Water and Sanitary

8. All PVC pipe over 14 feet of cover shall be extra strength with minimum pipe stiffness of 115 psi.

SHEET REVISION LOG REVISION DESCRIPTION NO. NO.

GATES SUBDIVISION UNIT 1

BEXAR COUNTY, TX SANITARY SEWER IMPROVEMENTS



SHEET INDEX


Sheet Title	Sheet Number
SANITARY SEWER COVER SHEET	6.0
OVERALL SANITARY SEWER PLAN (SHEET 1 OF 2)	6.1
OVERALL SANITARY SEWER PLAN (SHEET 2 OF 2)	6.2
LINE "A" PLAN & PROFILE (SHEET 1 OF 2)	6.3
LINE "A" PLAN & PROFILE (SHEET 2 OF 2)	6.4
LINE "B" PLAN & PROFILE	6.5
LINE "C', "D" & "E" PLAN & PROFILE	6.6
LINE "F" & "G" PLAN & PROFILE	6.7
LINE "H', "I' & "K"" PLAN & PROFILE	6.8
LINE "J" PLAN & PROFILE	6.9

LOCATION MAP NOT-TO-SCALE

OWNER INFORMATION MEH HOLDING COMPANY LTD 1202 W. BITTERS, BUILDING 1, SUITE 1200 SAN ANTONIO, TX 78216

DEVELOPER'S NAME: MEH HOLDING COMPANY LTD CITY: SAN ANTONIO PHONE#: TOTAL ACREAGE: 35.11 AC. SAWS BLOCK MAP#: 216562, 216560, 214560 TOTAL EDU'S: 95 PLAT NO.: 21-11800645


THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAF








PLAT NO. 21-11800645


SHEET 6.0
























GATES SUBDIVISION UNIT 1

BEXAR COUNTY, TX WATER IMPROVEMENTS




LOCATION MAP NOT-TO-SCALE

OWNER INFORMATION MEH HOLDING COMPANY LTD 1202 W. BITTERS, BUILDING 1, SUITE 1200 SAN ANTONIO, TX 78216

SHEET INDEX

Sheet Title	Sheet Number
WATER DISTRIBUTION COVER SHEET	7.0
WATER DISTRIBUTION PLAN (SHEET 1 OF 2)	7.1
WATER DISTRIBUTION PLAN (SHEET 2 OF 2)	7.2
WATER DISTRIBUTION DETAILS (SHEET 1 OF 4)	7.3
WATER DISTRIBUTION DETAILS (SHEET 2 OF 4)	7.4
WATER DISTRIBUTION DETAILS (SHEET 3 OF 4)	7.5
WATER DISTRIBUTION DETAILS (SHEET 4 OF 4)	7.6






JOB NO.: 205-43-

SHEET REVISION LOG

DESCRIPTION

SHEET


REVISION



CLAYTON J. LINNEY

PLAT NO. 21-11800645

DRAWN:OM CHECKED:C SHEET NUMBER



No direct measurement or payment will be made for the work to be done or the equipment to be furnished under this item, but shall be considered subsidiary to the

TESTING FOR PRESSURE


PIPELINES


APPROVED


JULY 2022


REVISED


particular items of work for which unit prices are required in the proposal.











THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL



CLAYTON J. LINNEY


(SHE SUBDIVISION UNI S TAIL DE NOIL DISTRIBU WATER


21-11800645 JOB NO.:205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:##

PLAT NO.


GA


SHEET NUMBER:







1 OF 1









THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL



CLAYTON J. LINNEY

0F (SHEE SUBDIVISION UNIT BEXAR COUNTY, TX DETAILS DISTRIBUTION GATE WATER

2


PLAT NO. 21-11800645 JOB NO.:205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:## SHEET NUMBER:

		RESTR	AINED LENGTH FOR T	EES
PIPE SIZE (Inch)	BRANCH SIZE (Inch)	LENGTH OF RUN (Feet)	RESTRAINED LENGTH IN FEET, WHEN TEST PRESSURE=200 psi	RESTRAINED LENGTH IN FEET, WHEN TEST PRESSURE=150 ps
6	4	0	42	31
6	4	5	7	1
6	4	10	1	1
6	6	0	59	44
6	6	5	35	20
6	6	10	11	1
8	4	0	42	31
8	4	5	1	1
8	6	0	59	44
8	6	5	28	13
8	6	10	1	1
8	8	0	77	58
8	8	5	53	34
8	8	10	30	11
8	8	15	6	1

Restrained Length Calculations are for P.V.C. Pipe Bedded in Compacted Granular Material Extending to the Top of the Pipe. The Native Soil Material is Assumed to be Inorganic Clay of High Plasticity. Depth of Bury is Assumed to be 4 Feet.

- 1. These Calculations are Provided for Reference. The Restrained Length Shall be Designed Based Upon the Conditions Encountered During Installation.
- 2. All joints within the calculated length must be restrained. 3. If your distance between fittings is less than or equal to the calculated restraint length, restrain all joints between those fittings.

tral GLEAR	FOR TEES	DET-839-0	1 SHEET
	RESTRAINED LENGTHS	MARCH 2020	
		APPROVED	REVISED



PIPE SIZE (Inch)	BEND ANGLE (deg.)	LOW SIDE DEPTH	UPPER BEND RESTRAINED LENGTH IN FEET, WHEN TEST PRESSURE=200 psi	LOWER BEND RESTRAINED LENGTH IN FEET, WHEN TEST PRESSURE=200 psi	UPPER BEND RESTRAINED LENGTH IN FEET, WHEN TEST PRESSURE=150 psi	LOWER BEND RESTRAINED LENGTH IN FEET, WHEN TEST PRESSURE=150 psi
6	45	5	24	8	18	6
6	22.5	5	12	4	9	3
6	11.25	5	6	2	4	1
6	45	10	24	5	18	4
6	22.5	10	12	2	9	2
6	11.25	10	6	1	4	1
8	45	5	32	11	24	8
8	22.5	5	15	5	11	4
8	11.25	5	8	3	6	2
8	45	10	32	7	24	5
8	22.5	10	15	3	11	2
8	11.25	10	8	2	6	1
12	45	5	45	16	34	12
12	22.5	5	22	7	16	6
12	11.25	5	11	4	8	3
12	45	10	45	10	34	7
12	22.5	10	22	5	16	3
12	11.25	10	11	2	8	2


RESTRAINED LENGTH DESIGN

Restrained Length Calculations are for P.V.C. Pipe Bedded in Compacted Granular Material Extending to the Top of the Pipe. The Native Soil Material is Assumed to be Inorganic Clay of High Plasticity. Depth of Bury is Assumed to be 4 Feet.

- 1. These Calculations are Provided for Reference. The Restrained Length Shall be Designed Based Upon the Conditions
- Encountered During Installation.
- 2. All joints within the calculated length must be restrained. 3. If your distance between fittings is less than or equal to the calculated restraint length, restrain all joints between those fittings.

A	10			
•	腫		E	
		-		
֡	E Y	J.	ITY IS CLE	ITY IS CLEAR

R	EVISED
	R



		RESTR	AINED LENGTH FOR T	EES
PIPE SIZE (Inch)	BRANCH SIZE (Inch)	LENGTH OF RUN (Feet)	RESTRAINED LENGTH IN FEET, WHEN TEST PRESSURE=200 psi	RESTRAINED LENGTH IN FEET, WHEN TEST PRESSURE=150 psi
12	4	0	42	31
12	4	5	1	1
12	6	0	59	44
12	6	5	13	1
12	6	10	1	1
12	8	0	77	58
12	8	5	42	23
12	8	10	7	1
12	8	15	1	1
12	12	0	109	82
12	12	5	86	59
12	12	10	63	35
12	12	15	39	12


RESTRAINED LENGTH DESIGN

Restrained Length Calculations are for P.V.C. Pipe Bedded in Compacted Granular Material Extending to the Top of the Pipe. The Native Soil Material is Assumed to be Inorganic Clay of High Plasticity. Depth of Bury is Assumed to be 4 Feet.

- 1. These Calculations are Provided for Reference. The Restrained Length Shall be Designed Based Upon the Conditions
- Encountered During Installation. 2. All joints within the calculated length must be restrained.
- 3. If your distance between fittings is less than or equal to the calculated restraint length, restrain all joints between those fittings.

	East Central
- 1	TO TO THE TOTAL OF
	SHOTH E
	OUR QUALITY IS CLEAR

FOR TEES	DET-839-04	SHEET 2 OF 2
ESTRAINED LENGTHS	MARCH 2020	
	APPROVED	REVISED



L = Length to be Restrained

PIPE SIZE (Inch)	SMALL SIZE (Inch)	RESTRAINED LENGTH IN FEET, WHEN TEST PRESSURE=200 psi	RESTRAINED LENGTH IN FEET, WHEN TEST PRESSURE=150 psi
6	4	30	23
8	4	55	42
8	6	32	24
12	4	95	71
12	6	80	60
12	8	58	43

RESTRAINED LENGTH DESIGN


Restrained Length Calculations are for P.V.C. Pipe Bedded in Compacted Granular Material Extending to the Top of the Pipe. The Native Soil Material is Assumed to be Inorganic Clay of High Plasticity. Depth of Bury is Assumed to be 4 Feet.


- 1. These Calculations are Provided for Reference. The Restrained Length Shall be Designed Based Upon the Conditions
- Encountered During Installation.
- 2. All joints within the calculated length must be restrained. 3. If your distance between fittings is less than or equal to the calculated restraint length, restrain all joints between those fittings.



RESTRAINED LENGTHS	
FOR REDUCERS	

APPROVED REVISED JULY 2022 **DET-839-07**





L = Length to be Restrainedon Both Sides of Fitting

PIPE SIZE (Inch)	BEND ANGLE (deg)	RESTRAINED LENGTH IN FEET, WHEN TEST PRESSURE=200 psi	RESTRAINED LENGTH IN FEET, WHEN TEST PRESSURE=150 ps
6	90	23	17
6	45	9	7
6	22.5	5	3
6	11.25	2	2
8	90	30	22
8	45	12	9
8	22.5	6	4
8	11.25	3	2
12	90	43	32
12	45	18	13
12	22.5	8	6
12	11.25	4	3

RESTRAINED LENGTH DESIGN

Restrained Length Calculations are for P.V.C. Pipe Bedded in Compacted Granular Material Extending to the Top of the Pipe. The Native Soil Material is Assumed to be Inorganic Clay of High Plasticity. Depth of Bury is Assumed to be 4 Feet.

- 1. These Calculations are Provided for Reference. The Restrained Length Shall be Designed Based Upon the Conditions
- Encountered During Installation. 2. All joints within the calculated length must be restrained.
- 3. If your distance between fittings is less than or equal to the calculated restraint length, restrain all joints between those fittings.

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.




RESTRAINED LENGTHS	
FOR HORIZONTAL BENDS	


REVISED JULY 2022 **DET-839-08**

3

SUBDIVISION

PLAT NO. 21-11800645 JOB NO.:205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:## SHEET NUMBER:





THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

ENGINEERS + SURVEYING
3421 Paesanos Pkwy, Suite 200, San Antonio, TX 78231
Phone #: (210) 979-8444 • Fax #: (210) 979-8441
TBPE Firm #: 9513 • TBPLS Firm #: 10122300

ISSUE DATE 11/14/2023

REVISIONS

ADDED GATE

AVALVES

CLAYTON J. LINNEY

SINTE OF TEXAS

CLAYTON J. LINNEY

CLAYTON J. LINNEY

SINTE OF TEXAS

CLAYTON J. LINNEY

CLAYTON J. LINNEY

CLAYTON J. LINNEY

SINTE OF TEXAS

CLAYTON J. LINNEY

SINTE OF TEXAS

CLAYTON J. LINNEY

4

OF

ATES SUBDIVISION UNIT 1 BEXAR COUNTY, TX

> PLAT NO. 21-11800645 B NO.:205-43-04

DATE: OCTOBER 2021
DRAWN:OM CHECKED:##

SHEET NUMBER:

1. ALL OPERATORS SHALL SUBMIT A NOTICE OF INTENT (NOI) AT LEAST 48 HOURS IN ADVANCE AND ALL BEST MANAGEMENT PRACTICES (BMP'S) SHALL BE IN PLACE PRIOR TO STARTING CONSTRUCTION ACTIVITIES.

2. CONTRACTOR TO ENSURE THAT STRUCTURAL BMP'S ARE INSTALLED WITHIN THE LIMITS OF THE SITE BOUNDARY.

3. CONTRACTOR MAY INSTALL THE BEST MANAGEMENT PRACTICES IN PHASES THAT COINCIDE WITH THE DISTURBANCE OF UP GRADIENT AREAS. THIS PHASING SHOULD BE NOTED WITHIN THE MODIFICATIONS SECTION WITH THE SIGNATURE AND DATE OF THE RESPONSIBLE PARTY.

4. CONTRACTOR TO VERIFY SUFFICIENT VEGETATION IN AREAS DENOTED AS VEGETATED FILTER STRIP. IF INSUFFICIENT VEGETATION EXISTS, CONTRACTOR SHALL IMPLEMENT A DIFFERENT BEST MANAGEMENT PRACTICE AND WILL SHOW IT ON THIS PLAN WITH NOTATION IN THE MODIFICATIONS SECTION WITH THE SIGNATURE AND DATE OF THE RESPONSIBLE PARTY.

MAINTENANCE AND INSPECTION:

1. CONTRACTOR SHOULD LIMIT CONSTRUCTION ACTIVITIES TO ONLY THOSE AREAS SHOWN TO BE DISTURBED ON THIS PLAN. IF ADDITIONAL VEGETATED AREAS ARE DISTURBED, THEY SHOULD BE PROTECTED WITH APPROPRIATE BEST MANAGEMENT PRACTICES UNTIL THE AREAS HAVE BEEN STABILIZED AS PER THE SPECIFICATIONS OF THE SWPPP. THE AREAS OF THIS ADDITIONAL SOIL DISTURBANCE AND THE MEASURES USED SHOULD BE SHOWN ON THE SITE PLAN AND NOTED WITHIN THE MODIFICATIONS SECTION WITH THE SIGNATURE AND DATE OF THE RESPONSIBLE PARTY.

2. CONTRACTOR IS RESPONSIBLE FOR MAINTENANCE AND INSPECTION OF BMP'S AS PER THE SPECIFICATIONS OF THE SWPPP. THE CONTRACTOR MAY MODIFY THE CONTROLS AS NECESSARY TO PREVENT SEDIMENT RUNOFF. THESE MODIFICATIONS SHOULD BE SHOWN AND THE SITE PLAN AND NOTED WITHIN THE MODIFICATIONS SECTION WITH THE SIGNATURE AND DATE OF THE RESPONSIBLE PARTY.

3. LOCATION OF CONSTRUCTION ENTRANCE/EXIT, CONCRETE WASHOUT PIT, AND EQUIPMENT AND STORAGE ARE TO BE FIELD DETERMINED. LOCATIONS SHALL BE

PROJECT COMPLETION:

- 1. ALL DISTURBED AREAS ARES NOT COVERED BY IMPERVIOUS COVER ARE TO BE STABILIZED PER THE SWPPP AND PROJECT SPECIFICATIONS PRIOR TO REMOVAL OF ANY BMP'S AND/OR PRIOR TO FILING A NOTICE OF TERMINATION (NOT).
- 2. BEST MANAGEMENT PRACTICES MAY BE REMOVED IN PHASES IF ALL UPGRADIENT AREAS HAVE BEEN STABILIZED PER SWPPP AND PROJECT SPECIFICATIONS. THIS PHASING SHOULD BE NOTED WITHIN THE MODIFICATIONS SECTION WITH THE SIGNATURE AND DATE OF THE RESPONSIBLE PARTY.
- 3. CONTRACTOR TO ENSURE THEY HAVE MET ALL REQUIREMENTS OF THE SWPPP BEFORE FILING A NOTICE OF TERMINATION (NOT).

28' E.G.T.TV.E.

35' SANITARY

SEWER EASEMENT

LOT 902 BLOCK 5

100-YEAR FEMA FLOODPLAIN --- (PANEL NO. 48029C0440G) -

EFFECTIVE SEPTEMBER 28, 2010

20' SANITARY

SEWER EASEMENT


VARIABLE WIDTH PUBLIC DRAINAGE **EASEMENT**

1% AC ULTIMATE FLOODPLAIN PER FLOOD STUDY PREPARED BY KFW ENGINEERS


CONSTRUCTION

CONSTRUCTION

- 1. THIS EXHIBIT IS TO BE USED FOR THE PURPOSES OF STORMWATER POLLUTION PREVENTION ONLY. ALL OTHER CIVIL ENGINEERING INFORMATION SHOULD BE OBTAINED FROM THE APPROPRIATE CONSTRUCTION DOCUMENTS.
- 2. THE PURPOSE OF THE SIGNATURE AND SEAL OF THE ENGINEER ON THIS DOCUMENT IS TO DEMONSTRATE COMPLIANCE WITH THE TPDES STORMWATER POLLUTION PREVENTION PLAN REGULATIONS ONLY.
- 3. ALL OWNERS/OPERATORS ARE RESPONSIBLE FOR FAMILIARIZING THEMSELVES WITH THE STORMWATER POLLUTION PREVENTION PLAN AND COMPLYING WITH THE REGULATIONS CONTAINED WITHIN IT.



LOCATION MAP NOT-TO-SCALE



SW3P MODIFICATIONS

.

+ + + + + +

DISTURBED AREA

(SILT FENCE ALONG THE FRONT OF LOTS TO

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL

BE INSTALLED AFTER PAVING)

NATURAL VEGETATIVE BUFFER

INLET WITH PROTECTION

(GRAVEL FILTERS BAGS)

ROCK BERM

DATE	SIGNATURE	DESCRIPTION		

COORDINATION NOTE:

- CONTACT TIME WARNER TO COORDINATE CABLE TV SERVICE. (210) 244-0500
- 2. CONDUIT FOR ELECTRICAL SERVICE. CONFIRM REQUIREMENTS AND COORDINATE WITH CPS FOR INSPECTION. (210) 353-2246.
- 3. CONTACT AT&T TO COORDINATE TELEPHONE SERVICE. 1-800-449-7928.
- 4. CONTRACTOR TO COORDINATE WITH CPS PRIOR TO CONSTRUCTION TO PLAN ELECTRIC SERVICE.
- 5. CONTRACTOR TO COORDINATE WITH SAWS TO PLAN WATER AND SANITARY SEWER SERVICES (210) 704-7297
- 6. CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A CONSTRUCTION.

MINIMUM OF 48 HOURS PRIOR TO THE START OF LOT 4, BLOCK 2, C.B. 5135 **G4 ENTERPRISES** VARIABLE WIDTH PRIVATE DRAINAGE EASEMENT (VOL. 20001, PG. 621 O.P.R.) (VOL. 20001, PG. 621 O.P.R.) LIMITS OF CONSTRUCTION OWNER: G-4 ENTERPRISES, LTD. 20' BUILDING SETBACK LINE (VOL. 20001, PG. 621 O.P.R.) (VOL. 10407, PG. 895 O.P.R.) 15' WATER EASEMENT (VOL. 1079, PG. 758, O.P.R.) (VOL. 2910, PG. 1123, O.P.R.) FIELDSTONE WAY (70' R.O.W.) VARIABLE WIDTH CLEAR VISION EASEMENT SILT FENCE PHASE 2 PHASE : CONSTRUCTION LOT 1 REMAINING PORTION OF 257.33 ACRES CONSTRUCTIO BLOCK 4 (DOC #20190051458 O.P.R.) ENTRANCE/EXIT OWNER: MEH HOLDING COMPANY LTD EQUIPMENT (VOL. 1079, PG. 758, O.P.R.) EHICLE & MATERIALS VARIABLE WIDTH (VOL. 2910, PG. 1123, O.P.R.) STORAGE AREA. 50' x 50' ELEC., GAS, TELE., CATV., WATER, SANITARY SEWER & DRAINAGE EASEMENT. (ENTIRE EASEMENT TO EXPIRE UPON INCORPORATION INTO PLATTED STREET R.O.W.)




PLAT NO. 21-11800645 JOB NO.:205-43-04 DATE: OCTOBER 2021 DRAWN:OM CHECKED:CL SHEET NUMBER:

29' PRIVATE

DRAINAGE EASEMENT

628



ISOMETRIC PLAN VIEW

10 MIL PLASTIC-LINING FREE OF HOLES, TEARS, OR OTHER DEFECTS

PLAN VIEW

GENERAL NOTES:

SILT FENCE

SECTION A-A

SECTION B-B

<u>Materials:</u>
(1) Silt fence material should be polypropylene, polyethylene or polyamide woven or nonwoven fabric. The fabric width should be 36 inches, with a minimum unit weight of 4.5 oz/yd, mullen burst strength exceeding 190 lb/in2, ultraviolet stability exceeding 70%, and minimum apparent opening size of U.S. Sieve No.

(2) Fence posts should be made of hot rolled steel, at least 4 feet long with Tee or Ybar cross section, surface painted or galvanized, minimum nominal weight 1.25 lb/fl2, and Brindell hardness exceeding 140. (3) Woven wire backing to support the fabric should be galvanized 2" x 4" welded wire, 12 gauge minimum.

(1) Steel posts, which support the silt fence, should be installed on a slight angle toward the anticipated runoff source. Post must be embedded a minimum of 1- foot deep and spaced not more than 8 feet on center. Where water concentrates, the maximum spacing

(2) Lay out fencing down-slope of disturbed area, following the contour as closely as possible. The fence should be sited so that the maximum drainage area is 1/4 acre/i 00 feet

MAX. 6' SPACING MIN. (3) The toe of the silt fence should be trenched in with a spade or mechanical trencher, so that the down- slope face of the trench is flat and perpendicular to the line of flow. Where fence cannot be trenched in (e.g., pavement or rock outcrop), weight fabric flap with 3 inches of pea gravel on uphill side to prevent flow from seeping under fence. (4) The trench must be a minimum of 6 inches deep and 6 inches wide to allow for the silt fence fabric to be laid in the ground and backfilled with compacted material. (5) Silt fence should be securely fastened to each steel support post or to woven wire, which is in turn attached to the steel fence post. There should be a 3-foot overlap,

securely fastened where ends of fabric meet. (6) Silt fence should be removed when the site is completely stabilized so as not to block or impede stone flow or drainage.

Inspection and Maintenance Guidelines. (1) Inspect all fencing weekly, and after any rainfall.

(2) Remove sediment when buildup reaches 6 inches. (3) Replace any torn fabric or install a second line of fencing parallel to the torn section. (4) Replace or repair any sections crushed or collapsed in the course of construction activity. If a section of fence is obstructing vehicular access, consider relocating it to a spot where it will provide equal protection, but will not obstruct vehicles. A triangular filter dike may be preferable to a silt fence at common vehicle access points. (5) When construction is complete, the sediment should be disposed of in a manner that will not cause additional siltation and the prior location of the silt fence should be

revegetated. The fence itself should be disposed of in an approved landfill.

Vertical spacing

face of the slope

varies between

10' and 20'

measured along the

ENTRENCHMENT DETAIL N.T.S.

FIBER ROLL

TYPICAL FIBER ROLL INSTALLATION

THE MATERIAL, INSTALLATION, INSPECTION, AND MAINTENANCE OF FIBER ROLLS WILL BE PER THE MANUFACTURE'S SPECIFICATIONS AND SHALL ALSO COMPLY WITH THE TEXAS COMMISSION OF ENVIRONMENTAL QUALITY CURRENT "TECHNICAL GUIDANCE ON BEST MANAGEMENT PRACTICES" AS NOTED BELOW.

(1) Core material: Core material should be biodegradable or recyclable. Material may be compost, mulch, aspen wood fibers, chipped site vegetation, agricultural rice or wheat straw, coconut fiber, 100% recyclable fibers, or similar materials.

(2) Containment Mesh: Containment mesh should be 100% biodegradable, photodegradable or recyclable such as burlap, twine, UV photodegradable plastic, polyester, or similar material. When the fiber role will remain in place as part of a vegetative system use biodegradable or photodegradable mesh. For temporary installation recyclable mesh is recommended.

(1) Locate fiber rolls on level contours spaced as follows: Slope inclination of 4:1 (H:V) or flatter: Fiber rolls should be placed at a maximum interval of 20 ft. Slope inclination between 4:1 and 2:1 (H:V): Fiber Rolls should be placed at a maximum interval of 15 ft. (a closer spacing is more effective). Slope inclination 2:1 (H:V) or greater: Fiber Rolls should be placed at a maximum interval of 10 ft. (a closer spacing is more effective).

(3) Stake fiber rolls into a 2 to 4 in. deep trench with a width equal to the diameter of the fiber roll. (4) Drive stakes at the end of each fiber roll and spaced 4 ft maximum on center. (5) Use wood stakes with a nominal classification of 0.75 by 0.75 in. and minimum

(2) Turn the ends of the fiber roll up slope to prevent runoff from going around the

(6) If more than one fiber roll is placed in a row, the rolls should be overlapped, not Inspection and Maintenance Guidelines:

(1) Inspect prior to forecast rain, daily during extended rain events, after rain events, (2) Repair or replace split, torn, unraveling, or slumping fiber rolls. (3) If the fiber roll is used as a sediment capture device, or as an erosion control device to maintain sheet flows, sediment that accumulates behind the role must be periodically removed in order to maintain its effectiveness. Sediment should be removed when the accumulation reaches one-half the designated sediment storage

depth, usually one-half the distance between the top of the fiber roll and the adjacent ground surface. Sediment removed during maintenance may be incorporated into earthwork on the site or disposed of at an appropriate location.

CONSTRUCTION

EQUIPMENT

& VEHICLE STORAGE

MAINTENANCE AREA

CONSTRUCTION

AND WASTE

MATERIAL

STORAGE

AREA

GEOTEXTILE /

(1) The aggregate should consist of 4 to 8 inch washed stone over a stable foundation as specified in the plan. (2) The aggregate should be placed with a minimum thickness of 8 inches. (3) The geotextile fabric should be designed specifically for use as a soil filtration media with an approximate weight of 6 oz/yd2, a mullen burst rating of 140 lb/in2, and an equivalent opening size greater than a number

(4) If a washing facility is required, a level area with a minimum of 4 inch diameter washed stone or commercial rack should be included in the plans. Divert wastewater to a sediment trap or basin.

GEOTEXTILE FABRIC TO STABILIZE FOUNDATION

CONSTRUCTION ENTRANCE/EXIT

FABRIC CROSS-SECTION OF A CONSTRUCTION ENTRANCE/EXIT

(5) Place geotextile fabric and grade foundation to improve stability, especially where wet conditions are anticipated. (6) Place stone to dimensions and grade shown on plans. Leave surface smooth and slope for drainage. (7) Divert all surface runoff and drainage from the stone pad to a sediment trap or basin.

area. Grade crown foundation for positive drainage.

(3) The construction entrance should be at least 50 feet long.

(1) The entrance should be maintained in a condition, which will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repair andlor cleanout of any measures used to trap sediment. (2) All sediment spilled, dropped, washed or tracked onto public rights-of-way should be removed immediately by contractor. (3) When necessary, wheels should be cleaned to remove sediment prior to entrance onto public right-of-way.

Installation: (North Carolina, 1993)
(1) Avoid curves on public roads and steep slopes. Remove vegetation and other objectionable material from the foundation

(2) The minimum width of the entrance/exit should be 12 feet or the full width of exit roadway, whichever is greater.


foundation approximately 15 feet from the entrance to divert runoff away from the public road.

(8) Install pipe under pad as needed to maintain proper public road drainage.

(4) If the slope toward the road exceeds 2%, construct a ridge, 6 to 8 inches high with 3:1 (H:V) side slopes, across the

(4) When washing is required, it should be done on an area stabilized with crushed stone that drains into an approved sediment (5) All sediment should be prevented from entering any storm drain, ditch or water course by using approved methods.

STABILIZED CONSTRUCTION ENTRANCE / EXIT



---- 24" MIN. ----

(1) The berm structure should be, secured with a woven wire sheathing having maximum opening of 1 inch and a minimum wire diameter of 20 gauge galvanized and should be secured with shoat rings. (2) Clean, open graded 3- to 5-inch diameter rock should be used, except in areas where high velocities or large volumes of flow are expected, where 5- to 8-inch diameter rocks may be used.


(1) Lay out the woven wire sheathing perpendicular to the flow line. The sheathing should be 20 gauge

(4) Wrap the wire sheathing around the rock and secure with tie wire so that the ends of the sheathing overlap at least 2 inches, airl the bern retains its shape when walked upon. (5) Berm should be built along the contour at zero percent grade or as near as possible. (6) The ends of the berm should be tied into existing upslope grade and the berm should be buried in a

Inspection and Maintenance Guidelines: (1) Inspection should be made weekly and after each rainfall by the responsible party. For installations in streambeds, additional daily inspections should be made.

silt in an approved manner that will not cause any additional siltation.

(5) The berm should be replaced when the structure ceases to function as intended due to silt accumulation among the rocks, washout, construction traffic damage, etc. (6) The rock berm should be left in place until all upstream areas are stabilized and accumulated silt




woven wire mesh with 1 inch openings. (2) Berm should have a top width of 2 feet minimum with side slopes being 2:1 (H:V) or flatter. (3) Place the rock along the sheathing as shown in the diagram Figure 1-28), to a height not less than

trench approximately 3 to 4 inches deep to prevent failure of the control.

(2) Remove sediment and other debris when buildup reaches 6 inches and dispose of the accumulated

(3) Repair any loose wire sheathing. (4) The berm should be reshaped as needed during inspection.

ROCK BERM




THE TOP OF THE SACK GABIONS SHOULD BE LEVEL AND ORIENTED PERPENDICULAR TO THE DIRECTION OF FLOW. FILTER FABRIC MATERIAL SHALL BE FASTENED TO WOVEN WIRE FILTER FABRIC MATERIAL SHOULD MEET THE FOLLOWING SPECIFICATIONS: RESISTANT TO ULTRAVIOLET LIGHT, FABRIC SHOULD BE NON-WOVEN GEOTEXTILE WITH MINIMUM WEIGHT OF 3.5

OUNCES PER SQUARE YARD, MINIMUM MULLEN BURST STRENGTH OF GALLONS PER MINUTE PER SQUARE FOOT OF FRONTAL AREA. STONE SIZE: ±4"-8" OPEN GRADED CRUSHED LIMESTONE. INSPECT WEEKLY OR AFTER EACH RAINFALL EVENT AND REPAIR OR REPLACE AS NEEDED. WHEN SILT REACHES A DEPTH OF 6 INCHES OR MORE ABOVE

NATURAL GROUND, SILT SHALL BE REMOVED AND DISPOSED IN AN APPROVED MANNER THAT WILL NOT CONTRIBUTE TO RESILTATION. CONTAMINATED SEDIMENT MUST BE REMOVED AND DISPOSED OF OFF-SITE IN ACCORDANCE WITH APPLICABLE REGULATIONS.

> PLAT NO. 21-11800645 IOB NO. 205-43-04 ATE: OCTOBER 2021

> > RAWN:OM CHECKED:CL SHEET NUMBER.




GENERAL NOTES:

THE FILTER BAG MATERIAL SHALL BE MADE OF POLYPROPYLENE, POLYETHYLENE OR POLYAMIDE WOVEN FABRIC, MIN UNIT WEIGHT OF 4 OUNCES/SY, MULLEN BURST STRENGTH EXCEEDING 300 PSI AND ULTRAVIOLET STABILITY EXCEEDING 70%.

THE FILTER BAG SHALL BE FILLED WITH CLEAN, MEDIUM TO COARSE GRAVEL (0.31 TO 0.75 INCH DIAMETER)

GRAVEL FILTER BAG DETAIL



PLAN VIEW

SECTION A-A

ALL STORM DRAINAGE SYSTEMS INLETS SHOULD FILTER RUNOFF BEFORE
THE WATER IS DISCHARGED INTO STREAMS OR ONTO ADJACENT PROPERTIES,

DRAINAGE AREA TRIBUTARY TO AN AREA DRAIN INSTALLED WITH A GRAVEL FILTER SHOULD BE ONE ACRE.

ALL CURB INLET GRAVEL FILTERS SHOULD BE INSPECTED AND REPAIRED

AFTER EACH RUNOFF EVENT. SEDIMENT SHOULD BE REMOVED WHEN MATERIAL IS WITHIN THREE INCHES OF THE TOP OF THE CONCRETE BLOCKS

PERIODICALLY, THE GRAVEL SHOULD BE RAKED TO INCREASE INFILTRATION AND

CURB INLET PROTECTION GRAVEL FILTER BAGS

IF NO ADDITIONAL DOWNSTREAM TREATMENT EXISTS, THE MAXIMUM

UNLESS TREATMENT IS PROVIDED ELSEWHERE.

FILTERING OF RUNOFF WATERS.

GENERAL NOTES:

FILTERED RUNOFF

SOD PLACED IN CHECKER BOARD PATTERN SECTION A-A CHANNEL TO BE STABILIZED WITH SOD PLACED IN A CHECKER BOARD PATTERN TON THE CHANNEL BOTTOM AND ON THE SIDES UP TO 1/3 THE DEPTH OF

/EXIT

TYPICAL CONSTRUCTION STAGING AREA

CHANNEL LINING

OFFICE

SILT FENCE FLOW ARROWS

DETAIL ABOVE ILLUSTRATES MINIMUM DIMENSIONS. PIT CAN BE INCREASED IN SIZE DEPENDING ON EXPECTED FREQUENCY OF USE.

WASHOUT PIT SHALL BE LOCATED IN AN AREA EASILY ACCESSIBLE TO

WASHOUT PIT SHALL NOT BE LOCATED IN AREAS SUBJECT TO INUNDATION

FROM STORM WATER RUNOFF AND AT LEAST 50 FEET FROM SENSITIVE

CONCRETE TRUCK WASHOUT PIT

TYPE 4 SACK GABIONS

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.