



BID FORM
CONSTRUCTION OF PAVING, GRADING, & UTILITIES
FOR
George's Ranch Unit 2B

Bidders:

Pursuant to the foregoing Sec I - INVITATION TO BID and Sec II - INSTRUCTIONS TO BIDDERS, the undersigned bidder hereby proposed to do all Work for the unit prices bid to furnish all necessary superintendence, labor and miscellaneous items, to complete all work according to the bids, as provided in the construction plan and contract documents for the Construction of Paving, Grading and Utilities to the satisfaction of the owner/engineer, and bind themselves on acceptance of this proposal to machine, equipment, tools, materials, and insurance to execute a contract and bonds for completing said project within the time slated for the following prices to wit:

BIDDER SIGNATURE _____



BID FORM (SCHEDULE OF VALUES)					
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT BID PRICE	EXTENDED AMOUNT
ROADWAY ITEMS (KWCID NO. 4A)					
1	Clearing and Grubbing of ROW and lots for roadway, utilities, and drainage, Disposal as directed by Owner within George's Ranch, Complete in Place	8.00	AC.	\$ -	\$ -
2	Roadway Excavation within the Right-of-Way, Complete In Place	17,478	CY.	\$ -	\$ -
3	Roadway Embankment within the Right-of-Way, per Kendall County specifications, Complete In Place	4,797	CY.	\$ -	\$ -
4	Roadway & Drainage Hauloff, to be hauled as directed by Owner within George's Ranch, (Screening of material to use as fill, per Geotechnical requirements) Complete In Place	13,977	CY.	\$ -	\$ -
5	Hot Mix Asphaltic Pavement, (1.5" Compacted Depth, per TxDOT Item 340, Type D)	11,284	SY.	\$ -	\$ -
6	Prime Coat, MC-30 (0.16 gal/SY per TxDOT Item 310)	1,805	GAL.	\$ -	\$ -
7	Tack Coat(0.08 gal/SY per TxDOT Item 340)	903	GAL.	\$ -	\$ -
8	Crushed Limestone Base Material, (12" Compacted Depth, per TxDOT Item 247 Type A; Grade 2)	12,464	SY.	\$ -	\$ -
9	Kendall County 7" Standard Curb, Complete in Place	6,005	L.F.	\$ -	\$ -
10	Remove Header Curb & 6" Guardposts	60	L.F.	\$ -	\$ -
11	Traffic Control, Striping, Raised Pavement Markers & Street Signage, Complete in Place	1	LS.	\$ -	\$ -
12	Revegetation of ROW w/Temp. Irrigation	1	LS.	\$ -	\$ -
ROADWAY SUBTOTAL					\$ -
DRAINAGE ITEMS (KWCID NO. 4A)					
1	Drainage Channel Excavation, Complete in Place	1,385	CY.	\$ -	\$ -
2	Drainage Channel Embankment, Per Kendall County specifications, Complete in Place	89	CY.	\$ -	\$ -
3	15' Curb Inlet (5.5' Deep), Complete in Place	1	EA.	\$ -	\$ -
4	20' Curb Inlet (8.5' Deep), Complete in Place	1	EA.	\$ -	\$ -
5	20' Curb Inlet (5.0' Deep), Complete in Place	1	EA.	\$ -	\$ -
6	5' Sidewalk Box, Complete in Place	1	EA.	\$ -	\$ -
7	24" RCP, Storm Sewer, ASTM C-76, Class III, With Rubber Gasket Joints, All Depths, Complete in Place	47.86	L.F.	\$ -	\$ -
8	30" RCP, Storm Sewer, ASTM C-76, Class III, With Rubber Gasket Joints, All Depths, Complete in Place	572.62	L.F.	\$ -	\$ -
9	5' x 5' Single Box Culvert, Including all Excavation and Embankment, all Bedding Material, per TxDOT Item 400 & 462, Complete in Place	1,382.67	L.F.	\$ -	\$ -
10	5' x 5' x 5' Junction Box, Complete in Place	1	EA.	\$ -	\$ -

BIDDER SIGNATURE _____



BID FORM (SCHEDULE OF VALUES)					
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT BID PRICE	EXTENDED AMOUNT
11	7' x 7' x 7' Junction Box, Complete in Place	1	EA.	\$ -	\$ -
12	7' x 7' x 6.5' Junction Box, Complete in Place	2	EA.	\$ -	\$ -
13	Soil Fill (1/2" Min.) HPTRM with top soil, flexible growth medium with seed and soil amendments and light weight erosion control blanket, Complete in Place	1,779	SY.	\$ -	\$ -
14	Pipe Railing as per Kendall County Specifications, Complete in Place	61	L.F.	\$ -	\$ -
15	12" Thick Rock Gabion Mattress, with 12 Gauge Wire, Fasteners, Lacing, Anchor Bolts, per TxDOT Item 459, Complete in Place	116	SY.	\$ -	\$ -
16	High Performance Turf Reinforcement Mat (HPTRM), Complete in Place	1,779	SY.	\$ -	\$ -
17	Bermuda Hydromulch, Complete in Place	12,010	SY.	\$ -	\$ -
18	Concrete Headwalls and Wingwalls, per TxDOT Item 466, Weathered Finish, Complete in Place	21.00	CY.	\$ -	\$ -
19	Concrete Rip-Rap, Weathered Finish, Complete in Place	431	SY.	\$ -	\$ -
20	Concrete Baffle Blocks, Weathered Finish, Complete in Place	2.63	CY.	\$ -	\$ -
21	Design of Trench Excavation and Shoring Plan for Storm Sewer Construction, Complete in Place	1	LS.	\$ -	\$ -
22	Trench Safety System, All Depths, for Storm Sewer Construction, Complete in Place	2,003	L.F.	\$ -	\$ -
23	Tie into Existing Junction Box, Complete in Place	2	EA.	\$ -	\$ -
DRAINAGE SUBTOTAL					\$ -
DOMESTIC WATER ITEMS (KCWCID NO. 4A)					
1	10" C900, DR14 Polyvinyl Chloride (PVC) Water Line, All Bends, Reducers and Fittings, All Depths, Complete in Place	2,741	L.F.	\$ -	\$ -
2	6" C900, DR14 Polyvinyl Chloride (PVC) Water Line, All Bends, Reducers and Fittings, All Depths, Complete in Place	249	L.F.	\$ -	\$ -
3	10" AWWA Gate Valve (open counter-clockwise) and Box w/ concrete pad encasement, Complete in Place	7	EA.	\$ -	\$ -
4	Fire Hydrant Assembly, Including Hydrant, 6" D.I. Water Line, 6" AWWA Gate Valve and Box, and All Bends and Fittings, All Depths, Complete in Place	7	EA.	\$ -	\$ -
5	Tracer Wire Locate Box, Install one locate box at all valves (including FH's) and dead ends or blowoffs, Complete in Place	1	LS.	\$ -	\$ -
6	1" Long Dual Service, Complete in Place	12	EA.	\$ -	\$ -
7	1" Short Dual Service , Complete in Place	3	EA.	\$ -	\$ -
8	¾" Long Single Service , Complete in Place	5	EA.	\$ -	\$ -
9	¾" Short Single Service , Complete in Place	2	EA.	\$ -	\$ -
10	2" Permanent Blowoff, Complete in Place	2	EA.	\$ -	\$ -

BIDDER SIGNATURE _____



BID FORM (SCHEDULE OF VALUES)					
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT BID PRICE	EXTENDED AMOUNT
11	2" Temporary Blowoff, Complete in Place	2	EA.	\$ -	\$ -
12	Tracer Wire Locate Test, Per City of Boerne Requirements for Water Line Construction , Complete in Place	1	LS.	\$ -	\$ -
13	Hydrostatic Testing, Per City of Boerne Requirements	1	LS.	\$ -	\$ -
14	Coordination with Owner's Chlorination Contractor, after all punch list items are complete and prior to final acceptance	1	LS.	\$ -	\$ -
15	Design of Trench Excavation and Shoring Plan for Domestic Water Line Construction, Complete in Place	1	LS.	\$ -	\$ -
16	Trench Safety System (All Depths), for Water Line Construction , Complete in Place	2,990	L.F.	\$ -	\$ -
17	24" Diameter Steel Casing, All depths, per City Requirements, complete in Place	8	L.F.	\$ -	\$ -
18	Meter Boxes, Complete in Place	37	EA.	\$ -	\$ -
DOMESTIC WATER SUBTOTAL					\$ -
MISCELLANEOUS AND SWPPP ITEMS (KCWCID NO. 4A)					
1	Stabilized Construction Entrance, Complete in Place	2	EA.	\$ -	\$ -
2	Concrete Washout Pit	1	EA.	\$ -	\$ -
3	Staging Area	1	EA.	\$ -	\$ -
4	Filter Fabric Fence (When Authorized by Owner), Complete in Place	3,655	L.F.	\$ -	\$ -
5	Type 2 Rock Filter Berm (When Authorized by Owner), Complete in Place	129	L.F.	\$ -	\$ -
6	Bagged Gravel Inlet Filter (When Authorized by Owner), Complete in Place	105	LS.	\$ -	\$ -
7	Storm Water Pollution Prevention Plan, including Implementation, Permitting, Inspections, and Reporting, Complete in Place	1	LS.	\$ -	\$ -
8	Revegetation of Utility Easements w/Temp. Irrigation	2.79	AC.	\$ -	\$ -
MISCELLANEOUS & SW3P SUBTOTAL					\$ -
ELECTRIC ITEMS (KCWCID NO. 4A)					
1	Primary and Secondary Trenching	4,050	L.F.	\$ -	\$ -
2	Bedding Sand	1	LOT	\$ -	\$ -
3	Concrete Facilities, Complete in Place	1	LOT	\$ -	\$ -
4	6" Wide "CAUTION BURIED ELECTRIC BELOW" Tape (Red)	4,050	L.F.	\$ -	\$ -
5	Mule Tape (2500 lb Test Min.)	5,500	L.F.	\$ -	\$ -
6	1/2" to 3/4" Aggregate Gravel	1	LOT	\$ -	\$ -

BIDDER SIGNATURE _____



BID FORM (SCHEDULE OF VALUES)					
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT BID PRICE	EXTENDED AMOUNT
7	3" Sch 40 PVC Conduit (Primary & Secondary)	5,500	L.F.	\$ -	\$ -
8	3" 90° Sweeps Sch 80 PVC (3' Min. Radius Primary)	34	EA.	\$ -	\$ -
9	3" 90° Sweeps Sch 80 PVC (2' Min. Radius Secondary)	51	EA.	\$ -	\$ -
10	3" Sch 40 PVC Cap	38	EA.	\$ -	\$ -
11	Single Phase Transformer Pads	13	EA.	\$ -	\$ -
12	Single Phase Combination Sectionalizing Box Pads	3	EA.	\$ -	\$ -
13	Single Phase Sectionalizing Box	3	EA.	\$ -	\$ -
14	UK5 - Secondary Pedestals	21	EA.	\$ -	\$ -
15	Ground Rod Clamps	1	LOT	\$ -	\$ -
16	UM6-6 - Ground Rods (10' x 3/4" CU Clad)	16	EA.	\$ -	\$ -
17	Secondary Connector Blocks (Pedestal)	63	EA.	\$ -	\$ -
DRY UTILITIES SUBTOTAL					\$ -
TOTAL BID AMOUNT					\$ -
ALTERNATES					
ALTERNATE ITEMS (KCWCID NO. 4A)					
1	Dewatering System when Required, (When Authorized by Owner), Complete in Place	100	L.F.	\$ -	\$ -
2	Additional Cost Bedding & Backfill for Unsatisfactory Soil Conditions in Utility Trench (When Authorized by Owner), Complete in Place	100	L.F.	\$ -	\$ -
3	Extra Cement Stabilized Sand in ROW (When Authorized by Owner), All Depths, Complete in Place	100	L.F.	\$ -	\$ -
4	French Drain, all 4" PVC pipe, filter sock, gravel and filter fabric wrapping (When Authorized by Owner), Complete in Place	100	L.F.	\$ -	\$ -
5	Roadway & Drainage Hauloff, to be hauled to offsite location outside George's Ranch	9,893	CY.	\$ -	\$ -
6	Crushed Limestone Base Material, (8" Compacted Depth, per TxDOT Item 247 Type A; Grade 2)	12,464	SY.	\$ -	\$ -
7	Filter Fabric Fence Along Haul Route (When Authorized by Owner), Complete in Place	1,265	L.F.	\$ -	\$ -
8	Clearing and Grubbing of Haul Route and Stockpile Location, Disposal Offsite, Complete in Place	3.42	AC.	\$ -	\$ -
ALTERNATES SUBTOTAL					\$ -

BIDDER SIGNATURE _____