

IV. BID PROPOSAL

The undersigned, in compliance with the Instructions to Bidders for **GERONIMO HEIGHTS – PHASE 1 SITE DEVELOPMENT PLANS**, having examined the plans and specifications with related documents and having carefully read same and having visited the site surrounding the construction of the proposed work, hereby propose to furnish all superintendence, labor, hauling, materials, equipment, apparatus, machinery, tools, and supplies, and to construct the project in accordance with the Contract Documents within the time set forth herein and at the prices stated below:

Paving Improvements

Item No.	Quantity	Unit	Item Description and Total Written Unit Price	Unit Price	Amount
1	55	AC	<u>Clearing and Grubbing,</u> <u>Complete and in place, per acre,</u> For _____ dollars And _____ cents		
2	264.234	S.Y.	<u>Excavation/Embankment,</u> <u>Complete and in place, per square yard,</u> For _____ dollars And _____ cents		
3	24,202	S.Y.	<u>Subgrade Preparation,</u> <u>Complete and in place, per square yard,</u> For _____ dollars And _____ cents		
4	24,202	S.Y.	<u>8" Compacted Flexible Limestone Base Material,</u> <u>Complete and in place, per square yard,</u> For _____ dollars And _____ cents		
5	24,202	S.Y.	<u>Lime Stabilization,</u> <u>Complete and in place, per square yard,</u> For _____ dollars And _____ cents		
6	24,202	S.Y.	<u>Geogrid,</u> <u>Complete and in place, per square yard,</u> For _____ dollars And _____ cents		
7	16,849	S.Y.	<u>3" Hot Mix Asphaltic Concrete,</u> <u>Complete and in place, per square yard,</u> For _____ dollars And _____ cents		
8	12,610	L.F.	<u>Standard Curb and Gutter,</u> <u>Complete and in place, per linear foot,</u> For _____ dollars And _____ cents		
9	359	S.Y.	<u>Concrete Valley Gutter,</u> <u>Complete and in place, per square yard,</u> For _____ dollars And _____ cents		

10	15,425	S.F.	Sidewalk, Complete and in place, per square foot, For _____ dollars And _____ cents		
11	36	EA.	Sidewalk Ramps, Complete and in place, per each, For _____ dollars And _____ cents		
12	4	EA.	OSSF Driveway, Complete and in place, per each, For _____ dollars And _____ cents		
13	1	L.S.	Signage and Striping, Complete and in place, per lump sum, For _____ dollars And _____ cents		
14	2	EA.	Sawcut and Tie into Existing Pavement, Complete and in place, per each, For _____ dollars And _____ cents		
15	1	EA.	Emergency Access Gate, Complete and in place, per each, For _____ dollars And _____ cents		
16	1	L.S.	Surveying, Complete and in place, per lump sum, For _____ dollars And _____ cents		
Paving Improvements					

Drainage Improvements

Item No.	Quantity	Unit	Item Description and Total Written Unit Price	Unit Price	Amount
17	844	L.F.	24" Class III RCP, Complete and in place, per linear foot, For _____ dollars And _____ cents		
18	489	L.F.	36" Class III RCP, Complete and in place, per linear foot, For _____ dollars And _____ cents		
19	2,330	L.F.	48" Class III RCP, Complete and in place, per linear foot, For _____ dollars And _____ cents		
20	1,053	L.F.	6"x4' Reinforced Concrete Box, Complete and in place, per linear foot, For _____ dollars And _____ cents		

21	1	EA.	<u>4' x 4' Junction Box,</u> <u>Complete and in place, per each,</u> For _____ dollars And _____ cents		
22	1	EA.	<u>6' x 6' Junction Box,</u> <u>Complete and in place, per each,</u> For _____ dollars And _____ cents		
23	4	EA.	<u>8' x 8' Junction Box,</u> <u>Complete and in place, per each,</u> For _____ dollars And _____ cents		
24	24	EA.	<u>15' Curb Inlet,</u> <u>Complete and in place, per each,</u> For _____ dollars And _____ cents		
25	1	EA.	<u>5'x5' Area Inlet,</u> <u>Complete and in place, per each,</u> For _____ dollars And _____ cents		
26	1	EA.	<u>7'x7' Area Inlet,</u> <u>Complete and in place, per each,</u> For _____ dollars And _____ cents		
27	7	EA.	<u>Adjust Manhole Castings,</u> <u>Complete and in place, per each,</u> For _____ dollars And _____ cents		
28	859	L.F.	<u>Berm/Channel,</u> <u>Complete and in place, per linear foot,</u> For _____ dollars And _____ cents		
29	1	L.S.	<u>Detention Pond,</u> <u>Complete and in place, per lump sum,</u> For _____ dollars And _____ cents		
30	5,487	V.S.F.	<u>Detention Pond Concrete Wall,</u> <u>Complete and in place, per vertical</u> <u>square foot,</u> For _____ dollars And _____ cents		
31	4,467	L.F.	<u>Trench Safety System,</u> <u>Complete and in place, per linear foot,</u> For _____ dollars And _____ cents		

32	1	L.S.	<u>Surveying.</u> <u>Complete and in place, per lump sum.</u> For _____ dollars And _____ cents		
Drainage Improvements					

Water Improvements

Item No.	Quantity	Unit	Item Description and Total Written Unit Price	Unit Price	Amount
33	3,371	L.F.	<u>8" DR-18 C-900 P.V.C.,</u> <u>Complete and in place, per linear foot.</u> For _____ dollars And _____ cents		
34	3,100	L.F.	<u>8" DR-18 C-900 P.V.C. (Restrained Joint Pipe).</u> <u>Complete and in place, per linear foot.</u> For _____ dollars And _____ cents		
35	167	L.F.	<u>6" Class 350 DIP (FH Leads).</u> <u>Complete and in place, per linear foot.</u> For _____ dollars And _____ cents		
36	198	L.F.	<u>24" DR-25 P.V.C. Encasement Pipe.</u> <u>Complete and in place, per linear foot.</u> For _____ dollars And _____ cents		
37	90	L.F.	<u>24" D.I. Encasement Pipe.</u> <u>Complete and in place, per linear foot.</u> For _____ dollars And _____ cents		
38	49	EA.	<u>8" Gate Valve.</u> <u>Complete and in place, per each.</u> For _____ dollars And _____ cents		
39	16	EA.	<u>6" Gate Valve.</u> <u>Complete and in place, per each.</u> For _____ dollars And _____ cents		
40	5	EA.	<u>1" Air Release/Vacuum Valve (CAARV).</u> <u>Complete and in place, per each.</u> For _____ dollars And _____ cents		
41	6	EA.	<u>Flush Valve.</u> <u>Complete and in place, per each.</u> For _____ dollars And _____ cents		
42	6	EA.	<u>Rise Valve Castings.</u> <u>Complete and in place, per each.</u> For _____ dollars And _____ cents		

43	16	EA.	5 ¼" Fire Hydrant, Complete and in place, per each, For _____ dollars And _____ cents		
44	1	EA.	Connect to Existing Waterline, Complete and in place, per each, For _____ dollars And _____ cents		
45	19	EA.	Long Double Water Service, Complete and in place, per each, For _____ dollars And _____ cents		
46	2	EA.	Long Single Water Service, Complete and in place, per each, For _____ dollars And _____ cents		
47	27	EA.	Short Single Water Service, Complete and in place, per each, For _____ dollars And _____ cents		
48	1	L.S.	Cast Iron Fittings, Complete and in place, per lump sum, For _____ dollars And _____ cents		
49	6,638	L.F.	Trench Safety System, Complete and in place, per linear foot, For _____ dollars And _____ cents		
50	1	L.S.	Surveying, Complete and in place, per lump sum, For _____ dollars And _____ cents		
Water Improvements					

Wastewater Improvements

Item No.	Quantity	Unit	Item Description and Total Written Unit Price	Unit Price	Amount
51	1,565	L.F.	1.5" SDR11 HDPE Force Main, Complete and in place, per linear foot, For _____ dollars And _____ cents		
52	4,678	L.F.	2.0" SDR11 HDPE Force Main, Complete and in place, per linear foot, For _____ dollars And _____ cents		
53	236	L.F.	4.0" SCH. 80 P.V.C. Force Main Sleeves, Complete and in place, per linear foot, For _____ dollars And _____ cents		

54	8	EA.	1.5" Cleanout in Manhole, Complete and in place, per each, For _____ dollars And _____ cents		
55	19	EA.	2.0" Cleanout in Manhole, Complete and in place, per each, For _____ dollars And _____ cents		
56	27	EA.	Adjust Manhole Castings, Complete and in place, per each, For _____ dollars And _____ cents		
57	67	EA.	Single Service – Force Main, Complete and in place, per each, For _____ dollars And _____ cents		
58	67	EA.	EOne Grinder Pump Station, Complete and in place, per each, For _____ dollars And _____ cents		
59	6,239	L.F.	Trench Safety System, Complete and in place, per linear foot, For _____ dollars And _____ cents		
60	1	L.S.	Surveying, Complete and in place, per lump sum, For _____ dollars And _____ cents		
Wastewater Improvements					

Erosion/Sedimentation Control Improvements

Item No.	Quantity	Unit	Item Description and Total Written Unit Price	Unit Price	Amount
61	161,567	S.Y.	Revegetation (Hydromulch Seeding with Topsoil & Watering for Temporary and Permanent Revegetation), Complete and in place, per square yard, For _____ dollars And _____ cents		
62	2	EA.	Stabilized Construction Entrance, Complete and in place, per each, For _____ dollars And _____ cents		
63	14,614	L.F.	Silt Fence, Complete and in place, per linear foot, For _____ dollars And _____ cents		

64	2	EA.	Concrete Washout Area, Complete and in place, per each, For _____ dollars And _____ cents		
65	26	EA.	Inlet Protection, Complete and in place, per each, For _____ dollars And _____ cents		
66	1	L.S.	Maintain Temporary Controls, Complete and in place, per lump sum, For _____ dollars And _____ cents		
67	1	L.S.	Surveying, Complete and in place, per lump sum, For _____ dollars And _____ cents		
Erosion/Sedimentation Control Improvements					

Turn Lane Improvements

Item No.	Quantity	Unit	Item Description and Total Written Unit Price	Unit Price	Amount
68	6	STA	PREPARING ROW, Complete and in place, per station, For _____ dollars And _____ cents		
69	8	C.Y.	EXCAV (ROADWAY), Complete and in place, per cubic foot, For _____ dollars And _____ cents		
70	222	C.Y.	EMBANK (FNL)(OC)(TY B), Complete and in place, per cubic foot, For _____ dollars And _____ cents		
71	23	TON	LIME (COM OR QK)(SLURRY), Complete and in place, per ton, For _____ dollars And _____ cents		
72	770	S.Y.	LIME TRT (EXIST MATL)(10"), Complete and in place, per square yard, For _____ dollars And _____ cents		
73	138	GAL	PRIME COAT (MULTI OPTION), Complete and in place, per gallon, For _____ dollars And _____ cents		
74	396	TON	D-GR HMA TY-B PG64-22 (EXEMPT), Complete and in place, per ton, For _____ dollars And _____ cents		

75	76	TON	<u>D-GR HMA TY-D PG76-22,</u> <u>Complete and in place, per ton,</u> For _____ dollars And _____ cents		
76	142	GAL	<u>BONDING COURSE,</u> <u>Complete and in place, per gallon,</u> For _____ dollars And _____ cents		
77	860	S.Y.	<u>GEOGRID BASE REINFORCEMENT</u> <u>(TYPE 1),</u> <u>Complete and in place, per square yard,</u> For _____ dollars And _____ cents		
78	199	S.Y.	<u>DRIVEWAYS (CONC),</u> <u>Complete and in place, per square yard,</u> For _____ dollars And _____ cents		
79	2	MO	<u>BARRICADES, SIGNS AND TRAFFIC</u> <u>HANDLING,</u> <u>Complete and in place, per month,</u> For _____ dollars And _____ cents		
80	16	HR	<u>TMA (MOBILE OPERATION),</u> <u>Complete and in place, per hour,</u> For _____ dollars And _____ cents		
81	26	S.F.	<u>ALUMINUM SIGNS (TY-A),</u> <u>Complete and in place, per square foot,</u> For _____ dollars And _____ cents		
82	4	EA.	<u>IN SM RD SD SUP&AM</u> <u>TY10BWG(1)SA(P),</u> <u>Complete and in place, per each,</u> For _____ dollars And _____ cents		
83	33	L.F.	<u>REFL PAV MRK TY I</u> <u>(W)8"(DOT)090MIL),</u> <u>Complete and in place, per linear foot,</u> For _____ dollars And _____ cents		
84	370	L.F.	<u>REFL PAV MRK TY I</u> <u>(W)8"(SLD)(090MIL),</u> <u>Complete and in place, per linear foot,</u> For _____ dollars And _____ cents		

85	12	L.F.	REFL PAV MRK TY I (W)12"(SLD)(090MIL). Complete and in place, per linear foot. For _____ dollars And _____ cents		
86	2	EA.	REFL PAV MRK TY I (W)(ARROW)(090MIL). Complete and in place, per each. For _____ dollars And _____ cents		
87	2	EA.	REFL PAV MRK TY I (W)(WORD)(090MIL). Complete and in place, per each. For _____ dollars And _____ cents		
88	502	L.F.	REFL PAV MRK TY I (W)4"(SLD)(090MIL). Complete and in place, per linear foot. For _____ dollars And _____ cents		
89	44	L.F.	REFL PAV MRK TY I (Y)6"(SLD)(090MIL). Complete and in place, per linear foot. For _____ dollars And _____ cents		
90	19	EA.	REFL PAV MRK TY I-C. Complete and in place, per each. For _____ dollars And _____ cents		
91	736	L.F.	ELIM EXT PM & MRKS (4"). Complete and in place, per linear foot. For _____ dollars And _____ cents		
92	1,632	S.Y.	FURN & PLACE TOPSOIL (5"). Complete and in place, per square yard. For _____ dollars And _____ cents		
93	1,632	S.Y.	DRILL SEED (PERM RURAL CLAY). Complete and in place, per square yard. For _____ dollars And _____ cents		
94	1,632	S.Y.	DRILL SEED (TEMP WARM COOL). Complete and in place, per square yard. For _____ dollars And _____ cents		
95	0.11	TON	FERTILIZER. Complete and in place, per ton. For _____ dollars And _____ cents		

Bid Proposal

96	50	TGL	<u>VEGETATIVE WATERING.</u> <u>Complete and in place, per thousand</u> <u>gallons,</u> For _____ dollars And _____ cents		
97	1,535	S.Y.	<u>SOIL RET</u> <u>BLKT(SL MOD CLAY SHORT).</u> <u>Complete and in place, per square yard,</u> For _____ dollars And _____ cents		
98	612	L.F.	<u>TEMP SEDMT CONT FENCE (INSTALL).</u> <u>Complete and in place, per linear foot,</u> For _____ dollars And _____ cents		
99	612	L.F.	<u>TEMP SEDMT CONT FENCE</u> <u>(REMOVE).</u> <u>Complete and in place, per linear foot,</u> For _____ dollars And _____ cents		
Turn Lane Improvements					

Bid Proposal Summation

PAVING IMPROVEMENTS	
DRAINAGE IMPROVEMENTS	
WATER IMPROVEMENTS	
WASTEWATER IMPROVEMENTS	
EROSION/SEDIMENTATION CONTROL IMPROVEMENTS	
TURN LANE IMPROVEMENTS	
TOTAL "BASE BID" (ITEMS 1 - 99)	

Alternate Bid "A"

Item No.	Quantity	Unit	Item Description and Total Written Unit Price	Unit Price	Amount
100	24,202	S.Y.	<u>15" Compacted Flexible Limestone Base</u> <u>Material.</u> <u>Complete and in place, per square yard,</u> For _____ dollars And _____ cents		
101	-24,202	S.Y.	<u>Subtract (-) 8" Compacted Flexible</u> <u>Limestone Base Material.</u> <u>Complete and in place, per square yard,</u> For _____ dollars And _____ cents		
Total Amount Bid – Alternate "A"					\$