



BID FORM (SCHEDULE OF VALUES)					
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT BID PRICE	EXTENDED AMOUNT
1	PAYMENT AND PERFORMANCE BOND	1	L.S.		\$ -
2	MOBILIZATION	1	L.S.		\$ -
3	PREPARE RIGHT-OF-WAY/CLEARING	26	Ac.		\$ -
4	SITE EXCAVATION	28,171	C.Y.		\$ -
5	SITE EMBANKMENT	28,544	C.Y.		\$ -
6	CURB INLET GRAVEL FILTERS	179	L.F.		\$ -
7	CONCRETE WASHOUT PIT	1	EA.		\$ -
8	CONSTRUCTION EXITS (INSTALL/REMOVE)	2	EA.		\$ -
9	TEMPORARY SEDIMENT CONTROL FENCE	3,937	L.F.		\$ -
10	ROCK BERM	530	L.F.		\$ -
11	EARTHEN BERM	270	L.F.		\$ -
12	HYDROMULCH (DISTURBED OPEN SPACE)	11,755	S.Y.		\$ -
13	RETAINING WALL	294	S.F.		\$ -
SITEWORK SUBTOTAL					\$ -
1	STREET EXCAVATION	17,077	C.Y.		\$ -
2	STREET EMBANKMENT	6,320	C.Y.		\$ -
3	FLEXIBLE BASE (15" COMPACTED DEPTH)	15,291	S.Y.		\$ -
4	FLEXIBLE BASE (19" COMPACTED DEPTH)	3,165	S.Y.		\$ -
5	HOT MIX ASPHALTIC PAVEMENT, TYPE D (2.5" COMP. DEPTH)	13,036	S.Y.		\$ -
6	HOT MIX ASPHALTIC PAVEMENT, TYPE D (4" COMP. DEPTH)	2,628	S.Y.		\$ -
7	6" LIME TREATED SUBGRADE (54 LB/S.Y.)	18,456	S.Y.		\$ -
8	CONCRETE HEADER CURB	28	L.F.		\$ -
9	CONCRETE CURB & GUTTER	8,994	L.F.		\$ -
10	4' CONCRETE SIDEWALKS	1,255	S.Y.		\$ -

BIDDER SIGNATURE _____



BID FORM (SCHEDULE OF VALUES)					
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT BID PRICE	EXTENDED AMOUNT
11	TIMBER GUARD POSTS	5	EA.		\$ -
12	R1-1 STOP (30")(HIGH INTENSITY)	6	EA.		\$ -
13	OM4 END OF ROAD MARKER (18"X18")	3	EA.		\$ -
14	9 INCH [229mm] STREET NAME, BLOCK NUMBER (VARIES x9")(HIGH INTENSITY)	16	EA.		\$ -
15	TYPE II BLUE RAISED PAVEMENT MARKER	7	EA.		\$ -
16	SINGLE ADA RAMP	16	EA.		\$ -
17	DUAL ADA RAMP	8	EA.		\$ -
18	REMOVE CONC. HEADER CURB & GUARD POST	28	L.F.		\$ -
19	REMOVE CONC. CURB & GUTTER	64	L.F.		\$ -
20	REMOVE CONC. SIDEWALK	256	S.Y.		\$ -
21	STOCKPILE EXCESS MATERIAL ON-SITE	22,866	C.Y.		\$ -
STREET SUBTOTAL					\$ -
1	24" H.D.P.E.	524	L.F.		\$ -
2	30" H.D.P.E.	873	L.F.		\$ -
3	42" H.D.P.E.	179	L.F.		\$ -
4	48" H.D.P.E.	75	L.F.		\$ -
5	10' CURB INLET (8.5' DEPTH)	1	EA.		\$ -
6	15' CURB INLET (7.5' DEPTH)	1	EA.		\$ -
7	15' CURB INLET (8' DEPTH)	2	EA.		\$ -
8	5'x5' 4-WAY INLET (10' DEPTH)	1	EA.		\$ -
9	3'x3' 4-WAY INLET (7' DEPTH)	1	EA.		\$ -
10	SIDEWALK BOX (5 FT)	1	EA.		\$ -
11	10' CURB INLET EXTENSION	3	EA.		\$ -
12	4'x4'x8' JUNCTION BOX	2	EA.		\$ -

BIDDER SIGNATURE _____



BID FORM (SCHEDULE OF VALUES)					
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT BID PRICE	EXTENDED AMOUNT
13	4'x4'x7.5' JUNCTION BOX	1	EA.		\$ -
14	CONCRETE HEADWALL	3.8	C.Y.		\$ -
15	CONCRETE RIPRAP (5" THICK)	576	S.Y.		\$ -
16	CONCRETE BAFFLE BLOCKS	3	C.Y.		\$ -
17	HYDROMULCH (EARTHEN CHANNELS, POND INVERT/SIDE SLOPES)	10,538	S.Y.		\$ -
18	PIPE RAILING	31	L.F.		\$ -
19	8" X 12" ROCK RUBBLE	174	S.Y.		\$ -
20	TURF REINFORCEMENT MAT (LANDLOK)	1,153	S.Y.		\$ -
21	DRAINAGE EXCAVATION	12,860	C.Y.		\$ -
22	DRAINAGE EMBANKMENT	378	C.Y.		\$ -
DRAINAGE SUBTOTAL				\$	-
1	TRENCH EXCAVATION SAFETY PROTECTION	9,088	L.F.		\$ -
2	8" PVC SANITARY SEWER LINE (0' - 6')	213	L.F.		\$ -
3	8" PVC SANITARY SEWER LINE (6' - 8')	52	L.F.		\$ -
4	8" PVC SANITARY SEWER LINE (8' - 10')	1,577	L.F.		\$ -
5	8" PVC SANITARY SEWER LINE (10' - 12')	986	L.F.		\$ -
6	8" PVC SANITARY SEWER LINE (12' - 14')	740	L.F.		\$ -
7	8" PVC SANITARY SEWER LINE (14' - 16')	184	L.F.		\$ -
8	4' DIA. SANITARY SEWER MANHOLE (0'-6')	19	EA.		\$ -
9	4' DIA. EXTRA DEPTH MANHOLES (>6')	83	V.F.		\$ -
10	6" SANITARY SEWER LATERAL W/ CLEANOUT	5,336	L.F.		\$ -
11	VERTICAL STACKS	134	V.F.		\$ -
12	CONCRETE ENCASEMENT	12	C.Y.		\$ -
13	MANHOLE RING ENCASEMENT	3	EA.		\$ -

BIDDER SIGNATURE _____



BID FORM (SCHEDULE OF VALUES)					
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT BID PRICE	EXTENDED AMOUNT
14	SEWER MAIN TELEVISION INSPECTION	3,752	L.F.		\$ -
15	SANITARY SEWER MAIN TIE-IN (INCLUDE REMOVAL AND REPLACEMENT OF CURB, FLEX BASE, HMAC AND SIDEWALK)	1	EA.		\$ -
SANITARY SEWER SUBTOTAL					\$ -
1	TRENCH EXCAVATION PROTECTION	4,562	L.F.		\$ -
2	8" C-909, PC235 PIPE	3,673	L.F.		\$ -
3	12" C-909, PC235 PIPE	874	L.F.		\$ -
4	8" D.I., C-151 PIPE	15	L.F.		\$ -
5	3/4" SINGLE WATER SERVICE - LONG	3	EA.		\$ -
6	3/4" SINGLE WATER SERVICE - SHORT	2	EA.		\$ -
7	1" DUAL WATER SERVICE - LONG	19	EA.		\$ -
8	1" DUAL WATER SERVICE - SHORT	28	EA.		\$ -
9	3/4" IRRIGATION SERVICE - SHORT	3	EA.		\$ -
10	8" GATE VALVE & BOX, COMPLETE	14	EA.		\$ -
11	12" GATE VALVE & BOX, COMPLETE	4	EA.		\$ -
12	METER BOXES	102	EA.		\$ -
13	STANDARD FIRE HYDRANT COMPLETE W/ VALVE	8	EA.		\$ -
14	CAST IRON FITTINGS	4.57	TON		\$ -
15	DISINFECTION & HYDROSTATIC TESTING	1	EA.		\$ -
16	2" PERMANENT BLOWOFF	2	EA.		\$ -
17	2" TEMPORARY BLOWOFF	2	EA.		\$ -
18	24" STEEL CASING	82	L.F.		\$ -
19	WATER MAIN TIE-IN	2	EA.		\$ -
20	DISINFECTION SAMPLE PORT STATION	1	EA.		\$ -

BIDDER SIGNATURE _____



BID FORM (SCHEDULE OF VALUES)					
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT BID PRICE	EXTENDED AMOUNT
21	2 - 4" SCH. 40 PVC CONDUITS (IRRIGATION)	220	L.F.		\$ -
WATER SUBTOTAL					\$ -
TOTAL BASE BID AMOUNT					
TOTAL BASE BID AMOUNT					\$ -
ADD ALTERNATE ITEMS					
1	JOINT TRENCH CONDUIT CROSSING (3-2.5" SCH 40 PVC - GVEC)	100	L.F.		\$ -
2	JOINT TRENCH CONDUIT CROSSING (5-2.5" SCH 40 PVC - GVEC)	100	L.F.		\$ -
3	CONDUIT CROSSING (1-4" SCH 40 PVC - CENTERPOINT)	100	L.F.		\$ -
4	JOINT TRENCH CONDUIT CROSSING (2-4" SCH 40 PVC & 1-4" SCH 80 PVC - AT&T, SPECTRUM, HOTWIRE)	100	L.F.		\$ -
ADD ALTERNATE TOTAL AMOUNT					\$ -

BIDDER SIGNATURE _____