



Sheet List Table	
CONSTRUCTION PLANS: GENERAL NOTES	
G1	GENERAL NOTES
CONSTRUCTION PLANS: UTILITY CONSTRUCTION PLANS	
U1	UTILITY LAYOUT PLAN
CONSTRUCTION PLANS: STREET & DRAINAGE CONSTRUCTION PLANS	
S1	STREET PLAN & PROFILE - WYATT WAY
S2	STANDARD STREET DETAILS*
S3	ADA RAMP STANDARDS*
S4	TYPICAL CONCRETE DRIVEWAY STANDARDS*
CONSTRUCTION PLANS: TRAFFIC CONSTRUCTION PLANS	
T1	TRAFFIC SIGNAGE PLAN
T2	TXDOT SIGN MOUNTING DETAILS*
T3	TXDOT SIGN MOUNTING DETAILS*
CONSTRUCTION PLANS: DRAINAGE CONSTRUCTION PLANS	
D1	MASTER DRAINAGE PLAN - ULTIMATE CONDITIONS
D2	DRAINAGE PLAN & PROFILE - DRAIN 3F
D3	DRAINAGE PLAN & PROFILE - DRAIN 3G
D4	DRAINAGE PLAN & PROFILE - DRAIN 3H
D5	DRAINAGE PLAN & PROFILE - DRAIN 3I
D6	DRAINAGE PLAN & PROFILE - DRAIN 3J
D7	CONCRETE RIP-RAP AND INLET DETAILS*
D8	INLET DETAIL*
D9	INLET DETAIL & EROSION CONTROL DETAILS*
CONSTRUCTION PLANS: SANITARY SEWER CONSTRUCTION PLANS	
SS1	SANITARY SEWER GENERAL NOTES AND DETAILS*
SS2	SANITARY SEWER DETAILS*
SS3	SANITARY SEWER MASTER PLAN
SS4	SANITARY SEWER PLAN AND PROFILE - LINE "3A"
SS5	SANITARY SEWER PLAN AND PROFILE - LINE "3J"
CONSTRUCTION PLANS: WATER DISTRIBUTION CONSTRUCTION PLANS	
W1	WATER DISTRIBUTION STANDARD DETAILS*
W2	WATER DISTRIBUTION STANDARD DETAILS*
W3	WATER DISTRIBUTION PLAN
CONSTRUCTION PLANS: MISCELLANEOUS CONSTRUCTION PLANS	
E1	STORMWATER POLLUTION PREVENTION PLAN
E2	STORMWATER POLLUTION PREVENTION PLAN DETAILS*
GR1	GRADING PLAN
* DENOTES STANDARD DETAILS ADOPTED FOR USE ON THIS PROJECT	



**Preliminary**  
11/30/2023 8:40:09 AM



GRACE VALLEY RANCH  
PHASE 3 STREET EXTENSION  
CONSTRUCTION PLANS


**DEVELOPER:**  
LENNAR HOMES OF TEXAS LAND AND  
CONSTRUCTION, LTD.  
CONTACT: RICHARD MOTT, P.E.  
1922 DRY CREEK WAY, SUITE 101  
SAN ANTONIO, TEXAS 78259  
TEL: (210) 403-6282

4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P:(210) 681.2951 F: (210) 523.7112

DRAWN BY	DATE	PLAT NO.
K.M.H./N.N.R./M.O.H.	11/29/2023	
CHECKED BY	PROJECT NO.	CUDE ENGINEERS
CHRIS CHAFFEE, P.E.	03346.006	TBPE No. 455 TBPLS No. 10048500

I HAVE REVIEWED THIS PLAN SET  
FOR QUALITY ASSURANCE AND  
QUALITY CONTROL PURPOSES.

THIS PLAN SET HAS BEEN PREPARED,  
DESIGNED AND REVIEWED UNDER MY  
DIRECT SUPERVISION.



4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P:(210) 681.2951 F: (210) 523.7112

GRACE VALLEY RANCH PHASE 3  
STREET EXTENSION

GENERAL NOTES

DATE

11/29/2023

PROJECT NO.

03346.014

DRAWN BY

MAS

CHECKED BY

KMH

REVISIONS

- 1.
- 2.
- 3.
- 4.
- 5.
- 6.
- 7.
- 8.
- 9.

CUDE ENGINEERS

TBPE No. 455  
TBPLS No. 10048500

G1

GENERAL NOTES:

FOR ROADS INTENDED FOR MAINTENANCE BY GUADALUPE COUNTY:

1. PRIOR TO THE COMMENCEMENT OF ANY WORK, THE COUNTY SHALL ATTEND A PRECONSTRUCTION MEETING INCLUDING (BUT NOT LIMITED TO) THE CITY, ENGINEER, CONTRACTOR, DEVELOPER'S INSPECTION REPRESENTATIVE, AND DEVELOPER'S CONSTRUCTION MATERIAL TESTING REPRESENTATIVE.
2. DURING CONSTRUCTION, NOTIFY THE COUNTY AT CONSTRUCTION@CO.GUADALUPE.TX.US AT LEAST 48 HOURS IN ADVANCE OF ANY WORK TO BE PERFORMED AFFECTING SUBGRADE, BASE, OR PAVEMENT INCLUDING BACKFILL OF ANY PROPOSED UTILITIES UNDERNEATH THE PAVEMENT AND FILL AREAS UPON WHICH PAVEMENT IS PROPOSED TO BE PLACED. SUCH NOTIFICATION IS ALSO REQUIRED BEFORE IMPLEMENTING ANY APPROVED TRAFFIC CONTROL PLANS ON EXISTING COUNTY-MAINTAINED ROADS. FULL CLOSURE OF COUNTY ROADS REQUIRES AT LEAST ONE MONTH ADVANCE NOTICE AND IS SUBJECT TO THE DISCRETION OF THE COUNTY ENGINEER AND POSSIBLE APPROVAL BY GUADALUPE COUNTY COMMISSIONERS COURT PER TRANSPORTATION CODE, CHAPTER 251.
3. DURING CONSTRUCTION, PROVIDE ALL INSPECTION AND TESTING REPORTS TO THE COUNTY AT CONSTRUCTION@CO.GUADALUPE.TX.US AS SOON AS AVAILABLE FOR IDENTIFICATION AND CORRECTION OF ANY EMERGING DEFICIENCIES.
4. AT THE COMPLETION OF CONSTRUCTION, PROVIDE AS-BUILT DRAWINGS AND A LETTER SIGNED AND SEALED BY THE ENGINEER OF RECORD CERTIFYING THAT:
  - ALL IMPROVEMENTS WERE MADE IN ACCORDANCE WITH THE APPROVED IMPROVEMENT PLANS AND COUNTY REGULATIONS.
  - ANY CHANGED IMPROVEMENTS WERE MADE IN ACCORDANCE WITH THE COUNTY'S REGULATIONS.
  - THE ELEVATIONS AND GRADES WERE TAKEN BY AN ON-SITE SURVEY ON A DATE SPECIFIED TO ENSURE THAT ALL PAVEMENT, INLETS, MANHOLES, AND APPURTENANCES ARE CONSTRUCTED TO GRADE AS SHOWN ON THE RECORD DRAWINGS AND ARE IN COMPLIANCE WITH THE APPROVED PLANS AND SPECIFICATIONS.
  - ALL TRUNK STORM SEWERS AND LEADS ARE OF THE PROPER SIZED AND AND THAT ALL IMPROVEMENTS ARE CAPABLE OF PERFORMANCE AS DESIGNED AND APPROVED.

FOR ROADS INTENDED FOR PRIVATE MAINTENANCE:

1. PRIOR TO THE COMMENCEMENT OF ANY WORK, THE COUNTY SHALL ATTEND A PRECONSTRUCTION MEETING INCLUDING (BUT NOT LIMITED TO) THE CITY, ENGINEER, CONTRACTOR, DEVELOPER'S INSPECTION REPRESENTATIVE, AND DEVELOPER'S CONSTRUCTION MATERIAL TESTING REPRESENTATIVE.
2. DURING CONSTRUCTION, NOTIFY THE COUNTY AT CONSTRUCTION@CO.GUADALUPE.TX.US AT LEAST 48 HOURS IN ADVANCE OF ANY WORK TO BE PERFORMED AFFECTING SUBGRADE, BASE, OR PAVEMENT INCLUDING BACKFILL OF ANY PROPOSED UTILITIES UNDERNEATH THE PAVEMENT AND FILL AREAS UPON WHICH PAVEMENT IS PROPOSED TO BE PLACED. SUCH NOTIFICATION IS ALSO REQUIRED BEFORE IMPLEMENTING ANY APPROVED TRAFFIC CONTROL PLANS ON EXISTING COUNTY-MAINTAINED ROADS. FULL CLOSURE OF COUNTY ROADS REQUIRES AT LEAST ONE MONTH ADVANCE NOTICE AND IS SUBJECT TO THE DISCRETION OF THE COUNTY ENGINEER AND POSSIBLE APPROVAL BY GUADALUPE COUNTY COMMISSIONERS COURT PER TRANSPORTATION CODE, CHAPTER 251.
3. DURING CONSTRUCTION, PROVIDE ALL INSPECTION AND TESTING REPORTS TO THE COUNTY AT CONSTRUCTION@CO.GUADALUPE.TX.US AS SOON AS AVAILABLE FOR IDENTIFICATION AND CORRECTION OF ANY EMERGING DEFICIENCIES.
4. AT THE COMPLETION OF CONSTRUCTION, PROVIDE AS-BUILT DRAWINGS.

CONSTRUCTION SEQUENCING: (LIST PROCESS ON CONSTRUCTION PLAN SET)

1. CALL THE PLANNING AND DEVELOPMENT SERVICES DEPARTMENT 48 HOURS PRIOR TO BEGINNING ANY WORK AND SCHEDULE A RECONSTRUCTION MEETING WITH THE CITY AND ALL AFFECTED UTILITY PROVIDERS, THE GENERAL CONTRACTOR, THE DEVELOPER AND THE DEVELOPER'S ENGINEER.
2. OBTAIN A SITE DEVELOPMENT PERMIT FROM THE PLANNING AND DEVELOPMENT SERVICES DEPARTMENT.
3. PROVIDE THE PLANNING AND DEVELOPMENT SERVICES DEPARTMENT WITH EVIDENCE ALL TCEQ LICENSES AND REQUIREMENTS ARE UP TO DATE.
4. INSTALL TEMPORARY EROSION CONTROLS AND TREE PROTECTION FENCING PRIOR TO ANY CLEARING AND GRUBBING. NOTIFY THE CITY WHEN INSTALLED.
5. ROUGH-CUT ALL REQUIRED OR NECESSARY PONDS. EITHER THE PERMANENT OUTLET STRUCTURE OR A TEMPORARY OUTLET MUST BE CONSTRUCTED PRIOR TO DEVELOPMENT OF ANY EMBANKMENT OR EXCAVATION THAT LEADS TO PONDING CONDITIONS. THE OUTLET SYSTEM MUST CONSIST OF A LOW-LEVEL OUTLET AND AN EMERGENCY OVERFLOW MEETING THE REQUIREMENTS OF THE UDC. THE OUTLET SYSTEM SHALL BE PROTECTED FROM EROSION AND SHALL BE MAINTAINED THROUGHOUT THE COURSE OF CONSTRUCTION UNTIL FINAL RESTORATION IS ACHIEVED.
6. DELIVER APPROVED ROUGH CUT SHEETS TO THE CITY ENGINEER PRIOR TO CLEARING AND GRUBBING.
7. ROUGH GRADE STREETS. NO DEVELOPMENT OF EMBANKMENT WILL BE PERMITTED AT THIS TIME.
8. INSTALL ALL UTILITIES TO BE LOCATED UNDER THE PROPOSED PAVEMENT OR WITHIN THE ROAD RIGHT-OF-WAY.
9. DELIVER STORM SEWER CUT SHEETS TO THE CITY ENGINEER.
10. BEGIN INSTALLATION OF STORM SEWER LINES. UPON COMPLETION, RESTORE AS MUCH DISTURBED AREA AS POSSIBLE, PARTICULARLY CHANNELS AND LARGE OPEN AREAS.
11. DELIVER FINAL GRADE CUT SHEETS TO THE CITY ENGINEER.
12. RE-GRADE STREETS TO SUB-GRADE.
13. ENSURE THAT UNDERGROUND UTILITY CROSSINGS ARE COMPLETED. LAY 1ST COURSE BASE MATERIAL ON STREETS.
14. INSTALL CURB AND GUTTER.
15. LAY FINAL BASE COURSE ON ALL STREETS.
16. LAY ASPHALT.
17. COMPLETE FINAL GRADING AND RESTORATION OF DETENTION, SEDIMENTATION / FILTRATION PONDS.
18. COMPLETE PERMANENT EROSION CONTROL AND RESTORATION OF SITE VEGETATION.
19. REMOVE AND DISPOSE OF TEMPORARY EROSION CONTROLS.
20. COMPLETE ANY NECESSARY FINAL DRESS UP OF AREAS DISTURBED.

STREET AND DRAINAGE GENERAL NOTES:

1. ALL WORK IS TO BE INSTALLED IN ACCORDANCE WITH STANDARDS OF THE CITY OF CIBOLO MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT WILL CONFORM TO APPLICABLE CITY OF CIBOLO SUBDIVISIONS REGULATIONS AND, STANDARD SPECIFICATIONS AND DETAILS.
2. FOR ALL REFERENCES TO THE TEXAS DEPARTMENT OF TRANSPORTATION (TXDOT), THE CONTRACTOR SHALL SEE THEIR CURRENT STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MAINTENANCE OF HIGHWAYS, STREETS, AND BRIDGES, WHICH IS ALSO LOCATED AT [WWW.TXDOT.GOV](http://www.txdot.gov).
3. ALL CONCRETE SHALL BE AS DETAILED ON THE PLAN SHEETS AND MEET MATERIAL REQUIREMENTS OF GUADALUPE COUNTY.
4. ALL REINFORCING STEEL SHALL BE GRADE 60, MEET THE MATERIAL AND CONSTRUCTION REQUIREMENTS OF GUADALUPE COUNTY.
5. CONCRETE CURING SHALL BE WITH AN IMPERVIOUS MEMBRANE APPLICATION AND SHALL MEET THE MATERIAL AND APPLICATION REQUIREMENTS OF THE CITY OF SAN ANTONIO'S "MEMBRANE CURING" AND BE LISTED ON THE GUADALUPE COUNTY APPROVED LIST OF SUPPLIERS. IN ADDITION TO THE CONTRACTOR APPLYING THE CURING COMPOUND THEY ARE TO INSTALL CONTRACTION/EXPANSION JOINTS ON CONCRETE WORK.
6. ALL CONCRETE CONSTRUCTION AND FINISHING SHALL MEET THE REQUIREMENTS OF GUADALUPE COUNTY.
7. THE CONTRACTOR IS REQUIRED TO ATTEND A PRE-CONSTRUCTION CONFERENCE AND SHALL SCHEDULE IT WITH THE CITY PLANNING AND ENGINEERING DEPARTMENT (RUDY KLEIN A1 (210) 658-9900 EXT 3139) A MINIMUM OF ONE (1) WEEK PRIOR TO BEGINNING CONSTRUCTION.
8. MANHOLES SHALL BE BROKEN BELOW THE FINISH GRADE LEVEL UNTIL THE BASE IS COMPLETED AND THEN RESTORED.
9. THE ENGINEER WILL STAKE THE STREET ONE TIME ONLY AND FURNISH CUT SHEETS TO THE STREET CONTRACTOR. ANY CONSTRUCTION STAKES REMOVED OR DESTROYED BY THE CONTRACTOR OR HIS EMPLOYEES WILL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
10. AN INDEPENDENT TESTING LABORATORY APPROVED BY THE CITY OF CIBOLO SHALL PERFORM ALL "FIELD AND LABORATORY TESTING". THE CITY REQUIRES ALL INSPECTION AND/OR TESTING FIRMS TO BE ACCREDITED, QUALIFIED, AND IN COMPLIANCE WITH THE REQUIREMENTS OF ASTM E329, "STANDARD SPECIFICATION FOR AGENCIES ENGAGED IN CONSTRUCTION INSPECTION AND/OR TESTING". FIRMS MUST PRESENT A COPY OF THEIR CURRENT, OFFICIAL ACCREDITATION BY THE AMERICAN ASSOCIATION FOR LABORATORY ACCREDITATION (A2LA) OR THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO) AND CURRENT AMRL AND CCRL PROFICIENCY RESULTS. THE FIRMS SHALL BE

ACCREDITED IN ALL MATERIAL TEST PROCEDURES REQUIRED TO BE PERFORMED FOR EACH PROJECT.

11. THE DEVELOPER WILL HIRE A THIRD PARTY FOR CONSTRUCTION MATERIAL TESTING IN WHICH THE CONTRACTOR WILL REQUIRE TO COORDINATE AND PROVIDE NECESSARY INFORMATION TO THEM. THE FOLLOWING TEST SCHEDULE SHALL BE ADHERE TO:
  - A. ALL IMPORT FILL PLACED IN THE STREET'S SUBGRADE SHALL BE SELECT MATERIAL, WITH A PLASTICITY INDEX LESS THAN TWENTY (20), AND COMPACTED IN MAXIMUM EIGHT (8) INCH LIFTS TO 98% DENSITY OF TXDOT'S TEST METHOD TEX 113-E. PROVIDE TESTING ON EACH EIGHT (8) INCH COMPACTED LIFT. SUBGRADE MOISTURE DENSITY TESTING SHALL BE AT THE MINIMUM FREQUENCY OF THREE (3) PER BLOCK AND SHALL NOT TO EXCEED FIVE HUNDRED (500) FOOT SPACING.
  - B. FLEXIBLE BASE TESTING SHALL INCLUDE – P.I., L.L., GRADATION, AND WET BALL MILL OF MATERIAL SHALL BE TESTED UPON DELIVERY TO THE PROJECT AND AS DIRECTED BY THE CITY. MOISTURE DENSITY TESTING SHALL BE AT THE MINIMUM RATE OF THREE (3) PER BLOCK AND SHALL NOT TO EXCEED FIVE HUNDRED (500) FOOT SPACING. THE QUALITY CONTROL TEST ON THE MATERIALS SHALL BE PERFORMED BY THE CONTRACTOR'S CITY APPROVED TESTING FIRM. IN-PLACE DENSITY SHALL MEET THE REQUIREMENTS DETAILED IN THE CITY'S SUBDIVISION REGULATIONS.
  - C. HOT AND WARM MIX ASPHALTIC CONCRETE (HMAC/WMAC) DENSITY – IN PLACE DENSITY TESTING SHALL RESULT BETWEEN 92% AND 97% OF THE MAXIMUM THEORETICAL GRAVITY PER TEX 207-F. A SET OF TWO (2) CORES SHALL BE RANDOMLY SAMPLED AT A DISTANCE NOT TO EXCEED FIVE HUNDRED (500) FOOT SPACING PER BLOCK. ALL QUALITY CONTROL NUCLEAR TESTING OF THE IN-PLACE HMAC/WMAC IS FOR QUALITY CONTROL INFORMATION ONLY. THE HMAC/WMAC THICKNESS IS REQUIRED TO BE MEASUREMENT BY CORE. FIELD QUALITY CONTROL PERSONNEL SHALL BE TXDOT LEVEL II CERTIFIED AND BE PRESENT AT START AND THROUGH THE DURATION OF THE PLACEMENT OPERATIONS OF THE HMAC/WMAC TO DOCUMENT DENSITY, THICKNESS, AND COMPACTION AND PLACEMENT OPERATIONS. THE CITY WILL DETERMINE THE REMOVAL AND REPLACEMENT OF ALL FAILED PRODUCTION AND PLACEMENT HMAC/WMAC TEST RESULTS.
  - D. RECYCLED ASPHALT SHINGLES (RAS) AND RECYCLED ASPHALT PAVEMENT (RAP) SHALL NOT BE USED IN ANY HMAC OR WMAC MIXES.
  - E. CONCRETE STRUCTURES – A MINIMUM OF ONE (1) SET OF COMPRESSIVE CONCRETE STRENGTH TEST OF 4, SIX (6) INCH DIAMETER CYLINDERS EACH WILL BE TESTED PER EACH STRUCTURE AND THE FREQUENCY SHALL BE NO LESS THAN ONE (1) SET PER SIXTY (60) CUBIC YARDS OF CONCRETE PLACED AND AT LEAST ONE (1) SET PER DAY.

CERTIFICATE OF APPROVAL BY CITY ENGINEER:

APPROVED ON THIS THE \_\_\_\_ DAY OF \_\_\_\_\_, 20\_\_\_\_, BY THE CITY ENGINEER, CITY OF CIBOLO, TEXAS.

CITY ENGINEER, CITY OF CIBOLO

"RELEASE OF THIS APPLICATION DOES NOT CONSTITUTE A VERIFICATION OF ALL DATA, INFORMATION AND CALCULATIONS SUPPLIED BY THE APPLICANT. THE ENGINEER OF RECORD IS SOLELY RESPONSIBLE FOR THE COMPLETENESS, ACCURACY AND ADEQUACY OF HIS/HER SUBMITTAL, WHETHER OR NOT THE APPLICATION IS REVIEWED FOR CODE COMPLIANCE BY THE CITY ENGINEER."

"ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE ENGINEER WHO PREPARED THEM. IN APPROVING THESE PLANS, THE CITY OF CIBOLO MUST RELY UPON THE ADEQUACY OF THE WORK OF THE DESIGN ENGINEER."

- F. CONCRETE CURB AND SIDEWALK – PROVIDE ONE (1) SET OF FOUR (4), SIX (6) INCH DIAMETER CYLINDERS PER EACH 500 LINEAR FEET OF CURB AND/OR SIDEWALK AND AT LEAST ONE (1) SET PER DAY.
  - G. THE CONTRACTOR SHALL SUBMIT CONCRETE, WMAC, AND HMAC DESIGNS A MINIMUM OF 2 WEEKS PRIOR TO THE PLACEMENT OF THE MATERIAL.
12. PROOF ROLLING – ALL SUBGRADE AND EACH LIFT OF BASE MATERIAL SHALL BE PROOF-ROLLED TO THE SATISFACTION OF THE CITY. THE CONTRACTOR SHALL PROVIDE THE NECESSARY EQUIPMENT AND OPERATORS FOR PROOF-ROLLING AS DIRECTED BY THE CITY. SOFT AND YIELDING AREAS DISCOVERED SHALL BE CORRECTED BY THE CONTRACTOR AT THEIR EXPENSE.
  13. SURFACE STRUCTURES SUCH AS MAILBOXES, STREET SIGNS, FENCES, DRIVEWAYS, SIDEWALKS, LANDSCAPING, CONCRETE ISLANDS, CURBS OR CONCRETE DRIVEWAYS, ETC., VISIBLE AT THE TIME OF THE SURVEY ARE SHOWN ON THE PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SAFEGUARD AND MAINTAIN ANY AND ALL SURFACE STRUCTURES DURING THE COURSE OF WORK AND TO REPLACE OR REPAIR THOSE ITEMS WHICH ARE DAMAGED BY THE CONTRACTOR WITH LIKE OR BETTER QUALITY AND SHALL BE RESPONSIBLE FOR RESTORING TO ITS ORIGINAL OR BETTER CONDITION (NO SEPARATE PAY ITEM).
  14. LOCATIONS AND DEPTHS OF EXISTING UTILITIES SHOWN ON THE PLANS ARE UNDERSTOOD TO BE APPROXIMATE. ACTUAL LOCATIONS MUST BE FIELD VERIFIED BY THE CONTRACTOR AT LEAST 48 HOURS PRIOR TO CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL UTILITIES, PROTECT THEM DURING CONSTRUCTION AND REPAIR ANY DAMAGE TO OTHER UTILITIES AT NO COST TO THE CITY OF CIBOLO.
  15. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SEE THAT ALL SIGNS AND BARRICADES ARE PROPERLY INSTALLED AND MAINTAINED. ALL LOCATIONS AND DISTANCES WILL BE DECIDED UPON IN THE FIELD BY THE CONTRACTOR, USING THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES. THE CITY'S CONSTRUCTION INSPECTOR/TRAFFIC ENGINEERING REPRESENTATIVE WILL ONLY BE RESPONSIBLE TO INSPECT BARRICADES AND SIGNS. IF IN THE OPINION OF THE TRAFFIC ENGINEERING REPRESENTATIVE/ CONSTRUCTION INSPECTOR, THE TRAFIC CONTROL DEVICES DO NOT CONFORM TO ESTABLISHED STANDARDS, ARE INCORRECTLY PLACED OR INSUFFICIENT IN QUANTITY TO PROTECT THE TRAVELING GENERAL PUBLIC, THE CONSTRUCTION INSPECTOR WILL HAVE THE OPTION OF STOPPING THE OPERATIONS UNTIL SUCH TIME AS THE CONDITIONS ARE CORRECTED AT NO EXPENSE TO THE CITY OF CIBOLO.
  16. DEVELOPER/CONTRACTOR TO INSTALL ALL STREET NAME SIGNS, STOP SIGNS, SPEED LIMIT, YIELD SIGNS, ETC. SIGNS & STREET NAMES SHALL MEET TEXAS MUTCD STANDARDS.
  17. THE STREET CONTRACTOR IS REQUIRED TO ADJUST ALL EXISTING MANHOLES (SEE "ADJUSTING EXISTING MANHOLES" OF THE SPECIFICATION) AND WATER VALVES TO MATCH THE GRADE OF THE STREET SECTION OR THE ELEVATION SPECIFIED ON THE PLANS OR AS DIRECTED BY THE ENGINEER.
  18. DUE TO FEDERAL REGULATIONS TITLE 49, PART 192.181 ACCESS TO GAS VALVES MUST BE MAINTAINED AT ALL TIMES. THE CONTRACTOR MUST PROTECT AND WORK AROUND ANY GAS VALVES THAT ARE IN THE PROJECT AREA.
  19. CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF UNDERGROUND UTILITIES AND OTHER UNDERGROUND STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. CONTRACTOR WILL NOTIFY ALL UTILITY COMPANIES AT LEAST 72 HOURS PRIOR TO EXCAVATION.

CITY OF CIBOLO	(210) 658-9900
GVSLUD	(830) 914-2330
GVTC	(830) 885-4411
GVEC	1-800-401-8345
DIG TESS	1-800-344-8377
TEXAS STATE WIDE ONE CALL LOCATORS	1-800-545-6005 OR 811
  20. CONCRETE CURB SHALL BE CONSTRUCTED WITH A MAXIMUM OF EIGHTY (80) FEET BETWEEN EXPANSION JOINTS AND MARKED AT TEN (10) FOOT INTERVALS WITH APPROVED STEEL MARKING TOOLS. EXPANSION JOINTS SHALL BE PLACED AT THE BEGINNING OF ALL RADII AND AT A MAXIMUM OF EIGHTY (80) FOOT INTERVALS AS DIRECTED BY THE ENGINEER.
  21. THE CONTRACTOR SHALL NOTIFY THE CITY PLANNING AND ENGINEERING DEPARTMENT (RUDY KLEIN A1 (210) 658-9900 EXT 3139) PRIOR TO PLACING BACKFILL OR CONCRETE AND PRIOR TO ANY TESTING. CONTRACTOR SHALL REQUEST INSPECTIONS A MINIMUM OF 24 HOURS IN ADVANCE. NO INSPECTIONS ARE AVAILABLE BETWEEN 1:00 P.M. AND 1:00 P.M. OR AFTER 4:00 PM DAILY, ON WEEKENDS, OR ON CITY HOLIDAYS.
  22. CONCRETE SIDEWALKS SHALL HAVE TOOLED WEAKENED PLANE JOINTS EVERY FOUR (4) FEET AND DOWELED EXPANSION JOINT WITH ONE QUARTER INCH (¼) BITUMASTIC MATERIAL. FORTY FEET (40) ON CENTER AND ABUTTING EXISTING STRUCTURES.
  23. ALL WORKMANSHIP AND MATERIAL SHALL CONFORM TO THE CITY OF CIBOLO ORDINANCES FOR PUBLIC WORKS CONSTRUCTION AND GUADALUPE COUNTY
  24. CONTRACTOR SHALL INSTALL CURB FOR HANDICAP RAMPS AS SHOWN ON THE PLANS AND ADA STANDARD PLAN SHEETS.
  25. CONTRACTOR SHALL PROVIDE BRASS KEYS TO BE USED TO OPEN LOCKING MANHOLE COVERS ON DRAINAGE STRUCTURES DURING PRELIMINARY INSPECTION FOR ACCEPTANCE OF PROJECT.
  26. EXISTING STREETS TRENCHES ARE TO BE BACKFILLED WITH FLOWABLE FILL FROM THE TOP OF THE BEDDING MATERIAL TO WITHIN TWO (2) INCHES OF THE FINISHED GRADE ALLOWING FOR THE SURFACE HMAC/WMAC.


27. REMOVE EXISTING CURB ON ALL NEW DRIVEWAYS AND PLACE THE COMPLETE PAVEMENT THICKNESS WITH A MINIMUM OF FIVE (5) INCHES THICKNESS ON RESIDENTIAL AND SIX (6) INCHES MINIMUM ON COMMERCIAL; DEPENDING ON TRAFFIC WEIGHT.
28. CONCRETE PLACED IN NEW DRIVEWAYS INCLUDING ALLEYS SHALL MEET A MINIMUM 3,000 PSI COMPRESSIVE STRENGTH AT 28 DAYS.
29. EXCESS MATERIAL IS TO BE DISPOSED OF AS DIRECTED BY THE ENGINEER. NO EXCESS MATERIAL SHALL BE DUMPED OR ALLOWED TO ENTER ANY WATERWAY, CULVERT OR OTHER DRAINAGE STRUCTURE. THE CONTRACTOR SHALL NOT PLACE ANY MATERIAL IN THE 100-YEAR FLOODPLAIN WITHOUT OBTAINING AN APPROVED FLOOD PLAIN PERMIT.
30. ANY WORK COMPLETED WITHOUT PRIOR AUTHORIZATION WHETHER INCLUDED IN THE PLANS AND SPECIFICATIONS OR NOT, SHALL NOT BE COMPENSATED BY THE CITY OF UNIVERSAL CITY.
31. PRIOR TO THE COMMENCEMENT OF ANY WORK, THE COUNTY MUST ATTEND A PRE-CONSTRUCTION MEETING INCLUDING (BUT NOT LIMITED TO) THE CITY, ENGINEER, CONTRACTOR, DEVELOPER'S INSPECTION REPRESENTATIVE, AND DEVELOPER'S CONSTRUCTION MATERIAL TESTING REPRESENTATIVE.
32. DURING CONSTRUCTION, NOTIFY THE COUNTY AT CONSTRUCTION@CO.GUADALUPE.TX.US AT LEAST 48 HOURS IN ADVANCE OF ANY WORK TO BE PERFORMED AFFECTING SUBGRADE, BASE, OR PAVEMENT INCLUDING BACKFILL OF ANY PROPOSED UTILITIES UNDERNEATH THE PAVEMENT AND FILL AREAS UPON WHICH PAVEMENT IS PROPOSED TO BE PLACED. SUCH NOTIFICATION IS ALSO REQUIRED BEFORE IMPLEMENTING ANY APPROVED TRAFFIC CONTROL PLANS ON EXISTING COUNTY-MAINTAINED ROADS. FULL CLOSURE OF COUNTY ROADS REQUIRES AT LEAST ONE MONTH ADVANCE NOTICE AND IS SUBJECT TO THE DISCRETION OF THE COUNTY ENGINEER AND POSSIBLE APPROVAL BY GUADALUPE COUNTY COMMISSIONERS COURT PER TRANSPORTATION CODE, CHAPTER 251.
33. DURING CONSTRUCTION, PROVIDE ALL INSPECTION AND TESTING REPORTS TO THE COUNTY AT CONSTRUCTION@CO.GUADALUPE.TX.US AS SOON AS AVAILABLE FOR IDENTIFICATION AND CORRECTION OF ANY EMERGING DEFICIENCIES.
34. AT THE COMPLETION OF CONSTRUCTION, PROVIDE AS-BUILT DRAWINGS.

MISCELLANEOUS NOTES:

1. ACCESS TO THIS SITE IS PROVIDED THROUGH TWO PROPOSED DRIVEWAYS ALONG GREEN VALLEY RD.
2. DRIVEWAYS ARE SHOWN FOR ILLUSTRATIVE PURPOSES ONLY TO DENOTE A POTENTIAL CONFLICT WITH DRAINAGE FACILITY AND/OR ADA RAMP. ALL DRIVEWAYS WILL BE BUILT WITH HOMEBUILDING.
3. ALL REQUIRED ADA RAMP ARE SHOWN ON THE PLANS. ONLY ADA RAMPS WITHOUT RESIDENTIAL LOT FRONTAGE SHALL BE BUILT WITH THE STREET INFRASTRUCTURE.
4. CONTRACTOR SHALL REFERENCE TREE PLAN AND PRIVATE GRADING PLAN FOR CLEARING AND GRADING LIMITS.
5. PRIOR TO THE INSTALLATION OF STREET BASE MATERIAL, CONTRACTOR SHALL COORDINATE WITH ENGINEER AND UTILITY PROVIDERS TO INSTALL NECESSARY CONDUITS FOR UTILITY INSTALLATION.
6. CONTRACTOR IS RESPONSIBLE FOR ENSURING POSITIVE SITE DRAINAGE AT ALL TIMES DURING AND UPON COMPLETION OF INFRASTRUCTURE.
7. CONTRACTOR IS REQUIRED TO NOTIFY ENTERPRISE UTILITIES WHEN ENCRANCHING UPON THE EXISTING GAS EASEMENT ON SITE.

CITY OF CIBOLO NOTES:

1. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE CITY OF CIBOLO DESIGN AND CONSTRUCTION MANUAL AND THE UNIFIED DEVELOPMENT CODE, HERE AFTER REFERRED TO THE UDC.
2. APPROVAL OF THESE CONSTRUCTION PLANS BY THE CITY OF CIBOLO DOES NOT CONSTITUTE A VERIFICATION OF ALL DATA, INFORMATION AND CALCULATIONS SUPPLIED BY THE APPLICANT. THE ENGINEER OF RECORD IS SOLELY RESPONSIBLE FOR THE COMPLETENESS, ACCURACY AND ADEQUACY OF HIS/HER SUBMITTAL WHETHER OR NOT THE APPLICATION IS REVIEWED FOR CODE COMPLIANCE BY THE CITY ENGINEER.
3. ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE ENGINEER WHO PREPARED THEM. IN APPROVING THESE PLANS, THE CITY OF CIBOLO MUST RELY ON THE ADEQUACY OF THE WORK OF THE ENGINEER.
4. DESIGN PROCEDURES ARE IN COMPLETE COMPLIANCE WITH THE CITY OF CIBOLO DESIGN AND CONSTRUCTION MANUAL. IT IS THE RESPONSIBILITY OF THE ENGINEER TO REQUEST A WAIVER FROM ANY ASPECT OF THESE PLANS THAT DO NOT COMPLY WITH THE UDC.
5. A MINIMUM OF TWO EXISTING BENCH MARKS TIED TO CITY OF CIBOLO GRID SHOULD BE SHOWN ON THE PLANS. IN ADDITION TWO PERMANENT BENCHMARKS PER SUBDIVISION SHALL BE INSTALLED IN EACH SUBDIVISION TO INCLUDE DESCRIPTION, LOCATION, AND ELEVATION AND TIE TO CITY OF CIBOLO STANDARDS WHEN POSSIBLE.
6. CAST BRONZE SURVEY MARKERS SHALL BE PLACED IN CONCRETE IN PERMANENT, ACCESSIBLE LOCATIONS AT THE TIME OF CONSTRUCTION. THE LOCATIONS OF THE MARKERS SHALL BE INDICATED ON THE CONSTRUCTION PLANS. A MINIMUM OF ONE MARKER SHALL BE PLACED FOR EACH 20 ACRES OF THE PROJECT.
7. PRIOR TO BEGINNING CONSTRUCTION, THE OWNER OR HIS AUTHORIZED REPRESENTATIVE SHALL CONVENE A PRE-CONSTRUCTION CONFERENCE BETWEEN THE CITY OF CIBOLO, CONSULTING ENGINEER, CONTRACTOR, AND ANY OTHER AFFECTED PARTIES. NOTIFY THE CITY OF CIBOLO AT LEAST 48 HOURS PRIOR TO THE TIME OF THE CONFERENCE AND 48 HOURS PRIOR TO THE BEGINNING OF CONSTRUCTION.
8. THE CONTRACTOR SHALL GIVE THE CITY A MINIMUM OF 48 HOURS NOTICE BEFORE BEGINNING EACH PHASE OF CONSTRUCTION.
9. BARRICADES, BUILT TO CITY OF CIBOLO SPECIFICATIONS, SHALL BE CONSTRUCTED ON ALL DEAD-END STREETS AND AS NECESSARY DURING CONSTRUCTION TO MAINTAIN JOB SAFETY. (STREETS, ETC. MAY BE LISTED IN ADDITION TO OR INSTEAD OF NOTE.)
10. IF BLASTING IS PLANNED BY THE CONTRACTOR, A BLASTING PERMIT MUST BE SECURED PRIOR TO COMMENCEMENT OF ANY BLASTING.
11. ANY EXISTING PAVEMENT, CURBS, AND/ OR SIDEWALKS DAMAGED OR REMOVED WILL BE REPAIRED BY THE CONTRACTOR AT HIS EXPENSE BEFORE ACCEPTANCE OF THE SUBDIVISION.
12. THE LOCATION OF ANY WATER AND / OR WASTEWATER LINES SHOWN ON THE PLANS MUST BE VERIFIED BY THE PUBLIC WORKS DEPARTMENT.
13. USE ONE CALL UTILITY SYSTEM: DIAL 1-800-344-8377, 48 HOURS BEFORE YOU DIG.
14. ALL STORM SEWER PIPES TO BE CLASS III RCP UNLESS NOTED OTHERWISE.






THE CONTRACTOR SHALL BE AWARE THAT EXISTING UTILITIES ARE WITHIN THE BOUNDARY. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO HAVE THESE UTILITIES LOCATED PRIOR TO COMMENCING CONSTRUCTION. THE CONTRACTOR SHALL USE EXTREME CAUTION WHEN WORKING IN THIS AREA. ANY DAMAGE DONE TO THESE EXISTING FACILITIES WILL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO REPAIR.

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL BE IN ACCORDANCE WITH THE TRENCH EXCAVATION SAFETY PROTECTION THAT COMES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATION. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.


WATER METERS TO BE PLACED WITHIN RIGHT-OF-WAY TO AVOID CONFLICT WITH TRANSFORMERS/SECONDARY ENCLOSURE ELECTRIC SERVICE.

1. SLEEVE INSTALLATION TO BE COMPLETED IN ACCORDANCE TO GVEC ISSUED ELECTRICAL PLAN.

2. ONLY 2 1/2 INCH SCHEDULE 40 GRAY ELECTRICAL CONDUIT IS TO BE USED AND IS TO BE SUPPLIED BY THE DEVELOPER. ALL JOINTS MUST BE GULDED.
3. ALL ELECTRICAL CONDUIT SHALL BE INSTALLED AT LEAST 18 INCH BELOW SUB-GRADE OR 4 FT. FROM FINISH GRADE ON NON-WATER SIDE. WHEN ELECTRICAL CROSSINGS ARE REQUIRED TO CROSS WATER MATERS, THEY MUST BE 2 FT. BELOW OR 2 FT ABOVE WATER MATERS, BUT NOT LESS THAN 48 INCHES OF COVER BELOW FINISH GRADE (PIT SAND MAY BE REQUIRED).
4. ALL CONDUIT PIPES SHOULD BE LAID FLAT IN THE DITCH, SIDE BY SIDE, NOT STACKED OR TWISTED, IF MORE THAN TWO PIPES ARE IN A DITCH YOU MUST NUMBER THE INSIDE, BOTTOM OF EACH PIPE (E.G. 1, 2, 3, 4).
5. ALL OTHER UTILITIES MUST MAINTAIN A MINIMUM OF 3 FT. OF SEPARATION FROM THE ELECTRICAL CROSSING DITCH.
6. NO OTHER UTILITY CROSSINGS SHOULD BE STUBBED OUT IN FRONT OF ELECTRICAL TRANSFORMERS OR SWITCHES.
7. NO OTHER UTILITIES ARE TO BE PLACED IN THE SAME DITCH AS THE ELECTRICAL CROSSING.
8. ALL CROSSINGS ARE TO BE INSTALLED AT THE PROPERTY LINE UNLESS THERE ARE WATER MATERS EXISTING ON EACH SIDE OF THE PROPERTY LINE AT THE CROSSING LOCATION. IF THERE ARE WATER MATERS AND WATER MATER CONFLICTS EXIST, THE ELECTRICAL CROSSING MUST BE MOVED 7' FROM THE PROPERTY LINE TO AVOID WATER MATERS. ALL OTHER UTILITY CROSSINGS MUST BE LOCATED 3 FT. ON OPPOSITE SIDE OF PROPERTY LINE.
9. ALL CROSSINGS MUST BE INSPECTED BY A GVIC REPRESENTATIVE BEFORE THEY ARE BACKFILLED. PLEASE PROVIDE ONE WEEK NOTICE AS TO WHEN INSPECTIONS WILL BE NEEDED.
10. ALL ELECTRICAL CONDUIT LOCATIONS SHALL BE PROVIDED ON A SEPARATE EXHIBIT THAT MUST BE REQUESTED BY THE CONTRACTOR TO THE ENGINEER.



11/30/2023 8:40:20 AM



4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P:(210) 681.2951 F: (210) 523.7112

# GRACE VALLEY RANCH PHASE 3 STREET EXTENSION

## UTILITY LAYOUT PLAN

11/29/2023  
.....  
PROJECT NO.  
03346.014

DRAWN BY  
MAS


CHECKED BY  
KMH

## REVISIONS

1. ....
2. ....
3. ....
4. ....
5. ....
6. ....
7. ....
8. ....
9. ....

**CUDE ENGINEERS**  
TBPE No. 455  
TBPLS No. 10048500

# U1




4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P:(210) 681.2951 F: (210) 523.7112

GRACE VALLEY RANCH PHASE 3

STREET EXTENSION

STREET PLAN & PROFILE - WYATT WAY




Preliminary  
11/30/2023 8:40:21 AM

- LEGEND
- PROPOSED SIDEWALK
  - SIDEWALK CONSTRUCTED WITH INFRASTRUCTURE
  - STREET WASHOUT (SEE DETAIL SHEET S6)
  - STREET CENTERLINE
  - EXISTING CONTOURS
  - TOP OF CURB SPOT ELEVATION
  - DRIVEWAY
  - PAVEMENT ELEVATION

COSA TYPE "III" WHEEL CHAIR RAMPS ARE INDICATED THUS  
" III " UNLESS OTHERWISE NOTED.

(SEE DETAIL SHEET S3) FOR ADA RAMPS AT SIDEWALK INTERSECTIONS.  
DETECTABLE WARNING PAVEMENT WITH TRUNCATED DOMES ONLY.

HORIZONTAL SCALE: 1" = 20'  
VERTICAL SCALE: 1" = 5'



DATE	11/29/2023
PROJECT NO.	03346.014
DRAWN BY	MAS
CHECKED BY	KMH
REVISIONS	
1.	
2.	
3.	
4.	
5.	
6.	
7.	
8.	
9.	
CUDE ENGINEERS	
TBPE No. 455	
TBPLS No. 10048500	
PLAT NO.	XX-XXXXXXX
SAWS JOB NO.	XX-XXXX

S1

1. PAVEMENT SECTION REQUIRED IS TO BE DETERMINED BY GEOTECHNICAL ENGINEER ON-SITE.

SUBGRADE NOTES (\*):

- THE SUBGRADE WILL BE PROOFROLLED TO IDENTIFY SOFT AREAS BEFORE STABILIZATION.
- THE SUBGRADE PLASTICITY INDEX VALUE IS EXPECTED TO BE GREATER THAN 20. SUBGRADE STABILIZATION IS NEEDED.
- ALL FILL UNDER ROADWAY TO BE MAX P15.
- UNDERCUT SOFT, WEAK, AND UNSTABLE SOILS BY EXCAVATING BELOW SUBGRADE LEVEL TO EXPOSE STABLE SOILS. THE EXCAVATED SOIL CAN BE USED TO RESTORE THE EXCAVATION SUBGRADE, PROVIDED THAT THE SOILS ARE RELATIVELY FREE AND CLEAN OF DELETERIOUS MATERIAL AND MATERIALS EXCEEDING 3 INCHES IN MAXIMUM DIMENSION. THE EXCAVATED SOIL, OR IMPORTED FILL SOIL, SHALL BE PLACED IN MAXIMUM 6-INCH COMPACTED LIFTS. EACH LIFT OF SOIL SHALL BE MOISTURE CONDITIONED BETWEEN PLUS OR MINUS THREE (+3) PERCENTAGE POINTS OF THE OPTIMUM MOISTURE CONTENT AND COMPACTED TO AT LEAST 95 PERCENT OF THE MAXIMUM DRY DENSITY DETERMINED IN ACCORDANCE WITH THE STANDARD COMPACTION EFFORT (ASTM D 698). IF UNDERCUTTING DEEPER THAN ABOUT 3 FEET IS NEEDED, CONTACT ESI.
- SOIL SUBGRADE AREAS REQUIRING FILL PLACEMENT SHOULD BE SCARIFIED TO A DEPTH OF ABOUT EIGHT (8) INCHES AND MOISTURE CONDITIONED BETWEEN PLUS OR MINUS TWO (+2) POINTS OF THE OPTIMUM MOISTURE CONTENT. THE MOISTURE CONDITIONED SUBGRADE SHOULD THEN BE COMPACTED TO AT LEAST 95 PERCENT OF THE MAXIMUM DRY DENSITY DETERMINED IN ACCORDANCE WITH ASTM D 698. THE SUBGRADE SHOULD BE MOISTURE CONDITIONED JUST PRIOR TO FILL PLACEMENT SO THE SUBGRADE MAINTAINS ITS COMPACTION MOISTURE LEVELS AND DOES NOT DRY OUT.
- ANY FILL 5' OR GREATER IN THICKNESS IS TO BE COMPACTED TO D1557.
- ON-SITE SOILS (GENERAL FILL), SELECT FILL OR GRANULAR FILL SOIL SHOULD BE PLACED TO ACHIEVE THE DESIRED ELEVATION.

- INPUT PARAMETERS ARE SHOWN IN TABLE NO. 6. PLEASE CALL US TO PROVIDE PAVEMENT RECOMMENDATIONS, IF NEEDED, FOR DIFFERENT INPUT VALUES.
- IF REPETITIVE TRUCK OR HEAVY TRUCK TRAFFIC IS ANTICIPATED, PLEASE CONTACT US FOR REVISED PAVEMENT RECOMMENDATIONS.
- PAVEMENT SECTION RECOMMENDATIONS ARE BASED ON A CBR VALUE OF 1.8. THE PAVEMENT RECOMMENDATIONS PRESENTED ABOVE ARE NOT BASED ON THE SHRINK / SWELL CHARACTERISTICS OF THE UNDERLYING SOILS. IF WATER IS ALLOWED TO GET UNDERNEATH THE ASPHALT / CONCRETE OR IF MOISTURE CONTENT OF THE BASE OR SUBGRADE CHANGES SIGNIFICANTLY, THEN PAVEMENT DISTRESS WILL OCCUR. MOISTURE PENETRATION UNDERNEATH THE ASPHALT PAVEMENT SURFACE WILL BE REDUCED BY USING DEEPER CURBS; CURBS EXTENDING A MINIMUM OF 3 INCHES INTO SUBGRADE.
- THE PAVEMENT CAN EXPERIENCE CRACKING AND DEFORMATION DUE TO SHRINKAGE AND SWELLING CHARACTERISTICS OF THE SOILS AS DESCRIBED IN THE VERTICAL MOVEMENTS SECTION OF THIS REPORT.

- AT THE TIME OF CONSTRUCTION, THE FINAL PAVEMENT SUBGRADE WILL BE OBSERVED AND VERIFIED BY A REPRESENTATIVE OF TTL, INC.


- THE PRIME COAT SHOULD CONSIST OF SEALING THE BASE WITH AN OIL SUCH AS MC-30 OR AE-P ASPHALT CEMENT. THE PRIME COAT SHOULD BE APPLIED AT A RATE NOT TO EXCEED 0.35 GALLONS PER SQUARE YARD WITH MATERIALS WHICH MEET TXDOT ITEM 300. THE PRIME COAT WILL HELP TO MINIMIZE PENETRATION OF RAINFALL AND OTHER MOISTURE THAT PENETRATES THE BASE.

- THE ASPHALTIC MATERIAL USED FOR TACK COAT SHALL MEET THE REQUIREMENTS FOR "ASPHALT CEMENT", "CUT-BACK ASPHALT" OR "EMULSIFIED ASPHALT" IN ITEM NO. 300, "ASPHALT, OILS AND EMULSIONS" OF THE TEXAS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS. THE ASPHALTIC MATERIAL USED FOR TACK COAT SHALL BE THE TYPE OR GRADE SHOWN IN THE REFERRING SPECIFICATION, OR ON THE PLANS, OR AS DIRECTED/APPROVED BY THE ENGINEER.




STREET TYPE	HMAC TYPE "D"	LIME STABILIZED SUBGRADE	FLEX BASE (TY A GR 2)	STRUCTURAL NUMBER
LOCAL "A"	2.5"	---	10"	2.50

### PIPE ANCHORAGE DETAILS




CONCRETE RIP-RAP AT PIPE  
RAILING BASE PLATE DETAIL

1) CONTRACTOR TO FLARE CONCRETE RIP-RAP TO 8" AT PROPOSED PIPE RAILING BASE PLATE LOCATIONS.




N.T.S.



N.T.S.




NOTE:  
REFERENCE GEOTECHNICAL REPORT TTL, INC NO. 00200903122.01 FOR BORING INFORMATION AND  
CBR LOCATIONS.

 WYATT WAY STA. 18+72.23 - 26+48.09

LOCAL "A" - CURB & GUTTER DETAIL

N.T.S



N.T.S.

4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P:(210) 681.2951 F: (210) 523.7112

# GRACE VALLEY RANCH PHASE 3 STREET EXTENSION

## STANDARD STREET DETAILS

DATE  
11/29/2023

PROJECT NO.  
03346.014

DRAWN BY  
MAS

CHECKED BY  
KMH

## REVISIONS










1. ....
2. ....
3. ....
4. ....
5. ....
6. ....
7. ....
8. ....
9. ....

CUDE ENGINEERS  
TBPE No. 455  
TBPLS No. 10048500

# S2

DETAILS ON THIS DRAWING ARE NOT TO SCALE

REPRODUCTION OF THE ORIGINAL SIGNED AND SEALED PLAN AND/OR ELECTRONIC MEDIA MAY HAVE BEEN INADVERTENTLY ALTERED. CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE SCALE OF THE DOCUMENT AND CONTACTING CUDE ENGINEERS TO VERIFY DISCREPANCIES PRIOR TO CONSTRUCTION.



**SIDEWALK PROFILES AND GRADE REQUIREMENTS**

NOTE:  
STAMPED CONCRETE TRUNCATED DOMES WILL NOT BE ALLOWED TO BE USED FOR DETECTABLE WARNING ON WHEELCHAIR RAMPS. CONTRACTOR MUST SUBMIT TRUNCATED DOME INFORMATION THAT IS TO BE USED ON WHEELCHAIR RAMPS TO THE PROJECT MANAGER FOR APPROVAL AT LEAST 30 DAYS PRIOR TO INSTALLATION.

DATE  
11/29/2023  
PROJECT NO.  
03346.014


DRAWN BY  
MAS  
CHECKED BY  
KMH

**REVISIONS**

1.	
2.	
3.	
4.	
5.	
6.	
7.	
8.	
9.	

CUDE ENGINEERS  
TBPE No. 455  
TBPLS No. 10048500

S3



4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P: (210) 681.2951 F: (210) 523.7112

GRACE VALLEY RANCH PHASE 3

STREET EXTENSION

TYPICAL CONCRETE DRIVEWAY STANDARDS

DATE  
11/29/2023  
PROJECT NO.  
03346.014  
DRAWN BY  
MAS  
CHECKED BY  
KMH


REVISIONS	
1.	
2.	
3.	
4.	
5.	
6.	
7.	
8.	
9.	

CUDE ENGINEERS  
TBPE No. 455  
TBPLS No. 10048500

S4


Preliminary

11/30/2023 8:40:21 AM




TYPICAL RESIDENTIAL DRIVEWAY SECTION

WITH SIDEWALK ABUTTING CURB




TYPICAL RESIDENTIAL DRIVEWAY SECTION

WITH SIDEWALK SEPARATED FROM CURB




TYPICAL RESIDENTIAL DRIVEWAY SECTION

WHERE PROPERTY IS LOWER THAN STREET & SIDEWALK IS ABUTTING CURB




TYPICAL RESIDENTIAL DRIVEWAY SECTION

WHERE PROPERTY IS LOWER THAN STREET & SIDEWALK IS SEPARATED FROM CURB



TYPICAL COMMERCIAL DRIVEWAY SECTION

WITH SIDEWALK ABUTTING CURB



TYPICAL COMMERCIAL DRIVEWAY SECTION

WITH SIDEWALK SEPARATED FROM CURB


CONCRETE DRIVEWAY NOTES

- DRIVEWAY PENETRATION REFERS TO A PORTION OF THE DRIVEWAY THAT MAY BE NECESSARY TO RECONSTRUCT WITHIN PRIVATE PROPERTY TO COMPLY WITH A MAXIMUM DRIVEWAY SLOPE. THIS PORTION OF THE DRIVEWAY SHALL BE PAID FOR UNDER THE FOLLOWING ITEMS AS MAY APPLY:  
A) CONCRETE DRIVEWAY PAID FOR UNDER ITEM NO. 503.1 OR 503.2  
B) ASPHALTIC CONCRETE DRIVEWAY PAID FOR UNDER ITEM NO. 503.4 AND SHALL INCLUDE A MINIMUM OF 1" ASPHALT TYPE 'D' & 6" FLEXIBLE BASE  
C) GRAVEL DRIVEWAY PAID FOR UNDER ITEM NO. 503.5 AND SHALL INCLUDE A MINIMUM OF 6" FLEXIBLE BASE

- 7" MINIMUM HEIGHT WILL NOT NECESSARILY OCCUR AT THE PROPERTY LINE. IT MAY OCCUR WITHIN THE RIGHT OF WAY OR WITHIN THE DRIVEWAY PENETRATION ON PRIVATE PROPERTY.
- THE PROPOSED DRIVEWAY SHOULD MATCH THE EXISTING WIDTH AT THE PROPERTY LINE BUT UNLESS AUTHORIZED BY THE CITY TRAFFIC ENGINEER, THE WIDTH SHALL BE WITHIN THE FOLLOWING VALUES:

TYPE	MINIMUM	MAXIMUM
RESIDENTIAL	10'	20'
COMMERCIAL - ONE WAY	12'	20'
COMMERCIAL - TWO WAY	24'	30'


- FOR LOCAL TYPE "A" STREETS, SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 5' AND IF SEPARATED FROM THE CURB, THE SIDEWALK SHALL BE LOCATED A MINIMUM OF 3' FROM THE BACK OF CURB.
- FOR OTHER THAN LOCAL TYPE "A" STREETS, THE SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 5' AND SEPARATED A MINIMUM OF 3' FROM THE BACK OF CURB OR, AS AN OPTION, THE SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 6' WHEN LOCATED AT THE BACK OF CURB.
- DUMMY JOINTS PARALLEL TO THE CURB SHALL BE PLACED WHERE THE SIDEWALK MEETS THE DRIVEWAY. DUMMY JOINTS PERPENDICULAR TO THE CURB, AND WITHIN THE BOUNDARIES OF THE PARALLEL DUMMY JOINTS, SHALL BE PLACED AT INTERVALS EQUAL TO THE WIDTH OF THE SIDEWALK.
- A MINIMUM OF TWO ROUND AND SMOOTH DOWEL BARS 3/8" IN DIAMETER AND 18" IN LENGTH SHALL BE SPACED 18" APART AT EACH EXPANSION JOINT.
- SIDEWALK RAMP LENGTHS SHALL BE OF SUFFICIENT LENGTH TO MAINTAIN 8.33% (1:12) MAXIMUM SLOPE. WHERE SIDEWALKS CROSS DRIVEWAYS, SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2%.
- SIDEWALK RAMP SURFACE SHALL BE BRUSH FINISHED.



- NOTE:
- COST OF REINFORCEMENT TO BE INCLUDED IN UNIT COST OF ITEM 307.1.
  - CONCRETE RETAINING WALL COMBINATION TYPE SHALL BE USED FOR CONCRETE DRIVEWAYS.


DRIVEWAY - CONCRETE RETAINING WALL

ON COMPACTED SUBGRADE




CURB PROFILE AT DRIVEWAY

WITH SIDEWALK ABUTTING CURB




TYPICAL DRIVEWAY PLAN VIEW

WITH SIDEWALK ABUTTING CURB




CURB PROFILE AT DRIVEWAY

WITH SIDEWALK SEPARATED FROM CURB



TYPICAL DRIVEWAY PLAN VIEW


WITH SIDEWALK SEPARATED FROM CURB




LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD.  
100 NE LOOP 410, SUITE 1155  
SAN ANTONIO, TX 78216  
TEL: (210) 403-6200  
CONTACT PERSON: RICHARD MOTT, P.E.  
**CIVIL ENGINEER:**  
CUDE ENGINEERS  
CONTACT PERSON: CHRIS CHAFFEE, P.E.  
4122 POND HILL ROAD, SUITE 101  
SAN ANTONIO, TX 78231  
TEL: (210) 681-2951  
FAX: (210) 523-7112

NOTE:  
CONTRACTOR TO COORDINATE SIGN PLACEMENT WITH SIDEWALK/ADA RAMP CONSTRUCTION TO AVOID ANY POSSIBLE CONFLICTS.

**Preliminary**  
11/30/2023 8:40:22 AM



CUDEENGINEERS.COM



4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P: (210) 681.2951 F: (210) 523.7112

GRACE VALLEY RANCH PHASE 3  
STREET EXTENSION


TRAFFIC SIGNAGE PLAN

DATE  
11/29/2023  
PROJECT NO.  
03346.014  
DRAWN BY  
MAS  
CHECKED BY  
KMH

REVISIONS	
1.	
2.	
3.	
4.	
5.	
6.	
7.	
8.	
9.	

CUDE ENGINEERS  
TBPE No. 455  
TBPLS No. 10048500

T1



THE USE OF THIS SPECIFICATION IS GOVERNED BY THE TERMS AND CONDITIONS OF THE LICENSE AGREEMENT. THE USER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND FOR OBTAINING ALL NECESSARY INFORMATION FROM THE APPROPRIATE AGENCIES. THE USER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION FROM THE APPROPRIATE AGENCIES.

## SIGN SUPPORT DESCRIPTIVE CODES

(Descriptive Codes correspond to project estimates and quantities sheets)

SM RD SGN ASSM TY XXXXX (X)XX (X-XXXX)

### Post Type

- FRP = Fiberglass Reinforced Plastic Pipe (see SMD(FRP))
- TWT = Thin-Walled Tubing (see SMD(TWT))
- 10BNC = 10 BNC Tubing (see SMD(SLP-1) to SLP-3)
- S80 = Schedule 80 Pipe (see SMD(SLP-1) to SLP-3)

### Anchor Type

- UA = Universal Anchor - Concrete (see SMD(FRP) and (TWT))
- UB = Universal Anchor - Bolted (see SMD(FRP) and (TWT))
- WS = Wedge Anchor Steel - (see SMD(TWT))
- WP = Wedge Anchor Plastic (see SMD(TWT))
- SA = Sillplate - Concrete (see SMD(SLP-1) to SLP-3)
- SB = Sillplate - Bolted (see SMD(SLP-1) to SLP-3)

### Sign Mounting Description

- P = Freeway, "P" (see SMD(SLP-1) to SLP-3), (TWT), (FRP)
- T = Freeway, "T" (see SMD(SLP-1) to SLP-3), (TWT)
- U = Freeway, "U" (see SMD(SLP-1) to SLP-3)
- IF REQUIRED
- TEXT or TEXT = Number of Extensions (see SMD(SLP-1) to SLP-3), (TWT)
- MC = Extruded Metal Mount (see SMD(SLP-1) to SLP-3)
- MC = 1, 1/2 W/ing Channel (see SMD(SLP-1) to SLP-3)
- EXAL = Extruded Aluminum Sign Panels (see SMD(SLP-1) to SLP-3)

## REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT

To avoid vehicle under-carriage snagging, any substantial reaction of a breakaway support when it is broken away, should not project more than 4 inches above a 60-inch chord (i.e., typical space between wheel paths).

## PAVED SHOULDER

### LESS THAN 6 FT. WIDE

When the shoulder is 6 ft. or less in width, the sign must be placed at least 12 ft. from the edge of the travel lane.

### GREATER THAN 6 FT. WIDE

When the shoulder is greater than 6 ft. in width, the sign must be placed at least 6 ft. from the edge of the shoulder.

### T-INTERSECTION

When this sign is needed at the end of a two-lane, two-way roadway, the right edge of the sign should be in line with the centerline of the roadway. Place as close to ROW as practical.

### BEHIND BARRIER

### BEHIND GUARDRAIL

\*Sign clearance based on distance required for proper guard rail or concrete barrier performance.

### BEHIND CONCRETE BARRIER

\*Sign clearance based on distance required for proper guard rail or concrete barrier performance.

## TYPICAL SIGN ATTACHMENT DETAIL

Boils used to mount sign panels to the clamp are 5/16-18 UNC galvanized square head with nut, nylon washer, flat washer and lock washer. The bolt length is 1 foot for aluminum.

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized nut head per ASTM A307 with nut and stainless-steel lock washer. The sign panel length is 48 inches for vertical post signs and sign clamp types are applied in the middle of the sign. The bolt length may need to be adjusted depending upon field conditions.

Sign clamps may be either the specific design shown or the universal clamp.

Post diameter	Approximate Bolt Length
3" diameter	Specific Clamp Universal Clamp
2 1/2" nominal	3 or 3 1/2" 3 1/2 or 4"
2" nominal	3 or 3 1/2" 3 1/2 or 4"

### CURB & GUTTER OR RAISED ISLAND

### SIGNS WITH PLAQUES

When a supplemental plaque or secondary sign is used, the 7 ft sign height is measured to the bottom of the supplemental plaque or secondary sign.

### RESTRICTED RIGHT-OF-WAY (When 6 ft min. is not possible.)

Sign-of-way restrictions may be created by rocks, water, vegetation, forests, buildings, a narrow island, or other factors.

In situations where a lateral restriction prevents the minimum horizontal clearance from the edge of the travel lane, signs should be placed as far from the travel lane as practical.

\*\*\* Post may be shorter if protected by guardrail or if Engineer determines the post could not be hit due to extreme slope.

DATE: 01/10/2010 REVISED: 01/08/2010

BY: [Signature] DATE: [Signature] DATE: [Signature] DATE: [Signature]

**Universal Anchor System  
with Fiberglass Reinforced Plastic (FRP) Post**

**General Notes:**

- FRP sign supports for a single type sign support may be used for signs up to and including 16 square feet. Dual post installation may be used for signs up to and including 32 square feet.
- All nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing."
- See the Traffic Operations Division website for detailed drawings of sign cramps. The website address is: <http://www.txdot.gov/publications/Traffic.htm>

**FRP POST REQUIREMENTS**

- Materials shall conform to the requirements of Departmental Material Specification DMS-4410 and will be furnished in 6' or 12' long gray color as specified elsewhere in the plans.
- Thickness of FRP sign support is  $0.125'' \pm 0.031'' - 0.0''$ .
- FRP sign supports are prequalified by the Traffic Operations Division. Prequalification procedures are obtained by writing:  
Texas Department of Transportation  
Traffic Operations Division  
125 East 11th Street  
Austin, Texas 78701-0483

**UNIVERSAL ANCHOR SYSTEM INSTALLATION PROCEDURES**

- Dig foundation hole. Where soil is less than encountered at ground level, the foundation shall be a minimum depth of 18". When solid rock is encountered below ground level, the hole shall be drilled to a minimum depth of 18" or provide a minimum foundation depth of 30". If solid rock is encountered, the selected depth shall be noted on the plans. The minimum length of 18". Any material removed from the socket/shaft shall be from the bottom and the clearance requirements given on DMS-4410 must be followed. The inner surface of the socket/shaft must remain free of concrete or other debris.
- The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a tub/crate is permitted to be allowed by Engineer. Concrete shall be Class A.
- Insert base post in foundation hole to bottom shown and fill hole with concrete. Cut base post from bottom and ensure a minimum of 18" embedment if installed in solid rock.
- Level and plumb the base post with coupler using a torque level and set concrete set a minimum of 4 days, unless otherwise directed by Engineer. Bottom of base post shall be above the concrete footing.
- Attach sign to FRP post.
- Insert sign post into base post. Lower until the post comes to rest on the steel rod.
- Use hammer to ensure the coupler is firmly seated. Top of coupler should be level with top of base post in most instances.
- Check sign to ensure there is no twist. If loose, increase the tightening of coupler.

**BOLT-DOWN DETAILS**

**TYPICAL SIGN MOUNTING DETAIL FOR FRP SUPPORT WITH SINGLE SIGN**

**TYPICAL SIGN MOUNTING DETAIL FOR FRP SUPPORT WITH BACK-TO-BACK SIGNS**

**SMD (FRP) - 08**

[STANDARD] JULY 2007		ON 1987	ON 1988	ON 1989	ON 1990
9-08	REVISED	CNO	NELLY	JOB	HISSENEY
		QTY	QUANTITY		SHEET NO.
263					

### Wedge Anchor Steel System

**Wedge Anchor Steel System**

Class A Concrete

Non-reinforced Concrete Footing (shall be used unless noted elsewhere in the plans). Foundation should have approx. 2.0 c of concrete.

SMB RD SON ASSM TY TWT (EXCISE)

### Universal Anchor System with Thin-Walled Tubing Post

**Universal Anchor System with Thin-Walled Tubing Post**

Class A Concrete

Non-reinforced Concrete Footing (shall be used unless noted elsewhere in the plans). Foundation should have approx. 2.0 c of concrete.

SMB RD SON ASSM TY TWT (EXCISE)

### Wedge Anchor High Density Polyethylene (HDPE) System

**Wedge Anchor High Density Polyethylene (HDPE) System**

Class A Concrete

Non-reinforced Concrete Footing (shall be used unless noted elsewhere in the plans). Foundation should have approx. 2.0 c of concrete.

SMB RD SON ASSM TY TWT (EXCISE)

### Sign Installation Using a Prefabricated T-Bracket for Thin-Wall Tubing Post

**Sign Installation Using a Prefabricated T-Bracket for Thin-Wall Tubing Post**

Class A Concrete

Non-reinforced Concrete Footing (shall be used unless noted elsewhere in the plans). Foundation should have approx. 2.0 c of concrete.

SMB RD SON ASSM TY TWT (EXCISE)

### GENERAL NOTES

1. The Wedge Anchor System and the Universal Anchor System with thin wall tubing post may be used to support up to 10 square feet of sign area.
2. The tubular socket, wedge and prefabricated T-bracket shall be permanently marked to indicate manufacturer, method, design, and location of marking are subject to the approval of the TMDOT Traffic Signs Engineer.
3. Except for posts (13 B&E tubing), clamps, nuts and bolts, all components shall be requalified. A list of approved vendors may be obtained from the material Provider's list web page. The website address is <http://www.texas.gov/roadsigns/traffic.htm>
4. Material used as post with this system shall conform to the following specifications:
  - 13 B&E (13.86) 0.375\"/>
5. Sign supports shall be the sizes and shown shown on the plans.
6. Additional sign clips required on the T-bracket post for 24\"/>

**WEDGE ANCHOR SYSTEM INSTALLATION PROCEDURE**

1. Dig foundation hole. Where solid rock is encountered at ground level, the foundation shall be a minimum depth of 18\"/>


**UNIVERSAL ANCHOR SYSTEM INSTALLATION PROCEDURE**

1. Dig foundation hole. Where solid rock is encountered at ground level, the foundation shall be a minimum depth of 18\"/>

NOTE

The devices shall be installed per manufacturer's recommendations. Installation procedures shall be provided to the Engineer by Manufacturer.

**Preliminary**  
11/30/2023 8:40:22 AM




4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P(210) 681.2951 F: (210) 523.7112

# GRACE VALLEY RANCH PHASE 3 STREET EXTENSION

TXDOT SIGN MOUNTING DETAILS

## TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



### NOTE

There are various devices approved for the Triangular Slipbase System. Please reference the Material Producer List for approved slip base systems. The devices shall be installed per manufacturer's recommendations. Installation procedures shall be provided to the Engineer by Contractor.

### GENERAL NOTES


- Slip base shall be permanently marked to indicate manufacturer, method, design, and location of marking are subject to approval of the TXDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:
  - 10 BNC tubing 12-875" outside diameter
  - 0.124" nominal wall thickness
  - Seamless or electric-resistance welded steel tubing or pipe
  - Steel shall be HSLA 80 or 55 per ASTM A101 or ASTM A106
  - Other steels may be used if they meet the following:
    - 50,000 PSI minimum yield strength
    - 50,000 PSI minimum tensile strength
    - 0.012" minimum elongation in 2"
  - Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"
  - Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"
  - Galvanization per ASTM A123 or ASTM A653 240. For pre-painted steel tubing (ASTM A653), recast use outside diameter weld seam by metallizing with zinc wire per ASTM B833.
- Schedule 80 Pipe 12-875" outside diameter
  - 0.124" nominal wall thickness
  - Seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the following:
    - 50,000 PSI minimum yield strength
    - 50,000 PSI minimum tensile strength
    - 0.012" minimum elongation in 2"
  - Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"
  - Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"
  - Galvanization per ASTM A123
- See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is <http://www.txdot.gov/traffic/traffic.htm>
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

### ASSEMBLY PROCEDURE

- Foundation
  - 1. Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
  - 2. The Engineer may permit placement of concrete less than 2 cubic yards to be placed in portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be placed in a suitable container may be allowed by Engineer. Concrete shall be placed in a suitable container may be allowed by Engineer.
  - 3. Pump the pipe and the slip base stub into the center of the concrete. Rotate the stub and turn while pulling it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
  - 4. From the stub, allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
  - 5. The triangular slipbase system is multi-directional and is designed to release when struck from any direction.

- Support
  - 1. Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip base is below the edge of pavement or 7 to 7.5 feet above side plane when the side plane is above the edge of the travelway. The cut shall be plane and straight.
  - 2. Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLP-2)-08 for clearances based on sign types.


## CONCRETE ANCHOR



## TEXAS DEPARTMENT OF TRANSPORTATION Traffic Operations Division SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM SMD (SLP-11)-08

REVISED	DATE	BY	CHKD	APP'D	REASON
1	07/02/2007	JULY 2007			
2	09/08/2007	REVISION			
3	09/08/2007	REVISION			
4	09/08/2007	REVISION			
5	09/08/2007	REVISION			
6	09/08/2007	REVISION			
7	09/08/2007	REVISION			
8	09/08/2007	REVISION			
9	09/08/2007	REVISION			
10	09/08/2007	REVISION			
11	09/08/2007	REVISION			
12	09/08/2007	REVISION			
13	09/08/2007	REVISION			
14	09/08/2007	REVISION			
15	09/08/2007	REVISION			
16	09/08/2007	REVISION			
17	09/08/2007	REVISION			
18	09/08/2007	REVISION			
19	09/08/2007	REVISION			
20	09/08/2007	REVISION			
21	09/08/2007	REVISION			
22	09/08/2007	REVISION			
23	09/08/2007	REVISION			
24	09/08/2007	REVISION			
25	09/08/2007	REVISION			
26	09/08/2007	REVISION			
27	09/08/2007	REVISION			
28	09/08/2007	REVISION			
29	09/08/2007	REVISION			
30	09/08/2007	REVISION			
31	09/08/2007	REVISION			
32	09/08/2007	REVISION			
33	09/08/2007	REVISION			
34	09/08/2007	REVISION			
35	09/08/2007	REVISION			
36	09/08/2007	REVISION			
37	09/08/2007	REVISION			
38	09/08/2007	REVISION			
39	09/08/2007	REVISION			
40	09/08/2007	REVISION			
41	09/08/2007	REVISION			
42	09/08/2007	REVISION			
43	09/08/2007	REVISION			
44	09/08/2007	REVISION			
45	09/08/2007	REVISION			
46	09/08/2007	REVISION			
47	09/08/2007	REVISION			
48	09/08/2007	REVISION			
49	09/08/2007	REVISION			
50	09/08/2007	REVISION			
51	09/08/2007	REVISION			
52	09/08/2007	REVISION			
53	09/08/2007	REVISION			
54	09/08/2007	REVISION			
55	09/08/2007	REVISION			
56	09/08/2007	REVISION			
57	09/08/2007	REVISION			
58	09/08/2007	REVISION			
59	09/08/2007	REVISION			
60	09/08/2007	REVISION			
61	09/08/2007	REVISION			
62	09/08/2007	REVISION			
63	09/08/2007	REVISION			
64	09/08/2007	REVISION			
65	09/08/2007	REVISION			
66	09/08/2007	REVISION			
67	09/08/2007	REVISION			
68	09/08/2007	REVISION			
69	09/08/2007	REVISION			
70	09/08/2007	REVISION			
71	09/08/2007	REVISION			
72	09/08/2007	REVISION			
73	09/08/2007	REVISION			
74	09/08/2007	REVISION			
75	09/08/2007	REVISION			
76	09/08/2007	REVISION			
77	09/08/2007	REVISION			
78	09/08/2007	REVISION			
79	09/08/2007	REVISION			
80	09/08/2007	REVISION			
81	09/08/2007	REVISION			
82	09/08/2007	REVISION			
83	09/08/2007	REVISION			
84	09/08/2007	REVISION			
85	09/08/2007	REVISION			
86	09/08/2007	REVISION			
87	09/08/2007	REVISION			
88	09/08/2007	REVISION			
89	09/08/2007	REVISION			
90	09/08/2007	REVISION			
91	09/08/2007	REVISION			
92	09/08/2007	REVISION			
93	09/08/2007	REVISION			
94	09/08/2007	REVISION			
95	09/08/2007	REVISION			
96	09/08/2007	REVISION			
97	09/08/2007	REVISION			
98	09/08/2007	REVISION			
99	09/08/2007	REVISION			
100	09/08/2007	REVISION			

**Preliminary**  
11/30/2023 8:40:22 AM



### NOTE

There are various devices approved for the Triangular Slipbase System. Please reference the Material Producer List for approved slip base systems. The devices shall be installed per manufacturer's recommendations. Installation procedures shall be provided to the Engineer by Contractor.

### GENERAL NOTES


- Slip base shall be permanently marked to indicate manufacturer, method, design, and location of marking are subject to approval of the TXDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:
  - 10 BNC tubing 12-875" outside diameter
  - 0.124" nominal wall thickness
  - Seamless or electric-resistance welded steel tubing or pipe
  - Steel shall be HSLA 80 or 55 per ASTM A101 or ASTM A106
  - Other steels may be used if they meet the following:
    - 50,000 PSI minimum yield strength
    - 50,000 PSI minimum tensile strength
    - 0.012" minimum elongation in 2"
  - Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"
  - Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"
  - Galvanization per ASTM A123 or ASTM A653 240. For pre-painted steel tubing (ASTM A653), recast use outside diameter weld seam by metallizing with zinc wire per ASTM B833.
- Schedule 80 Pipe 12-875" outside diameter
  - 0.124" nominal wall thickness
  - Seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the following:
    - 50,000 PSI minimum yield strength
    - 50,000 PSI minimum tensile strength
    - 0.012" minimum elongation in 2"
  - Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"
  - Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"
  - Galvanization per ASTM A123
- See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is <http://www.txdot.gov/traffic/traffic.htm>
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

### ASSEMBLY PROCEDURE

- Foundation
  - 1. Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
  - 2. The Engineer may permit placement of concrete less than 2 cubic yards to be placed in portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be placed in a suitable container may be allowed by Engineer. Concrete shall be placed in a suitable container may be allowed by Engineer.
  - 3. Pump the pipe and the slip base stub into the center of the concrete. Rotate the stub and turn while pulling it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
  - 4. From the stub, allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
  - 5. The triangular slipbase system is multi-directional and is designed to release when struck from any direction.


- Support
  - 1. Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip base is below the edge of pavement or 7 to 7.5 feet above side plane when the side plane is above the edge of the travelway. The cut shall be plane and straight.
  - 2. Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLP-2)-08 for clearances based on sign types.

## CONCRETE ANCHOR



## TEXAS DEPARTMENT OF TRANSPORTATION Traffic Operations Division SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM SMD (SLP-31)-08

SIGN MOUNTING DETAILS					
SMALL ROADSIDE SIGNS					
TRIANGULAR SLIPBASE SYSTEM					
SMD (SLIP-3) -08					
② 1x001 July 2002		Dm 1x001		Ch 1x001	Sh 1x001
REVISIONS		CMT		SECT	JOB
9-08					HIGHWAY
		DIST		COUNTY	SHEET NO.



Site Plan

Legend:

- A = Acres
- C = Census

Scale: 1" = 100'

North Arrow

Streets:

- Homestead Parkway
- Paige Place
- Gadwall Avenue
- Thea Meadows
- Drake Drive
- Wyatt Way
- Canvasback Court
- Petey Place
- Kayden Court

Lot Details:

- A3 = 10.15 Ac. C = 0.74 CN = 92
- A6 = 11.60 Ac. C = 0.74 CN = 92
- A11 = 7.92 Ac. C = 0.74 CN = 92
- A2 = 8.62 Ac. C = 0.74 CN = 92
- A12 = 4.27 Ac. C = 0.74 CN = 92
- A9 = 2.86 Ac. C = 0.74 CN = 92
- A10 = 4.63 Ac. C = 0.74 CN = 92
- A1 = 4.38 Ac. C = 0.74 CN = 92
- A7 = 2.14 Ac. C = 0.74 CN = 90.65
- A13 = 5.07 Ac. C = 0.74 CN = 89.63


Other Features:

- Thea Meadows
- Drake Drive
- Kayden Court
- Canvasback Court
- Petey Place
- Wyatt Way
- Gadwall Avenue
- Paige Place
- Homestead Parkway


# D1

REPRODUCTION OF THE ORIGINAL SIGNED AND SEALED PLAN AND/OR ELECTRONIC MEDIA MAY HAVE BEEN INADVERTENTLY ALTERED. CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE SCALE OF THE DOCUMENT AND CONTACTING CUDE ENGINEERS TO VERIFY DISCREPANCIES PRIOR TO CONSTRUCTION.





STA. 9+78.50 TO STA. 15+13.95




DATE 11/29/2023
PROJECT NO. 03346.014
DRAWN BY MAS
CHECKED BY KMH
REVISIONS


- 1.
- 2.
- 3.
- 4.
- 5.
- 6.
- 7.
- 8.
- 9.

CUDE ENGINEERS  
TBPE No. 455  
TBPLS No. 10048500

## D3



## STA. 10+03.00 TO STA. 11+64.09



DATE  
11/29/2023

PROJECT NO.  
03346.014

DRAWN BY  
MAS


CHECKED BY  
KMH

**REVISIONS**

- 1.
- 2.
- 3.
- 4.
- 5.
- 6.
- 7.
- 8.
- 9.

CUDE ENGINEERS  
TBPE No. 455  
TBPLS No. 10048500

# D4



4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P: (210) 681.2951 F: (210) 523.7112

GRACE VALLEY RANCH PHASE 3


STREET EXTENSION

DRAINAGE PLAN & PROFILE - DRAIN 3I

DATE	11/29/2023
PROJECT NO.	03346.014
DRAWN BY	MAS
CHECKED BY	KMH
REVISIONS	
1.	
2.	
3.	
4.	
5.	
6.	
7.	
8.	
9.	

CUDE ENGINEERS  
TBPE No. 455  
TBPLS No. 10048500

D5





DETAIL 'A'

SCALE: 1"= 5'

NOTES:

1. ALL CONCRETE LINING SHALL DEVELOP A MINIMUM COMPRESSIVE STRENGTH OF NOT LESS THAN 3000 PSI IN 28 DAYS.
2. 85% OF CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATION PRIOR TO ACCEPTANCE OF THE CHANNEL BY THE CITY OF CIBOLO & GUADALUPE COUNTY. HYDROMULCH PAY ITEM TO INCLUDE SOIL SEEDING, OR SODDING & WATERING FOR THE TIME PERIOD NEEDED TO ACHIEVE 85% VEGETATION.
3. REFERENCE TYPICAL CONCRETE CHANNEL RIP-RAP STANDARDS FOUND ON SHEET D7.




DRAIN "3I" SECTION  
(N.T.S.)

LEGEND:

- = EARTHEN
- = CONCRETE
- = EXISTING CONTOURS
- = PROPOSED CONTOURS
- = TOP OF WALL ELEVATION
- = BOTTOM OF WALL ELEVATION


DRAIN '3I' HYDRAULIC SUMMARY	
SECTION	"3I-1"
STATION	10+14.09- 10+46.90
Q <sub>25</sub> (cfs)	36.60
n	0.015
S (%)	1.50
D (ft)	2.00
d <sub>b</sub> (ft)	1.00
V (fps)	9.15
Bw (ft)	4






DRAIN '3I'

STA. 10+03.00 TO STA. 10+54.95

HORIZONTAL SCALE: 1" = 20'  
VERTICAL SCALE: 1" = 5'






1. ALL CONCRETE LINING SHALL DEVELOP A MINIMUM COMPRESSIVE STRENGTH OF NOT LESS THAN 3000 PSI IN 28 DAYS.
2. 85% OF CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATION PRIOR TO ACCEPTANCE OF THE CHANNEL BY THE CITY OF CIBOLO & GUADALUPE COUNTY. HYDROMULCH PAY ITEM TO INCLUDE SOIL, SEEDING, OR SODDING & WATERING FOR THE TIME PERIOD NEEDED TO ACHIEVE 85% VEGETATION.
3. REFERENCE TYPICAL CONCRETE CHANNEL RIP-RAP STANDARDS FOUND

# Preliminary


11/30/2023 8:40:23 AM

## DRAIN '3J'

STA. 10+00.00 TO STA. 14+84.22



REPRODUCTION OF THE ORIGINAL SIGNED AND SEALED PLAN AND/OR ELECTRONIC MEDIA MAY HAVE BEEN INADVERTENTLY ALTERED. CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE SCALE OF THE DOCUMENT AND CONTACTING CUDE ENGINEERS TO VERIFY DISCREPANCIES PRIOR TO CONSTRUCTION



4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P:(210) 681.2951 F: (210) 523.7112

# GRACE VALLEY RANCH PHASE 3

# STREET EXTENSION

DRAINAGE PLAN &amp; PROFILE - DRAIN 3J

DATE \_\_\_\_\_

11/29/2023

PROJECT NO.  
03346.014

DRAWN

MAS

CHECKED BY  
KMH

## REVISIONS




1. ....
2. ....
3. ....
4. ....
5. ....
6. ....
7. ....
8. ....
9. ....

CUDE ENGINEERS



TBPE No. 455  
TBPLS No. 10048500


# D6

11/30/2023 8:40:23 AM









4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P(210) 681.2951 F: (210) 523.7112

GRACE VALLEY RANCH PHASE 3  
STREET EXTENSION  
SANITARY SEWER GENERAL NOTES AND DETAILS

**Preliminary**  
11/30/2023 8:40:24 AM

DATE  
11/29/2023  
PROJECT NO.  
03346.014

DRAWN BY  
MAS  
CHECKED BY  
KMH

REVISIONS

- 1.
- 2.
- 3.
- 4.
- 5.
- 6.
- 7.
- 8.
- 9.

CUDE ENGINEERS  
TBPE No. 455  
TBPLNo. 10048500

SS1

GREEN VALLEY SPECIAL UTILITY DISTRICT SANITARY SEWER SYSTEM GENERAL NOTES.

THE STANDARD SPECIFICATIONS AND DRAWINGS (SD) ARE PROVIDED AS A TECHNICAL RESOURCE FOR ENGINEERING PROFESSIONALS FOR USE IN DESIGN AND CONSTRUCTION OF SEWER COLLECTION SYSTEMS PROJECTS MANAGED AND CONTRACTED BY THE GREEN VALLEY SPECIAL UTILITY DISTRICT (GVSD).

GENERAL: THE OWNER, DEVELOPER, ENGINEERING FIRM SHALL SUBMIT TO THE GREEN VALLEY SPECIAL UTILITY DISTRICT (GVSD) ENGINEER, FOR APPROVAL, TWO (2) COPIES OF ALL PLANS, E-PLANS AND PROFILES, PLUMBING LOGS, WHICH HAVE BEEN DESIGNED AND THE DRAWINGS SEALED BY A REGISTERED PROFESSIONAL ENGINEER, WHEN APPROVED, ONE (1) COPY WILL BE RETURNED TO THE OWNER, DEVELOPER, ENGINEERING FIRM, SO MARKED. THE OWNER WILL BE REQUIRED TO MAKE ALL CHANGES INDICATED BY THE GVSD ENGINEER, AND RETURN WITH ALL CHANGES, CORRECTIONS, BACK TO GVSD FOR APPROVAL.

1. ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL BE APPROVED BY THE GVSD AND COMPLY WITH:  
A. CURRENT GVSD TECHNICAL SPECIFICATIONS FOR UTILITIES CONSTRUCTION.  
B. TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ), FORMERLY TEXAS NATURAL RESOURCE CONSERVATION COMMISSION (NRC), DESIGN CRITERIA FOR SEWAGE SYSTEMS 31 TAC 317.1, 31 TAC 317.2 AND 31 TAC 317.3, 30 TAC 30 TAC 317.3 AND 30 TAC 317.4 AND 30 TAC 317.5.
2. THE CONTRACTOR IS TO NOTIFY AND MAKE ARRANGEMENTS WITH THE GVSD INSPECTIONS DIVISION AT (830)942.3200 OR (210)747.2229 48 HOURS PRIOR TO ANY EXCAVATION A PRE-CONSTRUCTION CONFERENCE SHALL BE HELD BEFORE ANY EXCAVATION OR WORK BEGINS.
3. WORK SHALL NOT BE PERFORMED ON SATURDAYS, SUNDAYS OR HOLIDAYS BEFORE 7:30 AM. OR AFTER 4:30 P.M. UNLESS PRIOR APPROVAL IS GRANTED BY THE GVSD ENGINEER.

EXISTING MANHOLES/SEWER

4. CONTRACTOR WILL MAINTAIN SERVICE TO ALL EXISTING SANITARY SEWERS AT ALL TIMES DURING CONSTRUCTION. CONTRACTOR WILL MARK, CLEAN, LAID, ETC. OUT OF MANHOLES AND ANY STOPPAGES CAUSED BY DEBRIS DURING CONSTRUCTION. CONTRACTOR WILL UNPLUG STOPPAGES AT CONTRACTORS EXPENSE. ANY DAMAGE TO EXISTING MANHOLES OR SEWER MAIN WILL BE CORRECTED AT THE CONTRACTORS EXPENSE. CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO PREVENT DAMAGE TO EXISTING MANHOLES, COVERS, OR CONES FROM EQUIPMENT AND MATERIALS USED OR TAKEN THROUGH THE WORK AREA. IF AN EXISTING OR NEW MANHOLE COVER, RING, OR CONE IS DAMAGED BY THE CONTRACTOR IT SHALL BE REPLACED AS DIRECTED BY THE GVSD INSPECTOR. MANHOLES WILL NEED TO BE REPAIRED AFTER SEALING. IF SEAL COATING IS BROKEN, CONTRACTOR WILL HAVE MANHOLE RECOATED. RESEAL ALL LEAKS AT CONTRACTORS EXPENSE.  
A. CONTRACTOR TO ENSURE ALL PLUGS USED TO PLUG SEWER LINES, WHILE TESTING THE PROJECT (SUCH AS AIR PLUGS, SOLIDITY TEST PLUGS, ETC) ARE LABELED, MARKED OR TAGGED. PROJECT INSPECTOR WILL RECORD HOW MANY PLUGS ARE BENE USED, LOCATION AND I.D. WITHIN COLLECTION SYSTEM. CONTRACTOR WILL REPORT TO PROJECT INSPECTOR OF ANY LOST OR UNRESTRAINED PLUGS INTO SEWER COLLECTION SYSTEM.  
B. CONTRACTOR WILL BE HELD LIABLE FOR ANY DAMAGES TO SEWER COLLECTION SYSTEM STOPPAGES, OVER FLOWS, BACKUP INTO HOMES CAUSED BY LOST RUN-AWAY SEWER PLUGS THAT WERE USED ON THAT PROJECT OR OUTFALL LINE WASTEWATER TREATMENT PLANTS.  
C. CONTRACTOR WILL ALSO BE RESPONSIBLE FOR ANY DAMAGE TO WASTEWATER TREATMENT APPARATUS, SUCH AS SCUMED PUMPS, ETC. CAUSED BY LOST OF RUN-AWAY SEWER PLUGS. CONTRACTOR WILL BE HELD LIABLE FOR DAMAGES, AS WELL AS COST OF REPAIRS.
5. ALL WORK IN THE TEXAS HIGHWAY DEPARTMENT, BEAR COUNTY, GUADALUPE COUNTY, AND CITY OF GILBOA RIGHT OF WAY SHALL BE DONE IN ACCORDANCE WITH RESPECTIVE CONSTRUCTION SPECIFICATIONS AND PERMITS.
6. ALL WORK IN PUBLIC STREETS SHALL BE COORDINATED WITH AND APPROVED BY THE BEAR COUNTY OR GUADALUPE COUNTY PUBLIC WORKS DEPARTMENT TRAFFIC DIVISION AND STREET ENGINEER.
7. DUE TO FEDERAL REGULATIONS TITLE 48, PART 192.101, CITY PUBLIC SERVICE MUST MAINTAIN ACCESS TO GAS VALVES AT ALL TIMES. THE CONTRACTOR MUST PROTECT AND WORK AROUND VALVES THAT ARE IN THE PROTECTED AREAS.
8. NO TESTING WILL BE PERFORMED PRIOR TO 30 DAYS FROM THE COMPLETE INSTALLATION OF THE SANITARY SEWER LINES.  
THE FOLLOWING SEQUENCE WILL BE STRICTLY ADHERED TO:  
A. PULL MANHOLE - AFTER 30 DAYS OF INSTALLATION  
B. PERFORM AIR TEST  
C. PULL WIPER AFTER STREET HAS BEEN ASPHALTED IN NEW SUBDIVISIONS  
D. VACUUM TEST ALL MANHOLES WITHIN THE PROJECT  
E. CCTV ALL NEW LINE-PAN (TTL) ALL SERVICE LATERALS TO 10' MAX CLEAN OUT, FLOOD ALL LINES BEFORE CITY, SUBMIT DVD.
9. CONTRACTOR SHALL SUBMIT FIELD COPY PLANS AND PROFILES SHOWING AS-BUILT WORK AT END OF PROJECT. CITY DVD AND COMPACTION DENSITY REPORTS FOR MAIN SEWER LINE AND ALL SERVICE LATERALS TRENCHES, WARRANTY LETTERS ON MATERIALS, WORKMANSHIP FOR 6 MONTHS AFTER FINAL ACCEPTANCE.
10. ALL MANHOLES SHALL BE CONSTRUCTED SO THAT THE TOP OF THE RING IS AT LEAST TWELVE (12) INCHES ABOVE THE FINISHED GRADE OF THE SURROUNDING GROUND EXCEPT WHEN LOCATED IN PAVED AREAS. IN PAVED AREAS THE MANHOLE RING SHALL BE FLUSH WITH THE PAVEMENT. ALL NEW INSTALLED MANHOLES WILL BE WITH A 30" INCH OPENING, MINIMUM. WITH THE GVSD LOGO ON THE COVER. EVERY TRENCH MANHOLE COVER WILL HAVE A "HOLE FOR A VENT".
11. ALL MANHOLES SHALL BE WITH A 30" INCH OPENING, MINIMUM. WATER TIGHT RING AND COVERS, WITH THE GVSD LOGO, ON PRIVATE PROPERTY. MANHOLE RING AND COVER SHALL BE TYPICAL MANHOLE COVER WATER TIGHT.  
A. BEFORE BACK FILLING/COMPACTION/CONCRETE ENCASEMENT  
ALL MANHOLE JOINT SECTION/CONCRETE, CONCRETE SECTIONS AND GRADE RING SHALL BE WRAPPED WITH GATOR WRAP SEALING SYSTEM, BUT, ADHESIVE SEALANT WITH A MINIMUM THICKNESS OF 30 MILS. INFILTRATED WRAPPED WITH RISER WRAP SEALING SYSTEM. GATOR WRAP MATERIAL, RUBBER MEETS ASTM C522/MASTIC MEETS ASTM C 690 OR APPROVE BY THE GVSD ENGINEER SUBSTITUTION ON OUTSIDE FOR IL GROUND WATER TABLE.

12. IF CONCRETE THROAT RINGS ARE TO BE INSTALLED, A MINIMUM OF TWO AND A MAXIMUM OF FOUR THROAT RINGS WILL BE USED AT EACH MANHOLE FOR ADJUSTMENT.
  13. INFILTRATION DISHES WILL BE REQUIRED IN MANHOLES WHERE APPLICABLE (I.E. SUCH AS LOW DRAINAGE AREAS) AND EVERY THIRD MANHOLE SHALL BE VENTED. 30" INCH MANHOLE COVER WITH 1" INCH HOLE CENTER OF COVER WHERE APPLICABLE.
- Note: Manhole cover inserts shall be FRV Industries, Inc., "Inflow Protector-Cover" "Preco Industries Ltd., "Sewer Guard", or approved equal, and shall be installed in strict accordance with the manufacturer's recommendations. The Contractor shall be responsible for making the necessary field measurements for the manufacturer prior to construction.
- A. ALL MANHOLES MUST HAVE 360-480 FEET SPACING BETWEEN MANHOLES TO PROVIDE ACCESS TO SEWER LINES FOR CLEANING. ON THE GVSD PUBLIC SEWER EASEMENT A 16 FOOT GATE WITH LOCK WILL BE PROVIDED BY THE CONTRACTOR FOR ACCESS TO CLEANING AND MAINTAINING SEWER LINES.
  - B. DROP MANHOLES SHALL BE REQUIRED WHEN THE INFLOW ELEVATION IS MORE THAN TWENTY-FOUR (24) INCHES ABOVE THE OUTFLOW ELEVATION. DROP SHALL BE LOCATED OUTSIDE THE MANHOLE WITH ITS FLOW LINE ELEVATION LOCATED BETWEEN THE CENTER LINE AND TOP OF SEWER LINE.
  14. ALL MANHOLES WILL BE CONCRETE ENCASEMENT 1' FOOT AROUND RING, 28-INCH DEEP AFTER GATOR WRAP SEALING SYSTEM HAS BEEN APPLIED.
  15. NEW MANHOLE PROTECTIVE COATING, LINER IS FOR THE PURPOSE OF INFILTRATION BECAUSE OF HIGH WATER TABLE LOCATION PROVIDED IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATION AND PER THE FOLLOWING SPECIFICATIONS:  
A. MANHOLE PROTECTIVE COATING/CONCRETE LINER WILL BE RESPONSIBLE FOR MANHOLES ON PROJECT SAFETY ASSESSMENT. MINIMUM SPACE ENTRY SIZE 18" OCCUPATIONAL SAFETY AND HEALTH STANDARDS, 28 CFR 1910.146 APP E  
B. THE CONTRACTOR SHALL NOTIFY THE GVSD UTILITY INSPECTIONS DEPARTMENT WITH A MINIMUM OF 2 DAYS ADVANCE NOTICE OF THE START OF ANY FIELD SURFACE PREPARATION WORK OF COATING APPLICATION WORK OF MANHOLES.  
C. ALL NEW MANHOLES IN NEW DEVELOPMENTS SHALL BE 30" INCH OPENING, WATER TIGHT AND THE INTERIOR WALL COATED WITH A GVSD APPROVED SEWER STRUCTURE FOR ALL MANHOLES, SEWER/CACT 2000 HR REGULAR, WITH THE REQUIRED ONE-INCH THICK APPLICATION.

- APPROVED MATERIALS ARE AS FOLLOWS:  
CEMENTITIOUS COATING WITH REQUIRED HALF-INCH THICK APPLICATION
- SEWERCACT 2000 HR REGULAR
  - REFRATTA HAC 100
  - MAXIMUM CAL PLUS
- EPOXY COATING, WITH SPECIFIED THICKNESS APPLICATION
- AROMATIC POLYUREA SCP DRAPOLINER REQUIRED THICKNESS 125 MILS

- D. WARRANTY LETTER ON MANHOLE PROTECTIVE COATING FOR 10 YEARS AFTER FINAL ACCEPTANCE OF THE PROJECT DOCUMENTS.  
I. ANY CONNECTIONS TO EXISTING MANHOLES WILL REQUIRE A 3-INCH CRADLE TO SUPPORT INCOMING PIPE. A RUBBER GASKET WILL ALSO BE REQUIRED (CENTERED AT MANHOLE WALL) WITH GROUTING AT INTERIOR AND EXTERIOR PENETRATIONS. PENETRATION INTO MANHOLE WILL BE CORE DRILLED, ANY DAMAGE EXISTING THE MANHOLE WILL BE REPAIRED AT CONTRACTORS EXPENSE. IF THE MANHOLE IS BROKEN, THE MANHOLE WILL BE RECOATED WITH THE SAME MATERIALS. IF EXISTING SEWER MANHOLES SEAL, SUCH DAMAGE TO MANHOLE WILL BE REPAIRED WITH SAME MATERIALS AND ONE-INCH THICKNESS.
- II. ANY AND ALL EXISTING MANHOLES WITHIN CONSTRUCTION PROJECT THAT TIE IN ARE DONE BY CONTRACTOR TO STRENGTH ADJUSTMENT, RECONSTRUCTION, OR LEAKING MANHOLE WILL BE COAT SEALED AT CONTRACTORS EXPENSE.
17. IN MANHOLES OR PIPES WHERE MORE THAN ONE MANHOLE OR PIPE IS TO BE CONNECTED, THE MANHOLE SHALL BE RECOATED WITH THE SAME MATERIALS. IF EXISTING SEWER MANHOLES SEAL, SUCH DAMAGE TO MANHOLE WILL BE REPAIRED WITH SAME MATERIALS AND ONE-INCH THICKNESS.
18. ALL PVC SEWER PIPES SHALL HAVE COMPRESSION OR MECHANICAL JOINTS.
19. SEWER PIPE CONNECTIONS TO PRECAST MANHOLES SHALL BE APPROVED BY THE GVSD. THIS CONNECTION SHALL USE FLEXIBLE "BOOT" TYPE CONNECTOR SUCH AS THE PER PORTABLE SEAL SYSTEM BY ENGINEER APPROVED EQUAL, AND COMPLY WITH ASTM D203, SEWER PIPE CONNECTIONS TO MONOLITHIC MANHOLES WILL BE AS SHOWN ON THE STANDARD DETAIL SHEET. ANY CHANGES IN THESE METHODS MUST BE APPROVED BY THE GVSD ENGINEER.
21. ALL PIPE TRENCHING, BEDDING AND BACKFILL SHALL BE DONE IN ACCORDANCE WITH APPROPRIATE ASTM STANDARDS SPECIFICATIONS (REFERENCE C 312, C 317, 24X6X10, ASTM D 12 (ANSI A10.2) OR ASTM D 2321 (ANSI MS 1710), ALL COMPACTION & 90% DENSITY TESTS ACROSS THE BOARD, 1 RANDOM DENSITY TEST PER LOT FOR EVERY 400 FEET.  
A. SAND MIGRATION: BEFORE PREVENTION COLLAR WHEN CHANGING THE INITIAL BACKFILL FROM SELECT INITIAL BACKFILL TO OPTIONAL SELECT INITIAL BACKFILL, A TWO (2) FOOT LONG CLASS D CONCRETE ENCASEMENT, EVERY 180' FEET ALONG PIPE AND 20 FEET FROM WALL OF MANHOLE IN EACH DIRECTION, NO EXTRA PAY ITEM.

- AA. BEDDING SHALL CONSIST OF 1'X20'X2 GRADE 4 (1 1/2"-1 5/8") COMMONLY KNOWN AS SEWER GRAVEL.
- B. SEWER LINE LOCATION
- I. SEWER LINES SHALL BE SIZED AND EXTENDED THROUGH THE LIMITS OF A DEVELOPMENT TO SERVE ADJACENT PROPERTY, WITH MANHOLE AND SUB-OUT AT END OF SEWER LINE.  
A. IN PHASED CONSTRUCTION OF THOROUGHFARES, THE SEWER LINE SHALL BE EXTENDED THE ENTIRE LENGTH OF THE THOROUGHFARE BEING CONSTRUCTED.
  - II. NO PUBLIC SEWER LINE SHALL BE LOCATED NEARER THAN FIVE (5) FEET FROM ANY TREE.
  - III. SIZES AND GRADES FOR SANITARY SEWER SHALL BE AS REQUIRED BY THE GVSD ENGINEER AND CONSIDERATION SHALL BE GIVEN TO POSSIBLE EXTENSIONS FOR FUTURE DEVELOPMENT. NO SANITARY SEWERS, OTHER THAN LATERALS AND MAINS, SHALL BE LESS THAN EIGHT (8) INCH IN DIAMETER.
22. WHEN SEWER LATERALS ARE TO BE CONNECTED TO EXISTING SEWER MAINS AND NO SUB-OUT HAS BEEN INSTALLED, THE CONNECTION MUST BE MADE WITH AN APPROVED SERVICE AND/E AS PER 31 TAC 313.5(C) (7), NEW INVERT TO BE BUILT, SMOOTH CHANNEL FOR NEW PIPES/PIPE AT 2% FLOW.
  23. ALL RESIDENTIAL SERVICE LATERALS SHALL BE SOR 26 WITH RATING OF 15 PSI, BE EXTENDED TO THE PROPERTY LINE AT 8' (3) CARPED AND SEALED, ATTACH TO SEWER BURIAL TAPE TO THE END OF ALL SEWER LATERALS AND BRING UP TO THE GROUND LEVEL FOR MARKER (GREEN). (SEE HOWE LATERALS DETAILS).
- A. SEWER SERVICE LATERALS, THE SIZES AND LOCATIONS OF LATERALS SHALL BE DESIGNATED AS FOLLOWS UNLESS OTHERWISE DIRECTED BY THE GVSD ENGINEER:
- I. IN GENERAL, FOR SINGLE FAMILY DWELLING, THE LATERAL SIZE SHALL BE FOUR (4) INCH MINIMUM. HOWE LATERALS SHALL BE IN STALL CENTER OF THE LOT AND SHALL HAVE A TEN (10) FOOT SEPARATION FROM THE WATER SERVICE. THE SERVICE SHALL THEN BE EXTENDED AT A FORTY-FIVE (45) DEGREE ANGLE TO FOUR (4) FEET ABOVE THE FINISHED GRADE AND CAPTED. USE SEWER BURIAL TAPE TO MARK ALL SEWER SERVICE LATERALS.
  - II. MULTIPLE LOTS, APARTMENTS, LOCAL RETAIL AND COMMERCIAL SIX (6) INCH MINIMUM, MANUFACTURING AND INDUSTRIAL, EIGHT (8) INCH MINIMUM, OR LARGER AS REQUIRED.
- TRAPS AND INTERCEPTORS (F00 - TEOQ)

UNIFORM PLUMBING CODE, CITY OF SAN ANTONIO BUILDING INSPECTIONS DEPARTMENT, ALL COMMERCIAL BUILDINGS WILL HAVE TRAPS (F00-TEQ).

OIL SEPARATORS

WHICH INCLUDE OIL SEPARATOR-GASOLINE SERVICE STATIONS, CAR WASHES, GARAGES, DRY CLEANERS, CHEMICAL PLANTS, GAS PLANTS, HIDE PROCESSORS, TESTING LABORATORIES, OR ANY PLACE WHERE OIL OR SOLVENTS MAY BE DISCHARGED INTO THE SANITARY SEWER SYSTEM. THE SIZING CRITERIA FOR OIL SEPARATORS SHALL BE BASED ON THE G.P.M. RATE OF ALL FUTURE, APPLIANCE OR APERTURE, DRAINING INTO SEWER.

SAND INTERCEPTORS

SAND INTERCEPTORS SHALL BE INSTALLED IN THE SEWER SYSTEM OF THE FOLLOWING ESTABLISHMENTS, GARAGES, CAR WASHES, SERVICE STATIONS, OR ANY PLACE OF BUSINESS WHERE HEAVY SOLIDS MAY BE INTRODUCED INTO THE SANITARY SEWER SYSTEM. THE SIZING CRITERIA FOR A SAND INTERCEPTOR SHALL BE BASED ON G.P.M. X 12 MINUTE RETENTION TIMES TO OBTAIN THE TANK SIZE IN GALLONS CAPACITY.

AUTOMATIC CAR WASHES

WITH HIGH PRESSURE SPRAYS AND/AND BRUSHES INSTALL A 50 G.P.M. INTERCEPTOR, MINIMUM. MIN 4" INCH DIAMETER. THE SIZE OF THE INTERCEPTOR SHALL BE BASED ON THE G.P.M. RATE OF EACH ADDITIONAL WASH BAY OVER A SINGLE BAY OR PORTABLE WASHER TYPE VEHICLE WASHES SHALL INSTALL A 20 G.P.M. INTERCEPTOR MINIMUM.


NEUTRALIZING DEVICES

IN NO CASE SHALL CORROSIVE LIQUIDS, SPENT ACIDS, OR OTHER HARMFUL CHEMICALS WHICH ARE DANGEROUS OR POISONOUS BE DISCHARGED INTO THE SANITARY SEWER SYSTEM. IF ANY NOXIOUS OR TOXIC FUMES, DISCHARGE INTO THE SANITARY SEWER SYSTEM WITH OUT BEING NOXIOUSLY NEUTRALIZED BY PASSING THROUGH A SAND INTERCEPTOR SHALL BE BASED ON THE NEUTRALIZING DEVICE, SUCH DEVICE SHALL BE PROVIDED WITH A SUFFICIENT INTAKE OF FUTURE MEDIUM CONSISTENT ON MARBLE CHIPS, 30 AS THE MARBLE'S CONTENTS NON-NUTRIOUS BEFORE BEING DISCHARGED INTO THE SANITARY SEWER SYSTEM.

LIMIT TRAPS

PUBLIC AND PRIVATE WASHBASINS AND COMMERCIAL LAUNDRIES SHALL INSTALL A LIMIT TRAP EQUIPPED WITH A CONVENIENTLY LOCATED AND EASILY REMOVABLE WIRE BASKET OR OTHER DEVICE. THE BASKET SHALL BE PROVIDED PLAINLY LABELED BY ENGINEER/PLUMBER. PLUMBER WILL WORK CLOSELY WITH THE GVSD INSPECTOR ON JAIL TESTING AND TELEVISION BY MAKING ARRANGEMENTS 48 HOURS IN ADVANCE. SEWER SERVICE LATERALS SHALL BE INSTALLED AT CONTRACTORS EXPENSE AND RE-INSPECTED.

41. A PROPERTY LINE CLEAN OUT (PFL) SHALL BE INSTALLED FOR RESIDENTIAL SERVICES. CLEAN OUTS IN THE SIDEWALK OR DRIVEWAY SHALL HAVE A CAST IRON BOOT, CLEAN OUT NOT LOCATED IN A SIDEWALK OR DRIVEWAY SHALL BE LOCATED ON REINFORCED CONCRETE PAD A MINIMUM OF TWELVE (12) INCHES BY TWELVE (12) INCHES BY SIX (6) INCHES THICK, ALL PROPERTY LINE CLEAN OUTS SHALL INCLUDE A LID WITH SEWER IN GREEN COLOR.
47. FENCING, ANY AND ALL FENCING INCLUDING ELECTRIC FENCE, WHETHER OR NOT IDENTIFIED ON THE PLANS, MUST BE MAINTAINED AT ALL TIMES. ANY AND ALL DAMAGES DIRECTLY ATTRIBUTED TO THE CONTRACTOR MUST BE REPLACED TO EQUAL OR BETTER CONDITIONS AT THE CONTRACTORS EXPENSE AND AS APPROVED BY THE PROJECT MANAGER. GAPS IN THE FENCING MUST BE PROVIDED AT LOCATIONS WHERE THE SEWER LINE EASEMENT CROSSES FENCING. FENCING REQUIRED TO PROTECT THE ACCESS TO EQUAL OR BETTER CONDITIONS AT THE CONTRACTORS EXPENSE AS APPROVED BY THE ENGINEER.
49. B. PROPERTY OWNER ACCESS: THE CONTRACTOR MUST MAINTAIN ACCESS FOR PRIVATE INDIVIDUALS AT ALL TIMES. IF NORMAL ACCESS IS DAMAGED DURING CONSTRUCTION THE CONTRACTOR MUST REPLACE THE ACCESS TO EQUAL OR BETTER CONDITIONS AT THE CONTRACTORS EXPENSE AS APPROVED BY THE ENGINEER.
50. A. CONTRACTOR IS RESPONSIBLE FOR LOCATION AND PROTECTION ALL UTILITIES WHETHER OR NOT SHOWN ON THE PLANS. SHOULD THE CONTRACTOR DAMAGE ANY UTILITIES THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL COSTS TO REPAIR THE UTILITIES TO THEIR ORIGINAL CONDITION. CONTRACTOR IS SOLELY RESPONSIBLE FOR LOST REVENUE, LOSSES, ETC. CLAIMED BY UTILITY COMPANIES DUE TO CONTRACTORS WORK. CONTRACTOR SHALL NOTIFY GVSD AND IMPACTED UTILITY COMPANIES 48 HRS. PRIOR TO BEGINNING WORK. CONTRACTOR SHALL VERIFY THE LOCATION OF UTILITIES AND REPORT ANY DISCREPANCIES TO THE ENGINEER.
51. CLEARING PERMANENT EASEMENTS, THE LIMITS OR BOTH THE EXISTING AND PARALLEL SEWER LINES PERMANENT EASEMENTS, AS DELINEATED IN THESE PLANS, MUST BE CLEARED IN ACCORDANCE WITH THE SPECIFICATION. THE CONTRACTOR MAY BE DIRECTED BY THE ENGINEER TO PROTECT AND AVOID CERTAIN TREES WITHIN THE LIMITS OF THE PERMANENT CONSTRUCTION EASEMENT. ALL BRUSH MUST BE REMOVED FROM SITE. NO BRUSH PILES TO REMAIN AFTER CONSTRUCTION. BURNING OF BRUSH OR TRASH WILL NOT BE ACCEPTABLE.
52. A. CONTRACTOR SHALL PROVIDE APPROPRIATE SAFE ACCESS AND BARRICADE WORK AT ALL TIMES TO PROTECT THE PUBLIC. THIS INCLUDES SUBSTANTIAL BARRICADES AROUND ALL TRENCHES, BORE PITS, OPEN EXCAVATIONS, EQUIPMENT, ETC. THE SITE MUST BE LEFT IN SECURE SAFE CONDITION AT NIGHT. IT IS THE CONTRACTORS RESPONSIBILITY TO TAKE NECESSARY PRECAUTIONS TO PROTECT THE PUBLIC THROUGHOUT THE DURATION OF THE PROJECT.
53. A. SHOULD CONTRACTOR SELECT A TRENCH EXCAVATION PROCEDURE THAT EXTENDS THE LIMITS OF SEEDING OR PAVING AND FINAL SITE PREPARATION (I.E. SLOPE BACK PROTECTION SYSTEM) HE WILL BE RESPONSIBLE FOR MEETING PLAN AND SPECIFICATION REQUIREMENTS TO THE NEW LIMITS AT NO ADDITIONAL COST TO GVSD.
54. B. WARNING: NOTE THAT CERTAIN PORTIONS OF THE PROJECT MAY PARALLEL AND/OR CROSS EXISTING UTILITIES. THE CONTRACTORS WILL BE REQUIRED TO PROTECT EXISTING UTILITIES. ADDITIONAL SUPPORTIVE SHORING MAY BE REQUIRED. IF IT IS SPREAD, THE CONTRACTOR'S RESPONSIBILITY TO PROTECT HIS WORKERS, EXISTING UTILITIES, AND FINISHED WORK THROUGHOUT THE JOB.
55. A. OVERHEAD ELECTRIC, CITY PUBLIC SERVICE (CPS) AN APPROPRIATE SAFE OVERHEAD CLEARANCE MUST BE MAINTAINED BETWEEN ALL EQUIPMENT AND PERSONNEL. THE CONTRACTOR SHALL NOTIFY CITY PUBLIC SERVICE AT 553-2700 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION IN THE VICINITY OF THE CPS OVERHEAD ELECTRIC LINE. CONTRACTOR SHALL MAINTAIN CPS RECOMMENDED CLEARANCE REQUIREMENTS.
56. B. BYPASS-PUMPING: THE CONTRACTOR IS RESPONSIBLE FOR ALL BYPASS PUMPING REQUIRED TO COMPLETE THE WORK. BYPASS PUMPS SHALL BE ADEQUATE TO HANDLE PEAK FLOW EVENTS DURING STORM EVENTS. CONTRACTOR SHALL HAVE STANDBY PUMPS AVAILABLE TO BYPASS FLOW IN CASE PRIMARY PUMP FAILS. CONTRACTOR WILL BE SOLELY RESPONSIBLE FOR ALL COSTS FOR CLEANUP OF AN UNAUTHORIZED DISCHARGE AND ANY ASSOCIATED FINES.
58. B. CONTRACTOR SHALL BACKFILL ALL OPEN TRENCHES AT THE END OF THE DAY. CONTRACTOR SHALL NOT INSTALL MORE PIPE THAN CAN BE COVERED. NO OPEN TRENCHES WILL BE PERMITTED OVERNIGHT AT THE END OF OPEN PIPE. ALL OPEN TRENCHES WILL BE PLUGGED OVERNIGHT.
59. B. THE PROJECT AREA MAY BE SUBJECT TO ARCHEOLOGICAL MONITORING, SHOULD THE CONTRACTOR DISCOVER ANY ARCHEOLOGICAL REMAINS DURING CONSTRUCTION. SHOULD THE CONTRACTOR SHALL STOP ALL WORK IN THE AREA OF THE DEPOSITS AND IMMEDIATELY CALL THE PROJECT MANAGER.
60. B. CONTRACTOR TO NOTE THAT PORTIONS OF THE CONSTRUCTION ARE WITHIN THE LIMITS OF THE 100 YEAR FLOODPLAIN. THE CONTRACTOR IS REQUIRED TO KEEP THE CHANNEL CLEAR OF POTENTIAL OBSTRUCTIONS TO FLOOD FLOWS. POTENTIAL OBSTRUCTIONS INCLUDE HIGH CONSTRUCTION EQUIPMENT, TEMPORARY ROADS, EXCAVATION CHANNELS, EXCAVATED MATERIAL, STOCKPILS OF DEBRIS, ETC. UNDETERMINED WEATHER CONDITIONS WHERE FLOODING IS LIKELY, OBSTRUCTIONS SHALL BE IMMEDIATELY REMOVED BY THE CONTRACTOR AT NO ADDITIONAL COST TO GVSD. THE CONTRACTOR ASSUMES ALL RISK FOR UNFINISHED WORK.



GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM STANDARD DETAILS (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: MAY 6, 2020	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. G-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1


GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	SANITARY SEWER SYSTEM GENERAL NOTES (I OF 2)
REVISED: JANUARY 28, 2021	REVISIONS TO THE STANDARD DETAILS OF THE SYSTEM
	DETAIL NO. S-1

GREEN VALLEY
--------------



4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P:(210) 681.2951 F: (210) 523.7112

GRACE VALLEY RANCH PHASE 3  
STREET EXTENSION

SANITARY SEWER DETAILS

**Preliminary**  
11/30/2023 8:40:24 AM

DATE  
11/29/2023

PROJECT NO.  
03346.014
















DRAWN BY  
MAS  
CHECKED BY  
KMH

REVISIONS

1.  
2.  
3.  
4.  
5.  
6.  
7.  
8.  
9.

CUDE ENGINEERS  
TBPE No. 455  
TBPLS No. 10048500

**SS2**




**TRENCH EXCAVATION PROTECTION**  
CONTRACTOR AND/OR CONTRACTORS' INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTORS' INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

**ENGINEER SANITARY SEWER GENERAL NOTES:**

- CONTRACTOR IS RESPONSIBLE FOR REPLACING ANY FENCING THAT IS REMOVED OR DAMAGED DURING CONSTRUCTION TO EXISTING OR BETTER CONDITION.
- CONTRACTOR IS TO NOTIFY ENGINEER OF ANY DISCREPANCIES OR UTILITY CONFLICTS.
- CONTRACTOR SHALL REFERENCE TREE PLAN AND PRIVATE GRADING PLAN FOR CLEARING AND GRADING LIMITS.
- CONTRACTOR SHALL REVEGETATE ALL DISTURBED AREAS WITHIN EASEMENT LIMITS UPON COMPLETION OF INFRASTRUCTURE

(e) LOCATION OF WATERLINES. THE FOLLOWING RULES APPLY TO INSTALLATIONS OF WATERLINES, WASTEWATER MAINS OR LATERALS, AND OTHER CONVEYANCES/APPURTENANCES IDENTIFIED AS POTENTIAL SOURCES OF CONTAMINATION. FURTHERMORE, ALL RATINGS SPECIFIED SHALL BE DEFINED BY ASTM OR AWWA STANDARDS UNLESS STATED OTHERWISE. NEW MAINS, SERVICE LINES, OR LATERALS ARE THOSE THAT ARE INSTALLED WHERE NO MAIN, SERVICE LINE, OR LATERAL PREVIOUSLY EXISTED, OR WHERE EXISTING MAINS, SERVICE LINES, OR LATERALS ARE REPLACED WITH PIPES OF DIFFERENT SIZE OR MATERIAL.

- WHEN NEW POTABLE WATER DISTRIBUTION LINES ARE CONSTRUCTED, THEY SHALL BE INSTALLED NO CLOSER THAN NINE FEET IN ALL DIRECTIONS TO WASTEWATER COLLECTION FACILITIES. ALL SEPARATION DISTANCES SHALL BE MEASURED FROM THE OUTSIDE SURFACE OF EACH OF THE RESPECTIVE PIECES.
- POTABLE WATER DISTRIBUTION LINES AND WASTEWATER MAINS OR LATERALS THAT FORM PARALLEL UTILITY LINES SHALL BE INSTALLED IN SEPARATE TRENCHES.
- NO PHYSICAL CONNECTION SHALL BE MADE BETWEEN A DRINKING WATER SUPPLY AND A SEWER LINE. ANY APPURTENANCE SHALL BE DESIGNED AND CONSTRUCTED SO AS TO PREVENT ANY POSSIBILITY OF SEWAGE ENTERING THE DRINKING WATER SYSTEM.
- WHERE THE NINE-FOOT SEPARATION DISTANCE CANNOT BE ACHIEVED, THE FOLLOWING CRITERIA SHALL APPLY.
  - NEW WATERLINE INSTALLATION - PARALLEL LINES.
    - WHERE A NEW POTABLE WATERLINE PARALLELS AN EXISTING, NON-PRESSURE OR PRESSURE RATED WASTEWATER MAIN OR LATERAL AND THE LICENSED PROFESSIONAL ENGINEER LICENSED IN THE STATE OF TEXAS IS ABLE TO DETERMINE THAT THE EXISTING WASTEWATER MAIN OR LATERAL IS NOT LEAKING, THE NEW POTABLE WATERLINE SHALL BE LOCATED AT LEAST TWO FEET ABOVE THE EXISTING WASTEWATER MAIN OR LATERAL, MEASURED VERTICALLY, AND AT LEAST FOUR FEET AWAY, MEASURED HORIZONTALLY, FROM THE EXISTING WASTEWATER MAIN OR LATERAL. EVERY EFFORT SHALL BE EXERTED NOT TO DISTURB THE BEDDING AND BACKFILL OF THE EXISTING WASTEWATER MAIN OR LATERAL.
    - WHERE A NEW POTABLE WATERLINE PARALLELS AN EXISTING PRESSURE-RATED WASTEWATER MAIN OR LATERAL AND IT CANNOT BE DETERMINED BY THE LICENSED PROFESSIONAL ENGINEER IF THE EXISTING LINE IS LEAKING, THE EXISTING WASTEWATER MAIN OR LATERAL SHALL BE REPLACED WITH AT LEAST 150 PSI PRESSURE-RATED PIPE. THE NEW POTABLE WATERLINE SHALL BE LOCATED AT LEAST TWO FEET ABOVE THE NEW WASTEWATER MAIN OR LATERAL, MEASURED VERTICALLY, AND AT LEAST FOUR FEET AWAY, MEASURED HORIZONTALLY, FROM THE REPLACED WASTEWATER MAIN OR LATERAL.
    - WHERE A NEW POTABLE WATERLINE PARALLELS A NEW WASTEWATER MAIN, THE WASTEWATER MAIN OR LATERAL SHALL BE CONSTRUCTED OF AT LEAST 150 PSI PRESSURE-RATED PIPE. THE NEW POTABLE WATERLINE SHALL BE LOCATED AT LEAST TWO FEET ABOVE THE WASTEWATER MAIN OR LATERAL, MEASURED VERTICALLY, AND AT LEAST FOUR FEET AWAY, MEASURED HORIZONTALLY, FROM THE WASTEWATER MAIN OR LATERAL.
    - NEW WATERLINE INSTALLATION - CROSSING LINES.
      - WHERE A NEW POTABLE WATERLINE CROSSES ABOVE A WASTEWATER MAIN OR LATERAL, THE SEGMENT OF THE WATERLINE PIPE SHALL BE CENTERED OVER AND MUST BE PERPENDICULAR TO THE WASTEWATER MAIN OR LATERAL SUCH THAT THE JOINTS OF THE WATERLINE PIPE ARE EQUIDISTANT AND AT LEAST NINE FEET HORIZONTALLY FROM THE CENTERLINE OF THE WASTEWATER MAIN OR LATERAL. WHEN CROSSING AN EXISTING WASTEWATER MAIN OR LATERAL AND IT IS DISTURBED OR SHOWS SIGNS OF LEAKING, THE WASTEWATER MAIN OR LATERAL SHALL BE REPLACED FOR AT LEAST NINE FEET IN BOTH DIRECTIONS (18 FEET TOTAL) WITH AT LEAST 150 PSI PRESSURE-RATED PIPE EMBEDDED IN CEMENT STABILIZED SAND (SEE CLAUSE (v) OF THIS SUBPARAGRAPH) FOR THE TOTAL LENGTH OF ONE PIPE SEGMENT PLUS 12 INCHES BEYOND THE JOINT ON EACH END.
      - THE POTABLE WATERLINE SHALL BE AT LEAST TWO FEET ABOVE AN EXISTING, NON-PRESSURE RATED WASTEWATER MAIN OR LATERAL.
      - THE POTABLE WATERLINE SHALL BE AT LEAST SIX INCHES ABOVE AN EXISTING, PRESSURE-RATED WASTEWATER MAIN OR LATERAL.
      - WHERE A NEW POTABLE WATERLINE CROSSES A NEW, NON-PRESSURE RATED WASTEWATER MAIN OR LATERAL, THE SEGMENT OF THE WATERLINE PIPE SHALL BE CENTERED OVER AND SHALL BE PERPENDICULAR TO THE WASTEWATER MAIN OR LATERAL SUCH THAT THE JOINTS OF THE WATERLINE PIPE ARE EQUIDISTANT AND AT LEAST NINE FEET HORIZONTALLY FROM THE CENTERLINE OF THE WASTEWATER MAIN OR LATERAL. THE POTABLE WATERLINE SHALL BE AT LEAST TWO FEET ABOVE THE WASTEWATER MAIN OR LATERAL, WHENEVER POSSIBLE, THE CROSSING SHALL BE CENTERED BETWEEN THE JOINTS OF THE WASTEWATER MAIN OR LATERAL. THE WASTEWATER PIPE SHALL HAVE A MINIMUM PIPE STIFFNESS OF 115 PSI AT 50% DEFLECTION. THE WASTEWATER MAIN OR LATERAL SHALL BE EMBEDDED IN CEMENT STABILIZED SAND (SEE CLAUSE (v) OF THIS SUBPARAGRAPH) FOR THE TOTAL LENGTH OF ONE PIPE SEGMENT PLUS 12 INCHES BEYOND THE JOINT ON EACH END. THE MATERIALS AND METHOD OF INSTALLATION SHALL CONFORM TO ONE OF THE FOLLOWING OPTIONS:
        - WITHIN NINE FEET HORIZONTALLY OF EITHER SIDE OF THE WATERLINE, THE WASTEWATER PIPE AND JOINTS SHALL BE CONSTRUCTED WITH PIPE MATERIAL HAVING A MINIMUM PRESSURE RATING OF AT LEAST 150 PSI. AN ABSOLUTE MINIMUM VERTICAL SEPARATION DISTANCE OF TWO FEET SHALL BE PROVIDED. THE WASTEWATER MAIN OR LATERAL SHALL BE LOCATED BELOW THE WATERLINE.




LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD.  
100 NE LOOP 410, SUITE 1155  
SAN ANTONIO, TX 78216  
TEL: (210) 403-6200  
CONTACT PERSON: RICHARD MOTT, P.E.  
**CIVIL ENGINEER:**  
CUDE ENGINEERS  
CONTACT PERSON: CHRIS CHAFFEE, P.E.  
4122 POND HILL ROAD, SUITE 101  
SAN ANTONIO, TX 78231  
TEL: (210) 681-2951  
FAX: (210) 523-7112

**CAUTION!!!**


THE CONTRACTOR SHALL BE AWARE THAT EXISTING UTILITIES ARE WITHIN THE BOUNDARY. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO HAVE THESE UTILITIES LOCATED PRIOR TO COMMENCING CONSTRUCTION. THE CONTRACTOR SHALL USE EXTREME CAUTION WHEN WORKING IN THIS AREA. ANY DAMAGE DONE TO THESE EXISTING FACILITIES WILL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO REPAIR.

**TRENCH EXCAVATION SAFETY PROTECTION**

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.





**TYPICAL SANITARY SEWER/ WATER CROSSING DETAIL**  
N.T.S.



**LEGEND**

EXISTING SANITARY SEWER	EX-8"SS
PROPOSED SANITARY SEWER	8"SS
EXISTING SANITARY SEWER MANHOLE	●
PROPOSED SANITARY SEWER MANHOLE	●
EXISTING WATER MAIN	EX-8"W
PROPOSED WATER MAIN	8"W
EXISTING STANDARD FIRE HYDRANT	⋈
PROPOSED STANDARD FIRE HYDRANT	⋈
EXISTING STANDARD GATE VALVE	⋈
PROPOSED STANDARD GATE VALVE	⋈
EXISTING PERMANENT BLOWOFF	⋈
PROPOSED PERMANENT BLOWOFF	⋈
PROPOSED LIGHT POLE	⋈
ELECTRIC, GAS, TELEPHONE, & CABLE T.V. EASEMENT	⋈
BUILDING SETBACK LINE	⋈

**Preliminary**  
11/30/2023 8:40:24 AM



4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P: (210) 681-2951 F: (210) 523-7112

GRACE VALLEY RANCH PHASE 3  
STREET EXTENSION  
SANITARY SEWER MASTER PLAN


DATE  
11/29/2023  
PROJECT NO.  
03346.014  
DRAWN BY  
MAS  
CHECKED BY  
KMH

REVISIONS
1.
2.
3.
4.
5.
6.
7.
8.
9.

CUDE ENGINEERS  
TBPE No. 455  
TBPLS No. 10048500

PLAT NO.  
XX-XXXXXXX  
SAWS JOB NO.  
XX-XXXX


**SS3**



LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD.  
100 NE LOOP 410, SUITE 1155  
SAN ANTONIO, TX 78216  
TEL: (210) 403-6200  
CONTACT PERSON: RICHARD MOTT, P.E.  
**CIVIL ENGINEER:**  
CUDE ENGINEERS  
CONTACT PERSON: CHRIS CHAFFEE, P.E.  
4122 POND HILL ROAD, SUITE 101  
SAN ANTONIO, TX 78231  
TEL: (210) 681-2951  
FAX: (210) 523-7112

**NOTE:**  
ALL SEWER LATERALS AND PROPERTY LINE CLEANSOUTS ARE TO BE LOCATED OUTSIDE OF DRIVEWAY PAVED AREAS.

**TRENCH EXCAVATION SAFETY PROTECTION**  
CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.




## LINE "3A"


STA. 19+75.49 TO 27+52.92

**Preliminary**  
11/30/2023 8:40:25 AM

HORIZONTAL SCALE: 1" = 50'  
VERTICAL SCALE: 1" = 5'



CUDEENGINEERS.COM



4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P: (210) 681-2951 F: (210) 523-7112

GRACE VALLEY RANCH PHASE 3  
STREET EXTENSION

SANITARY SEWER PLAN AND PROFILE - LINE "3A"

DATE  
11/29/2023  
PROJECT NO.  
03346.014  
DRAWN BY  
MAS  
CHECKED BY  
KMH


REVISIONS

- 1.
- 2.
- 3.
- 4.
- 5.
- 6.
- 7.
- 8.
- 9.

CUDE ENGINEERS  
TBPE No. 455  
TBPLS No. 10048500

PLAT NO.  
XX-XXXXXXX  
SAWS JOB NO.  
XX-XXXX

**SS4**



4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P:(210) 681.2951 F: (210) 523.7112

GRACE VALLEY RANCH PHASE 3

STREET EXTENSION

SANITARY SEWER PLAN AND PROFILE - LINE "3J"

DATE  
11/29/2023

PROJECT NO.  
03346.014

DRAWN BY  
MAS

CHECKED BY  
KMH


REVISIONS

- 
- 
- 
- 
- 
- 
- 
- 
- 

CUDE ENGINEERS  
TBPE No. 455  
TBPLS No. 10048500

PLAT NO.  
XX-XXXXXXX  
SAWS JOB NO.  
XX-XXXX

SS5



LINE "3J"

STA. 10+00.00 TO 10+60.00

Preliminary


11/30/2023 8:40:25 AM


HORIZONTAL SCALE: 1" = 50'  
VERTICAL SCALE: 1" = 5'

NOTE:  
ALL SEWER LATERALS AND PROPERTY LINE CLEANOUTS  
ARE TO BE LOCATED OUTSIDE OF DRIVEWAY PAVED AREAS.

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR  
STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL  
REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE  
ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO  
IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS,  
PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT  
DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS  
AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY  
PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH  
EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY  
RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY  
PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND  
ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.





4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P:(210) 681.2951 F: (210) 523.7112

GRACE VALLEY RANCH PHASE 3

STREET EXTENSION

WATER DISTRIBUTION STANDARD DETAILS

DATE

11/29/2023

PROJECT NO.  
03346.014

DRAWN BY

MAS

CHECKED BY

KMH
















REVISIONS


- 1.
- 2.
- 3.
- 4.
- 5.
- 6.
- 7.
- 8.
- 9.

CUDE ENGINEERS  
TBPE No. 455  
TBPLS No. 10048500

W1

Preliminary  
11/30/2023 8:40:25 AM





1. RESTRAINED LENGTH CALCULATIONS FOR P.V.C PIPE BEDDED IN COMPACTED GRANULAR MATERIAL, EXTENDING TO THE TOP OF THE PIPE. MAT OF SOIL MATERIAL, IS ASSUMED TO BE INORGANIC CLAY OF HIGH PLASTICITY. DEPTH OF BURY IS ASSUMED TO BE 4 FEET.
2. THESE CALCULATIONS ARE PROVIDED FOR REFERENCE. THE RESTRAINED LENGTH SHALL BE DESIGNED BASED UPON THE CONDITIONS ENCOUNTERED DURING INSTALLATION.
3. ALL JOINTS WITHIN THE RESTRAINED LENGTH SHALL BE RESTRAINED.

### RESTRAINED LENGTH FOR REDUCERS

PIPE SIZE (INCHES)	SMALL SIZE (INCHES)	RESTRAINED LENGTH IN FEET, WHEN TEST PRESSURE = 200 PSI	RESTRAINED LENGTH IN FEET, WHEN TEST PRESSURE = 150 PSI
8	4	30	23
8	4	55	42
8	6	32	24
12	4	95	71
12	6	80	60
12	8	58	43
16	4	131	98
16	6	120	90
16	8	104	78
16	12	60	45
24	12	110	83

1. RESTRAINED LENGTH CALCULATIONS FOR P.V.C PIPE BEDDED IN COMPACTED GRANULAR MATERIAL EXTENDING TO THE TOP OF THE PIPE. NATIVE SOIL MATERIAL IS ASSUMED TO BE INORGANIC CLAY OF HIGH PLASTICITY. DEPTH OF BURY IS ASSUMED TO BE 4 FEET.
2. THESE CALCULATIONS ARE PROVIDED FOR REFERENCE. THE RESTRAINED LENGTH SHALL BE DESIGNED BASED UPON THE CONDITIONS ENCOUNTERED DURING INSTALLATION.
3. ALL JOINTS WITHIN THE RESTRAINED LENGTH SHALL BE RESTRAINED.

### RESTRAINED LENGTH FOR DEAD

PIPE SIZE (INCHES)	RESTRAINED LENGTH IN FEET, WHEN TEST PRESSURE = 200 PSI	RESTRAINED LENGTH IN FEET, WHEN TEST PRESSURE = 150 PSI
4	42	32
6	59	44
8	77	58
12	109	82
16	142	105
24	222	154

1. RESTRAINED LENGTH CALCULATIONS FOR P.V.C PIPE BEDDED IN COMPACTED GRANULAR MATERIAL EXTENDING TO THE TOP OF THE PIPE. NATIVE SOIL MATERIAL IS ASSUMED TO BE INORGANIC CLAY OF HIGH PLASTICITY. DEPTH OF BURY IS ASSUMED TO BE 4 FEET.
2. THESE CALCULATIONS ARE PROVIDED FOR REFERENCE. THE RESTRAINED LENGTH SHALL BE DESIGNED BASED UPON THE CONDITIONS ENCOUNTERED DURING INSTALLATION.
3. ALL JOINTS WITHIN THE RESTRAINED LENGTH SHALL BE RESTRAINED.

Diagram illustrating the dimensions for a T-junction:

- $L_r$  = LENGTH OF PIPE ALONG THE RUN FREE OF JOINTS
- $L$  = LENGTH TO BE RESTRAINED

PIPE SIZE (INCHES)	BRANCH LENGTH (INCHES)	LENGTH OF RUN (FEET)	RESTRAINED LENGTH (FEET) 200 PSI, 100°F	RESTRAINED LENGTH (FEET) 200 PSI, 100°F
6	4	5	7	1
6	4	5	7	1
6	6	0	59	44
6	6	0	59	44
6	6	10	11	1
6	6	10	43	31
6	4	5	1	1
6	6	0	59	44
6	6	5	28	13
6	6	5	28	13
8	3	0	77	58
8	3	0	53	38
8	3	10	30	11
8	3	10	30	11
12	4	0	42	31
12	4	0	42	31
12	6	0	66	44
12	6	10	11	1
12	6	10	11	1
12	6	10	71	56
12	6	5	42	23
12	6	5	42	23
12	8	16	1	1
12	12	13	109	80
12	12	5	66	59
12	12	6	63	56
12	12	16	38	12
12	12	16	42	32
16	4	5	1	1
16	4	5	1	1
16	6	5	1	1
16	6	5	78	58
16	8	5	58	20
16	8	5	110	83
16	12	0	10	1
16	12	0	58	21
16	12	0	58	21
16	12	20	7	1
16	18	5	142	108
16	18	5	123	87
16	18	16	504	48
16	18	16	65	49
24	24	5	186	30
24	24	5	189	119
24	24	16	170	20
24	24	16	103	53
24	24	16	77	20

1. RESTRAINED LENGTH CALCULATIONS FOR P/V PIPE BEDED IN COMPACTED GRAVELLY MATERIAL EXISTING TO THE TOP OF THE PIPE. NATIVE SOIL MATERIAL IS ASSUMED TO BE INDIANIC CLAY OF HIGH PLASTICITY. DEPTH OF BURY IS ASSUMED TO BE 4 FEET.	10	0	110	83
	16	12	5	64
	16	12	10	59
	16	12	15	53
	16	12	20	7
	16	15	0	142
	16	15	5	108
	16	15	10	67
	16	15	15	65
	16	15	20	49
2. THESE CALCULATIONS ARE PROVIDED FOR REFERENCE. THE RESTRAINED LENGTH SHALL BE DESIGNED BASED UPON THE CONDITIONS ENCOUNTERED DURING INSTALLATION.	24	24	5	109
	24	24	10	136
	24	24	15	103
	24	24	20	53
3. ALL JOINTS WITHIN THE RESTRAINED LENGTH SHALL BE RESTRAINED.	24	24	0	110
	24	24	5	64
	24	24	10	59
	24	24	15	53
	24	24	20	7
	24	24	0	142
	24	24	5	108
	24	24	10	67
	24	24	15	65
	24	24	20	49

[illegible]

1. FITTINGS SHALL BE MUELLER OR APPROVED EQUAL.
2. A TRACER WIRE SHALL BE INSTALLED ON THE SERVICE LINE TAPED AT 10-INCH INCREMENTS.

MAIN SIZE	METER SIZE	MAIN SADDLE	CORPORATION	ANGLE STOP
<12"	5/8"	8-Ø1804 IP	H-15028 IP 1"	H-14258: 1"x 3/4"

**NOTES:**

1. BACKFILL ALL EXTERIOR METAL SURFACES IN SILICA SAND
2. ALL REMAINING BASES IN THE REACTION BLOCK SHALL BE NO. 4

Diagram illustrating the construction of a reaction block assembly. The assembly consists of a central reaction block (1'-6" wide) surrounded by a 4" gap, which is then filled with silica sand. The entire assembly is supported by a base. A horizontal pipe or duct is shown passing through the block, with a 1" MIN. gap between the pipe and the block. The pipe is secured with a bolt and nut. The base is labeled 'A' on both sides.

## 222


**PLAN VIEW**

EXISTING GRADE

2" GI NIPPLE, THD.

2" GI SOLID PLUG, THD.

## SECTION 1

	GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD DETAILS	2" TEMPORARY BLOW-OFF ASSEMBLY ON 12" TO 16" MAINS
---	---	---

**NOTES:**

1. EMBED ALL EXTERIOR METAL SURFACES IN SILICA SAND.
2. ALL REINFORCING BARS IN THE REACTION BLOCK SHALL BE NO. 5.

**PLAN VIEW**

 <b>GREEN VALLEY</b> ENGINEERING & DESIGN	STANDARD DETAILS	20" OR LARGER MAINS (JOINT RESTRAINT)
	REVISED: FEBRUARY 2021 THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.	DETAIL NO. <b>W-26</b>

**NOTES:**

1. EMBED ALL EXTERIOR METAL SURFACES IN SILICA SAND.
2. ALL REINFORCING BARS IN THE REACTION BLOCK SHALL BE NO. 5.

2'-0"

4"

4"

STEEL NIPPLE, P.C. FLG. WITH REACTION STOP RING (1 1/2" O.D.)

REACTION BLOCK

3'-0"

8'-0"

SILICA SAND MINIMUM 6 INCHES

SLIP-ON FLANGE WELDED TO

**PLAN VIEW**

LID SET PARALLEL AND  
 ALIGN WITH TOP OF CURB  
 OR PAVEMENT, SET  
 2-INCHES ABOVE FINISHED  
 GRADE

EXISTING GRADE

1" SOLID PLUG, THD.

2,500 PSI  
 CONCRETE

SLOPE TO DRAIN

1" PVC (DEEP HOLE) WITH 1/2"x1" (W.N.) ROCK OR GRAVEL DRAIN POCKET

6" PVC PIPE (WITHOUT BOOT)

1" ECCENTRIC TAP & 1" DI COUPLING  
 WELDED TO FLANGE 1" SOLID PLUG, THD.

3/4"x2" THICK BRICK  
 OR PIPE EXTENSION  
 IF REQUIRED

CONTROL VALVE  
 (MULLER OR EQUIVALENT)

DI NIPPLE

DI PIPE, THD.

90° DI ELBOW, THD.

SILICA SAND  
 MINIMUM 6 INCHES

ECCENTRIC TAP & 1" DI COUPLING

RECOMMENDED  
 LENGTH (W.H.S.)

BLIND FLANGE

**SECTION VIEW (A-A)**

	STANDARD DETAILS	BLOW-OFF ASSEMBLY	
	REVISED: FEBRUARY 2021	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.	DETAIL NO. W-28

Diagram illustrating the correct fitting conditions for Foster Adaptors:

- TYPICAL TEE CONDITION:** Shows a Tee fitting with a Foster Adaptor installed on the branch line. The adaptor is correctly positioned to ensure a secure seal.
- TYPICAL FITTING TO FITTING CONDITION:** Shows a Tee fitting with a Foster Adaptor installed on the main line. The adaptor is correctly positioned to ensure a secure seal.

### TYPICAL

1. FOSTER ADAPTORS, OR APPROVED EQUAL, REQUIRED AT ALL FITTING TO FITTING CONNECTIONS AND FITTING TO VALVE CONNECTIONS.

1. ALL WORKSMANSHIP AND MATERIALS FOR THE WATER SYSTEM SHALL CONFORM TO THE WATER STANDARDS AND DESIGN CRITERIA OF GREEN VALLEY SPECIAL UTILITY DISTRICT (GVSD).
2. PVC MAINS 12-INCHES AND BELOW SHALL CONFORM TO AWWA C-409 PRESSURE CLASS 235 OR ABOVE DEPENDING ON SYSTEM PRESSURES. PVC MAIN GREATER THAN 12 INCHES SHALL CONFORM TO AWWA C-900. ALL ABOVE-GRADING ON-SYSTEM PRESSURES. WATER MAINS SHALL HAVE AN ABSOLUTE MINIMUM DEPTH OF 5-FEET BELOW ROADWAY LEVEL AND 42-INCHES IN ALL OTHER AREAS.
3. ALL WATER MAIN DRAIN IRON FITTINGS SHALL BE MECHANICAL JOINT AND CONFORM TO ANSI/AWWA C-158 OR C-110. ALL BOLTS SHALL HAVE KOTE OR APPROVED EQUIV. ANTI-SEIZURE COMPOUND. ALL FITTINGS SHALL BE 150# RATED. FITTINGS SHALL BE USED BY FOSTER ADAPTOR OR ANCHOR NIPPLE, FOSTER ADAPTOR, ANCHOR NIPPLE, OR FORD LINE-FLANGE. RETAINER GLANDS AND THROAT BLOCKS SHALL BE USED ON ALL FITTINGS AND UNIONS.
4. TRACER WIRE SHALL BE INSTALLED ON ALL PIPELINES INCLUDING SERVICE LINES AND BROUGHT INTO VALVE AND METER BOXES FOR LOCATING PURPOSES. INSTALLED WROOF PROTECTORS SHALL BE USED TO SPICE WIRES TOGETHER. A 12-INCH-WIDE DEFTABLE MESH TAP SHALL BE USED TO LOCATE ALL MAINS.
5. EXCEEDING MAXIMUM DEFLECTION IS PROHIBITED. THE ANGULAR DEFLECTION AT BELL-SPIGOT JOINTS SHALL NOT EXCEED ONE (1) DEGREE. THIS WILL PRODUCE A 4-INCH OFFSET FOR EVERY 20-FOOT SECTION OF PIPE. JOINT DEFLECTION IS ACHIEVED AFTER THE JOINT IS ASSEMBLED IN STRAIGHT ALIGNMENT AND DEFLECTED TO THE REFERENCE MARK. THE BELL SHALL BE BENT TO THE REFERENCE MARK. THE DEFLECTION SHALL BE MEASURED TO THE PRESSURE USING A PLY BAR OR OTHER SUITABLE MEANS. CARE SHOULD BE TAKEN NOT TO EXCEED THE MAXIMUM DEFLECTION ALLOWED OR TO DAMAGE THE PIPE WITH MACHINERY. ABRUPT CHANGES IN DIRECTION SHALL BE ACCOMPLISHED WITH FITTINGS.
6. OVER STRESSING THE BELL BY OVER INSERTING THE JOINTS, OVERBELLING, AND PASSING THE INTERSECTION REFERENCE MARK IS PROHIBITED AND WILL REQUIRE REMOVAL AND REINSTALLATION.
7. STANDARD FIRE HYDRANT SHALL INCLUDE HYDRANT, 8-INCH RESILIENT GATE VALVE AND BOX, ANCHOR FITTINGS, DUCTILE IRON PIPE, AND ALL APPURTENANCES. HYDRANT SHALL BE LIMITED TO THOSE MANUFACTURED BY MUELLER, AVE. AMERICAN FLOW, CLOW, OR EAST JORDAN. ONLY MUELLER HYDRANTS & E&J SHALL BE USED IN LINE OF CITY OF CHICO'S JURISDICTION. CHICO FIRE DEPARTMENT SHALL BE FACTORY SET TO 150 PSI. HYDRANTS SHALL HAVE A STORTZ CONNECTION ON STEAMER NOZZLE. FITTINGS FOR PUS SHALL BE FULLY RESTRAINED AND TIED TO VALVE.

11/30/2023 8:40:25 AM



4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P:(210) 681.2951 F: (210) 523.7112

# GRACE VALLEY RANCH PHASE 3 STREET EXTENSION

## WATER DISTRIBUTION STANDARD DETAILS

DATE  
1/29/2023

PROJECT NO.  
03346.014

DRAWN BY  
MAS

CHECKED BY  
KMH


## REVISIONS

1. ....
2. ....
3. ....
4. ....
5. ....
6. ....
7. ....
8. ....
9. ....

CUDE ENGINEERS

TBPE No. 455  
TBPLS No. 10048500

# W2




LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD.  
100 NE LOOP 410, SUITE 1155  
SAN ANTONIO, TX 78216  
TEL: (210) 403-6200  
CONTACT PERSON: RICHARD MOTT, P.E.  
**CIVIL ENGINEER:**  
CUDE ENGINEERS  
CONTACT PERSON: CHRIS CHAFFEE, P.E.  
4122 POND HILL ROAD, SUITE 101  
SAN ANTONIO, TX 78231  
TEL: (210) 681-2951  
FAX: (210) 523-7112

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS, AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEES OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.


- NOTES:
1. IN THE CITY OF CIBOLO, FIRE HYDRANTS SHALL BE MUELLER OR EJ TYPE AND SHALL BE 2' MINIMUM AND 7' MAXIMUM FROM THE BACK OF CURB.
  2. DISINFECTION SHALL BE BY MACHINE CHLORINATION.
  3. CONTRACTOR TO UTILIZE APPROVED WATER LINE STOPS AND/OR MUELLER INSERTION-VALVES TO MINIMIZE WATER OUTGAGES AS REQUIRED BY GVSUD DURING CONSTRUCTION.
  4. MOISTURE DENSITY COMPACTION TESTING FREQUENCY- WATER MAIN TRENCHES REQUIRED EVERY 300 L.F. FOR EACH VERTICAL FOOT OF COMPACTED BACKFILL. SERVICES RANDOMLY SELECTED AS REQUIRED BY GVSUD INSPECTOR.
  5. ALL TESTING AND TEST REPORTS SHALL BE COORDINATED WITH GVSUD INSPECTOR BY THE CONTRACTOR.
  6. ALL DUCTILE IRON PIPE TO BE AMERICAN, ZINC COATED, AWWA/ANSI C-151



LOCAL RESIDENTIAL FIRE HYDRANT DETAIL (5' SIDEWALK)


N.T.S.

- NOTE:
1. EXCLUSIVE OF THE TEE, PAYMENT FOR THE FIRE HYDRANT SHALL INCLUDE ALL FITTINGS, 6" D.I. PIPE AND 6" GATE VALVE & BOX.
  2. FIRE HYDRANT TO BE INSTALLED OUTSIDE OF THE LIMITS OF ALL PROPOSED SIDEWALKS.



TYPICAL SANITARY SEWER/ WATER CROSSING DETAIL

N.T.S.



WATER METER BOX LOCATION (60' R.O.W.)



N.T.S.

LEGEND

- |   |                |
|---|----------------|
| EXISTING SANITARY SEWER                         | EX-8"SS        |
| PROPOSED SANITARY SEWER                         | 8"SS           |
| EXISTING SANITARY SEWER MANHOLE                 | 8"SM           |
| PROPOSED SANITARY SEWER MANHOLE                 | EX-8"SM        |
| EXISTING WATER MAIN                             | EX-8"W         |
| PROPOSED WATER MAIN                             | 8"W            |
| EXISTING STANDARD FIRE HYDRANT                  | 8"FH           |
| PROPOSED STANDARD FIRE HYDRANT                  | 8"PFH          |
| EXISTING STANDARD GATE VALVE                    | 8"GV           |
| PROPOSED STANDARD GATE VALVE                    | 8"PGV          |
| EXISTING PERMANENT BLOWOFF                      | 8"PB           |
| PROPOSED PERMANENT BLOWOFF                      | 8"PPB          |
| ELECTRIC, GAS, TELEPHONE, & CABLE T.V. EASEMENT | E.G.T.C.A.ESMT |
| BUILDING SETBACK LINE                           | B.S.L.         |


Preliminary

11/30/2023 8:40:26 AM



CURB / WATER CROSSING - DETAIL 'A'

N.T.S.




LOCAL "A" STREET CROSS-SECTION

N.T.S.

CAUTION!!!

THE CONTRACTOR SHALL BE AWARE THAT EXISTING UTILITIES ARE WITHIN THE SITE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO HAVE THESE UTILITIES LOCATED PRIOR TO COMMENCING CONSTRUCTION. THE CONTRACTOR SHALL USE EXTREME CAUTION WHEN WORKING IN THIS AREA. ANY DAMAGE DONE TO THESE EXISTING FACILITIES WILL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO REPAIR.



4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P:(210) 681.2951 F: (210) 523.7112

GRACE VALLEY RANCH PHASE 3  
STREET EXTENSION

WATER DISTRIBUTION PLAN


DATE  
11/29/2023  
PROJECT NO.  
03346.014  
DRAWN BY  
MAS  
CHECKED BY  
KMH

REVISIONS

1.	
2.	
3.	
4.	
5.	
6.	
7.	
8.	
9.	

CUDE ENGINEERS  
TBPE No. 455  
TBPLS No. 10048500


W3





LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD.  
100 NE LOOP 410, SUITE 1155  
SAN ANTONIO, TX 78216  
TEL: (210) 403-6200  
CONTACT PERSON: RICHARD MOTT, P.E.  
**CIVIL ENGINEER:**  
CUDE ENGINEERS  
CONTACT PERSON: CHRIS CHAFFEE, P.E.  
4122 POND HILL ROAD, SUITE 101  
SAN ANTONIO, TX 78231  
TEL: (210) 681-2951  
FAX: (210) 523-7112

NOTE:

1. ALL SILT FENCES AND/OR ROCK BERMS AND TEMPORARY CONSTRUCTION ENTRANCES/EXITS SHALL BE PLACED AT THE MOST DOWN-GRADIENT POINT OF CONSTRUCTION AS SHOWN ON THIS SITE PLAN. CONTRACTOR SHALL TAKE INTO CONSIDERATION ANY PROPOSED CONSTRUCTION THAT MAY TAKE PLACE AT THESE LOCATIONS. ANY RELOCATION OF SILT FENCE, ROCK BERMS AND/OR TEMPORARY CONSTRUCTION ENTRANCES/EXITS SHALL BE AT THE CONTRACTOR'S EXPENSE.
2. AREA OF SOIL DISTURBANCES INCLUDE STREET RIGHT-OF-WAYS, UTILITY EASEMENTS & LOTS.
3. THERE WILL NOT BE STORMWATER DISCHARGES INTO THE FEMA FLOOD PLAIN.
4. THE CONTRACTOR IS REQUIRED TO MAINTAIN EROSION CONTROLS THROUGHOUT THE DURATION OF THE PROJECT.
5. THE CITY INSPECTOR HAS THE AUTHORITY TO HAVE THE CONTRACTOR MODIFY THE EROSION CONTROLS AT THE DEVELOPER'S EXPENSE. THE DEVELOPER SHALL BE NOTIFIED OF THESE MODIFICATIONS PRIOR TO COMMENCEMENT OF MODIFICATIONS.



**Preliminary**  
11/30/2023 8:40:26 AM



4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P: (210) 681-2951 F: (210) 523-7112


GRACE VALLEY RANCH PHASE 3  
STREET EXTENSION

STORMWATER POLLUTION PREVENTION PLAN

DATE  
11/29/2023  
PROJECT NO.  
03346.014  
DRAWN BY  
MAS  
CHECKED BY  
KMH


REVISIONS
1.
2.
3.
4.
5.
6.
7.
8.
9.

CUDE ENGINEERS  
TBPE No. 455  
TBPLS No. 10048500




LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD.  
100 NE LOOP 410, SUITE 1155  
SAN ANTONIO, TX 78216  
TEL: (210) 923-6200  
CONTRACTOR: RICHARD MOTT, P.E.  
CIVIL ENGINEER  
CUDE ENGINEERS, INC. SHOULD BE POLYPROPYLENE, POLYETHYLENE OR POLYAMIDE WOVEN OR NON WOVEN FABRIC. THE FABRIC WIDTH SHOULD BE 36 INCHES. THE MINIMUM UNIT WEIGHT OF 4.5 OZ/YD, MULLEN BURST STRENGTH EXCEEDING 130 LB/IN 2, ULTRAVIOLET STABILITY EXCEEDING 70%, AND APPARENT OPENING SIZE OF U.S. SIEVE NO. 30.  
CONTACT PERSON: CHRIS CHAFFEE, P.E.  
4122 POND HILL ROAD, SUITE 101  
SAN ANTONIO, TX 78231  
TEL: (210) 681-2951  
FAX: (210) 681-2951  
1. LAY OUT FENCING DOWN SLOPE OF DISTURBED AREA, FOLLOWING THE CONTOUR AS CLOSELY AS POSSIBLE. THE FENCE SHOULD BE SITED SO THAT THE MAXIMUM DRAINAGE AREA IS 1/4 ACRE/100 FEET OF FENCE.  
2. THE TOE OF THE SILT FENCE SHOULD BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWN-SLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. WHERE FENCE CANNOT BE TRENCHED IN (E.G., PAVEMENT OR ROCK OUTCROPS), WEIGHT FABRIC FLAP WITH 3 INCHES OF PEA GRAVEL ON UPHILL SIDE TO PREVENT FLOW FROM SEEPING UNDER FENCE.  
3. THE TRENCH MUST BE A MINIMUM OF 6 INCHES DEEP AND 6 INCHES WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL.  
4. SILT FENCE SHOULD BE SECURELY FASTENED TO EACH STEEL SUPPORT POST OR TO WOVEN WIRE, WHICH IS IN TURN ATTACHED TO THE STEEL FENCE POST. THERE SHOULD BE A 3-FOOT OVERLAP, SECURELY FASTENED WHERE ENDS OF FABRIC MEET.  
5. SILT FENCE SHOULD BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.  
6. REMOVE SEDIMENT WHEN BUILDUP REACHES 6 INCHES, OR INSTALL A SECOND LINE OF FENCING PARALLEL TO THE OLD FENCE.  
7. REPLACE ANY TORN FABRIC OR INSTALL A SECOND LINE OF FENCING PARALLEL TO THE TORN SECTION.  
8. REPLACE OR REPAIR ANY SECTIONS CRUSHED OR COLLAPSED IN THE COURSE OF CONSTRUCTION ACTIVITY. IF A SECTION OF FENCE IS OBSTRUCTING VEHICULAR ACCESS, CONSIDER RELOCATING IT TO A SPOT WHERE IT WILL PROVIDE EQUAL PROTECTION, BUT WILL NOT OBSTRUCT VEHICLES. A TRIANGULAR FILTER DIKE MAY BE PREFERABLE TO A SILT FENCE AT COMMON VEHICLE ACCESS POINTS.

**1** **SILT FENCE DETAIL**  
SCALE: NONE




**5** **TYP. CONSTRUCTION STAGING AREA**  
SCALE: NONE




**NOTES:**  
1. THE BERM STRUCTURE SHOULD BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM OPENING OF 1 INCH AND A MINIMUM WIRE DIAMETER OF 20 GAUGE GALVANIZED AND SHOULD BE SECURED WITH SHOOT RINGS.  
2. CLEAN, OPEN GRADED 3 TO 5 INCH DIAMETER ROCK SHOULD BE USED, EXCEPT IN AREAS WHERE HIGH VELOCITIES OR LARGE VOLUMES OF FLOW ARE EXPECTED, WHERE 5-TO 8-INCH DIAMETER ROCKS MAY BE USED.  
3. LAY OUT THE WOVEN WIRE SHEATHING PERPENDICULAR TO THE FLOW LINE.  
4. BERM SHOULD HAVE A TOP WIDTH OF 2 FEET MINIMUM WITH SIDE SLOPES BEING 2:1 (H:V) OR FLATTER.  
5. PLACE THE ROCK ALONG THE SHEATHING TO A HEIGHT NOT LESS THAN 18".  
6. WRAP THE WIRE SHEATHING AROUND THE ROCK AND SECURE WITH THE WIRE SO THAT THE ENDS OF THE SHEATHING OVERLAP AT LEAST 2 INCHES, AND THE BERM RETAINS ITS SHAPE WHEN WALKED UPON.  
7. BERM SHOULD BE BUILT ALONG THE CONTOUR AT ZERO PERCENT GRADE OR AS NEAR AS POSSIBLE.  
8. THE ENDS OF THE BERM SHOULD BE TIED INTO EXISTING UPSLOPE GRADE AND THE BERM SHOULD BE BURIED IN A TRENCH APPROXIMATELY 3 TO 4 INCHES DEEP TO PREVENT FAILURE OF THE CONTROL.  
9. INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL BY THE RESPONSIBLE PARTY. FOR INSTALLATIONS IN STREAMBEDS, ADDITIONAL DAILY INSPECTIONS SHOULD BE MADE. THE BERM SHOULD BE RESHAPED AS NEEDED DURING INSPECTION.  
10. REMOVE SEDIMENT AND OTHER DEBRIS WHEN BUILDUP REACHES 6 INCHES AND DISPOSE OF THE ACCUMULATED SILT OF IN AN APPROVED MANNER AND REPAIR ANY LOOSE WIRE SHEATHING.  
11. THE BERM SHOULD BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED DUE TO SILT ACCUMULATION AMONG THE ROCKS, WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC.  
12. THE ROCK BERM SHOULD BE LEFT IN PLACE UNTIL ALL UPSTREAM AREAS ARE STABILIZED AND ACCUMULATED SILT REMOVED.

**2** **ROCK BERM DETAIL**  
SCALE: NONE




**BAGGED GRAVEL INLET FILTER NOTES**  
1. THE GRAVEL BAG MATERIAL SHOULD BE POLYPROPYLENE, POLYETHYLENE, POLYAMIDE OR COTTON BURLAP WOVEN FABRIC, MINIMUM UNIT WEIGHT 4 OZ/YD 2, MULLEN BURST STRENGTH EXCEEDING 300 PSI AND ULTRAVIOLET STABILITY EXCEEDING 70 PERCENT.  
2. THE BAG LENGTH SHOULD BE 24 INCHES, WIDTH SHOULD BE 18 INCHES AND THICKNESS SHOULD BE 6 INCHES.  
3. THE GRAVEL BAGS SHOULD BE FILLED WITH 3/4" GRAVEL.  
4. WHEN A GRAVEL BAG IS FILLED WITH GRAVEL, THE OPEN END OF THE GRAVEL BAG SHOULD BE STAPLED OR TIED WITH NYLON OR POLY CORD.  
5. THE GRAVEL BAGS SHOULD BE PLACED AS SHOWN ON THE DETAIL. THE GRAVEL BAGS SHALL BE STACKED TO FORM A CONTINUOUS BARRIER AROUND THE INLETS. THE BAGS SHOULD BE TIGHTLY ABUTTED AGAINST EACH OTHER TO PREVENT RUNOFF FROM FLOWING BETWEEN THE BAGS.  
6. INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL. REPAIR OR REPLACEMENT SHOULD BE MADE PROMPTLY AS NEEDED BY THE CONTRACTOR.  
7. CHECK PLACEMENT OF DEVICE TO PREVENT GAPS BETWEEN DEVICE AND CURB.  
8. REMOVE SEDIMENT WHEN BUILDUP REACHES A DEPTH OF 3 INCHES. REMOVED SEDIMENT SHOULD BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.  
9. STRUCTURES SHOULD BE REMOVED AND THE AREA STABILIZED ONLY AFTER THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

**6** **BAGGED GRAVEL INLET FILTER**  
SCALE: NONE



**GENERAL NOTES**  
1. LENGTH SHALL BE AS SHOWN ON THE CONSTRUCTION DRAWINGS BUT NOT LESS THAN 50 FEET.  
2. THICKNESS SHALL BE NOT LESS THAN 8 INCHES.  
3. WIDTH SHALL BE NOT LESS THAN FULL WIDTH OF ALL POINTS OF INGRESS OR EGRESS.  
4. STABILIZED AREA MAY BE WIDENED OR LENGTHENED TO ACCOMMODATE A TRUCK WASHING AREA WHEN SHOWN ON THE CONSTRUCTION DRAWING. AN OUTLET SEDIMENT TRAP MUST BE PROVIDED FOR THE TRUCK WASHING AREA.  
5. STONE MATERIAL SHALL CONSIST OF 3 TO 5 INCH OPEN GRADED ROCK AND SHALL BE PLACED IN A LAYER OF AT LEAST 8 INCHES THICKNESS.  
**NOTES:**  
1. THE AGGREGATE SHOULD CONSIST OF 4 TO 8 INCH WASHED STONE OVER A STABLE FOUNDATION.  
2. THE AGGREGATE SHOULD BE PLACED WITH A MINIMUM THICKNESS OF 8 INCHES.  
3. THE GEOTEXTILE FABRIC SHOULD BE DESIGNED SPECIFICALLY FOR USE AS A SOIL FILTRATION MEDIA WITH AN APPROXIMATE WEIGHT OF 6 OZ/YD 2, A MULLEN BURST RATING OF 140 LB/IN 2, AND AN EQUIVALENT OPENING SIZE GREATER THAN A NUMBER 50 SIEVE.  
4. AVOID CURVES ON PUBLIC ROADS AND STEEP SLOPES. REMOVE VEGETATION AND OTHER OBJECTIONABLE MATERIAL FROM THE FOUNDATION AREA. GRADE CROWN FOUNDATION FOR POSITIVE DRAINAGE.  
5. THE MINIMUM WIDTH OF THE ENTRANCE/EXIT SHOULD BE 12 FEET OR THE FULL WIDTH OF EXIT ROADWAY, WHICHEVER IS GREATER.  
6. THE CONSTRUCTION ENTRANCE SHOULD BE AT LEAST 50 FEET LONG.  
7. PLACE GEOTEXTILE FABRIC AND GRADE FOUNDATION TO IMPROVE STABILITY, ESPECIALLY WHERE WET CONDITIONS ARE ANTICIPATED.  
8. PLACE STONE TO DIMENSIONS AND GRADE SHOWN. LEAVE SURFACE SMOOTH AND SLOPE FOR DRAINAGE.  
9. THE ENTRANCE SHOULD BE MAINTAINED IN A CONDITION, WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.  
10. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ON TO PUBLIC RIGHTS-OF-WAY SHOULD BE REMOVED IMMEDIATELY BY CONTRACTOR.  
11. WHEN NECESSARY, WHEELS SHOULD BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY.  
12. WHEN WASHING IS REQUIRED, IT SHOULD BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN.  
13. ALL SEDIMENT SHOULD BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATER COURSE.


**3** **TEMPORARY CONSTRUCTION ENTRANCE / EXIT**  
SCALE: NONE



**NOTES:**  
1. DETAIL ABOVE ILLUSTRATES MINIMUM DIMENSIONS. PIT CAN BE INCREASED IN SIZE DEPENDING ON EXPECTED FREQUENCY OF USE.  
2. WASHOUT PIT SHALL BE LOCATED IN AN AREA EASILY ACCESSIBLE TO CONSTRUCTION TRAFFIC.  
3. WASHOUT PIT SHALL NOT BE LOCATED IN AREAS SUBJECT TO INUNDATION FROM STORM WATER RUNOFF.

**4** **CONCRETE TRUCK WASHOUT PIT**  
SCALE: NONE

**Preliminary**  
11/30/2023 8:40:26 AM




4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P: (210) 681.2951 F: (210) 523.7112

GRACE VALLEY RANCH PHASE 3  
STREET EXTENSION  
STORMWATER POLLUTION PREVENTION PLAN DETAILS

DATE  
11/29/2023  
PROJECT NO.  
03346.014  
DRAWN BY  
MAS  
CHECKED BY  
KMH


REVISIONS	
1.	
2.	
3.	
4.	
5.	
6.	
7.	
8.	
9.	

CUDE ENGINEERS  
TBPE No. 455  
TBPLS No. 10048500




LENNAR HOMES OF TEXAS LAND AND CONSTRUCTION, LTD.  
100 NE LOOP 410, SUITE 1155  
SAN ANTONIO, TX 78216  
TEL: (210) 403-6200  
CONTACT PERSON: RICHARD MOTT, P.E.  
**CIVIL ENGINEER:**  
CUDE ENGINEERS  
CONTACT PERSON: CHRIS CHAFFEE, P.E.  
4122 POND HILL ROAD, SUITE 101  
SAN ANTONIO, TX 78231  
TEL: (210) 681-2951  
FAX: (210) 523-7112

LEGEND



NOTE:

LOT GRADING BASED ON SLABS BEING 15' BEHIND FRONT PROPERTY LINE.  
MINIMUM SLAB EXPOSURE IS 1.0'.  
ALL ELEVATIONS AT FRONT PROPERTY LINE ARE 0.30' ABOVE CURB ELEVATION ON LOCAL TYPE "A" STREETS.  
TYPICAL PAD SIZES ARE 75' x 30' ON LOCAL TYPE "A" STREETS.  
CONTRACTOR TO REFERENCE TREE PRESERVATION PLAN.  
CONTOURS SHOWN ON STREET ARE TOP OF STREET.



DENSITY TEST FREQUENCY

NOT TO SCALE

GENERAL SPECIFICATIONS FOR SITE PREPARATION

1. GENERAL DESCRIPTION

THIS ITEM SHALL CONSIST OF ALL CLEARING AND GRUBBING, DEMOLITION, PREPARATION OF LAND TO BE FILLED, FILLING OF THE LAND, SPREADING, COMPACTION TESTING AND INSPECTION OF THE FILL, AND ALL SUBSIDIARY WORK NECESSARY TO COMPLETE THE GRADING OF THE CUT AND FILL AREAS TO CONFORM WITH THE LINES, GRADES AND SLOPES AS SHOWN ON THE APPROVED PLANS.

ALL LOT GRADING MUST MEET REQUIREMENTS OF FHWA/HUD HANDBOOK 4140.3, SPECIFICATIONS FOR LAND DEVELOPMENTS ON CONTROLLED EARTHWORK, DATASHEET 79G. HUD 79G REQUIREMENTS FOR FILL MATERIAL OF 6 INCHES AND MORE WILL BE CONDUCTED. ALL CUT AREAS WILL ALSO MEET THE REQUIREMENTS FOR HUD 79G COMPACTION TESTING. IN ADDITION, ENGINEERS MUST PROVIDE VERIFICATION OF ALL AREAS WHICH DO NOT REQUIRE HUD 79G.

2. CLEARING THE AREA TO BE FILLED

ALL TIMBER, LOGS, TREES, BRUSH AND RUBBISH SHALL BE REMOVED FROM THE SITE.

3. SCARIFYING THE AREA TO BE FILLED

ALL ORGANIC MATTER SHALL BE REMOVED FROM THE SURFACE UPON WHICH THE FILL IS TO BE PLACED, AND THE SURFACE SHALL THEN BE DISKED OR SCARIFIED TO A MINIMUM DEPTH OF SIX INCHES (6"), ALL SURFACE RUTS OR OTHER UNEVEN FEATURES WILL BE LEVELED PRIOR TO FIELD DENSITY TESTING.

4. COMPACTING THE AREA TO BE FILLED

FOLLOWING THE CLEARING AND DISKING OR SCARIFYING OF THE FILL AREA, IT SHALL BE BLADED UNTIL IT IS UNIFORM AND FREE FROM LARGE CLODS. THE AREA SHALL BE BROUGHT TO THE ADEQUATE MOISTURE CONTENT AND COMPACTED (TYPICALLY) TO NOT LESS THAN NINETY PERCENT (90%) OF MAXIMUM DENSITY IN ACCORDANCE WITH THE CURRENT ASTM D 1557 COMPACTION PROCEDURE, OR 95% OF MAXIMUM DENSITY IN ACCORDANCE WITH THE CURRENT TxDOT-TEX-113-E COMPACTION PROCEDURE.

5. FILL MATERIALS

THE MATERIALS USED SHALL BE FREE FROM ORGANIC MATTER AND OTHER DELETERIOUS SUBSTANCES, SUCH AS TREES, BRUSH AND RUBBISH.

6. DEPTH AND MIXING OF FILL LAYERS

THE SELECTED FILL MATERIAL SHALL BE PLACED IN LEVEL, UNIFORM LAYERS WHICH, WHEN COMPACTED, SHALL HAVE A DENSITY CONFORMING TO THAT STIPULATED ABOVE. EACH LAYER SHALL BE THOROUGHLY MIXED DURING THE SPREADING TO ENSURE UNIFORMITY OF MATERIAL IN EACH LAYER. COMPACTED LAYER THICKNESS MAY VARY DEPENDING ON THE COMPACTION EQUIPMENT OF DEMONSTRATED CAPABILITY. THE MAXIMUM LOOSE DEPTH FOR ANY MATERIAL SHALL NOT EXCEED TWELVE INCHES (12"). FOR TESTING REQUIREMENTS OF FILL MATERIAL, SEE DENSITY TESTING.

7. ROCK

WHEN FILL MATERIAL INCLUDES ROCK, THE MAXIMUM ROCK SIZE SHALL BE AS APPROVED BY THE GEOTECHNICAL ENGINEER. NO LARGE ROCKS SHALL BE ALLOWED TO NEST AND ALL VOIDS MUST BE FILLED WITH SMALL STONES OR SOIL AND ADEQUATELY COMPACTED. NO LARGE ROCKS WILL BE PERMITTED WITHIN EIGHTEEN INCHES (18") OF THE FINISHED GRADE.

8. COMPACTION OF FILL LAYER

COMPACTION EQUIPMENT SHALL BE CAPABLE OF COMPACTING THE FILL TO THE SPECIFIED DENSITY. COMPACTION SHALL BE ACCOMPLISHED WHILE THE FILL MATERIAL IS AT OR NEAR THE APPROPRIATE MOISTURE CONTENT. COMPACTION OF EACH LAYER SHALL BE CONTINUOUS OVER THE ENTIRE STRUCTURAL AREA (BENEATH PROPOSED STRUCTURES).

9. COMPACTION OF SLOPES

THE FACES OF FILL SLOPES SHALL BE COMPACTED. COMPACTION OPERATIONS SHALL BE CONTINUED UNTIL THE SLOPE FACES ARE STABLE BUT NOT TOO DENSE FOR PLANTING ON THE SLOPES. COMPACTION OF THE SLOPE FACES MAY BE DONE PROGRESSIVELY IN INCREMENTS OF THREE TO FIVE FEET (3' TO 5') IN FILL HEIGHT AS THIS FILL PROGRESSES OR AFTER THE FILL HAS BEEN BROUGHT TO ITS TOTAL HEIGHT.

10. MOISTURE CONTENT

THE FILL MATERIAL SHALL BE COMPACTED AT THE APPROPRIATE MOISTURE CONTENT SPECIFIED FOR THE SOILS BEING USED. APPROPRIATE MOISTURE CONTENT IS DEFINED, TYPICALLY, AS OPTIMUM MOISTURE CONTENT; HOWEVER, FOR EXPANSIVE SOILS IT MAY BE GREATER THAN OPTIMUM MOISTURE CONTENT, AND OTHER MOISTURE CONTENTS MAY BE NECESSARY TO PRODUCE THE DESIRED RESULTS WITH CERTAIN SOILS.


11. DENSITY TESTS

FIELD DENSITY TESTS SHALL BE PERFORMED ON LAYERS OF FILL WHEN THE FILL IS BEING PLACED AS DIRECTED BY THE GEOTECHNICAL ENGINEER. THE MAXIMUM FILL HEIGHT BETWEEN DENSITY TESTING SHALL BE EIGHTEEN INCHES (18"). ALL TESTING SHALL BE REQUESTED BY THE CONTRACTOR TO MEET THE CONTRACTOR'S CONSTRUCTION SCHEDULE. NOTIFICATION BY THE CONTRACTOR TO CONDUCT TESTS SHALL BE AT LEAST THE DAY BEFORE. THIS NOTIFICATION SHALL INCLUDE THE FILL AREA LOCATION (LOT AND BLOCK), THE LIFT OR HEIGHT OF FILL AND APPROXIMATE DESIRED TIME OF TESTING. WHEN THESE TESTS INDICATE THAT THE DENSITY OF ANY LAYER OF FILL OR PORTION THEREOF IS BELOW THE REQUIRED DENSITY, THE PARTICULAR LAYER OR PORTION SHALL BE REWORKED AND RETESTED AT THE EXPENSE OF THE CONTRACTOR UNLESS THE CONTRACTOR CAN SHOW EVIDENCE THAT CIRCUMSTANCES BEYOND HIS CONTROL REQUIRED THE RETESTING. GENERALLY, THE SPECIFIC TESTING WILL BE AS FOLLOWS AND CONDUCTED BY GEOTECHNICAL ENGINEER.


1. THE LAND TO BE FILLED (PREPARED SUBGRADE) SHALL BE PREPARED AND TESTED AT A FREQUENCY AS DETERMINED BY THE GEOTECHNICAL ENGINEER.
2. THE FIRST LIFT OF COMPACTED FILL (GENERALLY 8 TO 12-IN.) SHALL BE TESTED AS DETERMINED BY THE GEOTECHNICAL ENGINEER. ANY AREAS SUPPORTING THE PROPOSED STRUCTURES REQUIRING FILL SHALL BE TESTED FOR DENSITY COMPLIANCE.
3. FILLS SHALL BE TESTED A MAXIMUM OF EACH EIGHTEEN INCHES (18") OF FILL.
4. TEST RESULTS WILL BE PROVIDED BY THE FIELD TECHNICIAN TO THE CONTRACTOR WHEN POSSIBLE; HOWEVER, ALL TEST RESULTS ARE TO BE REVIEWED BY THE GEOTECHNICAL ENGINEER FOR COMPLIANCE. THE ENGINEER WILL NOTIFY THE CONTRACTOR OF ALL THE TEST RESULTS.

12. CUT/FILL LOTS

AREAS INVOLVING CUT ON ONE PORTION AND FILL ON ANOTHER PORTION OF A SPECIFIC LOT SHALL BE PREPARED TO A MINIMUM DEPTH OF 6-IN. AND WILL BE THE SAME MATERIAL CLASSIFICATION AT THE SAME COMPACTION AND MOISTURE CONTENT. A MINIMUM OF TWO (2) FIELD DENSITY TESTS SHALL BE REQUIRED ON EACH CUT/FILL LOT FOR THE PURPOSE OF DETERMINING UNIFORMITY OF THE AREA SUPPORTING THE PROPOSED STRUCTURES.



**Preliminary**  
11/30/2023 8:40:26 AM



4122 Pond Hill Road, Suite 101  
San Antonio, Texas 78231  
P: (210) 681.2951 F: (210) 523.7112

GRACE VALLEY RANCH PHASE 3  
STREET EXTENSION

GRADING PLAN

DATE  
11/29/2023  
PROJECT NO.  
03346.014  
DRAWN BY  
MAS  
CHECKED BY  
KMH

REVISIONS

- 1.
- 2.
- 3.
- 4.
- 5.
- 6.
- 7.
- 8.
- 9.

CUDE ENGINEERS  
TBPE No. 455  
TBPLS No. 10048500

**GR1**