

BID FORM (SCHEDULE OF VALUES)					
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT BID PRICE	EXTENDED AMOUNT
1	MOBILIZATION	1	L.S.		\$ -
2	CURB INLET GRAVEL FILTERS	67	L.F.		\$ -
3	CONCRETE WASHOUT PIT	1	EA.		\$ -
4	CONSTRUCTION EXITS (INSTALL/REMOVE)	1	EA.		\$ -
5	TEMPORARY SEDIMENT CONTROL FENCE	2,214	L.F.		\$ -
6	ROCK BERM	135	L.F.		\$ -
7	EARTHEN BERM	240	L.F.		\$ -
8	HYDROMULCHING (DISTURBED OPEN SPACE) INCLUDES IRRIGATION FOR 85% VEGETATION ESTABLISHMENT	2,904	S.Y.		\$ -
SITEWORK SUBTOTAL					\$ -
1	STREET EXCAVATION	1,790	C.Y.		\$ -
2	STREET EMBANKMENT	1,249	C.Y.		\$ -
3	FLEXIBLE BASE (12" COMPACTED DEPTH)	8,838	S.Y.		\$ -
4	6" LIME TREATED SUBGRADE (24 LB/S.Y.)	8,838	S.Y.		\$ -
5	HOT MIX ASPHALTIC PAVEMENT, TYPE D (2.5" COMP. DEPTH)	7,423	S.Y.		\$ -
6	CONCRETE HEADER CURB	84	L.F.		\$ -
7	CONCRETE CURB & GUTTER	1,413	L.F.		\$ -
8	CONCRETE MOUNTABLE CURB	2,980	L.F.		\$ -
9	ADA CURB RAMPS (DEVELOPER RESPONSIBILITY)	2	EA.		\$ -
10	CONCRETE SIDEWALKS	115	S.Y.		\$ -
11	TIMBER GUARD POSTS	15	EA.		\$ -
12	R1-1 STOP (30")(HIGH INTENSITY)	5	EA.		\$ -
13	0M-4 END OF ROAD MARKER (18"X18")	9	EA.		\$ -
14	9 INCH [229mm] STREET NAME, BLOCK NUMBER (VARIES x9")(HIGH INTENSITY)	12	EA.		\$ -
15	TYPE II BLUE RAISED PAVEMENT MARKER	4	EA.		\$ -
16	REMOVE HEADER CURB AND GUARD POSTS	56	L.F.		\$ -
STREET SUBTOTAL					\$ -

INITIALS: _____

BID FORM (SCHEDULE OF VALUES)					
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT BID PRICE	EXTENDED AMOUNT
1	DRAINAGE EXCAVATION	5,023	C.Y.		\$ -
2	DRAINAGE EMBANKMENT	989	C.Y.		\$ -
3	30" R.C.P.	411	L.F.		\$ -
4	36" R.C.P.	251	L.F.		\$ -
5	JUNCTION BOX (COMPLETE) (4'x4')	1	EA.		\$ -
6	INLET TYPE II (COMPLETE)(20 FT)	1	EA.		\$ -
7	INLET TYPE II (COMPLETE)(25 FT)	1	EA.		\$ -
8	INLET EXTENSIONS (10')	1	EA.		\$ -
9	CONCRETE BAFFLE BLOCKS	1	C.Y.		\$ -
10	CONCRETE RIPRAP (5" THICK)	25	S.Y.		\$ -
11	8"x12" ROCK RUBBLE	40	S.Y.		\$ -
DRAINAGE SUBTOTAL					\$ -
1	TRENCH EXCAVATION SAFETY PROTECTION	5,817	L.F.		\$ -
2	8" PVC SANITARY SEWER LINE (8' - 10')	841	L.F.		\$ -
3	8" PVC SANITARY SEWER LINE (10' - 12')	84	L.F.		\$ -
4	4' DIA. SANITARY SEWER MANHOLE (0'-6')	4	EA.		\$ -
5	4' DIA. DOGHOUSE SANITARY SEWER MANHOLE	1	EA.		\$ -
6	4' DIA. EXTRA DEPTH MANHOLES (>6')	21	VF		\$ -
7	6" SANITARY SEWER LATERAL W/ CLEANOUT	4,892	L.F.		\$ -
8	SEWER MAIN TELEVISION INSPECTION (8" - 20")	925	L.F.		\$ -
9	EXISTING MANHOLE CONNECTION	1	EA.		\$ -
10	6" VERTICAL STACK	30	V.F.		\$ -
SANITARY SEWER SUBTOTAL					\$ -
1	TRENCH EXCAVATION PROTECTION	2,347	L.F.		\$ -
2	8" C-909, PC235 PIPE	2,347	L.F.		\$ -
3	1" SINGLE WATER SERVICE - LONG	3	EA.		\$ -
4	1" SINGLE WATER SERVICE - SHORT	14	EA.		\$ -

INITIALS: _____

BID FORM (SCHEDULE OF VALUES)					
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT BID PRICE	EXTENDED AMOUNT
5	1" DUAL WATER SERVICE - LONG	19	EA.		\$ -
6	1" DUAL WATER SERVICE - SHORT	26	EA.		\$ -
7	8" GATE VALVE & BOX, COMPLETE	19	EA.		\$ -
8	METER BOXES	107	EA.		\$ -
9	STANDARD F.H. COMPLETE W/ VALVE	4	EA.		\$ -
10	CAST IRON FITTINGS	2.12	TON		\$ -
12	DISINFECTION & HYDROSTATIC TESTING	1	EA.		\$ -
13	2" PERMANENT BLOWOFF	3	EA.		\$ -
14	2" TEMPORARY BLOWOFF	1	EA.		\$ -
15	24" C-909 PVC CASING	303	L.F.		\$ -
WATER SUBTOTAL					\$ -
<u>TOTAL BASE BID AMOUNT</u>					
TOTALBASE BID AMOUNT					\$ -
<u>ADD ALTERNATE ITEMS</u>					
1	JOINT TRENCH CONDUIT CROSSING (3-2.5" SCH 40 PVC - GVEC)	100	L.F.		\$ -
2	JOINT TRENCH CONDUIT CROSSING (5-2.5" SCH 40 PVC - GVEC)	100	L.F.		\$ -
3	CONDUIT CROSSING (1-4" SCH 40 PVC - CENTERPOINT)	100	L.F.		\$ -
4	JOINT TRENCH CONDUIT CROSSING (2-4" SCH 40 PVC & 1-4" SCH 80 PVC - AT&T, SPECTRUM, HOTWIRE)	100	L.F.		\$ -
TOTAL ADD ALTERNATE AMOUNT					\$ -

INITIALS: _____