PROJECT LOCATION MAP

SCALE: N.T.S.

PROJECT BENCHMARK

SITE TBM #52 SET MAG IN BOC N: 13767808.168 E: 2281821.220 ELEV: 578.61

SITE TBM #54

SET MAG IN BOC N: 13768766.896 E: 2281744.113 ELEV: 592.12

LEGAL DESCRIPTION

WITHIN A FENCED AREA.

SAID EASEMENT.

BEING A 10.38 ACRE TRACT OF LAND SITUATED IN THE JOHN D. CLEMENTS SURVEY, ABSTRACT NO. 11, GUADALUPE COUNTY, TEXAS. BEING A PORTION OF A 214.411 ACRE TRACT RECORDED IN DOCUMENT NO. 2018-99023476, OFFICIAL PUBLIC RECORDS, GUADALUPE COUNTY, TEXAS.

SPRINGS HILL WATER SUPPLY CORPORATION NOTES:

- 1. EXISTING WATER INFRASTRUCTURE IN THE VICINITY OF THE TRACT IS AVAILABLE TO SERVE THE PROPOSED DEVELOPMENT. IF THE DEVELOPMENT EXCEEDS THE CAPACITY OF THE EXISTING WATER INFRASTRUCTURE, THEN IT WILL BE THE DEVELOPER'S RESPONSIBILITY TO MAKE THE NECESSARY IMPROVEMENTS TO THE EXISTING WATER INFRASTRUCTURE TO PROVIDE SUFFICIENT CAPACITY. THE EXTENT OF THE NECESSARY WATER IMPROVEMENTS WILL BE OUTLINED IN A MEMORANDUM OF UNDERSTANDING OR NON-STANDARD SERVICE AGREEMENT PRIOR TO THE APPROVAL OF ANY FINAL PLAT.
- 2. SHWSC SHALL HAVE ACCESS TO METER LOCATIONS FROM THE FRONT YARD WITH THE LOCATION NOT BEING
- ANY EASEMENT DESIGNATED AS A SHWSC UTILITY EASEMENT SHALL REMAIN OPEN ACCESS AT ALL TIMES AND SHALL NOT BE WITHIN A FENCED AREA.
- ALL SHWSC EASEMENTS ARE FOR CONSTRUCTION, MAINTENANCE (INCLUDING BUT NOT LIMITED TO REMOVAL OF TREES AND OTHER OBSTRUCTIONS), READING OF METERS, AND REPAIR OF ANY SHWSC FACILITY LOCATED WITHIN
- WATER LINE IS TO BE CONSTRUCTED IN ACCORDANCE WITH SPRINGS HILL WATER SUPPLY CORPORATION STANDARD DRAWINGS AND SPECIFICATIONS.
- WATER MAIN SHALL HAVE A MINIMUM OF 30 INCHES OF COVER, OTHERWISE CONCRETE ENCASEMENT WILL BE
- CONTRACTOR WILL KEEP THE AREA ON TOP OF AND AROUND THE WATER METER BOX FREE OF ALL OBJECTS AND
- NO METER BOXES TO BE SET IN DRIVEWAYS. ANY METER BOX SET IN A DRIVEWAY WILL BE RELOCATED AT THE CONTRACTOR'S AND/OR DEVELOPER'S EXPENSE.
- NO VALVES, HYDRANTS, ETC. SHALL BE CONSTRUCTED WITHIN CURBS, SIDEWALKS, DRIVEWAYS, OR ROADWAYS. SHWSC WILL NOT BE RESPONSIBLE FOR ANY DAMAGES TO CONCRETE OR PAVED AREAS IF DEVELOPER DOES NOT
- 10. PERMANENT TIE-INS TO IN-SERVICE MAINS SHALL ONLY BE CONSTRUCTED FOLLOWING FLUSHING, DISINFECTION, TESTING, AND APPROVAL BY SHWSC. TEMPORARY CONNECTIONS FOR FILLING, FLUSHING, AND TESTING MUST BE EQUIPPED WITH SHWSC-PROVIDED BACKFLOW PREVENTION TO MAINTAIN CROSS-CONNECTION CONTROL

GENERAL NOTES:

- 1. ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE ENGINEER OF RECORD. IN ACCEPTING THESE PLANS, THE CITY OF SEGUIN MUST RELY UPON THE ADEQUACY OF THE WORK OF THE ENGINEER OF RECORD. 2. IF CONSTRUCTION HAS NOT COMMENCED WITHIN TWO-YEAR OF CITY APPROVAL FOR CONSTRUCTION, THAT APPROVAL IS NO LONGER VALID.
- 3. THE MOST CURRENT EDITIONS OF THE CITY OF SAN ANTONIO STANDARD SPECIFICATIONS AND THE TEXAS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS AND BRIDGES SHALL FOLLOWED FOR ALL CONSTRUCTION EXCEPT AS AMENDED BY THE CITY OF SEGUIN STANDARD
- 4. PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL CONTACT THE CITY SEGUIN TO SET A
- PRE-CONSTRUCTION MEETING. 5. CONTRACTOR TO CONTACT ASSIGNED CAPITAL PROJECTS CONSTRUCTION INSPECTOR OR CONSTRUCTION PROJECT
- MANAGER IN ACCORDANCE WITH THE PRE-CONSTRUCTION MEETING REQUIREMENTS. 6. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SEE THAT ALL TEMPORARY AND PERMANENT TRAFFIC CONTROL DEVICES ARE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE PLANS AND LATEST EDITION OF THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES. IF THE NEED ARISES, ADDITIONAL TEMPORARY TRAFFIC CONTROL DEVICES MAY BE ORDERED BY THE ENGINEERING REPRESENTATIVE AT THE CONTRACTOR'S EXPENSE.
- 7. DRAINAGE IMPROVEMENTS SUFFICIENT TO MITIGATE OFFSITE IMPACT OF CONSTRUCTION MUST BE COMPLETED AND IN PLACE PRIOR TO INCREASING RUNOFF FROM THE SITE.
- 8. NO PORTION OF THE SUBDIVISION IS LOCATED WITHIN ANY SPECIAL FLOOD HAZARD AREA (100 YR. FLOOD), AS DEFINED BY THE GUADALUPE COUNTY, TEXAS, FIRM PANEL NUMBER 48187C0260F EFFECTIVE DATE 11/02/2007, AS PREPARED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY.
- 9. THIS PROJECT IS NOT LOCATED WITHIN THE EDWARDS AQUIFER RECHARGE ZONE. 10. GAS UTILITIES ARE NOT INCLUDED IN THE CIVIL CONSTRUCTION PLANS. FINAL GAS UTILITY DESIGN SHALL BE APPROVED BY THE CITY FOR WORK WITHIN PUBLIC RIGHT-OF-WAY.

SEGUIN, TEXAS CIVIL SITE CONSTRUCTION PLANS

GREENSPOINT HEIGHTS

UNIT 3B


M/I HOMES OF SAN ANTONIO, LLC 4949 N. LOOP 1604 WEST SAN ANTONIO, TEXAS 78249

RF	QUIRED PERMITS	NUMBER
	CITY OF SEGUIN (STREETS & DRAINAGE)	#
2.	CITY OF SEGUIN (SANITARY SEWER)	#
3.	SPRINGS HILL WATER CO. (WATER)	#
4.	GUADALUPE VALLEY ELECTRIC CO-OP (ELEC)	#

Note: The Springs Hill Water Supply Corporation (SHWSC) signature above ompleteness and/or accuracy of these documents. Responsibility for the the Texas Licensed Professional Engineer whose seal and signature is affixed to

JANUARY 2024





PREPARED BY:



290 S. CASTELL AVE., STE. 100 P(830)625-8555*F(830)625-8556 TBPE FIRM F-10961 I TBPLS FIRM 1053600

NOTE TO CONTRACTOR:

BY THE ACT OF SUBMITTING A BID FOR THIS PROPOSED CONTRACT, THE BIDDER WARRANTS THAT THE BIDDER, AND ALL SUBCONTRACTORS AND MATERIAL SUPPLIERS HE INTENDS TO USE HAVE CAREFULLY AND THOROUGHLY REVIEWED THE DRAWINGS, SPECIFICATIONS AND ALL OTHER CONTRACT DOCUMENTS AND HAVE FOUND THEM COMPLETE AND FREE FROM ANY AMBIGUITIES AND SUFFICIENT FOR THE PURPOSE INTENDED. THE BIDDER FURTHER WARRANTS THAT TO THE BEST OF HIS OR HIS SUBCONTRACTORS' AND MATERIAL SUPPLIERS' KNOWLEDGE, ALL MATERIALS AND PRODUCTS SPECIFIED OR INDICATED HEREIN ARE ACCEPTABLE FOR ALL APPLICABLE CODES AND AUTHORITIES.

Sheet List Table

EROSION AND SEDIMENT CONTROL PLAN

CAVERN GROVE PLAN & PROFILE

STEEL FORGE PLAN & PROFILE

LIMESTONE RDG PLAN & PROFILE

WHISKEY PASS PLAN & PROFILE

CHANNEL 3B PLAN AND PROFILE

STORM LINE A PLAN AND PROFILE

STORM LINE B PLAN AND PROFILE

STREET SIGNAGE PLAN

STREET DETAILS (1 OF 2)

STREET DETAILS (2 OF 2)

STORM DETAILS (1 OF 2)

STORM DETAILS (2 OF 2)

WATER DETAILS (1 OF 2)

WATER DETAILS (2 OF 2)

OVERALL WASTEWATER PLAN

EXISTING WASTEWATER LINE D - PLAN AND PROFILE

|WASTEWATER LINE B — PLAN AND PROFILE

OVERALL WATER PLAN

WASTEWATER DETAILS

Sheet Title

COVER SHEET

GENERAL NOTES

PLAT (1 OF 2)

PLAT (2 OF 2)

EROSION DETAILS

GRADING PLAN GRADING DETAILS

Sheet Number

C3.02

C3.03

C3.05

C3.06

C4.01

C4.02

C4.04

C4.05

C5.02

C5.03

C6.01

C6.02

C6.03

THE LOCATION OF ALL EXISTING UTILITIES SHOWN ON THESE PLANS HAS BEEN BASED UPON RECORD INFORMATION ONLY AND MAY NOT MATCH LOCATIONS AND/OR DEPTHS AS CONSTRUCTED. THE CONTRACTOR SHALL CONTACT EACH OF THE INDIVIDUAL UTILITIES FOR ASSISTANCE IN DETERMINING EXISTING UTILITY LOCATIONS AND DEPTHS PRIOR TO BEGINNING ANY CONSTRUCTION. CONTRACTOR SHALL FIELD VERIFY LOCATIONS OF ALL UTILITY CROSSINGS PRIOR TO BEGINNING ANY CONSTRUCTION.

ANY QUANTITIES PROVIDE BY HMT OR OWNER ON THE PLANS, OPINION OF PROBABLE COST, BID SUMMARIES, ETC. ARE FOR CURSORY USE ONLY. CONTRACTOR IS RESPONSIBLE FOR BIDDING SIGNED AND SEALED CONSTRUCTION PLANS. IF A DISCREPANCY EXIST, CONTRACTOR SHALL CONTACT ENGINEER IMMEDIATELY.

CONTRACTOR IS RESPONSIBLE FOR CONFIRMING THE LOCATION AND ELEVATION OF ALL DOWNSTREAM CONNECTION POINTS PRIOR TO CONSTRUCTION. IF A DISCREPANCY EXIST, CONTRACTOR SHALL CONTACT ENGINEER IMMEDIATELY.

CONTRACTOR SHALL INSTALL ALL GRAVITY SEWER, GRAVITY STORM SEWER. CURBS AND PAVEMENT FROM THE MOST DOWNSTREAM POINT OF CONNECTION. IF IMPROVEMENTS ARE CONSTRUCTED FROM UPSTREAM TO DOWNSTREAM, THEN THE CONTRACTOR WILL TAKE FULL RISK AND LIABILITY OF ANY ISSUES THAT MIGHT ARISE FROM FLOWLINE ELEVATION DISCREPANCIES, UTILITY CONFLICTS, ETC.

CONTRACTOR IS RESPONSIBLE FOR THE STOCKPILING OF ANY EXCESS DIRT. ALL BIDS FROM CONTRACTOR SHOULD ACCOUNT FOR THE REMOVAL AND PLACEMENT OF ALL EARTHWORK TO INCLUDE STOCKPILING, EXPORT, IMPORT, ETC. IF A LOCATION OF PLACEMENT OF EXCESS DIRT IS NOT SHOWN ON THE PLANS, THEN CONTRACTOR SHALL CONTACT ENGINEER IMMEDIATELY TO DETERMINE THE MOST SUITABLE STOCKPILE LOCATION.

GENERAL NOTES

ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL COMPLY

A. CURRENT CITY OF SEGUIN CONSTRUCTION SPECIFICATIONS AND STANDARDS AS OF THE DATE OF THIS CONTRACT

B. THE MOST CURRENT EDITION OF TEXAS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS, AND BRIDGES".

ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE MOST CURRENT TEXAS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS, AND BRIDGES." ALONG WITH CURRENT CITY OF SEGUIN AND GUADALUPE COUNTY SPECIFICATIONS. ANY DISCREPANCIES BETWEEN SPECIFICATIONS SHALL BE RESOLVED BY THE ENGINEER PRIOR TO PROCEEDING WITH CONSTRUCTION.

CONTRACTOR SHALL PROCURE ALL PERMITS AND LICENSES, PAY ALL CHARGES, FEES, AND TAXES AREA AND GIVE ALL NOTICES NECESSARY AND INCIDENTAL TO THE DUE AND LAWFUL PROSECUTION OF THE

ANY EXISTING OFF-SITE IMPROVEMENTS THAT ARE DAMAGED OR UNDERCUT BY THE CONTRACTOR'S OPERATIONS SHALL BE REPAIRED OR REPLACED AS DIRECTED BY THE ENGINEER AND APPROVED BY THE OWNER OF THE EXISTING IMPROVEMENT AT THE CONTRACTOR'S EXPENSE. (NO SEPARATE PAY ITEM)

WORK COMPLETED BY THE CONTRACTOR WHICH HAS NOT RECEIVED A WORK ORDER OR CONSENT OF THE OWNER OR ENGINEER WILL BE SUBJECT TO REMOVAL AND REPLACEMENT BY AND AT THE EXPENSE OF

CONTRACTOR IS RESPONSIBLE FOR REMOVAL OF ALL WASTE MATERIALS UPON PROJECT COMPLETION. THE CONTRACTOR SHALL NOT PLACE ANY WASTE MATERIAL IN THE 100YR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN DEVELOPMENT PERMIT.

BARRICADES AND WARNING SIGNS SHALL CONFORM TO THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" AND SHALL BE LOCATED TO PROVIDE MAXIMUM PROTECTION TO THE PUBLIC AS WELL AS CONSTRUCTION PERSONNEL AND EQUIPMENT WHILE PROVIDING CONTINUOUS TRAFFIC FLOW AT ALL TIMES DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ALL DEVICES DURING CONSTRUCTION.

CONTRACTOR IS REQUIRED TO VERIFY PROJECT ELEVATIONS. THE TERM "MATCH EXISTING" SHALL BE UNDERSTOOD TO SIGNIFY BOTH HORIZONTAL AND VERTICAL ALIGNMENT.

WHEN MATCHING EXISTING PAVEMENTS, CURBS, DRIVES, AND WALKS, THEY SHALL BE SAW CUT FULL DEPTH AND REMOVED TO ALLOW FOR PROPOSED CONSTRUCTION. IF ANY EXISTING JOINT IS ENCOUNTERED, PRECAUTION SHALL BE TAKEN DURING REMOVAL OF CONCRETE SO AS NOT TO DAMAGE EXISTING DOWELS. ALL EXISTING DOWELS SHALL BE EXPOSED AND CLEANED.

ITEM OF WORK DESIGNATED "BY OTHERS" SHALL NOT BE CONSIDERED PART OF THIS CONTRACT.

ALL "COMPACTED SUBGRADE" SHALL CONSIST OF NATIVE MATERIAL SCARIFIED TO A MINIMUM DEPTH OF SIX INCHES AND COMPACTED TO 95% DENSITY ACCORDING TO DENSITY TEST METHOD TEX-115E OR ACCORDING TO ASTM D-698 AND TESTED BY ASTM D-2922.

ALL "FLEXIBLE BASE" SHALL BE TYPE "A", GRADE 4, ACCORDING TO TXDOT ITEM 247, COMPACTED TO 95% MODIFIED DENSITY AT A MOISTURE CONTENT BETWEEN -2 AND +3 OF OPTIMUM PERCENT MOISTURE ACCORDING TO ASTM D-1557 (MODIFIED PROCTOR) AND TESTED BY ASTM D-2922.

ASPHALT PAVEMENT SHALL BE THE TYPE SPECIFIED ON THE PLANS AND ACCORDING TO TXDOT ITEM 340 "HOT MIX ASPHALT CONCRETE PAVEMENT".

PRIME COAT USING MC-30 AT A RATE OF 0.2 GALLONS PER SQUARE YARD SHALL BE PLACED OVER PREPARED BASE AT LEAST ONE DAY PRIOR TO LAYING ASPHALTIC CONCRETE PAVEMENT. ANY NECESSARY TACK COAT SHALL BE MC-30 AT 0.05 GALLONS PER SQUARE YARD. IT IS REQUIRED THAT BOTH THE PRIME COAT AND THE TACK COAT BE APPLIED AT THE TEMPERATURE SPECIFIED UNDER

CONCRETE SHALL BE CLASS "A" ACCORDING TO TXDOT ITEM 421 UNLESS OTHERWISE ON PLANS.

REINFORCING STEEL SHALL BE FROM NEW BILLET AND SHALL CONFORM TO TXDOT ITEM 440. ALL DIMENSIONS RELATING TO REINFORCING STEEL ARE TO CENTER OF BARS EXCEPT WHEN REFERRING TO

ALL SAWED JOINTS SHALL BE SAWED WITHIN 24 HOURS OF POURING,

ABSOLUTELY NO WELDING OF REINFORCING BARS OR TORCHING TO BEND REINFORCING BARS SHALL BE ALLOWED WITHOUT THE SPECIFIC APPROVAL OF THE ENGINEER.

ORDINARY COMPACTION CONTROL IS REQUIRED ON THIS PROJECT.

ALL ROLLING FOR COMPACTION OF ASPHALTIC CONCRETE PAVEMENT SHALL BE COMPLETED BEFORE THE MIXTURE TEMPERATURE DROPS BELOW 175 DEG. (F).

ALL FILL MATERIAL SHALL BE SUBJECT TO THE ENGINEER'S APPROVAL.

CONTRACTOR AGREES TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND SHALL NOT BE LIMITED TO THE NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE OWNERS AND THE ENGINEER AND HIS EMPLOYEES, PARTNERS, OFFICES, DIRECTORS, OR CONSULTANTS, HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF THE WORK ON THIS PROJECT, EXCEPTING FROM LIABILITY ARISING FROM SOLE NEGLIGENCE OF THE OWNER OR ENGINEER, ENGINEER'S DIRECTORS, OFFICERS, EMPLOYEES, OR CONSULTANTS.

ALL CMP (CORRUGATED METAL PIPE) USED ON THIS PROJECT SHALL HAVE A MANNING'S "N" VALUE OF 0.024., UNLESS OTHERWISE SHOWN ON PLANS.

CONTRACTOR WILL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTING PER CURRENT CITY OF SEGUIN REQUIREMENTS. ALL TEST RESULTS SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL. ENGINEER AND OWNER RESERVE THE RIGHT TO HAVE THE CONTRACTOR REMOVE AND REPLACE ANY MATERIAL THAT WAS NOT TESTED OR FAILED TESTING. ALL COST ASSOCIATED WITH THE REMOVAL, REPLACEMENT AND TESTING SHALL BE PAID BY THE CONTRACTOR.

ALL PVC SLEEVES SHALL BE INSTALLED 3 FEET BELOW FINISHED GRADE AND ENDS SHALL BE MARKED SO THAT LOCATIONS OF SLEEVES CAN BE EASILY IDENTIFIED.

PRE-CONSTRUCTION CONFERENCE IS REQUIRED, ENGINEER WILL ARRANGE SUCH CONFERENCE IN COORDINATION WITH CITY OF SEGUIN PROJECT MANAGER AND INSPECTOR. NO CONSTRUCTION MAY BEGIN PRIOR TO THE PRE-CONSTRUCTION CONFERENCE.

CONTRACTOR SHALL COORDINATE WITH DRY UTILITY INSTALLERS AND SHARED TRENCHING SHALL BE UTILIZED. CUTTING THE STREETS AFTER COMPLETION BY DRY UTILITIES SHALL NOT BE ACCEPTABLE.

WHEN ALL IMPROVEMENTS ARE FOUND TO BE CONSTRUCTED AND COMPLETED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS AND WITH THE CITY'S STANDARDS, AND UPON RECEIPT OF ONE SET OF "RECORD DRAWINGS" PLANS, AND A DIGITAL COPY OF ALL PLANS (AUTOCAD 2000 MINIMUM) THE CITY ENGINEER SHALL ACCEPT SUCH IMPROVEMENTS FOR THE CITY OF SEGUIN, SUBJECT TO THE GUARANTY OF MATERIAL AND WORKMANSHIP PROVISIONS IN THIS SECTION.

EROSION / SEDIMENTATION CONTROL

AT A MINIMUM, THESE CONTROLS SHALL CONSIST OF ROCK BERMS AND/OR SILT FENCES CONSTRUCTED PARALLEL TO AND DOWN GRADIENT FROM THE TRENCHES. THE ROCK BERM OR SILT FENCES SHALL BE INSTALLED IN A MANNER SUCH THAT ANY RAINFALL RUNOFF SHALL BE FILTERED. HAY BALES SHALL NOT BE USED FOR TEMPORARY EROSION AND SEDIMENTATION CONTROLS.

ALL TEMPORARY EROSION AND SEDIMENTATION CONTROLS MUST BE INSTALLED PRIOR TO CONSTRUCTION AND SHALL BE MAINTAINED DURING CONSTRUCTION BY THE CONTRACTOR. THE CONTRACTOR SHALL REMOVE THE CONTROLS WHEN VEGETATION IS ESTABLISHED AND THE CONSTRUCTION AREA IS STABILIZED {31 TAC 313.5 (C)(12)}. ADDITIONAL PROTECTION MAY BE REQUIRED IF EXCESSIVE SOLIDS ARE BEING DISCHARGED FROM THE SITE.

ALL TEMPORARY EROSION AND SEDIMENTATION CONTROLS SHALL BE REMOVED BY THE CONTRACTOR AT FINAL ACCEPTANCE OF THE PROJECT BY THE OWNER/ENGINEER.

PLACEMENT OF TEMPORARY EROSION AND SEDIMENTATION CONTROLS SHALL BE IN ACCORDANCE WITH THE CONSTRUCTION PLANS. ACTUAL LOCATIONS MAY VARY SLIGHTLY FROM THE PLANS, BUT WILL BE VERIFIED BY THE ENGINEER/INSPECTOR IN THE FIELD PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL INSPECT THE CONTROLS AT WEEKLY INTERVALS AND AFTER EVERY SIGNIFICANT RAINFALL TO INSURE DISTURBANCE OF THE STRUCTURES HAS NOT OCCURRED. SEDIMENT DEPOSITED AFTER A RAINFALL SHALL BE REMOVED FROM THE SITE OR PLACED IN AN ENGINEER APPROVED DESIGNATED DISPOSAL AREA.

CONTRACTOR SHALL BE RESPONSIBLE TO INSURE THAT NO EROSION CONTROL MEASURES BLOCK THE DRAINAGE SYSTEM FROM WORKING AS DESIGNED.

UTILITIES

TEXAS ONE CALL SYSTEM

LOCATION AND DEPTH OF EXISTING UTILITIES SHOWN HERE ARE APPROXIMATE ONLY. ACTUAL LOCATIONS AND DEPTHS MUST BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTION OF ALL EXISTING UTILITIES ENCOUNTERED DURING CONSTRUCTION, INCLUDING THOSE NOT SHOWN ON THE DRAWINGS

ANY EXISTING UTILITIES, ON OR OFF THE SITE, THAT ARE DAMAGED OR UNDERCUT BY THE CONTRACTOR'S OPERATIONS SHALL BE REPAIRED OR REPLACED AS DIRECTED BY THE ENGINEER AND APPROVED BY THE RESPECTIVE UTILITY COMPANY AT THE CONTRACTOR'S EXPENSE.

CONTRACTOR SHALL NOTIFY APPROPRIATE UTILITY COMPANIES AND GOVERNMENTAL AGENCIES AT LEAST 48 HOURS PRIOR TO CONSTRUCTION AT:

THE CONTRACTOR SHALL NOTIFY THE FOLLOWING UTILITY COMPANIES 48 HOURS PRIOR TO EXCAVATION

SPRINGS HILL WATER SUPPLY CORPORATION (WATER) (830) 379-7683 CITY OF SEGUIN (SEWER) (830) 401-2222(830) 857-1200 GUADALUPE VALLEY ELECTRIC COOPERATIVE (ELECTRIC) TIME WARNER CABLE (830) 625-3408 (830) 303-1333

DUE TO FEDERAL REGULATIONS TITLE 49, PART 192(8), GAS COMPANIES MUST MAINTAIN ACCESS TO GAS VALVES AT ALL TIMES. THE CONTRACTOR MUST PROTECT THE WORK AROUND ANY GAS VALVES THAT ARE IN THE PROJECT AREA.

(800) 245 - 4545

CONTRACTOR SHALL REFERENCE GVEC UTILITIES PLANS FOR FINAL ELECTRICAL LINE DESIGNS AND LAYOUT.

WASTEWATER NOTES REVISION DATE: 3/31/11

1. THE CONTRACTOR SHALL MAINTAIN SERVICE TO EXISTING WASTEWATER SYSTEM AT ALL TIMES DURING CONSTRUCTION. 2. A MINIMUM OF 8" WASTEWATER PIPE AND FITTING (P.V.C. SDR-26, ASTM, D-3034, D-3212, F-477) ARE

REQUIRED ON NEW INSTALLATION. 3. ALL RESIDENTIAL WASTEWATER SERVICE LATERALS SHALL BE EXTENDED TO THE PROPERTY LINE AND A CLEANOUT SHALL BE INSTALLED AT THE PROPERTY LINE. SERVICES TO LOTS WILL EXTEND FOUR (4) FEET

PAST THE UNDERGROUND ELECTRIC CONDUIT IF ELECTRIC IS INSTALLED IN THE FRONT EASEMENT. 4. PIPE BEDDING OF WASTEWATER LINES SHALL BE MANUFACTURED No. 67 CRUSHED STONE. 5. SECONDARY BACKFILL OF WASTEWATER LINES SHALL GENERALLY CONSIST OF MATERIALS REMOVED FROM

THE TRENCH AND SHALL BE FREE FROM BRUSH, DEBRIS AND TRASH, NO ROCKS OR STONES HAVING ANY DIMENSION LARGER THAN 6 INCHES AT THE LARGEST DIMENSION. 6. ALL WASTEWATER PIPES SHALL HAVE COMPRESSION OR MECHANICAL JOINTS AS PER 30 TAC §217.53 (C)

7. FOR WASTEWATER LINES LESS THAN 24" IN DIAMETER, SELECT INITIAL BACKFILL MATERIAL SHALL BE PLACED IN TWO LIFTS.

7.1. THE FIRST LIFT SHALL BE SPREAD UNIFORMLY AND SIMULTANEOUSLY ON EACH SIDE AND UNDER THE SHOULDERS OF THE PIPE TO THE MID POINT OR SPRING LINE OF THE PIPE. 7.2. 8.2. THE SECOND LIFT SHALL BE PLACED TO A DEPTH AS SHOWN ON THE PIPE BACKFILL DETAIL. FOR PIPES LARGER THAN 24", 12" MAXIMUM LIFTS SHALL BE USED.

8. ALL MANHOLES MUST BE WATER TIGHT, EITHER MONOLITHIC, CAST-IN-PLACE CONRETE STRUCTURES OR PREFABRICATED MANHOLES SPECIFICALLY APPROVED BY CITY OF SEGUIN. THE MANHOLES SHALL HAVE WATER-TIGHT RINGS AND COVERS. WHEREEVER THEY ARE WITHIN THE 100 YEAR FLOODPLAIN, THE MANHOLE COVERS SHALL BE BOLTED. EVERY THIRD MANHOLE IN SEQUENCE SHALL HAVE AN ALTERNATE MEANS OF VENTING. 30 TAC §213.5 (C)(3)(A) AND 30 TAC §217.55 (O)

9. ALL MANHOLES SHALL BE CONSTRUCTED SO THAT THE TOP OF THE RING IS TWO INCHES (2") ABOVE SURROUNDING GROUND EXCEPT WHEN LOCATED IN PAVED AREA. IN PAVED ARES, THE MANHOLE RING SHALL BE FLUSH WITH PAVEMENT.

10. ALL NEW MANHOLES, UNLESS APPROVED BY CITY ENGINEERING, ARE TO HAVE COVERS WITH 32" OPENINGS. 11. WASTEWATER PIPE CONNECTIONS TO PRE-CAST MANHOLES WILL BE COMPRESSION JOINTS OR MECHANICAL "BOOT TYPE" JOINT AS APPROVED BY CITY OF SEGUIN

12. WASTEWATER LINES SHALL BE TESTED FROM MANHOLE TO MANHOLE. 13. IN AREAS WHERE A NEW WASTEWATER MANHOLE IS TO BE CONSTRUCTED OVER AN EXISTING WASTEWATER SYSTEM, IT SHALL BE THE CONTACTOR'S RESPONSIBILITY TO TEST THE EXISTING MANHOLES BEFORE CONSTRUCTION. AFTER THE PROPOSED MANHOLE(S) HAS BEEN BUILT. THE CONTRACTOR SHALL RE-TEST THE EXISTING SYSTEM TO THE SATISFACTION OF THE CONSTRUCTION INSPECTOR. (NO SEPARATE PAY

14. WHERE THE MINIMUM 9 FOOT SEPARATION DISTANCE BETWEEN WASTEWATER LINES AND WATER LINES / MAINS CANNOT BE MAINTAINED, THE INSTALLATION OF WASTEWATER LINES SHALL BE IN STRICT ACCORDANCE WITH TCEQ. THE WASTEWATER LINE SHALL BE CONSTRUCTED OF CAST IRON, DUCTILE OR PVC MEETING THE ASTM SPECIFICATION FOR BOTH PIPES AND JOINTS OF 150 PSI AND SHALL BE IN ACCORDANCE WITH 30 TAC \$217.53 (D) (3) (A) (I)

15. NO TESTING WILL BE PERFORMED PRIÒR TO 30 DÀYS FROM COMPLETE INSTALLATION OF THE WASTEWATER LINES. THE FOLLOWING SEQUENCE WILL BE STRICTLY ADHERED TO: 15.1. PULL MANDREL

15.2. PERFORM AIR TEST

ITEM TO WHICH IT RELATES.

15.3. CLEANING OF ANY DEBRIS 15.4. FLUSHING OF SYSTEM

15.5. TV INSPECTION (WITHIN 72 HOURS OF FLUSHING)

16. A MINIMUM OF 5 FEET OF COVER IS TO BE MAINTAINED OVER THE WASTEWATER MAIN AND LATERALS AT SUBGRADE

17. WASTEWATER MAIN CONNECTIONS MADE DIRECTLY TO EXISTING MANHOLES WILL REQUIRE SUCCESSFUL

TESTING OF THE MANHOLE IN ACCORDANCE WITH CITY OF SEGUIN CONSTRUCTION POLICY MANUAL. 18. TCEQ AND EPA REQUIRE EROSION AND SEDIMENTATION CONTROL FOR CONSTRUCTION OF WASTEWATER COLLECTION SYSTEMS. DEVELOPER OR AUTHORIZED REPRESENTATIVE SHALL PROVIDE EROSION AND SEDIMENTATION CONTROL AS NOTES ON THE PROJECT'S PLAN AND PROFILE SHEETS. ALL TEMPORARY EROSION AND SEDIMENTATION CONTROLS SHALL BE REMOVED BY THE CONTRACTOR AT FINAL ACCEPTANCE OF THE PROJECT BY CITY OF SEGUIN.

WATER NOTES REVISED 03/22

SHWSC GENERAL NOTES 1. ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THE PROJECT SHALL BE APPROVED BY SHWSC AND COMPLY WITH ALL APPLICABLE STANDARDS AND REGULATIONS.

2. CONTRACTOR SHALL NOT PROCEED WITH ANY WORK UNTIL WRITTEN APPROVAL IS OBTAINED FROM SHWSC. WORK COMPLETED BY THE CONTRACTOR, WHICH HAS NOT RECEIVED AN APPROVAL WILL BE SUBJECT TO REMOVAL AND REPLACEMENT BY AND AT THE EXPENSE OF THE CONTRACTOR AT THE PREROGATIVE OF SHWSC.

3. THE DEVELOPER DEDICATES THE WATER MAINS UPON COMPLETION BY THE DEVELOPER AND ACCEPTANCE BY SHWSC. SHWSC WILL OWN AND MAINTAIN SAID WATER MAINS WHICH ARE LOCATED WITHIN SAID SUBDIVISION (AS APPLICABLE).

4. CONTRACTOR AGREES TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY. THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS. THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD THE OWNERS AND THE ENGINEER AND HIS EMPLOYEES, PARTNERS OFFICERS, DIRECTORS, OR CONSULTANTS HARMLESS FROM ANY AND ALL LIABILITY. REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF THE WORK ON THIS PROJECT, EXCEPTING FROM LIABILITY ARISING FROM SOLE NEGLIGENCE OF THE OWNER OR ENGINEER, ENGINEER'S DIRECTORS, OFFICERS, EMPLOYEES, OR CONSULTANTS.

5. CONTRACTOR AND / OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION

6. CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING TO ITS ORIGINAL OR BETTER CONDITION, ANY DAMAGES DONE TO EXISTING FENCES, CURBS, STREETS, DRIVEWAYS, LANDSCAPING AND STRUCTURES, AND EXISTING UTILITIES (NOT ADJUSTED ON PLANS). COST OF RESTORATIONS, IF ANY, SHALL BE THE CONTRACTOR'S ENTIRE EXPENSE.

7. THE CONTRACTOR SHALL AVOID CUTTING ROOTS LARGER THAN ONE INCH IN DIAMETER WHEN EXCAVATING NEAR EXISTING TREES. EXCAVATION IN VICINITY OF TREES SHALL PROCEED WITH CAUTION. 8. CONTRACTOR SHALL PROCURE ALL PERMITS AND LICENSES, PAY ALL CHARGES, FEES AND TAXES AND GIVE

ALL NOTICES NECESSARY AND INCIDENTAL TO THE DUE AND LAWFUL PROSECUTION OF THE WORK. 9. NO EXTRA PAYMENT SHALL BE ALLOWED FOR WORK CALLED FOR ON THE PLANS BUT NOT INCLUDED ON THE BID SCHEDULE. THIS INCIDENTAL WORK WILL BE REQUIRED AND SHALL BE INCLUDED UNDER THE PAY

10. CONTRACTOR IS RESPONSIBLE FOR REMOVAL OF ALL WASTE MATERIALS UPON PROJECT COMPLETION. THE CONTRACTOR SHALL NOT PERMANENTLY PLACE ANY WASTE MATERIALS IN THE 100-YEAR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN DEVELOPMENT PERMIT.

11. THE CONTRACTOR SHALL NOT PLACE ANY MATERIALS ON THE RECHARGE ZONE OF THE EDWARDS AQUIFER WITHOUT AN APPROVED WATER POLLUTION ABATEMENT PLAN FROM THE TCEQ 31 TAC 313.4 AND 31 TAC 12. BARRICADES AND WARNING SIGNS SHALL CONFORM TO THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL

DEVICES" AND SHALL BE LOCATED TO PROVIDE MAXIMUM PROTECTION TO THE PUBLIC AS WELL AS CONSTRUCTION PERSONNEL AND EQUIPMENT WHILE ALWAYS PROVIDING CONTINUOUS TRAFFIC FLOW DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ALL DEVICES DURING CONSTRUCTION. 13. CONTRACTOR IS REQUIRED TO VERIFY PROJECT ELEVATIONS. THE TERM "MATCH EXISTING" SHALL BE

UNDERSTOOD TO SIGNIFY BOTH HORIZONTAL AND VERTICAL ALIGNMENT.

14. THE LOCATION OF UTILITIES, EITHER UNDERGROUND OR OVERHEAD, SHOWN WITHIN THE RIGHT OF WAY ARE APPROXIMATE AND SHALL BE VERIFIED BY THE CONTRACTOR BEFORE BEGINNING CONSTRUCTION OPERATIONS. 15. OSHA REGULATIONS PROHIBIT OPERATIONS THAT WILL BRING PERSONS OR EQUIPMENT WITHIN 10 FEET OF AN ENERGIZED LINE. WHERE WORKMEN AND/OR EQUIPMENT HAVE TO WORK CLOSE TO AN ENERGIZED ELECTRICAL LINE, THE CONTRACTOR SHALL NOTIFY THE ELECTRICAL POWER COMPANY INVOLVED AND MAKE WHATEVER ADJUSTMENTS NECESSARY TO ENSURE THE SAFETY OF THOSE WORKMEN

16. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO LOCATE UTILITY SERVICE LINES AS REQUIRED FOR CONSTRUCTION. UTILITY COMPANIES ARE ALSO PREVIOUSLY MENTIONED IN "UTILITY COMPANY NOTIFICATION". 17. DUE TO FEDERAL REGULATIONS TITLE 49, PART 192 (8), GAS COMPANIES MUST ALWAYS MAINTAIN ACCESS TO GAS VALVES. THE CONTRACTOR MUST PROTECT AND WORK AROUND ANY GAS VALVES THAT ARE IN THE

18. THE CONTRACTOR IS FULLY RESPONSIBLE FOR THE TRAFFIC CONTROL AND WILL BE RESPONSIBLE FOR FURNISHING ALL TRAFFIC CONTROL DEVICES, AND FLAGGERS. THE CONSTRUCTION METHODS SHALL BE CONDUCTED TO PROVIDE THE LEAST POSSIBLE INTERFERENCE TO TRAFFIC TO ALWAYS PERMIT THE CONTINUOUS CURB CUT DUE TO CONSTRUCTION OF NEW RIGHT-OF-WAY CONSTRUCTION MOVEMENT OF THE TRAFFIC IN ONE DIRECTION. THE CONTRACTOR SHALL CLEAN UP AND REMOVE FROM THE WORK AREA ANY LOOSE MATERIAL RESULTING FROM CONTRACT OPERATIONS AT THE END OF EACH WORKDAY.

19. PRIOR TO ORDERING MATERIALS TO BE USED IN CONSTRUCTION, CONTRACTOR SHALL PROVIDE SHWSC WITH FOUR (4) COPIES OF THE SOURCE, TYPE, GRADATION, MATERIAL SPECIFICATION DATA AND / OR SHOP DRAWINGS, AS APPLICABLE, TO SATISFY THE REQUIREMENTS OF THE FOLLOWING ITEMS AND ALL MATERIAL ITEMS REFERRED TO IN THESE LISTED ITEMS: A. WATER MAINS AND SERVICES

20. NO METER BOXES, VALVES, TO BE SET IN DRIVEWAYS OR SIDEWALKS. ANY METER BOXES SET IN THESE AREAS WILL BE RELOCATED AT CONTRACTOR'S AND/OR DEVELOPER'S EXPENSE.

21. WHERE THE MINIMUM 9-FOOT SEPARATION DISTANCE BETWEEN SEWER LINES AND WATER LINES / MAINS CANNOT BE MAINTAINED, THE INSTALLATION OF WATER LINES SHALL BE IN STRICT ACCORDANCE WITH TCEQ.

22. CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF THE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA NO VALVES, HYDRANTS, ETC. SHALL BE CONSTRUCTED WITHIN CURBS, SIDEWALKS, OR DRIVEWAYS. STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

23. UTILITY TRENCH COMPACTION WITH STREET RIGHT-OF-WAY.

A. ALL UTILITY TRENCH COMPACTION TEST WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER.

B. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. C. EACH LAYER OF MATERIAL SHALL BE COMPACTED AS SPECIFIED AND TESTED FOR DENSITY AND MOISTURE IN MARKINGS AT FINAL APPLICATION.

ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. D. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY SHWSC.

E. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE SHWSC INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

CONSTRUCTION NOTES

IT SHALL BE THE RESPONSIBILITY OF THE DEVELOPER, CONTRACTOR, SUBCONTRACTORS, BUILDERS, GEO-TECHNICAL ENGINEER, AND PROJECT ENGINEER TO IMMEDIATELY NOTIFY THE OFFICE OF THE CITY ENGINEER AND PROJECT ENGINEER IF THE PRESENCE OF GROUNDWATER WITHIN THE SITE IS EVIDENT. UPON NOTIFICATION THE PROJECT ENGINEER SHALL RESPOND WITH PLAN REVISIONS FOR THE MITIGATION OF THE GROUNDWATER ISSUE. THE CITY ENGINEER SHALL RESPOND WITHIN TWO (2) BUSINESS DAYS UPON RECEIPT OF THE MITIGATION PLAN. ALL CONSTRUCTION ACTIVITY, IMPACTED BY THE DISCOVERY OF GROUNDWATER, SHALL BE SUSPENDED UNTIL THE CITY ENGINEER GRANTS A WRITTEN APPROVAL OF THE GROUNDWATER MITIGATION

DRAINAGE IMPROVEMENTS SUFFICIENT TO MITIGATE THE IMPACT OF CONSTRUCTION SHALL BE INSTALLED PRIOR TO INCREASING RUNOFF FROM THE SITE.

FINISHED FLOOR ELEVATIONS

SURROUNDING GROUND, WHICH SHALL BE SLOPED IN A FASHION SO AS TO DIRECT STORMWATER AWAY FROM THE STRUCTURE. PROPERTIES ADJACENT TO STORMWATER CONVEYANCE STRUCTURES MUST HAVE FLOOR SLAB ELEVATION OR BOTTOM OF FLOOR JOISTS A MINIMUM OF ONE FOOT ABOVE THE 100-YEAR WATER FLOW ELEVATION IN THE STRUCTURE. DRIVEWAYS SERVING HOUSES ON THE DOWNHILL SIDE OF THE STREET SHALL HAVE A PROPERLY SIZED CROSS SWALE PREVENTING RUNOFF FROM ENTERING THE GARAGE.

THE ELEVATION OF THE LOWEST FLOOR SHALL BE AT LEAST 10 INCHES ABOVE THE FINISHED GRADE OF THE

ALL ROADWAY COMPACTION TESTS SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FLEXIBLE BASE OR FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED SIX-INCHES (6") COMPACTED. EACH LAYER OF MATERIAL, INCLUSIVE OF SUBGRADE, SHALL BE COMPACTED AS SPECIFIED AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL

BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER WILL PROVIDE THE CITY OF SEGUIN STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FLEXIBLE BASE, AND FILL MATERIAL, AND SUBGRADE, HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

<u>ITEM 340</u>

ASPHALTIC CONCRETE PAVEMENT SHALL BE TYPE "D" HOT MIX ASPHALT AS DEFINED IN TXDOT'S STANDARD SPECIFICATIONS FOR TXDOT STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREET AND BRIDGES, 2004 OR LATEST EDITION.

THE CITY OF SEGUIN WILL NOT ACCEPT THE USE OF RECYCLED ASPHALT PAVEMENT (RAP) OR RECYCLED ASPHALT SHINGLES (RAS) IN ASPHALT MIXTURES FOR NEW ROADWAYS. ANY DEBRIS INCLUSIONS WITHIN NEW ASPHALT PAVEMENTS WILL RESULT IN ASPHALT REMOVAL AND REPLACEMENT FROM CURB TO CURB FOR LIMITS TO BE DETERMINED BY THE CITY OF SEGUIN.

THE ASPHALTIC CONCRETE SURFACE COURSE SHALL BE PLANT MIXED, HOT LAID TYPE "D" MEETING THE SPECIFICATION REQUIREMENTS OF 2004 TXDOT ITEM 340. THE MIX SHALL BE DESIGNED FOR A STABILITY OF AT LEAST 35 AND SHALL BE COMPACTED TO BETWEEN 91 AND 95 PERCENT OF THE MAXIMUM THEORETICAL DENSITY AS DETERMINED BY TXDOT TEST METHOD TEX-227-F. THE ASPHALT CEMENT CONTENT BY PERCENT OF TOTAL MIXTURE WEIGHT SHALL FALL WITHIN A TOLERANCE OF +0.5 PERCENT FROM A SPECIFIC MIX DESIGN.

UTILITY TRENCH COMPACTION (ADDED TO THE CONSTRUCTION PLANS ON ALL UTILITY PLAN SHEETS) ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEOTECHNICAL ENGINEER AND APPROVED BY THE CITY OFSEGUIN STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SEGUIN STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE

(INDICATE THE 2 OPTIONS ON THE CONSTRUCTION PLANS).

1. SAWCUT EXISTING STREET AND MATCH TO NEW CONSTRUCTION.

2. SAWCUT EXISTING CURB TO TIE INTO EXISTING CONSTRUCTION.

CONSTRUCTION STABILIZED ENTRANCE

SAWCUT CURB FOR CONSTRUCTION ENTRANCE.

STABILIZED CONSTRUCTION AREA SHALL BE CONSTRUCTED OF 3"X5" ROCK TO BE PLACED A MINIMUM LENGTH OF 25-FT. AND MAINTAINED SO THAT CONSTRUCTION DEBRIS DOES NOT FALL WITHIN THE CITY RIGHT-OF-WAY. RIGHT-OF-WAY MUST BE CLEARED FROM MUD, ROCKS, ETC. AT ALL TIMES. (NOTES TO BE PLACED ON ALL WW PLAN & DETAIL SHEETS)

ENSURE ALL DRIVEWAY APPROACHES ARE BUILT IN GENERAL ACCORDANCE WITH A.D.A.

PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

<u>SIGNING AND PAVEMENT MARKING PLAN NOTES</u>

THE CONTRACTOR SHALL FURNISH AND INSTALL ALL REGULATORY AND WARNING SIGNS, STREETS NAME SIGNS AND SIGN MOUNTS IN ACCORDANCE WITH APPROVED ENGINEERING PLANS. THE CITY WILL INSPECT ALL SIGNS AT FINAL INSPECTION.

THE CONTRACTOR SHALL INSTALL ALL PAVEMENT MARKINGS IN ACCORDANCE WITH APPROVED ENGINEERING PLANS. THE CONTRACTOR SHALL NOTIFY THE CITY AT LEAST TWENTY-FOUR (24) HOURS PRIOR TO THE INSTALLATION OF ALL SEALER AND FINAL MARKINGS. THE CITY WILL INSPECT ALL

SIGNAGE NOTES

THE CONTRACTOR SHALL FURNISH AND INSTALL ALL REGULATORY, WARNING AND STREET NAME SIGNS AND SIGN MOUNTS IN ACCORDANCE WITH APPROVED ENGINEERING PLANS.

THE WEDGE ANCHOR STEEL SYSTEM AND THIN-WALLED TUBING POST SHALL BE USED FOR SIGNS WITH UP TO 10 SQUARE FEET OF SIGN AREA. MATERIALS AND INSTALLATION SHOULD FOLLOW THE TEXAS DEPARTMENT OF TRANSPORTATION (TXDOT) TRAFFIC STANDARDS SMD (GEN) - 08 AND SMD (TWT) -

THE TRIANGULAR SLIP BASE SYSTEM AND 10 BWG TUBING POST SHALL BE USED FOR SIGNS THAT HAVE 10 TO 16 SQUARE FEET OF SIGN AREA. MATERIALS AND INSTALLATION SHOULD FOLLOW THE TXDOT TRAFFIC STANDARDS SMD (GEN) - 08 AND SMD (SLIP-1-3)- 08. OBJECT MARKERS MATERIALS AND INSTALLATION SHOULD FOLLOW THE

SIGN MATERIALS INCLUDING ALUMINUM SIGN BLANKS AND SIGN FACE MATERIALS SHOULD FOLLOW THE TXDOT TRAFFIC STANDARDS TSR (1 - 5) - 08 AND DEPARTMENTAL MATERIAL SPECIFICATIONS DMS-7110 AND DMS-8300.

SEQUENCE OF CONSTRUCTION

1. INSTALL EROSION CONTROLS PER APPROVED PLAN.

THE CITY OF SEGUIN WILL INSPECT ALL SIGNS AT FINAL INSPECTION

TXDOT TRAFFIC STANDARDS D & OM (1 - 5) - 10.

2. TEMPORARY CONTROLS TO BE INSPECTED AND MAINTAINED WEEKLY AND PRIOR TO ANTICIPATED RAINFALL EVENTS, AND AFTER RAINFALL EVENTS, AS NEEDED. CONTRACTOR/OWNER SHALL PROVIDE A CONTACT NAME AND NUMBER FOR EROSION CONTROL ISSUES.

CONDUCT DEMOLITION ACTIVITIES, IF APPLICABLE

4. CONSTRUCT DRAINAGE IMPROVEMENTS, IF APPLICABLE.

5. CONSTRUCT CURB INLET PROTECTION AT THE TIME OF CURB INLET INSTALLATION. 6. CONSTRUCT DEVELOPMENT PER APPROVED PLANS.

8. CONTRACTOR TO VEGETATE ANY DISTURBED AREAS ONCE FINAL GRADING IS COMPLETE, AND ESTABLISH A MIN OF 70% VEGETATION PRIOR TO COMPLETION

7. INSTALL STREETSCAPE AND/OR LANDSCAPING IMPROVEMENTS.

9. REMOVE ALL TEMPORARY EROSION CONTROL MEASURES. 10. TPDES REQUIREMENTS - DISTURBED AREAS ON WITCH CONSTRUCTION ACTIVITIES HAVE CEASED (TEMPORARY OR PERMANENTLY) SHALL BE STABILIZED WITHIN 14 DAYS UNLESS ACTIVITY WILL BEGIN AGAIN WITHIN 21 DAYS



D S EENSI

Z

DATE: **JANUARY 2024**

MK/RR

DESIGNED BY: REVIEWED BY: CC HMT PROJECT NO.:


310.012

DRAWN BY:

FOR REFERENCE ONLY

290 S. CASTELL AVE., STE. 100 NEW BRAUNFELS, TX 78130 TBPE FIRM F-10961

EN GIN EERING & SURVEYING



GREENSPOINT HEIGHTS UNIT SEGUIN, TEXAS

 \mathcal{C}

REVISION DESCRIPTION

REVISION DATE

DATE: JANUARY 2024


DRAWN BY: MK/RR

DESIGNED BY: MA

REVIEWED BY: CC


HMT PROJECT NO.: 310.012

C0.03



FOR REFERENCE ONLY

NEW BR.
TBPE FIR



GREENSPOINT HEIGHTS UNIT SEGUIN, TEXAS

9F

3B

REVISION DESCRIPTION

REVISION DATE

DATE: JANUARY 2024

DRAWN BY: MK/RR


DESIGNED BY: MA


REVIEWED BY: CC

HMT PROJECT NO.:

310.012 **SHEET**

C0.04





ROCK BERM

FILTER DIKE CURB INLET PROTECTION

NOT

PER TPDES REQUIREMENTS, DISTURBED AREAS ON WHICH CONSTRUCTION ACTIVITIES HAVE CEASED (TEMPORARILY OR PERMANENT) SHALL BE STABILIZED WITHIN 14 DAYS UNLESS ACTIVITY RESUMES WITHIN 21 DAYS. SEEDING AND/OR HYDROMULCH DOES NOT CONSTITUTE STABILIZATION, MINIMUM 70 PERCENT VEGETATIVE COVER OR DISTURBED AREAS ID REQUIRED.

SILT FENCE AT PROPERTY LINE MAY BE SHOWN GRAPHICALLY OFFSET FROM PROPERTY LINE TO AVOID OVERLAP OF LINEWORK. CONTRACTOR SHALL NOT INSTALL EROSION CONTROL MEASURES BEYOND LIMITS OF CONSTRUCTION REGARDLESS OF GRAPHIC REPRESENTATION.

SEQUENCE OF CONSTRUCTION

- 1. INSTALL EROSION CONTROLS PER APPROVED PLAN.
- 2. TEMPORARY CONTROLS TO BE INSPECTED AND MAINTAINED WEEKLY AND PRIOR TO ANTICIPATED RAINFALL EVENTS, AND AFTER RAINFALL EVENTS, AS NEEDED. CONTRACTOR/OWNER SHALL PROVIDE A CONTACT NAME AND NUMBER FOR EROSION CONTROL ISSUES.
- 3. CONDUCT DEMOLITION ACTIVITIES, IF APPLICABLE.
- 4. CONSTRUCT DRAINAGE IMPROVEMENTS, IF APPLICABLE.
- 5. CONSTRUCT CURB INLET PROTECTION AT THE TIME OF CURB INLET INSTALLATION.
- 6. CONSTRUCT DEVELOPMENT PER APPROVED PLANS.
- 7. INSTALL STREETSCAPE AND/OR LANDSCAPING IMPROVEMENTS.
- GRADING IS COMPLETE, AND ESTABLISH A MIN OF 80% VEGETATION PRIOR TO COMPLETION. PER TPDES REQUIREMENTS, DISTURBED AREAS ON WHICH CONSTRUCTION ACTIVITIES HAVE CEASED (TEMPORARILY OR PERMANENTLY) SHALL BE STABILIZED WITHIN 14 DAYS UNLESS ACTIVITY RESUMES WITHIN 21 DAYS. SEEDING DOES NOT CONSTITUTE AS STABILIZATION.
- 9. REMOVE ALL TEMPORARY EROSION CONTROL MEASURES.
- 10. TPDES REQUIREMENTS DISTURBED AREAS ON WHICH CONSTRUCTION ACTIVITIES HAVE CEASED (TEMPORARY OR PERMANENTLY) SHALL BE STABILIZED WITHIN 14 DAYS UNLESS ACTIVITY WILL BEGIN AGAIN WITHIN 21 DAYS

SURVEYING TBPLS FIRM 1053

ENGINEERING & SURVEYING



EROSION AND SEDIMENT
CONTROL PLAN
GREENSPOINT HEIGHTS UNIT 3B
SEGUIN, TEXAS

NO. REVISION DESCRIPTION REVISION DATE

DATE: JANUARY 2024

DRAWN BY: MK/RR
DESIGNED BY: MA

REVIEWED BY: CC

HMT PROJECT NO.: 310.012

SHEET

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES.

CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24-HOURS PRIOR TO COMMENCING CONSTRUCTION.

5. INSTALL PIPE UNDER PAD AS NEEDED TO MAINTAIN PROPER PUBLIC ROAD DRAINAGE.

SEGUIN

TEXAS

It's real.

CRUSHED STONE OR COMMERCIAL RACK WHICH DRAINS TO A SEDIMENT TRAP OR BASIN.

6. WHEN NECESSARY, WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC

ROADWAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH 4 INCH MINIMUM

THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC ROADWAYS. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS

CONDITIONS DEMAND, AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT, ALL

SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC ROADWAY MUST BE REMOVED IMMEDIATELY.


8. ALL SEDIMENT SHOULD BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATER COURSE BY USING APPROVED METHODS.


STABILIZED CONSTRUCTION ENTRANCE


JUNE 1, 2013


STABILIZED CONSTRUCTION

ENTRANCE









290 S. CASTELL AVE., STE. 100 NEW BRAUNFELS, TX 78130 TBPE FIRM F-10961 TBPLS FIRM 1053600





GREENSPOINT HEIGHTS UNIT 3B

80

DATE: JANUARY 2024							
NO.							
REVISION DESCRIPTION							
REVISION DATE							
							_

DESIGNED BY: MA

REVIEWED BY: CC

HMT PROJECT NO.:


310.012

DRAWN BY:

MK/RR

SHEET

C1.02



BRAUN E FIRM I

* CHRISTOPHER J. CRIM 111347 01/04/2024

3B

NT HEIGHTS SUIN, TEXAS

DRAINAGE FEATURES, DETENTION BASIN MAINTENANCE AND EQUIPMENT ACCESS REQUIREMENTS:

LEGEND

BUILDING SETBACK LINE

UTILITY EASEMENT

LOT GRADING

DRAINAGE EASEMENT

SEE DETAILS SHEET C2.02

DRAINAGE FLOW DIRECTION

MINIMUM FINISHED FLOOR ELEVATION

700 PROPOSED CONTOURS

U.E.

FF=XXX.X'

SILT SHALL BE REMOVED AND THE BASIN RETURNED TO ORIGINAL LINES AND GRADES WHEN STANDING WATER CONDITIONS OCCUR OR THE BASIN STORAGE VOLUME IS REDUCED BY MORE THAN 10%.

- A. TO LIMIT EROSION, NO UNVEGETATED AREA SHALL EXCEED 10 SQ. FT. IN EXTENT.
- B. ACCUMULATED PAPER, TRASH, AND DEBRIS SHALL BE REMOVED EVERY 6 MONTHS OR AS NECESSARY TO MAINTAIN PROPER OPERATION.
- BASINS SHALL BE MOWED ANNUALLY BETWEEN THE MONTHS OF JUNE AND SEPTEMBER.
- CORRECTIVE MAINTENANCE IS REQUIRED ANY TIME A BASIN DOES NOT DRAIN COMPLETELY WITHIN 60 HOURS OR CESSATION OF INFLOW DURING CONSTRUCTION OF THE SUBDIVISION IMPROVEMENTS (IE: NO STANDING WATER IS ALLOWED).
- STRUCTURAL INTEGRITY OF BASINS SHALL BE MAINTAINED AT ALL TIMES.
- MAINTENANCE ACCESS DRIVES ARE TO BE A MINIMUM OF 4' WIDE WITH A 2% CROSS SLOPE TOWARDS CHANNEL/POND. VEHICLE FOR POND ACCESS SHOULD BE A BOBCAT S175 SKID STEER LOADER OR VEHICLE OF EQUAL TO LESSER SIZE.

GREENSPOIN

DATE: **JANUARY 2024**

DRAWN BY: DESIGNED BY: MA

EVIEWED BY: CC HMT PROJECT NO.:

310.012 **SHEET**

MINIMUM RISE FROM CURB TOP TO SLAB FLOOR: 27" + 8"

MINIMUM RISE FOR WOOD FLOOR USING 8" JOISTS: 35" + 9"

* WHERE THERE IS A HIGH BANK NEARBY OR A LONG SLOPE TOWARD HOUSE, A MINIMUM 6" PROTECTIVE SLOPE IS REQUIRED. ** LENGTH $\overline{DE} = [1/2(LOT WIDTH - (2x SWALE TURN RADIUS))] - [LOT WIDTH x (STREET GRADIENT x SWALE GRADIENT)]$

LOT TYPE (A)

43" (3.6') | 28" (2.3')

54" (4.5') | 39" (3.3')

SUB-TOTAL \overline{AF} FROM CURB TOP TO GROUND AT REAL BLDG WALL 35" (3.0') | 20" (1.7')

MINIMUM RISE FROM CURB TOP TO SLAB FLOOR: 35" + 8"

MINIMUM RISE FOR WOOD FLOOR USING 8" JOISTS: 35" + 9"

LOT TYPE ®

* WHERE THERE IS A HIGH BANK NEARBY OR A LONG SLOPE TOWARD HOUSE, A MINIMUM 6" PROTECTIVE SLOPE IS REQUIRED.

35" (2.9') | 24" (2.0')

46" (3.8') | 35" (2.9')

0.25" PER FOOT

GRADIENT FOR A

2% SWALE.

LOT TYPE ©

* WHERE THERE IS A HIGH BANK NEARBY OR A LONG SLOPE TOWARD HOUSE, A MINIMUM 6" PROTECTIVE SLOPE IS REQUIRED.

PROT. FRONT SLOPE UP FROM HIGH POINT OF SWALES

MINIMUM RISE FROM CURB TOP TO SLAB FLOOR: -7" + 8"

MINIMUM RISE FOR WOOD FLOOR USING 8" JOISTS: -7" + 19"

SUB-TOTAL \overline{AF} FROM CURB TOP TO GROUND AT FRONT BLDG WALL -7" $(-1.0') \mid -11$ " (1.3')

RESULTS OF

4" (0.3') | 2" (0.2')

3" (0.3') | 3" (0.3')

12" (-0.6') ' 8" (0.3')

1" (-0.3') |

1% SWALES

CALCULATIONS FOR SWALES

 $-11 \times 1.625' = -17\frac{3}{4}"$

PER FOOT GRADIENT FOR

USE 1.625" PER FOOT

GRADIENT FOR A 13.5%

 $= 3\frac{3}{4}$ "

15 x 0.25'

0 x 0.25'

16 x 0.25'

CALCULATION:

A 2% SWALE.

GENERAL SPECIFICATIONS FOR SITE PREPARATION

THIS ITEM SHALL CONSIST OF ALL CLEARING AND PREPARATION OF LAND TO BE FILLED, FILLING OF THE LAND, SPREADING, COMPACTION TESTING AND INSPECTION OF THE LAND, SPREADING OF THE CUT AND FILL AREAS TO CONFORM WITH THE LINES, GRADES AND SLOPES AS SHOWN ON THE APPROVED PLANS.

SCARIFYING THE AREA TO BE FILLED ALL ORGANIC MATTER SHALL BE REMOVED FROM THE SURFACE UPON WHICH THE FILL IS TO BE PLACED, AND SURFACE SHALL BE DISKED OR SCARIFIED TO A MINIMUM DEPTH OF SIX INCHES (6"), ALL SURFACE RUTS OR OTHER UNEVEN FEATURES WILL BE LEVELED PRIOR TO FIELD DENSITY TESTING.

COMPACTING THE AREA TO BE FILLED FOLLOWING THE CLEARING AND DISKING OR SCARIFYING OF THE FILL AREA, IT SHALL BE BLADED UNTIL IT IS UNIFORM AND FREE FROM LARGE CLODS. THE AREA SHALL BE BROUGHT TO ADEQUATE MOISTURE CONTENT AND COMPACTED (TYPICALLY) TO NOT LESS THAN NINETY PERCENT (90%) OF MAXIMUM DENSITY IN ACCORDANCE WITH THE CURRENT ASTM D 1557 COMPACTION PROCEDURE, OR 95% OF MAXIMUM DENSITY IN ACCORDANCE WITH THE THD-TEX-113-E COMPACTION PROCEDURE. ALL AREAS EXCEEDING (6") SIX INCHES IN DEPTH, MUST MEET WITH FHA/HUD HANDBOOK 4140.30 SPECIFICATIONS FOR LAND DEVELOPMENTS ON CONTROLLED EARTHWORK, DATASHEET 79G.

THE MATERIALS USED SHALL BE FREE FROM ORGANIC MATTER AND OTHER DELETERIOUS SUBSTANCES, SUCH AS TREES, BRUSH AND RUBBISH.

CALCULATIONS USE

0.25" PER FOOT

GRADIENT FOR A

2% SWALE.

DEPTH AND MIXING OF FILL LAYERS

THE SELECTED FILL MATERIAL SHALL BE PLACED IN LEVEL, UNIFORM LAYERS WHICH, WHEN COMPACTED, SHALL HAVE A DENSITY CONFORMING TO THE STIPULATED ABOVE.

EACH LAYER SHALL BE THOROUGHLY MIXED DURING THE SPREADING TO ENSURE UNIFORMITY OF MATERIAL IN EACH LAYER. COMPACTED LAYER THICKNESS MAY VARY DEPENDING ON THE COMAPCTION EQUIPMENT OF THE DEMONSTRATED CAPABILITY.

WHEN FILL MATERIAL INCLUDES ROCK, THE MAXIMUM ROCK SIZE SHALL BE AS APPROVED BY THE GEOTECHNICAL ENGINEER. NO LARGE ROCKS SHALL BE ALLOWED TO NEST AND ALL VOIDS MUST BE FILLED WITH SMALL STONES OR SOIL AND ADEQUATELY COMPACTED.

COMPACTION EQUIPMENT SHALL BE CAPABLE OF COMPACTING THE FILL TO THE SPECIFIED DENSITY. COMPACTION SHALL BE ACCOMPLISHED WHILE THE FILL MATERIAL IS AT OR NEAR THE APPROPRIATE MOISTURE CONTENT. COMPACTION OF EACH LAYER SHALL BE CONTINUOUS OVER THE ENTIRE STRUCTURAL AREA (BENEATH PROPOSED STRUCTURES).

THE FACES OF FILL SLOPES SHALL BE COMPACTION OF THE SLOPE FACE MAY BE DONE PROGRESSIVELY IN INCREMENTS OF THREE TO FIVE FEET (3' TO 5') IN FILL HEIGHT AS THIS FILL PROGRESSES OR AFTER THE FILL HAS BEEN BROUGHT TO ITS TOTAL HEIGHT.

FIELD DENSITY TESTS SHALL BE PERFORMED ON ALL LAYERS OF FILL WHEN THE FILL IS BEING PLACED AS DIRECTED BY THE GEOTECHNICAL ENGINEER. THE MAXIMUM FILL HEIGHT BETWEEN DENSITY TESTING SHALL BE TWELVE INCHES (12"). ALL TESTING SHALL BE REQUESTED BY THE CONTRACTOR TO MEET THE CONTRACTOR'S CONSTRUCTION SCHEDULE. NOTIFICATION BY THE CONTRACTOR TO CONDUCT TESTS SHALL BE AT LEAST THE DAY BEFORE. THIS NOTIFICATION SHALL INCLUDE THE FILL AREA LOCATION (LOT AND BLOCK), THE LIFT OR HEIGHT OF FILL AND APPROXIMATED DESIRED TIME OF TESTING. WHEN THESE TEST INDICATE THAT THE DENSITY OF ANY LAYER OF FILL OR PORTION THEREOF IS BELOW THE REQUIRED DENSITY, THE PARTICULAR LAYER OR PORTION SHALL BE REWORKED AND RETESTED AT THE EXPENSE OF THE CONTRACTOR UNLESS THE CONTRACTOR CAN SHOW EVIDENCE THAT CIRCUMSTANCES BEYOND HIS CONTROL REQUIRED THE RETESTING. GENERALLY, THE SPECIFIC TESTING WILL BE AS FOLLOWS AND CONDUCTED BY A GEO-TECHNICAL ENGINEER OR STAFF.

THE LAND TO BE FILLED (PREPARED SUBGRADE) SHALL BE PREPARED AND TESTED AT A FREQUENCY AS DETERMINED BY THE GEOTECHNICAL ENGINEER. 2. THE FIRST LIFT OF COMPACTED FILL (GENERALLY 8-12 IN.) SHALL BE TESTED AS DETERMINED BY THE GEOTECHNICAL ENGINEER. ANY AREAS SUPPORTING THE PROPOSED STRUCTURES REQUIRING FILL SHALL BE TESTED FOR DENSITY COMPLIANCE.


3. FILLS SHALL BE TESTED AT A MAXIMUM OF EACH TWELVE INCHES (12") OF FILL 4. TEST RESULTS WILL BE PROVIDED BY THE FIELD TECHNICIAN TO THE CONTRACTOR WHEN POSSIBLE: HOWEVER, ALL TEST RESULTS ARE TO BE REVIEWED BY THE GEOTECHNICAL ENGINEER FOR COMPLIANCE. THE ENGINEER WILL NOTIFY THE CONTRACTOR OF ALL TEST RESULTS.

AREAS INVOLVING CUT ON THE PORTION AND FILL ON ANOTHER PORTION OF A SPECIFIC LOT SHALL BE REQUIRED ON EACH CUT/FILL LOT FOR THE PURPOSE OF DETERMINING UNIFORMITY OF THE AREA SUPPORTING THE PROPOSED STRUCTURES.

HUD 79-G REQUIREMENT FOR FILL MATERIAL OF 6 INCHES AND MORE WILL BE CONDUCTED. ALL CUT AREAS WILL ALSO MEET THE REQUIREMENTS FOR HUD 79-G COMPACTION TESTING. IN ADDITION, ENGINEERS MUST PROVIDE VERIFICATION OF ALL AREAS WHICH DO NOT REQUIRE HUD 79-G. AFTER SITE GRADING IS COMPLETED, GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CONTRACTOR AND OWNER A 79-G LETTER.

DRAINAGE NOTE FINISHED FLOOR ELEVATIONS

THE ELEVATION OF THE LOWEST FLOOR SHALL BE AT LEAST 10 INCHES ABOVE THE FINISHED GRADE OF THE SURROUNDING GROUND, WHICH SHALL BE SLOPED IN A FASHION SO AS TO DIRECT STORMWATER AWAY FROM THE STRUCTURE. PROPERTIES ADJACENT TO STORMWATER CONVEYANCE STRUCTURES MUST HAVE FLOOR SLAB ELEVATION OR BOTTOM OF FLOOR JOISTS A MINIMUM OF ONE FOOT ABOVE THE 100-YEAR WATER FLOW ELEVATION IN THE STRUCTURE. DRIVEWAYS SERVING HOUSES ON THE DOWNHILL SIDE OF THE STREET SHALL HAVE A PROPERLY SIZED CROSS SWALE PREVENTING RUNOFF FROM ENTERING THE GARAGE.




NT HEIGHTS JUIN, TEXAS GREENSP(SE

REVISION DATE				
REVISION DESCRIPTION				
NO.				

JANUARY 2024 MK/RR DRAWN BY: DESIGNED BY: REVIEWED BY: CC HMT PROJECT NO.:

310.012



3+00

4+00

5+00

6+00

2+00

<u>LEGEND</u> EXISTING CONTOURS PROPOSED CONTOURS BUILDING SETBACK LINE U.E. UTILITY EASEMENT D.E. DRAINAGE EASEMENT A.D.A. RAMP FLOW ARROW WASHOUT CROWN AREAS SPILL CURB EXISTING GROUND LEFT (EG LT) EXISTING GROUND RIGHT (EG RT) EXISTING GROUND CENTER (EG CTR) — PROPOSED TOP OF CURB (PR TC) ACCESSIBLE CROSSING AREA CONTRACTOR TO ENSURE MAX 2% CROSS SLOPE IN THESE AREAS 2.0% MAX

SIDEWALK TO BE CONSTRUCTED BY SITE DEVELOPMENT CONTRACTOR <u>NOTES</u>

SIDEWALK RAMP TYPE
TO BE CONSTRUCTED AT TIME OF

STREET CONSTRUCTION (SEE DETAIL SHEET C3.08)

- 2. IN WASHOUT CROWN AREAS, THE CURB ON THE HIGH SIDE OF THE STREET SHOULD BE SPILL CURB AS DESIGNATED
- 3. CONTRACTOR TO CONSTRUCT SIDEWALK RAMPS WITH STREETS.

1. LOCAL STREETS WERE DESIGNED TO POSTED SPEED LIMIT

4. CONTRACTOR TO ENSURE POSITIVE DRAINAGE AWAY FROM STREET STUB OUT ENDS SO THAT NO "PONDING" OF WATER OCCURS.


ST 78′ 290 S. CASTELL / NEW BRAUNFELS TBPE FIRM F-109 TBPLS FIRM 1053



3B

ERN GROVE & PROFILE

NT HEIGHTS I GREENSPOIN SEGU CAVE PLAN



THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES

24-HOURS PRIOR TO COMMENCING CONSTRUCTION.

GREENSPOINT HEIGHTS

UNIT 1

UNIT 3A

310.012 SHEET

DRAWN BY:


DESIGNED BY: MA


REVIEWED BY: CC


HMT PROJECT NO .:

C3.01

MK/RR







<u>LEGEND</u> EXISTING CONTOURS PROPOSED CONTOURS BUILDING SETBACK LINE UTILITY EASEMENT U.E. DRAINAGE EASEMENT D.E.

A.D.A. RAMP

FLOW ARROW WASHOUT CROWN AREAS SPILL CURB

EXISTING GROUND LEFT (EG LT) EXISTING GROUND RIGHT (EG RT) EXISTING GROUND CENTER (EG CTR) PROPOSED TOP OF CURB (PR TC)

ACCESSIBLE CROSSING AREA CONTRACTOR TO ENSURE MAX 2% CROSS SLOPE IN THESE AREAS 2.0% MAX

SIDEWALK RAMP TYPE
TO BE CONSTRUCTED AT TIME OF STREET CONSTRUCTION (SEE DETAIL SHEET C3.08)

SIDEWALK TO BE CONSTRUCTED
BY SITE DEVELOPMENT CONTRACTOR

<u>NOTES</u>

SCALE: 1" = 5' VERT.

- 1. LOCAL STREETS WERE DESIGNED TO POSTED SPEED LIMIT
- IN WASHOUT CROWN AREAS, THE CURB ON THE HIGH SIDE OF THE STREET SHOULD BE SPILL CURB AS DESIGNATED ON THE PLANS.
- 3. CONTRACTOR TO CONSTRUCT SIDEWALK RAMPS WITH STREETS.
- 4. CONTRACTOR TO ENSURE POSITIVE DRAINAGE AWAY FROM STREET STUB OUT ENDS SO THAT NO "PONDING" OF WATER OCCURS.

CHRISTOPHER J. CRIM 111347

ST 78′

290 S. CASTELL ANEW BRAUNFELS TBPE FIRM F-109 TBPLS FIRM 1053

01/04/2024

3B

GREENSPOIN SEGU

FORGE PROFILE

DATE: **JANUARY 2024**

REVIEWED BY: CC

DRAWN BY:

MK/RR


DESIGNED BY: MA THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR HMT PROJECT NO .: SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES.

CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24-HOURS PRIOR TO COMMENCING CONSTRUCTION.


SHEET

310.012


GREENSPOINT HEIGHTS unit 3a UNIT 1









LIMESTONE RIDGE KNUCKLE







<u>LEGEND</u> EXISTING CONTOURS PROPOSED CONTOURS BUILDING SETBACK LINE

U.E. UTILITY EASEMENT D.E. DRAINAGE EASEMENT A.D.A. RAMP

FLOW ARROW

WASHOUT CROWN AREAS SPILL CURB EXISTING GROUND LEFT (EG LT)

EXISTING GROUND RIGHT (EG RT) EXISTING GROUND CENTER (EG CTR) — PROPOSED TOP OF CURB (PR TC)

ACCESSIBLE CROSSING AREA CONTRACTOR TO ENSURE MAX 2% CROSS SLOPE IN THESE AREAS 2.0% MAX

SIDEWALK RAMP TYPE
TO BE CONSTRUCTED AT TIME OF STREET CONSTRUCTION (SEE DETAIL SHEET C3.08)

SIDEWALK TO BE CONSTRUCTED BY SITE DEVELOPMENT CONTRACTOR

SCALE: 1" = 5' VERT.

- 1. LOCAL STREETS WERE DESIGNED TO POSTED SPEED LIMIT
- 2. IN WASHOUT CROWN AREAS, THE CURB ON THE HIGH SIDE OF THE STREET SHOULD BE SPILL CURB AS DESIGNATED
- 3. CONTRACTOR TO CONSTRUCT SIDEWALK RAMPS WITH STREETS.
- 4. CONTRACTOR TO ENSURE POSITIVE DRAINAGE AWAY FROM STREET STUB OUT ENDS SO THAT NO "PONDING" OF WATER OCCURS.

CHRISTOPHER J. CRIM 111347

290 S. CASTELL /
NEW BRAUNFELS
TBPE FIRM F-109
TBPLS FIRM 1053

01/04/2024

3B

NT HEIGHTS I

GREENSPOIN

STONE RDG & PROFILE LIMES' PLAN


THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES


24-HOURS PRIOR TO COMMENCING CONSTRUCTION.


GREENSPOINT HEIGHTS UNIT 3A UNIT 1 UNIT 2B DATE: **JANUARY 2024**

MK/RR DRAWN BY: DESIGNED BY: MA REVIEWED BY: CC HMT PROJECT NO .:

> 310.012 SHEET







<u>LEGEND</u> EXISTING CONTOURS PROPOSED CONTOURS BUILDING SETBACK LINE U.E. UTILITY EASEMENT

D.E. DRAINAGE EASEMENT A.D.A. RAMP FLOW ARROW

WASHOUT CROWN AREAS SPILL CURB EXISTING GROUND LEFT (EG LT)

> EXISTING GROUND RIGHT (EG RT) EXISTING GROUND CENTER (EG CTR) — PROPOSED TOP OF CURB (PR TC)

ACCESSIBLE CROSSING AREA CONTRACTOR TO ENSURE MAX 2% 2.0% MAX CROSS SLOPE IN THESE AREAS SIDEWALK RAMP TYPE


> STREET CONSTRUCTION (SEE DETAIL SHEET C3.05)


TO BE CONSTRUCTED AT TIME OF

SIDEWALK TO BE CONSTRUCTED BY SITE DEVELOPMENT CONTRACTOR

<u>NOTES</u>

- 1. LOCAL STREETS WERE DESIGNED TO POSTED SPEED LIMIT
- 2. IN WASHOUT CROWN AREAS, THE CURB ON THE HIGH SIDE OF THE STREET SHOULD BE SPILL CURB AS DESIGNATED ON THE PLANS.
- 3. CONTRACTOR TO CONSTRUCT SIDEWALK RAMPS WITH STREETS.
- 4. CONTRACTOR TO ENSURE POSITIVE DRAINAGE AWAY FROM STREET STUB OUT ENDS SO THAT NO "PONDING" OF WATER OCCURS.
- 5. PER NEW BRAUNFELS ORDINANCE SEC. 114-98(a)(6) ALL DRIVEWAY LOCATED ON A SINGLE FAMILY RESIDENCE ON A LOCAL STREET SHALL HAVE A MINIMUM SPACING OF 20'





THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES

24-HOURS PRIOR TO COMMENCING CONSTRUCTION.

SHEET

MK/RR

DATE: **JANUARY 2024**

DESIGNED BY: MA

REVIEWED BY: CC

310.012


HMT PROJECT NO .:

DRAWN BY:

ST 78′ 290 S. CASTELL /
NEW BRAUNFELS
TBPE FIRM F-109
TBPLS FIRM 1053

CHRISTOPHER J. CRIM 111347 01/04/2024

3B LNO EY PASS PROFILE WHISKE' PLAN & P GREENSPOIN



HORIZONTAL SCALE: 1:50

<u>LEGEND</u>

BUILDING SETBACK LINE

UTILITY EASEMENT DRAINAGE EASEMENT A.D.A. RAMP

ACCESSIBLE CROSSING AREA CONTRACTOR TO ENSURE MAX 2% 2.0% MAX CROSS SLOPE IN THESE AREAS

> SIDEWALK RAMP TYPE TO BE CONSTRUCTED AT TIME OF STREET CONSTRUCTION (SEE DETAIL SHEET C3.08)

SIDEWALK TO BE CONSTRUCTED BY SITE DEVELOPMENT CONTRACTOR

<u>NOTES</u>

- 1. LOCAL STREETS WERE DESIGNED TO POSTED SPEED LIMIT OF 25 MPH.
- 2. IN WASHOUT CROWN AREAS, THE CURB ON THE HIGH SIDE OF THE STREET SHOULD BE SPILL CURB AS DESIGNATED ON THE PLANS.
- 3. CONTRACTOR TO CONSTRUCT SIDEWALK RAMPS WITH STREETS.
- 4. CONTRACTOR TO ENSURE POSITIVE DRAINAGE AWAY FROM STREET STUB OUT ENDS SO THAT NO "PONDING" OF WATER OCCURS.
- 5. PER CITY OF SEGUIN UDC ROAD ADEQUACY TECHNICAL MANUAL, SECTION 4 ALL DRIVEWAY LOCATED ON A SINGLE FAMILY RESIDENCE ON A LOCAL STREET SHALL HAVE A MINIMUM SPACING OF 20'
- 6. MAILBOX PAD LOCATION(S) SHALL BE COORDINATED WITH POST OFFICES, OWNER AND ENGINEER, MAILBOX PADS SHALL BE LOCATED ADJACENT TO THE BACK OF SIDEWALKS AND SHALL BE ADA ACCESSIBLE.

SIGNAGE NOTES THE CONTRACTOR SHALL FURNISH AND INSTALL ALL REGULATORY, WARNING AND STREET NAME SIGNS AND SIGN MOUNTS IN ACCORDANCE WITH CITY OF SEGUIN DETAILS AND STANDARDS.

* 111347

ST 78′

290 S. CASTELL / NEW BRAUNFELS TBPE FIRM F-109 TBPLS FIRM 1053

CHRISTOPHER J. CRIM 01/04/2024

> 3B NT HEIGHTS I

SIGNAGE


DATE: **JANUARY 2024**

DRAWN BY: DESIGNED BY: MA

REVIEWED BY: CC HMT PROJECT NO .:

310.012

SHEET



BACKFILL WITH → 6" ← 1'-6" →

1' MIN \ 4" \ 1'-4" \

-FLEXBASE (CRUSHED STONE) TYPE A,

95% DENSITY PER TEX 113E. (NOT A SEPARATE BID ITEM)

TYPICAL CATCH CURB AND GUTTER

1. FOR CONCRETE CURB AND GUTTER REMOVEL/REPLACEMENT, INSTALLED

2. CURB AND GUTTER SHALL BE 3000 PSI CONCRETE IN ACCORDANCE WITH TXDOT ITEMS 361, 421, & 529 UNLESS SPECIFIED OTHERWISE IN

3. CONTRACTOR MAY INSTALL TYPE B HMAC BELOW CURB AND GUTTER IN

5. REFER TO PLANS FOR LOCATION FOR PROPOSED SIDEWALKS. REFER TO

─ N.T.S.

4. EXPANSION JOINT EVERY 40'. SEE SPECIFICATIONS FOR DETAILS.

SW SERIES DETAILS FOR SIDEWALK CONSTRUCTION DETAILS.

SECTION SHALL MATCH EXISTING CURB RADII.

PLACE OF FLEX BASE; NO ADDITIVE COST.

THE CONSTRUCTION DOCUMENTS.

GRADE 2 COMPACTED IN MAX 8" LIFT TO

#4 BARS-CONTINUOUS

TEXAS

It's real.

APPROVED MATERIAL

NOTES:

DATE ISSUED:

SEGUIN

TEXAS

It's real.

CONCRETE SIDEWALK SECTION

N.T.S.

∕-#4 BAR 24" O.C.

-#4 BARS CONTINUOUS

SEE STREET DETAIL


FOR DEPTH OF


BASE MATERIAL


STANDARD CURB AND GUTTER DETAIL

CATCH TYPE

CRB-2







DECEMBER 18, 2018 TITLE DATE BY

N.T.S.

STREET SIGN


RDWY-11.1

INSTALLATION DETAIL

SEGUIN

TEXAS

It's real.



NEW PAVEMENT TO EXISTING

NOT TO SCALE

*

Standard Highway Sign Designs for Texas

CHRISTOPHER J. CRIM

7

OF

TR

3B

NT HEIGHTS I


GREENSPOIN SEGU

SPEED LIMIT A B C D E F G H J K L 18 | 24 | 0.375 | 0.625 | 3 | 3 E | 2 | 8 E | 7.052 | 5.491 | 1.5 24 30 0.375 0.625 4 4 E 2 10 E 9.403 7.321 1.5 30 | 36 | 0.5 | 0.75 | 4.5 | 5 E | 2.5 | 12 E | 11.754 | 9.151 | 1.875 36 | 48 | 0.625 | 0.875 | 6 | 6 E | 5 | 14 E | 14.105 | 10.981 | 2.25 | 48 | 60 | 0.75 | 1.25 | 8 | 8 E | 6 | 16 E | 18.806 | 14.642 | 3


R2-1

COLORS: LEGEND - BLACK BACKGROUND - WHITE 1-10 May 2021

ALL PAVEMENT CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE TO THE "SUBSURFACE EXPLORATION AND PAVEMENT ANALYSIS, PROPOSED NEW STREETS, GREENSPOINT HEIGHTS SUBDIVISION", BY INTEC OF SAN ANTONIO, LP, DATED AUGUST 27, 2019 AS SUBMITTED UNDER THIS PERMIT.




TYPICAL LOCAL PAVEMENT SECTION NOT TO SCALE



TYPICAL COLLECTOR SPACE PAVEMENT SECTION*

NOT TO SCALE

* SECTION ONLY APPLIES TO WHISKEY PASS STATION 1+100 THRU 3+79.74



MK/RR DRAWN BY: DESIGNED BY: MA REVIEWED BY: CC


SHEET

310.012


HMT PROJECT NO .:


2012 Edition - Revision 4 STOP SIGN — 2' MIN.


SEE STREET DETAIL FOR DEPTH OF BASE MATERIAL





APPROVED MATERIAL













NEW TERMINATION OF THE TERMINATI



STREET DETAILS (2 OF 2)
GREENSPOINT HEIGHTS UNIT 3B
SEGUIN, TEXAS


REVISION DATE							
REVISION DESCRIPTION							
NO.							
DA ⁻	DATE: JANUARY 2024						
DR	DRAWN BY: MK/RR						
DESIGNED BY: MA							

REVIEWED BY: CC

HMT PROJECT NO.:
310.012

SHEET

C3.07



290 S. CASTELL / NEW BRAUNFEL! TBPE FIRM F-109 TBPLS FIRM 1053



 \mathcal{C} 3B PI HANNEL AND PR GREENSPOIN

DATE: **JANUARY 2024**

MK/RR DRAWN BY:

DESIGNED BY: MA

REVIEWED BY: CC HMT PROJECT NO .:

310.012 **SHEET**

LEGEND — 700 — EXISTING CONTOURS PROPOSED CONTOURS BUILDING SETBACK LINE B.L. U.E. UTILITY EASEMENT D.E. DRAINAGE EASEMENT S.B.C. SINGLE BOX CULVERT PROPOSED STORM DRAIN LINE 1" = 2' VERT.UTILITY CROSSING

ON GRADE INLET A2:

 $Q_{100} = 27.61 \text{ CFS}$

 $Q_{10} = 21.54 \text{ CFS}$

 $\frac{\text{IN SAG INLET A1:}}{Q_{100}} = 30.05 \text{ CFS}$

SPREAD = 15.73

 $Q_{10} = 15.31 \text{ CFS}$

 $D_{100} = 0.52$

 $D_{10} = 0.52'$

SPREAD = 7.02'


 $D_{100} = 0.69$

 $D_{10} = 0.59$

DRAINAGE FEATURES, DETENTION BASIN MAINTENANCE AND EQUIPMENT ACCESS REQUIREMENTS:

SILT SHALL BE REMOVED AND THE BASIN RETURNED TO ORIGINAL LINES AND GRADES WHEN STANDING WATER CONDITIONS OCCUR OR THE BASIN STORAGE VOLUME IS REDUCED BY MORE THAN 10%.


- A. TO LIMIT EROSION, NO UNVEGETATED AREA SHALL EXCEED 10 SQ. FT. IN EXTENT.
- B. ACCUMULATED PAPER, TRASH, AND DEBRIS SHALL BE REMOVED EVERY 6 MONTHS OR AS NECESSARY TO MAINTAIN PROPER OPERATION.
- C. BASINS SHALL BE MOWED ANNUALLY BETWEEN THE MONTHS OF JUNE AND SEPTEMBER.
- D. CORRECTIVE MAINTENANCE IS REQUIRED ANY TIME A BASIN DOES NOT DRAIN COMPLETELY WITHIN 60 HOURS OR CESSATION OF INFLOW DURING CONSTRUCTION OF THE SUBDIVISION IMPROVEMENTS (IE: NO STANDING WATER IS ALLOWED).
- E. STRUCTURAL INTEGRITY OF BASINS SHALL BE MAINTAINED AT ALL TIMES.
- F. MAINTENANCE ACCESS DRIVES ARE TO BE A MINIMUM OF 4' WIDE WITH A 2% CROSS SLOPE TOWARDS CHANNEL/POND. VEHICLE FOR POND ACCESS SHOULD BE A BOBCAT S175 SKID STEER LOADER OR VEHICLE OF EQUAL TO



 $Q_{100} = 57.66 \text{ CFS}$ $V_{100} = 5.31 \text{ FPS}$ $D_{100} = 1.15'$ S = 0.68%

 $Q_{25} = 43.61 \text{ CFS}$ $V_{25} = 4.91 \text{ FPS}$ $D_{25} = 0.99$ ' S = 0.68%

 $Q_2 = 23.82 \text{ CFS}$ $V_2 = 4.05 \text{ FPS}$ $\begin{array}{ccc}
D_2 & = & 0.72' \\
S & = & 0.68\%
\end{array}$



KEY MAP

REFER TO THE COVER SHEET FOR BENCHMARK INFORMATION.

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES.

CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24-HOURS PRIOR TO COMMENCING CONSTRUCTION.

ST 78′

290 S. CASTELL /
NEW BRAUNFELS
TBPE FIRM F-109
TBPLS FIRM 1053

*

CHRISTOPHER J. CRIM

111347

AN

N N O N

01/04/2024

3B

NT HEIGHTS SUIN, TEXAS

GREENSPOIN

DATE: **JANUARY 2024**


MK/RR DRAWN BY: DESIGNED BY: MA

REVIEWED BY: CC HMT PROJECT NO .: 310.012

SHEET

±----

STORM LINE A <u>0+50 - 3+00</u> <u>564</u> <u>564</u> FG — <u>562</u> <u>562</u> SAFETY END TREATMENT WITHOUT PIPE RUNNERS (SEE TxDOT DETAIL ON SHEET C4.05 <u>560</u> <u>560</u> ± 16 LF ~ ─± 99 LF ~ 2-18" RCP'S @ 0.20% 2-18" RCP'S-**@** 0.20% <u>558</u> EXISTING CONC. -CHANNEL END 30' CURB INLET A1 <u>556</u> <u>556</u> _STA=1+43.54 BEGIN 20' ON GRADE RIM=561.85 CURB INLET A2 2' CONC._ FL=557.940 STA = 2 + 42.57TOEDOWN BEGIN 30' CURB INLET A1 RIM = 562.45STA=1+26.41 FL=558.137 RIM = 561.85<u>554</u> <u>554</u> FL=557.904 <u>552</u> <u>552</u> 561.4 557.93 561.2 557.95 561.1 558.07 0+80 1+20 1+80 0+60 1+00 1 + 401+60 2+00 2+20 2+60 2+40



— 700 — EXISTING CONTOURS PROPOSED CONTOURS B.L. BUILDING SETBACK LINE U.E. UTILITY EASEMENT D.E. DRAINAGE EASEMENT S.B.C. SINGLE BOX CULVERT PROPOSED STORM DRAIN LINE 1" = 2' VERT.UTILITY CROSSING

ON GRADE INLET B2:

 $Q_{100} = 27.61 \text{ CFS}$


DRAINAGE FEATURES, DETENTION BASIN MAINTENANCE AND EQUIPMENT ACCESS REQUIREMENTS:

LEGEND

SILT SHALL BE REMOVED AND THE BASIN RETURNED TO ORIGINAL LINES AND GRADES WHEN STANDING WATER CONDITIONS OCCUR OR THE BASIN STORAGE VOLUME IS REDUCED BY MORE THAN 10%.

- A. TO LIMIT EROSION, NO UNVEGETATED AREA SHALL EXCEED 10 SQ. FT. IN EXTENT.
- B. ACCUMULATED PAPER, TRASH, AND DEBRIS SHALL BE REMOVED EVERY 6 MONTHS OR AS NECESSARY TO MAINTAIN PROPER OPERATION.
- C. BASINS SHALL BE MOWED ANNUALLY BETWEEN THE MONTHS OF JUNE AND SEPTEMBER.
- D. CORRECTIVE MAINTENANCE IS REQUIRED ANY TIME A BASIN DOES NOT DRAIN COMPLETELY WITHIN 60 HOURS OR CESSATION OF INFLOW DURING CONSTRUCTION OF THE SUBDIVISION IMPROVEMENTS (IE: NO STANDING WATER IS ALLOWED).
- E. STRUCTURAL INTEGRITY OF BASINS SHALL BE MAINTAINED AT ALL TIMES.
- F. MAINTENANCE ACCESS DRIVES ARE TO BE A MINIMUM OF 4' WIDE WITH A 2% CROSS SLOPE TOWARDS CHANNEL/POND. VEHICLE FOR POND ACCESS SHOULD BE A BOBCAT S175 SKID STEER LOADER OR VEHICLE OF EQUAL TO

N.T.S.




 $Q_{100} = 57.66 \text{ CFS}$ $V_{100} = 3.06 \text{ FPS}$ $D_{100} = 1.09^{\circ}$ S = 0.20%

CHANNEL 4

 $Q_{25} = 43.61 \text{ CFS}$ $V_{25} = 2.79 \text{ FPS}$ $D_{25} = 0.93'$ S = 0.20%

 $Q_2 = 23.82 \text{ CFS}$ $V_2 = 2.26 \text{ FPS}$ $V_2 = 0.66'$ $V_3 = 0.20\%$



KEY MAP


REFER TO THE COVER SHEET FOR BENCHMARK INFORMATION.

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL

CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24-HOURS PRIOR TO COMMENCING CONSTRUCTION.

UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES.


ST 78 290 S. CASTELL / NEW BRAUNFELS TBPE FIRM F-109 TBPLS FIRM 1053



3B 4

ШО ZX


NT HEIGHTS SUIN, TEXAS GREENSPOIN





DATE: **JANUARY 2024** MK/RR DRAWN BY: DESIGNED BY: MA


REVIEWED BY: CC HMT PROJECT NO .:

310.012 **SHEET**









290 S. CASTELL AVE., STE. 100 NEW BRAUNFELS, TX 78130 TBPE FIRM F-10961 TBPLS FIRM 1053600

ENGINEERING & SURVEYING



3B

STORM DETAILS
(1 OF 2)
GREENSPOINT HEIGHTS UNIT
SEGUIN, TEXAS

DATE: JANUARY 2024

DRAWN BY: MK/RR

DATE: JANUARY 2024

DRAWN BY: MK/RR


DESIGNED BY: MA


REVIEWED BY: CC


HMT PROJECT NO.:


SHEET


310.012











■ 290 S. CASTELL AVE., STE. 100 NEW BRAUNFELS, TX 78130 TBPE FIRM F-10961 TBPLS FIRM 1053600

NGINEERING & SURVEYING TE



 \mathcal{C}

လ လ

GREENSPOIN SEG

STORM DETAILS (2 OF 2)

REVISION DATE						
REVISION DESCRIPTION						
NO.						
DATE	: ,	JANU	JARY	′ 20	24	
DRAW	VN BY			MK/	 ⁄RR	

DRAWN BY: MK/RR


DESIGNED BY: MA


REVIEWED BY: CC


HMT PROJECT NO.:


310.012


C4.05






























 \mathcal{C}

GREENSPOIN

WATER

SHEET

310.012

DATE: **JANUARY 2024**


DESIGNED BY: MA


REVIEWED BY: CC


HMT PROJECT NO.:


DRAWN BY:


MK/RR














NOTES:


- 1. INSTALLATIONS SHALL BE MADE IN ACCORDANCE WITH INFORMATION SHOWN ON APPLICABLE STANDARD DRAWINGS AND WILL BE INSPECTED BY S.H.W.S.C. CONSTRUCTION INSPECTION PERSONNEL.
- 2. CUSTOMER ALSO INSTALLS WATER LINES INCLUDING FITTINGS AND VALVES ON BOTH SIDES OF METER, INSTALL METER BOXES AND COVERS. ALL IN ACCORDANCE WITH INFORMATION ON APPLICABLE STANDARD DRAWING. A VENTED SPACER MAY BE USED TO ASSURE PROPER SPACING AND ALIGNMENT OF METER
- 3. CUSTOMER IS RESPONSIBLE FOR METER BOX AND PIPING SYSTEM UNTIL METER IS INSTALLED AND WATER IS CONNECTED. ANY MISSING OR DAMAGED PARTS SHALL BE REINSTALLED BY CUSTOMER WHO SHALL GUARANTEE, FOR A PERIOD OF ONE (1) YEAR FROM DATE OF ACCEPTANCE, THAT CONNECTIONS TO S.H.W.S.C. SYSTEMS ARE FREE FROM DEFECTS IN WORKMANSHIP OR MATERIAL. CUSTOMER ALSO HAS THE RESPONSIBILITY TO ASSURE THAT ALL VALVES AND STOPS, METER BOX AND REMAIN CLEAR OF SIDEWALKS AND OTHER OBSTRUCTIONS.
- 4. S.H.W.S.C. ACTIVITY IS LIMITED TO INSTALLATION OF THE WATER METER AND INSPECTION OF CONNECTIONS TO S.H.W.S.C. WATER SYSTEMS. FOR MAINTENANCE PURPOSES, S.H.W.S.C. RESPONSIBILITY ENDS AT THE CUSTOMER'S WATER CUT-OFF VALVE.
- 5. NO METER BOX SHALL BE SET IN SIDEWALK OR DRIVEWAY AREA WITHOUT WRITTEN APPROVAL FROM S.H.W.S.C.
- 6. PIPING AND TUBING IN STREET RIGHT-OF-WAY AND IN EASEMENT AREA SHALL BE BEDDED IN GRANULAR MATERIAL AS REQUIRED IN THE SPECIFICATIONS. SERVICE LINES SHALL HAVE A MINIMUM COVER BELOW FINAL GRADE OF 42-INCHES.


SPRINGS HILL WATER SLIPPLY CORPORATION	SINGLE WATER SERVICE CONNECTION				
SPRINGS HILL WATER SUPPLY CORPORATION		REVISIONS: 03/15/2022	STANDARD NO. WA-22		












CHRISTOPHER J. CRIM

111347

01/04/2024



CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL

DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS

AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S)

WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH

EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE

PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTORS IMPLEMENTATION OF

THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH |

EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR

TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY


RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM

IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF

INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.

TESTING NOTE

EXISTING 8" WASTEWATER LINE FROM MANHOLE C1 TO MANHOLE D8, SHALL BE PRE—TESTED PRIOR TO CONSTRUCTION. PRE—TESTING WILL ALSO INCLUDE REFERENCED MANHOLES.



3B

NT HEIGHTS I

GREENSPOIN

S. CASTEL BRAUNFE E FIRM F-1 S FIRM 10

CITY OF SEGUIN NOTES:

ALL UTILITIES TO BE CONSTRUCTED PRIOR TO STREETS.

ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT/SIDEWALK SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEOTECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. DETERMINE THE MAXIMUM LIFT THICKNESS BASED ON THE ABILITY OF THE COMPACTING OPERATION AND EQUIPMENT USED TO MEET THE REQUIRED DENSITY. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E. TEX-114-E AND TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEOTECHNICAL ENGINEER AND APPROVED BY THE CITY OF SEGUIN PROJECT INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 200LF FOR EACH LIFT AND EVERY OTHER SERVICE LINE. UPON COMPLETION OF TESTING THE GEOTECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SEGUIN PROJECT INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS ADDITION DENSITY TESTS MAY BE REQUESTED BY THE CITY OF SEGUIN PROJECT


FOR PROJECTS WITH TRENCH DEPTHS EXCEEDING 5 FEET:

THIS PROJECT INCLUDES UTILITY INSTALLATIONS GREATER THAN 5-FEET IN DEPTH LOCATED IN PUBLIC RIGHT-OF-WAY OR EASEMENTS. DEEP TRENCHES POSE COMPACTION TESTING AND CONSTRUCTION CHALLENGES AND CITY METHODS FOR TESTING AND COMPACTION MAY NOT BE ACHIEVABLE. A UTILITY COMPACTION PLAN WILL BE REQUIRED AND MUST BE SUBMITTED FOR APPROVAL TO CITY PRIOR TO UTILITY INSTALLATION.

WASTEWATER SYSTEM NOTE:

SANITARY SEWER LATERALS/SERVICE LINES SHALL BE DESIGNED AND INSTALLED TO ENSURE THAT CLEANOUTS WILL <u>NOT</u> BE LOCATED WITHIN THE RESIDENTIAL DRIVEWAY, DRIVEWAY APRON, SIDEWALK, CURB AND/OR PUBLIC STREETS. THE BUILDER AND/OR DEVELOPER WILL BE RESPONSIBLE FOR REPAIR TO ROADWAY AND UTILITY INFRASTRUCTURE IF PUBLIC UTILITIES ARE INSTALLED INCORRECTLY.

RECONSTRUCTION OF MANHOLE STRUCTURE AND CONE MAY REQUIRE RE—COATING OF WASTEWATER MANHOLE IN ACCORDANCE WITH CITY REQUIREMENTS. CONFIRM WITH FIELD INSPECTOR AND WATER/WASTEWATER MAINTENANCE MANAGER.



REFER TO THE COVER SHEET FOR BENCHMARK INFORMATION.

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL

UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES.
CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES
24—HOURS PRIOR TO COMMENCING CONSTRUCTION.

REVISION DESCRIPTION

ATE: JANUARY 2024


DRAWN BY: MK/RR

DESIGNED BY: MA

HMT PROJECT NO.:
310.012

SHEET


C6.01



INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.


— 700 — EXISTING CONTOURS

EXISTING CONTOURS



24-HOURS PRIOR TO COMMENCING CONSTRUCTION.

FOR BENCHMARK INFORMATION.



— 700 — EXISTING CONTOURS — EXISTING CONTOURS BUILDING SETBACK LINE U.E. UTILITY EASEMENT D.E. DRAINAGE EASEMENT EXISTING WASTEWATER MANHOLE EXISTING WASTEWATER LINE EXISTING WASTEWATER SERVICE PROPOSED WASTEWATER MANHOLE PROPOSED WASTEWATER LINE PROPOSED WASTEWATER SERVICE UTILITY CROSSING

BRAL FIRM S FIR


CHRISTOPHER J. CRIM

 \mathcal{C}

POIN SEGI

GREENS

REMOVE EXISTING CAP AND CONNECT TO EXISTING STUBOUT 3+65.00 WWTR LINE B 6+03.16 WWTR LINE B WW MH WW MH E1 │8" FL (OUT)=558.06'(S) √8" FL=566.99' (S) 6+60.02 WWTR LINE B= 8" FL (IN)=558.16' (N) 3+80.01 WWTR LINE E │ 8" FL (OUT)=569.00'(W) 8" FL (IN)=569.10'(E) 8" FL (OUT)=569.10'(S) LEX EX WW MH D5 12" FL (OUT)=551.44' (E 12" FL (IN)=551.54' (W) 245.00 LF 8" D3034 SDR26 238.16 LF 8" D3034 SDR26 8" FL (IN)=551.87' (N) REMOVE EXISTING CAP AND CONNECT TO EXISTING STUBOUT 1+20.00 WWTR LINE B 8" FL=552.34' (S)



CITY OF SEGUIN NOTES:

ALL UTILITIES TO BE CONSTRUCTED PRIOR TO STREETS.

ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT/SIDEWALK SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEOTECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. DETERMINE THE MAXIMUM LIFT THICKNESS BASED ON THE ABILITY OF THE COMPACTING OPERATION AND EQUIPMENT USED TO MEET THE REQUIRED DENSITY. EACH LAYER OF MATERIAL SHALL BE COMPACTED A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E AND TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL B DETERMINED BY THE GEOTECHNICAL ENGINEER AND APPROVED BY THE CITY OF SEGUIN PROJECT INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 200LF FOR EACH LIFT AND EVERY OTHER SERVICE LINE.
UPON COMPLETION OF TESTING THE GEOTECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SEGUIN PROJECT INSPECTOR WITH ALL TESTIN DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS. ADDITIONAL DENSITY TESTS MAY BE REQUESTED BY THE CITY OF SEGUIN PROJECT INSPECTOR.


FOR PROJECTS WITH TRENCH DEPTHS EXCEEDING 5 FEET:

THIS PROJECT INCLUDES UTILITY INSTALLATIONS GREATER THAN 5-FEET IN DEPTH LOCATED IN PUBLIC RIGHT-OF-WAY OR EASEMENTS. DEEP TRENCHES POSE COMPACTION TESTING AND CONSTRUCTION CHALLENGES AND CITY METHODS FOR TESTING AND COMPACTION MAY NOT BE ACHIEVABLE. A UTILITY COMPACTION PLAN WILL BE REQUIRED AND MUST BE SUBMITTED FOR APPROVAL TO CITY PRIOR TO UTILITY INSTALLATION.

WASTEWATER SYSTEM NOTE:

SANITARY SEWER LATERALS/SERVICE LINES SHALL BE DESIGNED AND INSTALLED TO ENSURE THAT CLEANOUTS WILL NOT BE LOCATED WITHIN THE RESIDENTIAL DRIVEWAY, DRIVEWAY APRON, SIDEWALK, CURB AND/OR PUBLIC STREETS. THE BUILDER AND OR DEVELOPER WILL BE RESPONSIBLE FOR REPAIR TO ROADWAY AND UTILITY INFRASTRUCTURE IF PUBLIC UTILITIES ARE INSTALLED INCORRECTLY.

RECONSTRUCTION OF MANHOLE STRUCTURE AND CONE MAY REQUIRE RE-COATING OF WASTEWATER MANHOLE IN ACCORDANCE WITH CITY REQUIREMENTS. CONFIRM WITH FIELD INSPECTOR AND WATER/WASTEWATER MAINTENANCE MANAGER.



DATE:

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES.

CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES

24-HOURS PRIOR TO COMMENCING CONSTRUCTION.

HMT PROJECT NO.:

REFER TO THE COVER SHEET FOR BENCHMARK INFORMATION.

AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS. PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTORS IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLÉMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF

INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.

TRENCH EXCAVATION SAFETY PROTECTION


CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS


JANUARY 2024


MK/RR DRAWN BY: DESIGNED BY: MA


EVIEWED BY: CC 310.012


SHEET
















BOLTING DETAIL

Drawing Revision 09/01/2017 Designer: MAH

→ 30" DIA → 33 7/8" DIA----——— 40 3/4" DIA—— FRAME SECTION

-1/4" DIA NEOPRENE GASKET











လ လ

GREENSPOIN SEG

JANUARY 2024

MK/RR DRAWN BY: DESIGNED BY: MA

REVIEWED BY: CC HMT PROJECT NO .: 310.012

SHEET