

## ATTACHMENT B:

## PROPOSAL PRICING

BID PROPOSAL GUADALUPE ST WATER & SEWER EXTENSIONS					
BASE BID					
ITEM		UNIT		UNIT PRICE	TOTAL
NO.	QTY	RATE	ITEM DESCRIPTION	IN FIGURES	AMOUNT
<b>GENERAL ITEMS</b>					
1	1	LS	MOBILIZATION, OVERHEAD, BOND AND CONSTRUCTION STAKING		
2	1	LS	SITE PREPARATION, TOPSOIL REMOVAL AND REPLACEMENT, COMPLETE IN PLACE		
3	1	LS	TRAFFIC CONTROL		
4	1	LS	POTHOLE EXSITING UTILITIES (INCLUDING TIE-IN POINTS)		
5	1	LS	EROSION & SEDIMENT CONTROL-SWPPP IMPLEMENTATION & MAINTENANCE, SILT FENCE, ETC. COMPLETE IN PLACE.		
6	1	LS	HYDROSEED AND HYDROMULCH, COMPLETE IN PLACE		
7	868	SF	ASPHALT REPAIR		
8	1	LS	CITY OF SEGUIN PERMITTING FEES, COORDINATION, INSPECTIONS		
<b>GENERAL ITEMS SUBTOTAL</b>					
<b>SANITARY SEWER CONSTRUCTION ITEMS</b>					
9	1843	LF	8" SDR 26 PVC - STRUCTURAL BACKFILL, COMPLETE IN PLACE		
10	7	EA	CONCRETE MANHOLE - 4' DIA., COMPLETE IN PLACE		
11	1	EA	8" SOLID CAP		
12	1	EA	CONNECT TO EXISTING MANHOLE, COMPLETE IN PLACE		
13	1	EA	CONNECT EXISTING LINE TO PROPOSED MANHOLE, COMPLETE IN PLACE		
14	1	LS	BYPASS PUMPING PLAN DEVELOPMENT AND IMPLEMENTATION		
15	1	LS	TEMPORARY UTILITY POLE SHORING		
16	6	EA	RELLECTIVE MARKERS		
<b>SANITARY SEWER ITEMS SUBTOTAL</b>					

<b>WATERLINE CONSTRUCTION ITEMS</b>					
<b>17</b>	<b>740</b>	<b>LF</b>	<b>12" PVC DR-18, C900 WATER PIPE W/TRACER WIRE - NON STRUCTURAL BACKFILL, COMPLETE IN PLACE</b>		
<b>18</b>	<b>73</b>	<b>LF</b>	<b>12" PVC DR-18, C900 WATER PIPE W/TRACER WIRE - STRUCTURAL BACKFILL, COMPLETE IN PLACE</b>		
<b>19</b>	<b>8</b>	<b>LF</b>	<b>8" PVC DR-18, C900 WATER PIPE W/TRACER WIRE - NON STRUCTURAL BACKFILL, COMPLETE IN PLACE</b>		
<b>20</b>	<b>1</b>	<b>EA</b>	<b>8"X8" CUT-IN TEE, M.J.</b>		
<b>21</b>	<b>1</b>	<b>EA</b>	<b>12"x8" REDUCER M.J., COMPLETE IN PLACE</b>		
<b>22</b>	<b>5</b>	<b>EA</b>	<b>12" GATE VALVE M.J., COMPLETE IN PLACE</b>		
<b>23</b>	<b>6</b>	<b>EA</b>	<b>6" VALVE BOX, COMPLETE IN PLACE</b>		
<b>24</b>	<b>2</b>	<b>EA</b>	<b>2" BLOW-OFF ASSEMBLY (TEMPORARY), COMPLETE IN PLACE</b>		
<b>25</b>	<b>2</b>	<b>EA</b>	<b>12"X12" TEE M.J., COMPLETE IN PLACE</b>		
<b>26</b>	<b>2</b>	<b>EA</b>	<b>12" SOLID CAP</b>		
<b>27</b>	<b>1</b>	<b>EA</b>	<b>12"X8" TEE M.J., COMPLETE IN PLACE</b>		
<b>28</b>	<b>1</b>	<b>EA</b>	<b>8" GATE VALVE M.J., COMPLETE IN PLACE</b>		
<b>29</b>	<b>1</b>	<b>EA</b>	<b>8" SOLID CAP</b>		
<b>30</b>	<b>1</b>	<b>EA</b>	<b>12" 1/4 BEND M.J., COMPLETE IN PLACE</b>		
<b>31</b>	<b>1</b>	<b>EA</b>	<b>CONNECT TO EXISTING 12" WATER LINE, REMOVE 12" D.I. PLUG, COMPLETE IN PLACE</b>		
<b>32</b>	<b>1</b>	<b>EA</b>	<b>CONNECT TO EXISTING 8" WATER LINE W/ 8"X8" CUT-IN TEE, M.J., COMPLETE IN PLACE</b>		
<b>32</b>	<b>1</b>	<b>LS</b>	<b>WATERLINE CHLORINATION AND TESTING</b>		
<b>WATERLINE ITEMS SUBTOTAL</b>					
<b>TOTAL GUADALUPE ST. WATER AND SEWER EXTENSIONS</b>					
<b>TOTAL CALENDAR DAYS</b>					