



CONSTRUCTION PLANS for HICKORY RIDGE SUBDIVISION PHASE 1 UNIT 2




1"=100'

	Sheet List Table
Sheet Number	Sheet Title
100	CONSTRUCTION COVER
200	UTILITY COVER & DETAILS
201	OVERALL UTILITY PLAN
300	SANITARY SEWER COVER
301	OVERALL SANITARY SEWER PLAN
302	SANITARY SEWER LINE A PLAN & PROFILE
303	SANITARY SEWER LINE B PLAN & PROFILE
304	SANITARY SEWER LINE C PLAN & PROFILE
305	SANITARY SEWER LINE D PLAN & PROFILE
306	SANITARY SEWER LINE E PLAN & PROFILE
307	SANITARY SEWER LINE F PLAN & PROFILE
308	SANITARY SEWER DETAILS
400	WATER COVER
401	OVERALL WATER PLAN
402	WATER DETAILS
403	WATER DETAILS
500	STREET & DRAIN COVER
501	OVERALL GRADING PLAN
501A	RETAINING WALL ELEVATION DETAIL
502	BONFIRE PASS PLAN & PROFILE
503	WASABI PASS PLAN & PROFILE
504	SWEET MARIGOLD PLAN & PROFILE
505	ANNATOO DR PLAN & PROFILE
506	SUMMER SAVORY PLAN & PROFILE
507	GREY ELM PLAN & PROFILE
508	HAZEL BIRCH PLAN & PROFILE
509	DRAIN A PLAN & PROFILE
510	DRAIN B PLAN & PROFILE
511	DRAIN C PLAN & PROFILE
512	STREET DETAILS
513	STREET DETAILS
514	DRAIN DETAILS
515	DRAIN DETAILS
516	OVERALL SIGN PLAN
517	SIGN DETAILS
518	SIGN DETAILS
600	SEDIMENTATION & EROSION CONTROL COVER
601	SEDIMENTATION & EROSION CONTROL PLAN
602	SEDIMENTATION & EROSION CONTROL COVER NOTES
603	SEDIMENTATION & EROSION CONTROL COVER DETAILS




T1550 IH 10 WEST, SUITE 395 IN ANTONIO, TEXAS 78230-1037 PHONE: (210) 641-9999 FAX: (210) 641-6440 ISTRATION #F-10573 / #101943-65




RIDGE SUBDIVISION PHASE 1 UNIT 2


DRAFTING: K.P./G.P. CHECK: CODESIGN: L.E. CHECK: M.F.
SUBMITTAL PHASE:
DATE: 12
KCI JOB #: 7622073


UTILITY PLANS & DETAILS for





HICKORY RIDGE SUBDIVISION PHASE 1 UNIT 2




























OWNER/DEVELOPER:

CASTLEROCK COMMUNITIES 2401 FOUNTAIN VIEW DRIVE, SUITE 215 HOUSTON, TEXAS 77057 PHONE: (713) 600-7060



PREPARED BY: KCI TECHNOLOGIES, INC.


11550 IH 10 WEST, SUITE 395 SAN ANTONIO, TEXAS 78230-1037 PHONE: (210) 641-9999 FAX: (210) 641-6440 REGISTRATION #F-10573 / #101943-65



TYPICAL LOCAL "A" STREET SECTION NOT TO SCALE

ESIGN: L.E. CHECK: M.F

SUBMITTAL PHASE: (CI JOB #:



SANITARY SEWER CONSTRUCTION for HICKORY RIDGE SUBDIVISION PHASE 1 UNIT 2

CONSTRUCTION NOTES

ALL DEVELOPER PROJECTS

AQUA TEXAS GENERAL NOTE

PROPOSED AQUA TEXAS FACILITIES INCLUDE ITEMS OF THE PROPOSED WORK THE DEVELOPER PLANS TO CONVEY TO AQUA TEXAS TO OWN AND OPERATE UPON COMPLETION OF THE WORK AND AFTER SATISFYING CERTAIN OTHER REQUIREMENTS.

AQUA TEXAS HAS NO AGREEMENT OR CONTRACT WITH THE CONTRACTOR. THE PROPOSED AQUA TEXAS FACILITIES

AQUA TEXAS HAS NOT PROVIDED REVIEW RELATED TO ITEMS OF WORK NOT RELATED TO PROPOSED OR EXISTING AQUA TEXAS FACILITIES OR CONTRACTORS' SAFETY PRECAUSTIONS OR MEANS, METHODS, TECHINIQUES, SQUENCES OR PROCEDURES REQUIRED FOR THE CONTRACTOR TO PEFORM THEIR WORK.

ANY CONTRACTOR(S) USING THESE DRAWINGS SHALL OBTAIN AND THEREAFTER KEEP IN FORCE THROUGH THE DURATION OF THAT USE CUSTOMARY AND APPROPRIATE INSURANCE COVERAGE, WHICH SHALL INCLUDE WORKERS COMPENSATION AND EMPLOYERS' LIABILITY, COMMERCIAL GENERAL LIABILITY, COMMERCIAL AUTOMOBILE LIABILITY, AND UMBRELLA LIABILITY. CERTIFICATE(S) OF INSURANCE BY THE INSURER(S) ISSUING THE POLICIES SHALL BE FILED WITH AQUA TEXAS PRIOR TO COMMENCING CONSTRUCTION OF AQUA TEXAS FACILITIES

ANY CONTRACTOR(S) USING THESE DRAWINGS, BY SAID USE, SHALL INDEMNIFY, DEFEND AND HOLD HARMLESS AQUATEXAS, ITS OFFICERS, DIRECTORS, EMPLOYEES AND AGENTS FROM AND AGAINST ANY AND ALL CLAIMS, DEMANDS, DEBTS, SUITS, CAUSES OF ACTION, LOSSES, DAMAGES, JUDGMENTS, FINES, PENALTIES, LIABILITIES, AND COSTS, INCLUDING REASONABLE ATTORNEY FEES AND DEFENSE COSTS (COLLECTIVELY "DAMAGES") INCURRED BY AQUA ARISING OUT OF CONSTRUCTION OF THE AQUA TEXAS FACILITIES.

THE DEVELOPER, ENGINEER, OR CONTRACTOR SHALL CHAIR OR ATTEND A PRECONSTRUCTION MEETING WHICH INCLUDES AQUA TEXAS PERSONNEL. CONTACT AQUA TEXAS' BUSINESS DEVELOPMENT ENGINEER TO COORDINATE THE MEETING ATTENDANCE, SCHEDULE, AND CONTENT.

THE CONTRACTOR SHALL WORK WITH FINAL ENGINEERING PLANS MARKED TO INDICATE APPROVAL BY AQUA TEXAS' ENGINEERING DEPARTMENT. THE CONTRACTOR SHALL HAVE APPROVED PLANS ON HAND ANYTIME PROPOSED AQUA TEXAS FACILITIES ARE BEING CONSTRUCTED OR DISTURBED. AQUA TEXAS' APPROVAL SHOULD BE NOTED ON THE COVER SHEET ALONG WITH THE DATE THE PLANS WERE APPROVED.

NO PLAN CHANGES OR FIELD CHANGES RELATED TO THE CONSTRUCTION OF PROPOSED AQUA TEXAS FACILITIES SHALL BE ALLOWED WITHOUT THE WRITTEN APPROVAL OF AN AQUA TEXAS ENGINEERING DEPARTMENT REPRESENTATIVE

CONTRACTOR SHALL NOTIFY AQUA TEXAS 48 HOURS BEFORE:

BEGINNING CONSTRUCTION OF PROPOSED AQUA TEXAS FACILITIES NOTIFY: AQUA ENGINEERING AND AQUA OPERATIONS*

CONDUCTING REQUIRED SAMPLING OR TESTING NOTIFY: AQUA OPERATIONS*

TAPPING, CONNECTING, MODIFYING OR IN ANY OTHER WAY DISTURBING AQUA TEXAS FACILITIES NOTIFY: AQUA OPERATIONS*
*(AQUA ENGINEERING AND OPERATIONS CONTACTS SHALL BE DESIGNATED AT THE PRE-CONSTRUCTION MEETING)

AN AQUA TEXAS REPRESENTATIVE MAY BE ON SITE FROM TIME TO TIME TO OBERVE AND RECORD

CONNECTION TO AQUA FACILITITES
CONSTRUCTION PROGRESS AND CONDITIONS

TESTING AND SAMPLING.

THESE OBSERVATIONS AND RECORDS IN NO WAY CONSTITUTE APPROVAL OR ACCEPTANCE OF WORK BY THE

A CONTRACTOR'S REPRESENTATIVE SHALL ATTEND A PRE-FINAL AND FINAL WALK THROUGH CALLED BY THE DEVELOPER. FOLLOWING THE PREFINAL WALK THROUGH THE CONTRACTOR AND OTHER ATTENDEES SHALL PREPARE AN AGREED, WRITTEN PUNCH LIST OF WORK NECESSARY FOR COMPLETION OF PROPOSED AQUA TEXAS FACILITIES IN ACCORDANCE WITH THE APPROVED FINAL ENGINEERING PLANS. THE PURPOSE OF THE FINAL WALK THROUGH IS TO CONFIRM COMPLETION OF THE PUNCH LIST WORK ITEMS.

SEWER NOTE

1. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT NO SANITARY SEWER OVERFLOW (SSO) OCCURS AS A RESULT OF THEIR WORK. ALL CONTRACTOR PERSONNEL RESPONSIBLE FOR SSO PREVENTION AND CONTROL SHALL BE TRAINED ON PROPER RESPONSE. SHOULD AN SSO OCCUR, THE CONTRACTOR SHALL:

A. IDENTIFY THE SOURCE OF THE SSO AND NOTIFY SAWS EMERGENCY OPERATIONS CENTER (EOC) IMMEDIATELY

AT (210) 233-2014. PROVIDE THE ADDRESS OF THE SPILL AND AN ESTIMATED VOLUME OR FLOW.

B. ATTEMPT TO ELIMINATE THE SOURCE OF THE SSO.

C. CONTAIN SEWAGE EPOM THE SSO TO THE EXTENT OF PREVENTING A POSSIBLE CONTAMINATION OF

C. CONTAIN SEWAGE FROM THE SSO TO THE EXTENT OF PREVENTING A POSSIBLE CONTAMINATION OF WATERWAYS.

D. CLEAN UP SPILL SITE (RETURN CONTAINED SEWAGE TO THE COLLECTION SYSTEM IF POSSIBLE) AND PROPERLY DISPOSE OF CONTAMINATED SOIL/MATERIALS.

E. CLEAN THE AFFECTED SEWER MAINS AND REMOVE ANY DEBRIS.
F. MEET ALL POST-SSO REQUIREMENTS AS PER THE EPA CONSENT DECREE, INCLUDING LINE CLEANING AND TELEVISING THE AFFECTED SEWER

MAINS (AT SAWS DIRECTION) WITHIN 24 HOURS.

SHOULD THE CONTRACTOR FAIL TO ADDRESS AN SSO IMMEDIATELY AND TO AQUA TEXAS INC'S SATISFACTION, THEY WILL BE RESPONSIBLE FOR ALL COSTS INCURRED BY AQUA TEXAS INC., INCLUDING ANY FINES FROM EPA, TCEQ

AND/OR ANY OTHER FEDERAL, STATE OR LOCAL AGENCIES.

NO SEPARATE MEASUREMENT OR PAYMENT SHALL BE MADE FOR THIS WORK. ALL WORK SHALL BE DONE ACCORDING TO GUIDELINES SET BY THE TCEQ AND AQUA TEXAS INC.

2. IF BYPASS PUMPING IS REQUIRED, THE CONTRACTOR SHALL PERFORM SUCH WORK IN ACCORDANCE WITH SAWS STANDARD SPECIFICATION FOR WATER AND SANITARY SEWER CONSTRUCTION, ITEM NO. 865, "BYPASS PUMPING".

3. PRIOR TO TIE-INS, ANY SHUTDOWNS OF EXISTING FORCE MAINS OF ANY SIZE MUST BE COORDINATED WITH THE

AQUA TEXAS INC. CONSTRUCTION INSPECTION DIVISION AT LEAST ONE WEEK IN ADVANCE OF THE SHUTDOWN. THE CONTRACTOR MUST ALSO PROVIDE A SEQUENCE OF WORK AS RELATED TO THE TIE-INS; THIS IS AT NO ADDITIONAL COST TO AQUA TEXAS INC. OR THE PROJECT AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SEQUENCE THE WORK ACCORDINGLY.

4. SEWER PIPE WHERE WATER LINE CROSSES SHALL BE 160 PSI AND MEET THE REQUIREMENTS OF ASTM D2241, TAC 217.53 AND TCEQ 290.44(E)(4)(B). CONTRACTOR SHALL CENTER A 20' JOINT OF 160 PSI PRESSURE RATED PVC AT THE PROPOSED WATER CROSSING.

5. ELEVATIONS POSTED FOR TOP OF MANHOLES ARE FOR REFERENCE ONLY: IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO MAKE ALLOWANCES AND ADJUSTMENTS FOR TOP OF MANHOLES TO MATCH THE FINISHED GRADE OF THE PROJECT'S IMPROVEMENTS. (NSPI)

6. SPILLS, OVERFLOWS, OR DISCHARGES OF WASTEWATER: ALL SPILLS, OVERFLOWS, OR DISCHARGES OF

WASTEWATER, RECYCLED WATER, PETROLEUM PRODUCTS, OR CHEMICALS MUST BE REPORTED IMMEDIATELY TO THE SAWS INSPECTOR ASSIGNED TO THE COUNTER PERMIT OR GENERAL CONSTRUCTION PERMIT (GCP). THIS REQUIREMENT APPLIES TO EVERY SPILL, OVERFLOW, OR DISCHARGE REGARDLESS OF SIZE.

7. MANHOLE AND ALL PIPE TESTING (INCLUDING THE TV INSPECTION) MUST BE PERFORMED AND PASSED PRIOR TO

SPECIFICATIONS FOR WATER AND SANITARY SEWER CONSTRUCTION.

8. ALL PVC PIPE OVER 14 FEET OF COVER SHALL BE EXTRA STRENGTH WITH MINIMUM PIPE STIFFNESS OF 115 PSI.


FINAL FIELD ACCEPTANCE BY AQUA TEXAS INC. CONSTRUCTION INSPECTION DIVISION, AS PER THE AQUA TEXAS INC.

8. ALL PVC PIPE OVER 14 FEET OF COVER SHALL BE EXTRA STRENGTH WITH MINIMUM PIPE STIFFNESS OF 115 PSI.

* SEWER MAINS & LATERALS CROSSING WATER MAINS SHALL COMPLY WITH 30 TAC 290.44(e) AND 30 TAC 217.53(d) (FORMERLY 30 TAC 317.13 APPENDIX E)

SANITARY SEWER TESTING REQUIREMENTS:

CONTRACTOR TO REFERENCE SAWS SPECIFICATION ITEM NO. 849 "SANITARY SEWER ACCEPTANCE TESTING" FOR SANITARY SEWER TESTING REQUIREMENTS.
WEBSITE: https://apps.saws.org/business_center/specs/constspecs/constspecs_2020/index.cfm





Sheet List Table						
Sheet Number	Sheet Title					
300	SANITARY SEWER COVER					
301	OVERALL SANITARY SEWER PLAN					
302	SANITARY SEWER LINE A PLAN & PROFILE					
303	SANITARY SEWER LINE B PLAN & PROFILE					
304	SANITARY SEWER LINE C PLAN & PROFILE					
305	SANITARY SEWER LINE D PLAN & PROFILE					
306	SANITARY SEWER LINE E PLAN & PROFILE					
307	SANITARY SEWER LINE F PLAN & PROFILE					
308	SANITARY SEWER DETAILS					

<u>EGEND</u>

EXISTING EDGE OF PAVEMENT — — — — — — — — —	
EXISTING SANITARY SEWER MAIN— — — — — — —	— E8"/12" SS— — —
PROPOSED SANITARY SEWER MAIN- — — — — — — —	P8"/12" SS
EXISTING WATER MAIN— — — — — — — — — —	— — — —E8"/16" PVС— — — —
PROPOSED WATER MAIN— — — — — — — — — —	P8"/12" PVC
PROPOSED STREET LIGHT (100 WATT/SINGLE ARM)— — —	☀ L.P.

OTES

- NOTES

 1. ALL RESIDENTIAL SEWER SERVICE LATERALS ARE 6" DIA. AND 35 FEET IN LENGTH
- UNLESS NOTED OTHERWISE.
 ALL RESIDENTIAL SEWER SERVICE LATERALS SHALL BE CAPPED AND SEALED.
- 3. LATERALS TO LOTS SHALL BE SLOPED FROM THE TEE OR STACK AT 2% THROUGH THE G.E.T.TV.E. LOCATED IN THE FRONT OF THE LOT.

 4. ALL SEWER PIPE TO BE SDR-26 UNLESS OTHERWISE NOTED.
- CONTRACTOR TO ENSURE LATERALS AT PROPOSED DRY UITLITY CROSSINGS ARE LOCATED AT A DEPTH TO AVOID ANY CONFLICT WITH DRY UTILITY INSTALLATION.

OWNER/DEVELOPER:

CASTLEROCK COMMUNITIES
2401 FOUNTAIN VIEW DRIVE, SUITE 215
HOUSTON, TEXAS 77057
PHONE: (713) 600-7060




KCI TECHNOLOGIES, INC. 11550 IH 10 WEST. SUITE 395

PREPARED BY:


11550 IH 10 WEST, SUITE 395 SAN ANTONIO, TEXAS 78230-1037 PHONE: (210) 641-9999 FAX: (210) 641-6440 REGISTRATION #F-10573 / #101943-65 TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR
STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL.
REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED
INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT
CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR
PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF THE SYSTEMS, PROGRAMS AND/OR
PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION, SAFETY PROTECTION
THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS.
SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE
OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE
WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS
WORKING IN AND AROUND TRENCH EXCAVATION.



TYPICAL LOCAL "A" STREET SECTION

NOT TO SCALE







ORY RIDGE SUB PHASE 1 UNIT 2


DRAFTING: K.P./G.P. CHECK: C.F.
DESIGN: L.E. CHECK: M.P.S
SUBMITTAL PHASE:


DATE: 12/2
KCI JOB #: 76220738


#: T: **?**^^











LOCATION MAP


TRENCH EXCAVATION SAFETY PROTECTION

Contractor and/or contractor's independently retained employee or structural design/geotechnical/safety/equipment consultant, if any, shall. review these plans and available geotechnical information and the anticipated installation site(s) within the project work area in order to implement Contractor's trench excavation safety protection systems, programs and/or procedures. The Contractor's implementation of the systems, programs and/or procedures shall provide for adequate trench excavation, safety protection that complies with as a minimum, OSHA standards for trench excavations. Specifically, Contractor and/or Contractor's independently retained employee or safety consultant shall implement a trench safety program in accordance with OSHA standards governing the presence and activities of individuals working in and around trench excavation.


ALL RESIDENTIAL SEWER SERVICE LATERALS ARE 6" DIA. AND 35 FEET IN LENGTH


- UNLESS NOTED OTHERWISE. ALL RESIDENTIAL SEWER SERVICE LATERALS SHALL BE CAPPED AND SEALED.


 LATERALS TO LOTS SHALL BE SLOPED FROM THE TEE OR STACK AT 2% THROUGH THE
- G.E.T.TV.E. LOCATED IN THE FRONT OF THE LOT. ALL SEWER PIPE TO BE SDR-26 UNLESS OTHERWISE NOTED.
- CONTRACTOR TO ENSURE LATERALS AT PROPOSED DRY UITLITY CROSSINGS ARE LOCATED AT A DEPTH TO AVOID ANY CONFLICT WITH DRY UTILITY INSTALLATION.




SANITARY SEWER LINE











TYPICAL SANITARY SEWER/ WATER CROSSING DETAIL NOT TO SCALE






















45° PVC BEND ___











CHNOLOGIE

DRAFTING: K.P./G.P. CHECK: (DESIGN: L.E. CHECK: M.P. SUBMITTAL PHASE: (CI JOB #: 762207389 308

DOGHOUSE MANHOLE CONSTRUCTION:


- **CONTRACTOR SHALL REFERENCE STD. PRECAST MANHOLE DETAIL ON SHEET 308 FOR CONSTRUCTION REQUIREMENTS** 1. EXCAVATE TO EXISTING 8" SANITARY SEWER MAIN, SEE PROFILE FOR DEPTH.
- 2. EXPOSE EXISTING 8" SANITARY SEWER MAIN AND PREPARE AREA FOR INSTALLATION OF CAST-IN-PLACE MANHOLE BASE, PRE-CAST BASE W/ DOGHOUSE KNOCKOUT AND PRECAST RISER SECTIONS.
- INSTALL CRUSHED STONE TO ESTABLISH FOUNDATION FOR CAST-IN-PLACE MANHOLE BASE. USE 2 6" X 8" X 16" SOLID CONCRETE BLOCKS STACKED TWO HIGH (TWO SETS ON EACH SIDE OF EX. MAIN) TO ELEVATE PRE-CAST BASE W/ DOGHOUSE KNOCKOUT TO ALLOW FOR AT MINIMUM 12" OF CONCRETE TO BE INSTALLED BETWEEN INVERT OF
- LOWEST PIPE AND AND CRUSHED STONE LAYER. 4. INSTALL PRE-CAST BASE W/ DOGHOUSE KNOCKOUT.
- INSTALL ADDITIONAL PRECAST RISER SECTIONS AS NEEDED.
- POUR THE CAST-IN-PLACE DOGHOUSE MANHOLE BASE AND FORM THE FLOWLINE INVERTS. INSTALL EXTERNAL PIPE DROP AS REQUIRED.
- SAW CUT AND REMOVE EXISTING SANITARY SEWER PIPE INSIDE THE DOGHOUSE MANHOLE AREA. 9. DURING STREET CONSTRUCTION: INSTALL CONE SECTION, THROAT RINGS, FLOWABLE FILL, I&I BARRIER, MANHOLE

EXISTING MANHOLE RECONSTRUCTION CONSTRUCTION: CONTRACTOR SHALL FOLLOW SAWS STANDARD SPECIFICATION FOR CONSTRUCTION ITEM NO. 855 RECONSTRUCTION OF EXISTING MANHOLES. https://apps.saws.org/business_center/specs/constspecs/index.cfm

BYPASS PUMPING NOTE:

CONTRACTOR SHALL FOLLOW SAWS STANDARD SPECIFICATION FOR CONSTRUCTION ITEM NO. 865 BYPASS PUMPING SMALL DIAMETER SANITARY SEWER MAINS. https://apps.saws.org/business_center/specs/constspecs/index.cfm

SANITARY SEWER TESTING REQUIREMENTS: CONTRACTOR TO REFERENCE SAWS SPECIFICATION ITEM NO. 849 "SANITARY SEWER ACCEPTANCE TESTING" FOR SANITARY SEWER TESTING REQUIREMENTS. https://apps.saws.org/business_center/specs/constspecs/constspecs_2020/index.cfm



TYPICAL SANITARY SEWER/ WATER CROSSING DETAIL

NOT TO SCALE

WATERLINE CONSTRUCTION PLANS

HICKORY RIDGE SUBDIVISION PHASE 1 UNIT 2


- ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL BE APPROVED BY TH


- DEVELOPER. THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF UNDERGROUND UTILITIES AND DRAINAGE STRUCTURES LEAST 1-2 WEEKS PRIOR TO CONSTRUCTION WHETHER SHOWN ON PLANS OR NOT. PLEASE ALLOW UP TO 7 BUSINESS DAYS FOR LOCATES REQUESTING PIPE LOCATION MARKERS ON SAWS FACILITIES. THE FOLLOWING CONTACT
- INFORMATION ARE SUPPLIED FOR VERIFICATION PURPOSES:
- CITY OF ELMENDORF TEXAS STATE WIDE ONE CALL LOCATOR 1-800-545-6005 OR 811
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING EXISTING FENCES, CURBS, STREETS, DRIVEWAYS, SIDEWALKS, LANDSCAPING AND STRUCTURES TO ITS ORIGINAL OR BETTER CONDITION IF DAMAGES ARE MADE AS A RESULT OF THE PROJECT'S CONSTRUCTION.
- 8. ALL WORK IN TEXAS DEPARTMENT OF TRANSPORTATION (TXDOT) AND/OR BEXAR COUNTY RIGHT-OF-WAY SHALL BE DONE IN ACCORDANCE WITH RESPECTIVE CONSTRUCTION SPECIFICATIONS AND PERMIT REQUIREMENTS.
- 9. THE CONTRACTOR SHALL COMPLY WITH CITY OF ELMENDORF OR OTHER GOVERNING MUNICIPALITY'S TREE ORDINANCES WHEN EXCAVATING NEAR TREES.
- 10. THE CONTRACTOR SHALL NOT PLACE ANY WASTE MATERIALS IN THE 100-YEAR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN PERMIT.
- 11. HOLIDAY WORK: CONTRACTORS WILL NOT BE ALLOWED TO PERFORM CITY WORK ON CITY RECOGNIZED HOLIDAYS. REQUEST SHOULD BE SENT TO THE CITY.
- WEEKEND WORK: CONTRACTORS ARE REQUIRED TO NOTIFY THE CITY OF ELMENDORF 48 HOURS IN ADVANCE TO REQUEST WEEKEND WORK. REQUEST SHOULD BE SENT TO THE CITY.
- ANY AND ALL CITY UTILITY WORK INSTALLED WITHOUT HOLIDAY/WEEKEND APPROVAL WILL BE SUBJECT TO BE UNCOVERED FOR PROPER INSPECTION. 12. COMPACTION NOTE (ITEM 804): THE CONTRACTOR SHALL BE RESPONSIBLE FOR METTING THE COMPACTION
- REQUIREMENTS ON ALL TRENCH BACKFILL AND FOR PAYING FOR THE TESTS PERFORMED BY A THIRD PARTY. COMPACTION TESTS WILL BE DONE AT ONE LOCATION POINT RANDOMLY SELECTED, OR AS INDICATED BY THE CITY INSPECTOR AND/OR THE TEST ADMINISTRATOR, PER EACH 12-INCH LOOSE LIFT PER 400 LINEAR FEET AT A MINIMUM. THIS PROJECT WILL NOT BE ACCEPTED AND FINALIZED BY THE CITY WITHOUT THIS REQUIREMENT BEING MET AND VERIFIED BY PROVIDING ALL NECESSARY DOCUMENTED TEST RESULTS.
- 13. A COPY OF ALL TESTING REPORTS SHALL BE FORWARDED TO THE CITY OF ELMENDORF.

WATER NOTES:


- 1. PRIOR TO TIE-INS, ANY SHUTDOWNS OF EXISTING MAINS OF ANY SIZE MUST BE COORDINATED WITH THE CITY OF ELMENDORF AT LEAST ONE WEEK IN ADVANCE OF THE SHUTDOWN. THE CONTRACTOR MUST ALSO PROVIDE A SEQUENCE OF WORK AS RELATED TO THE TIE-INS; THIS IS AT NO ADDITIONAL COST TO THE CITY OR THE PROJECT AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SEQUENCE THE WORK ACCORDINGLY.
- ASBESTOS CEMENT (AC) PIPE, ALSO KNOWN AS TRANSITE PIPE WHICH IS KNOWN TO CONTAIN ASBESTOS-CONTAINING MATERIAL (ACM), MAY BE LOCATED WITHIN THE PROJECT LIMITS. SPECIAL WASTE MANAGEMENT PROCEDURES AND HEALTH AND SAFETY REQUIREMENTS WILL BE APPLICABLE WHEN REMOVAL AND/OR DISTURBANCE OF THIS PIPE OCCURS. SUCH WORK IS TO BE MADE UNDER SPECIAL SPECIFICATION ITEM NO. 3000, "SPECIAL SPECIFICATION FOR
- 3. VALVE REMOVAL: WHERE THE CONTRACTOR IS TO ABANDON A WATER MAIN, THE CONTROL VALVE LOCATED ON THE ABANDONING BRANCH WILL BE REMOVED AND REPLACED WITH A CAP / PLUG. (NSPI)
- 4. SUITABLE ANCHORAGE/THRUST BLOCKING OR JOINT RESTRAINT SHALL BE PROVIDED AT ALL OF THE FOLLOWING MAIN LOCATIONS: DEAD ENDS, PLUGS, CAPS, TEES, CROSSES, VALVES, AND BENDS, IN ACCORDANCE WITH THE STANDARD DRAWINGS DD-839 SERIES AND ITEM NO. 839, IN THE SAWS STANDARD SPECIFICATIONS FOR CONSTRUCTION.
- 6. PIPE DISINFECTION WITH DRY HTH FOR PROJECTS LESS THAN 800 LINEAR FEET. (ITEM NO. 847.3): MAINS SHALL BE DISINFECTED WITH DRY HTH WHERE SHOWN IN THE CONTRACT DOCUMENTS OR AS DIRECTED BY THE INSPECTOR, AND SHALL NOT EXCEED A TOTAL LENGTH OF 800 FEET. THIS METHOD OF DISINFECTION WILL ALSO BE FOLLOWED FOR MAIN REPAIRS. THE CONTRACTOR SHALL UTILIZE ALL APPROPRIATE SAFETY MEASURE TO PROTECT HIS PERSONNEL DURING DISINFECTION OPERATIONS.
- 7. BACKFLOW PREVENTION DEVICES: ALL IRRIGATION SERVICES WITHIN RESIDENTIAL AREAS ARE REQUIRED TO HAVE BACKFLOW PREVENTION DEVICES. ALL COMMERCIAL BACKFLOW PREVENTION DEVICES MUST BE APPROVED BY SAWS PRIOR TO INSTALLATION.
- 9. FINAL CONNECTION TO THE EXISTING WATER MAIN SHALL NOT BE MADE UNTIL THE WATER MAIN HAS BEEN PRESSURE TESTED, CHLORINATED, AND THE CITY OF ELMENDORF HAS RELEASED THE MAIN FOR TIE-IN AND USE.


TRENCH EXCAVATION SAFETY PROTECTION CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL. REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF THE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION, SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.






LOCATION MAP





FIRE HYDRANT DETAIL ON LOCAL "A" NOTE: Sidewalks and fire hydrants shall be installed per City of San Antonio Standard Specifications for Construction and SAWS Standard Specifications

for Construction.



FIRE HYDRANT DETAIL @ CORNER NOT TO SCALE

NOTE: Sidewalks and fire hydrants shall be installed per City of San Antonio Standard Specifications for Construction and SAWS Standard

OWNER/DEVELOPER:

50' R.O.W.

TYPICAL LOCAL "A" STREET SECTION

NOT TO SCALE

PROPOSED SANITARY SEWER MAIN

TYPICAL SANITARY SEWER/

WATER CROSSING DETAIL

-CURB

REFERENCE SAWS SPEC. ITEM 812

SEPARATION DISTANCE TO

COMPLY TCEQ REGULATION

30 TAC 290.44 (E) APPENDIX E

& 30 TAC 217.53 (D) APPENDIX

D - SEPARATION DISTANCE.

PROPOSED WATER MAIN

FLEXIBLE BASE

SEE STREET

FINISHED

- GROUND/PAVEMENT (TOP OF GRADE)

WHERE SEWER PIPE CROSSES A

WATER LINE. THE SEWER SHALL

REQUIREMENTS OF ASTM 02241

- WITH ONE 20' JOINT CENTERED

BE 160PSI AND MEET THE

AT THE WATER CROSSING.

CASTLEROCK COMMUNITIES 2401 FOUNTAIN VIEW DRIVE, SUITE 215 HOUSTON, TEXAS 77057 PHONE: (713) 600-7060



KCI TECHNOLOGIES, INC.

PREPARED BY:

11550 IH 10 WEST, SUITE 395 SAN ANTONIO, TEXAS 78230-1037 PHONE: (210) 641-9999 FAX: (210) 641-6440 REGISTRATION #F-10573 / #101943-65

1) SAWS REQUIRES GCPs AND COUNTER PERMITS TO USE LEAD FREE


- 2) ANCHORAGE/THRUST BLOCKING AND JOINT RESTRAINTS SHALL BE
- DONE IN ACCORDANCE WITH SAWS STANDARD SPECIFICATIONS FOR CONSTRUCTION. (ITEM NO. 839)


3) THE CITY OF ELMENDORF WATER SYSTEM IS HEREBY GRANTED THE RIGHT OF INGRESS AND EGRESS ACROSS GRANTOR'S ADJACENT PROPERTY TO ACCESS THE WATER AND/OR WASTEWATER EASEMENTS SHOWN.




RAFTING: K.P./G.P. CHECK: ESIGN: L.E. CHECK: M.P SUBMITTAL PHASE:


CI JOB #:








DRAFTING: K.P./G.P. CHECK: DESIGN: L.E. CHECK: M.P SUBMITTAL PHASE: 762207389











GENERAL NOTES:

- 1. ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL BE APPROVED BY THE CITY OF ELMENDORF AND COMPLY WITH THE PLANS, SPECIFICATIONS, GENERAL CONDITIONS AND WITH THE FOLLOWING AS APPLICABLE:
- A. CURRENT TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) "DESIGN CRITERIA FOR DOMESTIC WASTEWATER SYSTEM," TEXAS ADMINISTRATIVE CODE (TAC) TITLE 30 PART 1 CHAPTER 290
- B. CURRENT TXDOT "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS AND DRAINAGE."C. CURRENT "SAN ANTONIO WATER SYSTEM STANDARD SPECIFICATIONS FOR WATER AND SANITARY SEWER
- CONSTRUCTION."
- D. CURRENT CITY OF SAN ANTONIO "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION."

E. CURRENT CITY OF SAN ANTONIO "UTILITY EXCAVATION CRITERIA MANUAL" (UECM).

- 2. THE CONTRACTOR SHALL NOT PROCEED WITH ANY PIPE INSTALLATION WORK UNTIL THEY OBTAIN APPROVAL FROM THE CITY OF ELMENDORF AND HAS BEEN NOTIFIED BY THE CITY TO PROCEED WITH THE WORK AND HAS ARRANGED A MEETING WITH THE INSPECTOR AND CONSULTANT FOR THE WORK REQUIREMENTS. WORK COMPLETED BY THE CONTRACTOR WITHOUT APPROVAL BY THE CITY WILL BE SUBJECT TO REMOVAL AND REPLACEMENT AT THE EXPENSE OF THE CONTRACTORS AND/OR THE DEVELOPER.
- 3. THE CONTRACTOR SHALL OBTAIN THE SAWS STANDARD DETAILS FROM THE SAWS WEBSITE,
- HTTP://WWW.SAWS.ORG/BUSINESS_CENTER/SPECS. UNLESS OTHERWISE NOTED WITHIN THE DESIGN PLAN.

 4. THE CONTRACTOR IS TO MAKE ARRANGEMENTS WITH THE CITY OF ELMENDORF AT (210) 635-8210, ON NOTIFICATION PROCEDURES THAT WILL BE USED TO NOTIFY AFFECTED HOME RESIDENTS AND/OR PROPERTY OWNERS 48 HOURS PRIOR TO BEGINNING ANY WORK.
- 5. LOCATION AND DEPTH OF EXISTING UTILITIES AND SERVICE LATERALS SHOWN ON THE PLANS ARE UNDERSTOOD TO BE APPROXIMATE. ACTUAL LOCATIONS AND DEPTHS MUST BE FIELD VERIFIED BY THE CONTRACTOR AT LEAST 1 WEEK PRIOR TO CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO LOCATE UTILITY SERVICE LINES AS REQUIRED FOR CONSTRUCTION AND TO PROTECT THEM DURING CONSTRUCTION AT NO COST TO THE CITY OR THE DEVELOPER.
- 6. THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF UNDERGROUND UTILITIES AND DRAINAGE STRUCTURES AT LEAST 1-2 WEEKS PRIOR TO CONSTRUCTION WHETHER SHOWN ON PLANS OR NOT. PLEASE ALLOW UP TO 7 BUSINESS DAYS FOR LOCATES REQUESTING PIPE LOCATION MARKERS ON SAWS FACILITIES. THE FOLLOWING CONTACT INFORMATION ARE SUPPLIED FOR VERIFICATION PURPOSES:
- CITY OF ELMENDORF
 TEXAS STATE WIDE ONE CALL LOCATOR
 210-635-8210
 1-800-545-6005 OR 811
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING EXISTING FENCES, CURBS, STREETS, DRIVEWAYS, SIDEWALKS, LANDSCAPING AND STRUCTURES TO ITS ORIGINAL OR BETTER CONDITION IF DAMAGES ARE MADE AS A RESULT OF THE PROJECT'S CONSTRUCTION.
- 8. ALL WORK IN TEXAS DEPARTMENT OF TRANSPORTATION (TXDOT) AND/OR BEXAR COUNTY RIGHT-OF-WAY SHALL BE DONE IN ACCORDANCE WITH RESPECTIVE CONSTRUCTION SPECIFICATIONS AND PERMIT REQUIREMENTS.
- 9. THE CONTRACTOR SHALL COMPLY WITH CITY OF ELMENDORF OR OTHER GOVERNING MUNICIPALITY'S TREE ORDINANCES WHEN EXCAVATING NEAR TREES.
- 10. THE CONTRACTOR SHALL NOT PLACE ANY WASTE MATERIALS IN THE 100-YEAR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN PERMIT.
- 11. HOLIDAY WORK: CONTRACTORS WILL NOT BE ALLOWED TO PERFORM CITY WORK ON CITY RECOGNIZED HOLIDAYS. REQUEST SHOULD BE SENT TO THE CITY.
- WEEKEND WORK: CONTRACTORS ARE REQUIRED TO NOTIFY THE CITY OF ELMENDORF 48 HOURS IN ADVANCE TO REQUEST WEEKEND WORK. REQUEST SHOULD BE SENT TO THE CITY.
- REQUEST WEEKEND WORK. REQUEST SHOULD BE SENT TO THE CITY.

 ANY AND ALL CITY UTILITY WORK INSTALLED WITHOUT HOLIDAY/WEEKEND APPROVAL WILL BE SUBJECT TO BE
- UNCOVERED FOR PROPER INSPECTION.

 12. COMPACTION NOTE (ITEM 804): THE CONTRACTOR SHALL BE RESPONSIBLE FOR METTING THE COMPACTION REQUIREMENTS ON ALL TRENCH BACKFILL AND FOR PAYING FOR THE TESTS PERFORMED BY A THIRD PARTY. COMPACTION TESTS WILL BE DONE AT ONE LOCATION POINT RANDOMLY SELECTED, OR AS INDICATED BY THE CITY
- INSPECTOR AND/OR THE TEST ADMINISTRATOR, PER EACH 12-INCH LOOSE LIFT PER 400 LINEAR FEET AT A MINIMUM. THIS PROJECT WILL NOT BE ACCEPTED AND FINALIZED BY THE CITY WITHOUT THIS REQUIREMENT BEING MET AND VERIFIED BY PROVIDING ALL NECESSARY DOCUMENTED TEST RESULTS.

13. A COPY OF ALL TESTING REPORTS SHALL BE FORWARDED TO THE CITY OF ELMENDORF.

WATER NOTES

- PRIOR TO TIE-INS, ANY SHUTDOWNS OF EXISTING MAINS OF ANY SIZE MUST BE COORDINATED WITH THE CITY OF ELMENDORF AT LEAST ONE WEEK IN ADVANCE OF THE SHUTDOWN. THE CONTRACTOR MUST ALSO PROVIDE A SEQUENCE OF WORK AS RELATED TO THE TIE-INS; THIS IS AT NO ADDITIONAL COST TO THE CITY OR THE PROJECT AND
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SEQUENCE THE WORK ACCORDINGLY.

 2. ASBESTOS CEMENT (AC) PIPE, ALSO KNOWN AS TRANSITE PIPE WHICH IS KNOWN TO CONTAIN ASBESTOS-CONTAINING MATERIAL (ACM), MAY BE LOCATED WITHIN THE PROJECT LIMITS. SPECIAL WASTE MANAGEMENT PROCEDURES AND HEALTH AND SAFETY REQUIREMENTS WILL BE APPLICABLE WHEN REMOVAL AND/OR DISTURBANCE OF THIS PIPE OCCURS. SUCH WORK IS TO BE MADE UNDER SPECIAL SPECIFICATION ITEM NO. 3000, "SPECIAL SPECIFCATION FOR HANDLING ASBESTOS CEMENT PIPE."
- 3. VALVE REMOVAL: WHERE THE CONTRACTOR IS TO ABANDON A WATER MAIN, THE CONTROL VALVE LOCATED ON THE
- ABANDONING BRANCH WILL BE REMOVED AND REPLACED WITH A CAP / PLUG. (NSPI)

 4. SUITABLE ANCHORAGE/THRUST BLOCKING OR JOINT RESTRAINT SHALL BE PROVIDED AT ALL OF THE FOLLOWING MAIN LOCATIONS: DEAD ENDS, PLUGS, CAPS, TEES, CROSSES, VALVES, AND BENDS, IN ACCORDANCE WITH THE STANDARD
- DRAWINGS DD-839 SERIES AND ITEM NO. 839, IN THE SAWS STANDARD SPECIFICATIONS FOR CONSTRUCTION.

 5. ALL VALVES SHALL READ "OPEN RIGHT."
- 6. PIPE DISINFECTION WITH DRY HTH FOR PROJECTS LESS THAN 800 LINEAR FEET. (ITEM NO. 847.3): MAINS SHALL BE DISINFECTED WITH DRY HTH WHERE SHOWN IN THE CONTRACT DOCUMENTS OR AS DIRECTED BY THE INSPECTOR, AND SHALL NOT EXCEED A TOTAL LENGTH OF 800 FEET. THIS METHOD OF DISINFECTION WILL ALSO BE FOLLOWED FOR MAIN REPAIRS. THE CONTRACTOR SHALL UTILIZE ALL APPROPRIATE SAFETY MEASURE TO PROTECT HIS PERSONNEL DURING DISINFECTION OPERATIONS.
 7. BACKFLOW PREVENTION DEVICES:
- ALL IRRIGATION SERVICES WITHIN RESIDENTIAL AREAS ARE REQUIRED TO HAVE BACKFLOW PREVENTION DEVICES.
 ALL COMMERCIAL BACKFLOW PREVENTION DEVICES MUST BE APPROVED BY SAWS PRIOR TO INSTALLATION.
- 9. FINAL CONNECTION TO THE EXISTING WATER MAIN SHALL NOT BE MADE UNTIL THE WATER MAIN HAS BEEN PRESSURE TESTED, CHLORINATED, AND THE CITY OF ELMENDORF HAS RELEASED THE MAIN FOR TIE-IN AND USE.

ADDITIONAL NOTES:


- 1. LEAD FREE (0.25% LEAD) FIRE HYDRANTS TO BE USED.
- 2. ATTENTION CONTRACTORS: ALL SPILLS, OVERFLOWS, OR DISCHARGES OF WASTEWATER, RECYCLED WATER, PETROLEUM PRODUCTS, OR CHEMICALS MUST BE REPORTED IMMEDIATELY TO THE CITY. THIS REQUIREMENT APPLIES TO EVERY SPILL, OVERFLOW, OR DISCHARGE REGARDLESS OF SIZE. YOUR COMPLIANCE WILL ENABLE SAWS TO FULFIL REGULATORY REPORTING REQUIREMENTS.
- IT IS THE CONTRACTORS RESPONSIBILITY TO CONTROL SEWER FLOWS SO THAT A SPILL OVERFLOW, OR DISCHARGE DOES NOT OCCUR, IN THE EVENT THAT A SPILL, OVERFLOW, OR DISCHARGE OCCURS, THE CONTRACTOR MAY BE HELD LIABLE FOR:
- ALL FINES, PENALTIES, OR OTHER COSTS ASSESSED TO OR AGAINST BY SAWS BY ANY STATE, FEDERAL, OR OTHER GOVERNMENTAL AGENCY.
- CITY STAFF AND MATERIAL COSTS TO RESPOND TO THE SPILL, OVERFLOW, OR DISCHARGE, OR TO MITIGATE THE
- EFFECTS OF THE SPILL, OVERFLOW, OR DISCHARGE, OR TO SUPPORT THE CLEANUP EFFORT.
- ALL DAMAGES CAUSED TO CITY, OR ANY OTHER PERSONS OR ENTITIES THAT RESULT FROM THE SPILL, OVERFLOW, OR DISCHARGE
- DISCHARGE.

 3. ALL PROPOSED 8" PVC WATER PIPE SHALL BE C900 CLASS 235 DR-18.
- 4. ALL WATER METERS SHALL BE $\frac{5}{8}$ " UNLESS OTHERWISE NOTED.

ICKORY RIDGE SUBDIVISION PHASE 1 UNIT 2

DRAFTING: K.P./G.P. CHECK: C.F.
DESIGN: L.E. CHECK: M.P.S
SUBMITTAL PHASE:

DATE: 12/2
KCI JOB #: 76220738



STREET & DRAIN PLANS for HICKORY RIDGE SUBDIVISION PHASE 1 UNIT 2

LEGEND

WHEELCHAIR RAMPS ————————————————————————————————————	
WHEELCHAIR RAMP TYPE (I-IV)	1234
SINGLE DIRECTIONAL WHEELCHAIR RAMP ————	<u>01</u>
DUAL DIRECTIONAL WHEELCHAIR RAMP —————	© 2
WASHOUT CROWN —	
SIDEWALK TO BE BUILT BY DEVELOPER ————————————————————————————————————	
PROPOSED DRIVEWAY —	(OW)
TOP OF PVMT. ELEVATION ————————————————————————————————————	(940.00)
EXISTING STREET LIGHT ————————————————————————————————————	•ELP
PROPOSED STREET LIGHT (100 WATT)	•LP
PROPOSED FIRE HYDRANT ————————————————————————————————————	
EXISTING FIRE HYDRANT ————————————————————————————————————	

BEXAR COUNTY RIGHT OR WAY PERMIT MUST BE OBTAINED PRIOR TO WORKING IN EXISTING BEXAR COUNTY RIGHT OF WAY

GENERAL NOTES

1. All materials and construction procedures within the scope of this project shall, be approved by the City of San Antonio Public Works and comply with the following as applicable:

A. Reference to Current "San Antonio Water System Utility Specifications"

B. Reference to Current City of San Antonio "Standard Specifications for Public Works Construction"

2. The locations and depths of existing utilities, including service laterals, and drainage structures shown on the plans are approximate only. The Contractor shall verify the exact location and depths of underground utilities at least 48 hours prior to construction whether shown on plans or not, and to protect the same during construction. Texas State Wide One Call Locator 1—800—545—6005 City Public Service AT&T Time Warner Valero Energy Co.

3. The Contractor shall notify the City prior to the start of each phase of street construction and call for inspections with a minimum of 24 hours notice.

4. Testing will be paid for by Developer, coordinated by Contractor, and witnessed by City.

5. Minimum Testing Schedule:

Densities — Subgrade

Densities — Base

Proctors — Subgrade

Proctors — Base

Lime Series — Subgrade

Concrete — Structures

1 Per 500 Foot Minimum

1 Per Material Per Subdivision

1 Per 5,000 C.Y.

1 Per Material Per Subdivision

1 Set (3) Per 50 C.Y.

6. Transition washout crown to normal crown in 25'.

construction materials and/or debris.

7. No extra payment shall be allowed for work called for on the plans, but not included in the bid proposal. This incidental work will be required and shall be included in the pay item to which it relates.

8. The contractor shall be responsible for restoring to its original or better condition any damage done to existing fences, concrete islands, street paving, curbs, shrubs, bushes or driveways. (No separate pay item).

9. Due to federal regulations Title 49, Part 192.171 CPS must maintain access to gas valves at all times. The contractor must protect and work around any gas valves that are in the project area.

10. Contractor shall notify the city inspector twenty four (24) hours prior to backfill of any utility trenches to schedule for density test as required.

11. All waste material shall become property of the contractor and shall be his sole responsibility to dispose of this material off the limits of the project. No waste material shall be placed in existing lows

that will block or alter flow limits of existing artificial or natural drainage.

12. The contractor shall not place any waste material in the 100—year flood plain without first obtaining an


approved Flood Plain Development Permit.

13. The contractor shall maintain all adjoining streets and traveled routes free from spilled and/or tracked


14. It is the contractor's responsibility to see that all signs and barricades are properly installed and maintained. All locations and distances will be decided upon in the field by the contractor, using the "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES". The City's construction inspector will only be responsible to inspect barricades and signs. If, in the opinion of the construction inspector, the barricades and signs do not conform to established standards or are incorrectly placed or are insufficient in quantity to protect the general public, the inspector shall have the option to stop operations until such time as

TRENCH EXCAVATION SAFETY PROTECTION

Contractor and/or contractor's independently retained employee or structural design/geotechnical/safety/equipment consultant, if any, shall. review these plans and available geotechnical information and the anticipated installation site(s) within the project work area in order to implement Contractor's trench excavation safety protection systems, programs and/or procedures. The Contractor's implementation of the systems, programs and/or procedures shall provide for adequate trench excavation, safety protection that complies with as a minimum, OSHA standards for trench excavations. Specifically, Contractor and/or Contractor's independently retained employee or safety consultant shall implement a trench safety program in accordance with OSHA standards governing the presence and activities of individuals working in and around trench excavation.



LOCATION MAP



INTERSECTION & CUL DE SAC KEY MAP

OWNER/DEVELOPER:

CASTLEROCK COMMUNITIES

2401 FOUNTAIN VIEW DRIVE, SUITE 215

HOUSTON, TEXAS 77057

PHONE: (713) 600-7060

515 516 517 518

PREPARED BY:

KCI TECHNOLOGIES, INC.

Sheet Number

501A

503

509

510

Sheet List Table

STREET & DRAIN COVER

OVERALL GRADING PLAN

Sheet Title

RETAINING WALL ELEVATION DETAIL

SWEET MARIGOLD PLAN & PROFILE

SUMMER SAVORY PLAN & PROFILE

BONFIRE PASS PLAN & PROFILE

WASABI PASS PLAN & PROFILE

ANNATOO DR PLAN & PROFILE

GREY ELM PLAN & PROFILE

DRAIN A PLAN & PROFILE

DRAIN B PLAN & PROFILE

DRAIN C PLAN & PROFILE

STREET DETAILS

STREET DETAILS

DRAIN DETAILS

DRAIN DETAILS

SIGN DETAILS

SIGN DETAILS

OVERALL SIGN PLAN

HAZEL BIRCH PLAN & PROFILE

11550 IH 10 WEST, SUITE 395 SAN ANTONIO, TEXAS 78230-1037 PHONE: (210) 641-9999 FAX: (210) 641-6440 REGISTRATION #F-10573 / #101943-65

OGIES, INC.	ST, SUITE 395 EXAS 78230-1037 FURPOSES ONLY	0) 641-9999 641-6440 10573 / #101943-65
KCI TECHNOLOGIES, INC.	11550 IH 10 WEST, SUITE 395 SAN ANTONIO, TEXAS 78230-1037	PHONE: (210) 641-9999 FAX: (210) 641-6440 REGISTRATION #E-10573 / #101943-65
SKORY RIDGE SUBDIVISION	PHASE 1 UNIT 2	STREET & DRAIN COVER


RAFTING: K.P./G.P. CHECK:


SUBMITTAL PHASE:


(CI JOB #:


DESIGN: L.E. CHECK: M.P

500









LOCATION MAP NOT TO SCALE

STREETLIGHT NOTE STREETLIGHT POLES TO BE IN OPEN GREEN SPACE WHERE SHOWN ON PLANS.


CITY OF SAN ANTONIO WHEELCHAIR RAMP ~ TYPE I DRIVEWAY NOTE CITY OF SAN ANTONIO WHEELCHAIR RAMP ~ TYPE II DRIVEWAYS SHOWN ON THIS PLAN ARE FOR THE SOLE PURPOSE OF INDICATING A POTENTIAL CONFLICT WITH CITY OF SAN ANTONIO WHEELCHAIR RAMP ~ TYPE III CURB RAMP, DRAINAGE INFRASTRUCTURE, OR OTHER CONFLICT. DRIVEWAY LOCATION IS SUBJECT TO CHANGE


CITY OF SAN ANTONIO WHEELCHAIR
RAMP ~ TYPE IV (D1) TYPICAL SIDEWALK RAMP ~ SINGLE


D2 TYPICAL SIDEWALK RAMP ~ DUAL REFER TO WHEELCHAIR RAMP STANDARDS ON STREET DETAILS.

Line Table				Curve Table					
е	Length	Direction		Curve #	Length	Radius	Delta	Chord Direction	Chord Length
	14.00'	S09°35'57"W		C1	13.27'	500.00'	001°31'14"	N57° 51' 34"E	13.27'
!	158.97'	N57°05'57"E	ļ '						
	400 541	115000714485	ı						

					Curve Ta	able	
ength	Direction	Curve #	Length	Radius	Delta	Chord Direction	Chord Length
4.00'	S09°35'57"W	C1	13.27'	500.00'	001°31'14"	N57° 51' 34"E	13.27'
58.97'	N57°05'57"E						
08.51'	N58°37'11"E						
4	3.00' 8.97'	8.97' N57°05'57"E	00' S09°35'57"W C1 3.97' N57°05'57"E	00' S09°35'57"W C1 13.27'	.00' S09°35'57"W C1 13.27' 500.00' 3.97' N57°05'57"E	00' \$09°35'57"W C1 13.27' 500.00' 001°31'14" 8.97' N57°05'57"E	0.00' \$09°35'57"W 8.97' \$N57°05'57"E C1 13.27' \$500.00' \$001°31'14" \$N57° 51' 34"E







LEGEND

WHEELCHAIR RAMPS

PROPOSED DRIVEWAY

TOP OF CURB ELEVATION EXISTING STREET LIGHT

SIDEWALK TO BE BUILT BY DEVELOPER


PROPOSED STREET LIGHT (100 WATT)


WASHOUT CROWN

08080


940

★ ELP





DRAFTING: K.P./G.P. CHECK: DESIGN: L.E. CHECK: M.P SUBMITTAL PHASE: KCI JOB #:



LOCATION MAP NOT TO SCALE

∕-512.97 P

STREETLIGHT NOTE STREETLIGHT POLES TO BE IN OPEN GREEN SPACE WHERE SHOWN ON PLANS.

DRIVEWAY NOTE DRIVEWAYS SHOWN ON THIS PLAN ARE FOR THE SOLE PURPOSE OF INDICATING A POTENTIAL CONFLICT WITH CURB RAMP, DRAINAGE INFRASTRUCTURE, OR OTHER CONFLICT. DRIVEWAY LOCATION IS SUBJECT TO CHANGE BASED ON HOME SELECTION AND FINAL LOT DESIGN.

CITY OF SAN ANTONIO WHEELCHAIR
RAMP ~ TYPE I
CITY OF SAN ANTONIO WHEELCHAIR
RAMP ~ TYPE II CITY OF SAN ANTONIO WHEELCHAIR
RAMP ~ TYPE III
CITY OF SAN ANTONIO WHEELCHAIR
RAMP ~ TYPE IV

(D1) TYPICAL SIDEWALK RAMP ~ SINGLE (D2) TYPICAL SIDEWALK RAMP ~ DUAL

> REFER TO WHEELCHAIR RAMP STANDARDS ON STREET DETAILS.


ine Table					Curve T	able	
ength	Direction	Curve #	Length	Radius	Delta	Chord Direction	Chord Lengt
14.00'	N67°07'05"E	C1	44.99'	100.00'	025°46'40"	N22° 07' 05"E	44.61'
217.74'	N09°13'45"E						

L5 14.00' S09°59'35"E


ble			able			
Direction	Curve #	Length	Radius	Delta	Chord Direction	Chord Length
N67°07'05"E	C1	44.99'	100.00'	025°46'40"	N22° 07' 05"E	44.61'
N09°13'45"E						

LEGEND

2000 WHEELCHAIR RAMPS WASHOUT CROWN SIDEWALK TO BE BUILT BY DEVELOPER PROPOSED DRIVEWAY




TOP OF CURB ELEVATION	940
EXISTING STREET LIGHT	- ★ ELP
PROPOSED STREET LIGHT (100 WATT)	- ★ LP




	SCALE: 1" =	30'
POINT	CURB ELEV.	GUTTER ELEV
LT. PC	513.82	513.24
Α	514.24	513.66
В	514.76	514.18
С	515.17	514.59
D	515.30	514.72
Е	515.21	514.63
F		513.51

514.41




INTERSECTION DETAIL #1

SCALE: 1" = 10'



SWEET MARIGOLD


STA. 1+00.00 TO STA. 4+13.17



SUBDIVISION UNIT 2 PROFILE MARIGOL SWEET

TECHNOLOGIES

DRAFTING:K.P./G.P. CHECK: C.
DESIGN: L.E. CHECK: M.P. SUBMITTAL PHASE: KCI JOB #:



LOCATION MAP NOT TO SCALE

STREETLIGHT NOTE STREETLIGHT POLES TO BE IN OPEN GREEN SPACE WHERE SHOWN ON PLANS.

CITY OF SAN ANTONIO WHEELCHAIR RAMP ~ TYPE I

CITY OF SAN ANTONIO WHEELCHAIR RAMP ~ TYPE II DRIVEWAY NOTE DRIVEWAYS SHOWN ON THIS PLAN ARE FOR THE SOLE PURPOSE OF INDICATING A POTENTIAL CONFLICT WITH CURB RAMP, DRAINAGE INFRASTRUCTURE, OR OTHER CONFLICT. DRIVEWAY LOCATION IS SUBJECT TO CHANGE

CITY OF SAN ANTONIO WHEELCHAIR RAMP ~ TYPE III CITY OF SAN ANTONIO WHEELCHAIR
RAMP ~ TYPE IV


(D1) TYPICAL SIDEWALK RAMP ~ SINGLE D2 TYPICAL SIDEWALK RAMP ~ DUAL REFER TO WHEELCHAIR RAMP STANDARDS ON STREET DETAILS.


Line Table Line Length Direction L1 145.00' N35°00'25"E

LEGEND

WHEELCHAIR RAMPS WASHOUT CROWN SIDEWALK TO BE BUILT BY DEVELOPER PROPOSED DRIVEWAY


940 TOP OF CURB ELEVATION EXISTING STREET LIGHT ★ ELP PROPOSED STREET LIGHT (100 WATT)






ANNATTO DR.


STA. 1+00.00 TO STA. 2+45.00







SUBDIVISION

DRAFTING:K.P./G.P. CHECK: C.F
DESIGN: L.E. CHECK: M.P.S SUBMITTAL PHASE: KCI JOB #:











| TECHNOLOGIES, 11550 IH 10 WEST, SUITE 395 SAN ANTONIO, TEXAS 78230-1037 PHONE: (210) 641-9999 FAX: (210) 641-6440

(CI JOB #:









GEOTECHNICAL ENGINEERING STUDY (HICKORY RIDGE PHASE 1 UNIT 2) BY: RABA KISTNER PROJECT: NO. ASA22-114-00 JANUARY 9, 2023


LOCAL A PRIMARY PAVEMENT DESIGN

PAVEMENT DESIGN WAS PREPARED BY RABA KISTNER

PAVEMENT STRUCTURE (DESIGN CBR=5.0)	STR. COEF.	STR. NO.
2" HOT MIX ASPHALT TYPE D	0.44	0.88
8" FLEXIBLE BASE (TYPE A, GRADE 1 OR 2)	0.14	1.12
6" LIME STABILIZED SUBGRADE (18#/S.Y.)	0.08	0.48
	TOTAL	2.48

HAZEL BIRCH	STA. 1+00.00	TO	9+84.5
GREY ELM	STA. 1+00.00	TO	7+16.3
WASABI PASS	STA. 1+00.00	TO	3+80.7
BONFIRE PASS	STA. 1+00.00	TO	6+99.3
SWEET MARIGOLD	STA. 1+00.00	TO	4+13.1
ANNATTO DR	STA. 1+00.00	TO	2+45.0
SUMMER SAVORY	STA. 1+00.00	TO	15+57.3

EXISTING BASE — MATERIAL



NOTES:

1. THE SUBGRADE SOILS SHOULD BE TESTED FOR SOLUBLE SULPHATE CONTENT PRIOR TO INSTALLATION OF LIME OR CEMENT.

FILL MATERIAL NOTE:
IF FILL IS USED TO RAISE THE GRADE, APPROVED FILL MATERIAL UNDERNEATH THE PAVEMENT SHOULD BE ON—SITE MATERIAL,


FREE OF DELETERIOUS MATERIAL WITH MAXIMUM PLASTICITY INDEX VALUE OF 20 AND A MINIMUM CBR VALUE OF 3.0. THE GRAVEL SIZE SHOULD NOT EXCEED 3 INCHES IN DIAMETER. LIME OR CEMENT APPLICATION RATES SHOULD BE RE-EVALUATED FOR THE FILL MATERIAL. THE MATERIAL SHOULD BE PLACED AS PER APPLICABLE CITY AND/OR COUNTY GUIDELINES.


SUBGRADE MATERIAL NOTE: 1. SUBGRADE SOIL PLASTICITY INDEX SHOULD BE LESS THAN OR EQUAL TO 20 FOR PRIMARY PAVEMENT DESIGN.

- 2. IF THE SUBGRADE SOIL PLASTICITY INDEX VALUE IS GREATER THAN 20, THEN ONE OF THE FOLLOWING OPTIONS SHOULD BE FOLLOWED:
- 2.a. THE SUBGRADE SHOULD BE STABILIZED TO A DEPTH OF 6 INCHES (SEE ALTERNATE PAVEMENT DESIGN). 2.b. THE EXPANSIVE CLAYS SHOULD BE REMOVED AND REPLACED WITH SOILS WITH A PLASTICITY INDEX VALUE OF 20 OR
- 3. GEOTECHNICAL ENGINEER SHALL BE ON SITE TO MAKE SUBGRADE DETERMINATION AND PROVIDE/SUBMIT LETTER INDICATING STATION TO STATION FOR PLACEMENT OF EACH PVM'T. DESIGN SECTION TO BE APPROVED BY ENGINEER PRIOR TO PLACEMENT OF BASE.

FOR CONSTRUCTION VERIFICATION THE FOLLOWING SHALL BE CONDUCTED IN THE FIELD:


- AFTER INITIAL MIXING THE SOIL-LIME MIXTURE SHALL MELLOW FOR A PERIOD OF TWO TO THREE (2 3) DAYS. MAINTAIN MOISTURE DURING MELLOWING.
- AFTER MELLOWING AND FINAL MIXING, THE PULVERIZATION SHALL BE CHECKED USING THE FOLLOWING CRITERIA (REMOVE) NON-SLAKING AGGREGATES RETAINED ON THE % INCH SIEVE FROM THE SAMPLE): -MINIMUM PASSING 1 3/4" SIEVE
- -MINIMUM PASSING ¾" SIEVE 85 -MINIMUM PASSING NO. 4 SIEVE SAMPLE SOIL-LIME MIXTURE FOR DETERMINATION OF MAXIMUM DRY DENSITY (MDD). IN THE LABORATORY, MOLD SPECIMENS
- TO 95% OF MDD AT OPTIMUM MOISTURE CONTENT AND VERIFY UCS TO BE AT LEAST 160 PSI IN WITH PROCEDURE OUTLINED ABOVE FOR MIXTURE DESIGN.
- COMPACT AND CHECK FIELD DENSITY (MINIMUM OF 95% OF MDD REQUIRED);
- CURE FOR AN ADDITIONAL 2 TO 5 DAYS (TOTAL MELLOWING AND CURING TIME SHOULD TOTAL AT LEAST 5 DAYS).





1. ALLOW FOR REFLECTION BUTTONS ON BARRICADE POST USE ONE 3" BUTTON PER POST. 2. POST SHALL RECEIVE TWO COATS OF ALUMINUM PAINT. 3. 6" X 5'-6" BARRICADE POST PLACED 6" BACK OF CURB WITH 2'-4" ABOVE GROUND & 3'-2" BELOW GROUND. (5'-0" o.c. TYP.)

& BARRICADE POST



HEADER CURB DETAIL W/ REBAR

N.T.S.

S

CHNOLOGIE

RAFTING: K.P./G.P. CHECK: DESIGN: L.E. CHECK: M.P SUBMITTAL PHASE: (CI JOB #: 76220738

512


PRIME COAT - 0.2 GAL/SY - ITEM 202 TACK COAT - 0.1 GAL/SY - ITEM 203 HOT MIX -ASPHALT PAVEMENT 3/8" FILLET WELD_ & GROUND SMOOTH . VARIES BÄSED ON PAVEMENT SECTION 3" DIA. 90° ELBOW OR 4" DIA. 90° ELBOW MACHINE LAID CURB 3" DIA. DOUBLE — EXTRA STRONG — POST OR 4" DIA. STANDARD PIPE ITEM 501 ON FLEXIBLE BASE MATERIAL DETAIL OF 90° LIMITS OF PAVEMENT WELDING ELBOWS RECONSTRUCTION PRIME COAT - 0.2 GAL/SY - ITEM 202 * A NEAT END SECTION, SATISFACTORY TO THE ENGINEER, FROM SUBMITTED SHOP DRAWINGS, MAY BE USED IN LIEU OF THE 90° WELDING ELBOW SHOWN. NOT TO SCALE LIMITS OF NEW BASE TACK COAT - 0.1 GAL/SY - ITEM 203 SAW-CUT FOR SURFACE COURSE & BASE CONSTRUCTION SEE PAVEMENT STRUCTURE DETAILS EXISTING ASPHALT PAVEMENT

NEW SUBGRADE-

PAVEMENT JUNCTION DETAILS


NOT TO SCALE


CENTER IN SLAB PIPE ANCHORAGE DETAILS NOT TO SCALE.





___ FOR VERTICAL WALLS

NOT TO SCALE ITEM 522.1












DRAFTING: K.P./G.P. CHECK: C.F.


DESIGN: L.E. CHECK: M.P.S


SUBMITTAL PHASE:

DATE: 12/2

KCI JOB #: 76220738











DRAFTING: K.P./G.P. CHECK: DESIGN: L.E. CHECK: M.P SUBMITTAL PHASE: (CI JOB #: 762207389

CHNOLOGIE









RAFTING: K.P./G.P. CHECK:


DESIGN: L.E. CHECK: M.P


515

762207389

SUBMITTAL PHASE:

(CI JOB #:






HICKORY RIDGE SUBDIVISION PHASE 1 UNIT 2

<u>D</u>

DRAFTING: K.P./G.P. CHECK: C.F.
DESIGN: L.E. CHECK: M.P.S
GUBMITTAL PHASE:
DATE: 12/2
KCI JOB #: 76220738



SIGN FACE MATERIALS

SHALL CONFORM TO:

CONSTRUCTION OF ROADS & BRIDGES ON FEDERAL HIGHWAY

PROJECTS - FP-03 U.S. CUSTOMARY UNITS SECTION 718 GENERAL SERVICES ADMINISTRATION FEDERAL SPECIFICATIONS L-S-300C

3. ASTM D 4956 - 09**2**1

MAINTAIN 1" FROM EDGE OF SIGN

BLUE BACKGROUND

→ ¼" WHITE BORDER

gn

S

SHEET <u>46a</u>

WITH STREET DESIGNATION

WHITE LETTERS, NUMBERS & ARROWS


**Capital = 8"
Lower case =6"

-LENGTH 2'-0" MIN. 6'-0" MAX--

18" OVERHEAD STREET NAME SIGNS

HCKORY RIDGE SUBDIVISION PHASE 1 UNIT 2

DRAFTING: K.P./G.P. CHECK: C.F.
DESIGN: L.E. CHECK: M.P.S
SUBMITTAL PHASE:
DATE: 12/2
KCI JOB #: 76220738



SEDIMENTATION & EROSION CONTROL PLANS HICKORY RIDGE SUBDIVISION PHASE 1 UNIT 2

GENERAL NOTES

1. All materials and construction procedures within the scope of this project shall, be approved by the City of San Antonio Public Works and comply with the following as applicable: A. Reference to Current "San Antonio Water System Utility Specifications"

2. The locations and depths of existing utilities, including service laterals, and drainage structures shown on the plans are approximate only. The Contractor shall verify the exact location and depths of underground utilities at least 48 hours prior to construction whether shown on plans or not, and to protect the same during construction. Texas State Wide One Call Locator 1-800-545-6005 City Public

3. The Contractor shall notify the City prior to the start of each phase of street construction and call for inspections with a minimum of 24

4. Testing will be paid for by Developer, coordinated by Contractor, and witnessed by City

B. Reference to Current City of San Antonio "Standard Specifications for Public Works Construction"

5. Minimum Testing Schedule: 1 Per 500 Foot Minimum Densities - Subgrade 1 Per 500 Foot Minimum Proctors - Subgrade 1 Per Material Per Subdivision 1 Per 5,000 C.Y. Proctors - Base Lime Series - Subgrade 1 Per Material Per Subdivision Concrete - Structures 1 Set (3) Per 50 C.Y.

6. Transition washout crown to normal crown in 25'.

7. No extra payment shall be allowed for work called for on the plans, but not included in the bid proposal. This incidental work will be required and shall be included in the pay item to which it relates.

8. The contractor shall be responsible for restoring to its original or better condition any damage done to existing fences, concrete islands, street paving, curbs, shrubs, bushes or driveways. (No separate pay item).

9. Due to federal regulations Title 49, Part 192.171 CPS must maintain access to gas valves at all times. The contractor must protect and


10. Contractor shall notify the city inspector twenty four (24) hours prior to backfill of any utility trenches to schedule for density test as

11. All waste material shall become property of the contractor and shall be his sole responsibility to dispose of this material off the limits of the project. No waste material shall be placed in existing lows that will block or alter flow limits of existing artificial or natural drainage. 12. The contractor shall not place any waste material in the 100-year flood plain without first obtaining an approved Flood Plain

13. The contractor shall maintain all adjoining streets and traveled routes free from spilled and/or tracked construction materials and/or

14. It is the contractor's responsibility to see that all signs and barricades are properly installed and maintained. All locations and distances will be decided upon in the field by the contractor, using the "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES". The City's construction inspector will only be responsible to inspect barricades and signs. If, in the opinion of the construction inspector, the barricades and signs do not conform to established standards or are incorrectly placed or are insufficient in quantity to protect the general public, the inspector shall have the option to stop operations until such time as the conditions are corrected.

TRENCH EXCAVATION SAFETY PROTECTION CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL. REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS. PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF THE SYSTEMS. PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION, SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.



LOCATION MAP

Sheet List Table

SHEET	TITLE
600	SEDIMENTATION & EROSION CONTROL COVER
601	SEDIMENTATION & EROSION CONTROL PLAN
602	SEDIMENTATION & EROSION CONTROL COVER NOTES
603	SEDIMENTATION & EROSION CONTROL COVER DETAILS

LEGEND	
TEMPORARY SEDIMENT CONTROL FENCE— — — — —	SCF
TEMPORARY ROCK FILTER DAM— — — — — — — —	RFD
TYPE 1 CONSTRUCTION EXIT- — — — — — — — —	
CONCRETE WASHOUT PIT — — — — — — — — — — — — — — — — — — —	
GRAVEL FILTER BAGS- — — — — — — — — — — — — — — — — — — —	∞
LIMITS OF CONSTRUCTION— — — — — — — — —	LOC

SEDIMENT & EROSION CONTROL UNIT QUANTITY DESCRIPTION TEMPORARY ROCK FILTER DAM "TYPE 2" TYPE I CONSTRUCTION EXIT SILT CONTROL FENCE (INCLUDES J-HOOKS) **GRAVEL FILTER BAGS**

CONCRETE WASHOUT PIT

OWNER/DEVELOPER:

CASTLEROCK COMMUNITIES

2401 FOUNTAIN VIEW DRIVE, SUITE 215

HOUSTON, TEXAS 77057

PHONE: (713) 600-7060

GRADING SLOPE ARROW - - - - - - - - - - - - -

KCI TECHNOLOGIES, INC.


11550 IH 10 WEST, SUITE 395 SAN ANTONIO, TEXAS 78230-1037 PHONE: (210) 641-9999 FAX: (210) 641-6440 REGISTRATION #F-10573 / #101943-65

PREPARED BY:

SUBMITTAL PHASE: (CI JOB #:



RAFTING: K.P./G.P. CHECK: DESIGN: L.E. CHECK: M.F



SITE DESCRIPTION

titude: 29°15'27.75" N // Longitude: 98°19'2.0	9" W
ROJECT DESCRIPTION: Construction	n of subdivision improvements including: streets, sewer lines, water lines, and drainage improvements.
MAJOR SOIL DISTURBING ACTIVITI	Soil disturbing activities will include preparing right-of-way clearing, and grubbing, grading, excavation and
	r, sanitary sewer, storm sewer, and structures. Erosion and sediment controls.
OTAL PROJECT AREA: 25.308 AC	
	26.41 out of 25.308 AC (100%)
OTAL AREA TO BE DISTURBED:	26.41 out of 25.308 AC (100%)
OTAL AREA TO BE DISTURBED:	
OTAL AREA TO BE DISTURBED: VEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION):	0.54
OTAL AREA TO BE DISTURBED:	0.54
OTAL AREA TO BE DISTURBED: VEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION): VEIGHTED RUNOFF COEFFICIENT (POST-CONSTRUCTION):	0.54
OTAL AREA TO BE DISTURBED: VEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION): VEIGHTED RUNOFF COEFFICIENT (POST-CONSTRUCTION):	0.54 0.67 EGETATIVE
OTAL AREA TO BE DISTURBED: VEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION): VEIGHTED RUNOFF COEFFICIENT (POST-CONSTRUCTION): XISTING CONDITION OF SOIL & VE	0.54 0.67 EGETATIVE
OTAL AREA TO BE DISTURBED: VEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION): VEIGHTED RUNOFF COEFFICIENT (POST-CONSTRUCTION):	0.54 0.67 EGETATIVE
TOTAL AREA TO BE DISTURBED: VEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION): VEIGHTED RUNOFF COEFFICIENT (POST-CONSTRUCTION):	0.54 0.67 EGETATIVE
TOTAL AREA TO BE DISTURBED: VEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION): VEIGHTED RUNOFF COEFFICIENT (POST-CONSTRUCTION):	0.54 0.67 EGETATIVE
TOTAL AREA TO BE DISTURBED: VEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION): VEIGHTED RUNOFF COEFFICIENT (POST-CONSTRUCTION): EXISTING CONDITION OF SOIL & VECOVER AND % OF EXISTING VEGET	0.54 0.67 EGETATIVE
TOTAL AREA TO BE DISTURBED: WEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION): WEIGHTED RUNOFF COEFFICIENT (POST-CONSTRUCTION): EXISTING CONDITION OF SOIL & VECOVER AND % OF EXISTING VEGE	0.54 O.67 EGETATIVE TATIVE COVER: The existing topsoil is loamy fine sand. The exisiting site is well vegetated with patches of open area
TOTAL AREA TO BE DISTURBED: WEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION): WEIGHTED RUNOFF COEFFICIENT (POST-CONSTRUCTION): EXISTING CONDITION OF SOIL & VECOVER AND % OF EXISTING VEGE	0.54 O.67 EGETATIVE TATIVE COVER: The existing topsoil is loamy fine sand. The exisiting site is well vegetated with patches of open area
TOTAL AREA TO BE DISTURBED: WEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION): WEIGHTED RUNOFF COEFFICIENT (POST-CONSTRUCTION): EXISTING CONDITION OF SOIL & VECOVER AND % OF EXISTING VEGE	0.54 O.67 EGETATIVE TATIVE COVER: The existing topsoil is loamy fine sand. The exisiting site is well vegetated with patches of open area
TOTAL AREA TO BE DISTURBED: WEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION): WEIGHTED RUNOFF COEFFICIENT (POST-CONSTRUCTION): EXISTING CONDITION OF SOIL & VECOVER AND % OF EXISTING VEGE	0.54 O.67 EGETATIVE TATIVE COVER: The existing topsoil is loamy fine sand. The exisiting site is well vegetated with patches of open area
TOTAL AREA TO BE DISTURBED: WEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION): WEIGHTED RUNOFF COEFFICIENT (POST-CONSTRUCTION): EXISTING CONDITION OF SOIL & VECOVER AND % OF EXISTING VEGE	0.54 O.67 EGETATIVE TATIVE COVER: The existing topsoil is loamy fine sand. The exisiting site is well vegetated with patches of open area
TOTAL AREA TO BE DISTURBED: WEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION): WEIGHTED RUNOFF COEFFICIENT (POST-CONSTRUCTION): EXISTING CONDITION OF SOIL & VECOVER AND % OF EXISTING VEGE	0.54 O.67 EGETATIVE TATIVE COVER: The existing topsoil is loamy fine sand. The exisiting site is well vegetated with patches of open area

EROSION AND SEDIMENT CONTROLS

	TEMPORARY SEEDING
	PERMANENT PLANTING, SODDING, OR SEEDING
	MULCHING
	SOIL RETENTION BLANKET BUFFER ZONES
	PRESERVATION OF NATURAL RESOURCES
	Disturbed areas on which construction activity has ceased (temporarily or permanently) shall be stabilized within 14 days unless activities are scheduled to resume within 21 days.
TRUC	TURAL PRACTICES:
/	
	SILT FENCES
	HAY BALES ROCK BERMS
	DIVERSION, INTERCEPTOR, OR PERIMETER DIKES
	DIVERSION, INTERCEPTOR, OR PERIMETER SWALES
	DIVERSION DIKE AND SWALE COMBINATIONS
	PIPE SLOPE DRAINS
	PAVED FLUMES
	ROCK BEDDING AT CONSTRUCTION EXIT
	TIMBER MATTING AT CONSTRUCTION EXIT
Y	CHANNEL LINERS SEDIMENT TRADS
$\overline{}$	SEDIMENT TRAPS SEDIMENT BASINS
$\overline{}$	STORM INLET SEDIMENT TRAP
	STONE OUTLET STRUCTURES
	CURBS AND GUTTERS
	STORM SEWERS
	VELOCITY CONTROL DEVICES
THER	
,	
	er of activities will be as follows:
	temporary control, establish limits of construction, install silt fence, construction entrance/exit,
constru	temporary control, establish limits of construction, install silt fence, construction entrance/exit,
construction const	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, estion entrance/exit, and concrete wash out area.
2. Clear 3. Cons	temporary control, establish limits of construction, install silt fence, construction entrance/exit, ction entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities.
2. Clear 3. Cons 4. Cons	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, etion entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. truct sanitary sewer. truct storm drain.
2. Clear 3. Cons 4. Cons 5. Instal	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, stion entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. truct sanitary sewer. truct storm drain. I berm controls/BMP's.
2. Clear 3. Cons 4. Cons 5. Instal	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, etion entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. truct sanitary sewer. truct storm drain.
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, stion entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. truct sanitary sewer. truct storm drain. I berm controls/BMP's.
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, ction entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. truct sanitary sewer. truct storm drain. I berm controls/BMP's.
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follow	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, etion entrance/exit, and concrete wash out area. In the construct sanitary sewer. It the controls/BMP's. It the cont
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follow 9. Wher	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, ction entrance/exit, and concrete wash out area. In grub, excavate, and embank for channels/drains/pond/utilities. It truct sanitary sewer. It truct storm drain. I berm controls/BMP's. It truct water lines. It truct streets. It up with developer on BMP removal sequence. It all construction activity is complete and the site is stabilized and approved by the engineer, remove all temporary structural controls and stabilize areas disturbed
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follow 9. Wher	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, etion entrance/exit, and concrete wash out area. In the construct sanitary sewer. It the controls/BMP's. It the cont
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follow 9. Where project of by their	It temporary control, establish limits of construction, install silt fence, construction entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. truct sanitary sewer. truct storm drain. It bern controls/BMP's. truct water lines. truct streets. av up with developer on BMP removal sequence. at all construction activity is complete and the site is stabilized and approved by the engineer, remove all temporary structural controls and stabilize areas disturbed removal. contractor is responsible for implementing and maintaining the storm water pollution
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follor 9. Wher project of by their 10. The preventi	It temporary control, establish limits of construction, install silt fence, construction entrance/exit, stion entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. truct sanitary sewer. truct storm drain. It berm controls/BMP's. truct water lines. truct streets. w up with developer on BMP removal sequence. all construction activity is complete and the site is stabilized and approved by the engineer, remove all temporary structural controls and stabilize areas disturbed removal. contractor is responsible for implementing and maintaining the storm water pollution on plan.
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follor 9. Wher project of by their 10. The preventi	It temporary control, establish limits of construction, install silt fence, construction entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. truct sanitary sewer. truct storm drain. It bern controls/BMP's. truct water lines. truct streets. av up with developer on BMP removal sequence. at all construction activity is complete and the site is stabilized and approved by the engineer, remove all temporary structural controls and stabilize areas disturbed removal. contractor is responsible for implementing and maintaining the storm water pollution
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follor 9. Wher project of by their 10. The preventi	It temporary control, establish limits of construction, install silt fence, construction entrance/exit, stion entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. truct sanitary sewer. truct storm drain. It berm controls/BMP's. truct water lines. truct streets. w up with developer on BMP removal sequence. all construction activity is complete and the site is stabilized and approved by the engineer, remove all temporary structural controls and stabilize areas disturbed removal. contractor is responsible for implementing and maintaining the storm water pollution on plan.
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follow 9. Wher project of by their 10. The preventi	It temporary control, establish limits of construction, install silt fence, construction entrance/exit, stion entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. truct sanitary sewer. truct storm drain. It berm controls/BMP's. truct water lines. truct streets. w up with developer on BMP removal sequence. all construction activity is complete and the site is stabilized and approved by the engineer, remove all temporary structural controls and stabilize areas disturbed removal. contractor is responsible for implementing and maintaining the storm water pollution on plan.
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follow 9. Wher project of by their 10. The	It temporary control, establish limits of construction, install silt fence, construction entrance/exit, stion entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. truct sanitary sewer. truct storm drain. It berm controls/BMP's. truct water lines. truct streets. w up with developer on BMP removal sequence. all construction activity is complete and the site is stabilized and approved by the engineer, remove all temporary structural controls and stabilize areas disturbed removal. contractor is responsible for implementing and maintaining the storm water pollution on plan.
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follow 9. Wher project of by their 10. The preventi	It temporary control, establish limits of construction, install silt fence, construction entrance/exit, stion entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. truct sanitary sewer. truct storm drain. It berm controls/BMP's. truct water lines. truct streets. w up with developer on BMP removal sequence. all construction activity is complete and the site is stabilized and approved by the engineer, remove all temporary structural controls and stabilize areas disturbed removal. contractor is responsible for implementing and maintaining the storm water pollution on plan.
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follow 9. Wher project of by their 10. The preventing	Lemporary control, establish limits of construction, install silt fence, construction entrance/exit, and concrete wash out area. .grub, excavate, and embank for channels/drains/pond/utilities. .grub, excavate, and embank for
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follow 9. Wher project of by their 10. The preventing	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. gruct sanitary sewer. truct storm drain. I berm controls/BMP's. truct water lines. truct streets. vup with developer on BMP removal sequence. all construction activity is complete and the site is stabilized and approved by the engineer, remove all temporary structural controls and stabilize areas disturbed removal. contractor is responsible for implementing and maintaining the storm water pollution on plan. WATER MANAGEMENT: Storm water drainage will be conveyed by existing drainage structures, storm sewer, and streets. Any water discharged on the site for approved non-storm water discharges, shall be per permit conditions. The source contractors water place in the storm water discharges, shall be per permit conditions. The source
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follow 9. Wher project of by their 10. The preventing STORM	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. gruct sanitary sewer. truct storm drain. I berm controls/BMP's. truct water lines. truct streets. vup with developer on BMP removal sequence. all construction activity is complete and the site is stabilized and approved by the engineer, remove all temporary structural controls and stabilize areas disturbed removal. contractor is responsible for implementing and maintaining the storm water pollution on plan. WATER MANAGEMENT: Storm water drainage will be conveyed by existing drainage structures, storm sewer, and streets. Any water discharged on the site for approved non-storm water discharges, shall be per permit conditions. The source contractors water place in the storm water discharges, shall be per permit conditions. The source
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follow 9. Wher project of by their 10. The preventing STORM	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. gruct sanitary sewer. truct storm drain. I berm controls/BMP's. truct water lines. truct streets. vup with developer on BMP removal sequence. all construction activity is complete and the site is stabilized and approved by the engineer, remove all temporary structural controls and stabilize areas disturbed removal. contractor is responsible for implementing and maintaining the storm water pollution on plan. WATER MANAGEMENT: Storm water drainage will be conveyed by existing drainage structures, storm sewer, and streets. Any water discharged on the site for approved non-storm water discharges, shall be per permit conditions. The source contractors water place in the storm water discharges, shall be per permit conditions. The source
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follow 9. Wher project of by their 10. The preventing	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. gruct sanitary sewer. truct storm drain. I berm controls/BMP's. truct water lines. truct streets. vup with developer on BMP removal sequence. all construction activity is complete and the site is stabilized and approved by the engineer, remove all temporary structural controls and stabilize areas disturbed removal. contractor is responsible for implementing and maintaining the storm water pollution on plan. WATER MANAGEMENT: Storm water drainage will be conveyed by existing drainage structures, storm sewer, and streets. Any water discharged on the site for approved non-storm water discharges, shall be per permit conditions. The source contractors water place in the storm water discharges, shall be per permit conditions. The source
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follow 9. Wher project of by their 10. The preventing	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. gruct sanitary sewer. truct storm drain. I berm controls/BMP's. truct water lines. truct streets. vup with developer on BMP removal sequence. all construction activity is complete and the site is stabilized and approved by the engineer, remove all temporary structural controls and stabilize areas disturbed removal. contractor is responsible for implementing and maintaining the storm water pollution on plan. WATER MANAGEMENT: Storm water drainage will be conveyed by existing drainage structures, storm sewer, and streets. Any water discharged on the site for approved non-storm water discharges, shall be per permit conditions. The source contractors water place in the storm water discharges, shall be per permit conditions. The source
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follor 9. Wher project of by their 10. The preventing the prevention the prevention the prevention the prevention the preventing the prevention the prevention the prevention the	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. gruct sanitary sewer. truct storm drain. I berm controls/BMP's. truct water lines. truct streets. vup with developer on BMP removal sequence. all construction activity is complete and the site is stabilized and approved by the engineer, remove all temporary structural controls and stabilize areas disturbed removal. contractor is responsible for implementing and maintaining the storm water pollution on plan. WATER MANAGEMENT: Storm water drainage will be conveyed by existing drainage structures, storm sewer, and streets. Any water discharged on the site for approved non-storm water discharges, shall be per permit conditions. The source contractors water place in the storm water discharges, shall be per permit conditions. The source
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follor 9. Wher project of by their 10. The preventing TORM	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. gruct sanitary sewer. truct storm drain. I berm controls/BMP's. truct water lines. truct streets. vup with developer on BMP removal sequence. all construction activity is complete and the site is stabilized and approved by the engineer, remove all temporary structural controls and stabilize areas disturbed removal. contractor is responsible for implementing and maintaining the storm water pollution on plan. WATER MANAGEMENT: Storm water drainage will be conveyed by existing drainage structures, storm sewer, and streets. Any water discharged on the site for approved non-storm water discharges, shall be per permit conditions. The source contractors water place in the storm water discharges, shall be per permit conditions. The source
2. Clear 3. Cons 4. Cons 5. Instal 6. Cons 7. Cons 8. Follor 9. Wher project of by their 10. The preventing TORM	I temporary control, establish limits of construction, install silt fence, construction entrance/exit, and concrete wash out area. grub, excavate, and embank for channels/drains/pond/utilities. gruct sanitary sewer. truct storm drain. I berm controls/BMP's. truct water lines. truct streets. vup with developer on BMP removal sequence. all construction activity is complete and the site is stabilized and approved by the engineer, remove all temporary structural controls and stabilize areas disturbed removal. contractor is responsible for implementing and maintaining the storm water pollution on plan. WATER MANAGEMENT: Storm water drainage will be conveyed by existing drainage structures, storm sewer, and streets. Any water discharged on the site for approved non-storm water discharges, shall be per permit conditions. The source contractors water place in the storm water discharges, shall be per permit conditions. The source


	ndar days after the surrounding exposed ground has dried sufficiently to prevent further damage from heavy equipment. The areas adjacent to creeks and
drainage ways s	shall have priority followed by devices protecting storm sewer inlets.
	An inspection will be performed by a designated inspector every week as well as after every half inch or more of rain (as recorded on a non-freezing rain
	ated at the Project Site). An inspection and Maintenance Report will be made per each Inspection. Based on the inspection results, the controls shall be
	roject Site). An inspection and Maintenance Report will be made per each nspection report.
· 	
	RIALS: All waste materials will be collected and stored in a secured metal dumpster. The dumpster will meet all state and local city solid waste
	gulations. All trash and construction debris from the site will be deposited in the dumpster. The dumpster will be emptied as necessary or as required by local the trash will be hauled to a local dump. No construction waste material will be buried on site.
regulations and	the trash will be hadred to a local dump. No constituction waste material will be buried on site.
	WASTE (INCLUDING SPILL REPORTING): At a minimum, any products in the following categories are considered to be hazardous:
paints, acids for	cleaning masonry surfaces, cleaning solvents, asphalt products, chemical additives for soil stabilization or concrete curing compounds and additives. In the
event of a hazar	dous material spill, the spill coordinator shall be contacted immediately.
	<u> </u>
	ASTE: All sanitary waste will be collected from portable units as necessary, or as required by local regulations by a Licensed Sanitary Waste
SANITARY WA	
Management Co	ontractor.
Management Co	
Management Co	ontractor.
DFFSITE VEH	IICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
DFFSITE VEH HAU LOAI	UICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIRT ON ROAD REMOVED DAILY
DFFSITE VEH HAU LOAI	IICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
DFFSITE VEH HAU LOAI EXC	UICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIRT ON ROAD REMOVED DAILY
DFFSITE VEH HAU LOAI EXC	IICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIRT ON ROAD REMOVED DAILY BILIZED CONSTRUCTION ENTRANCE
DFFSITE VEH HAU LOAI V EXC	IICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIRT ON ROAD REMOVED DAILY BILIZED CONSTRUCTION ENTRANCE
DFFSITE VEH HAU LOAI V EXC	IICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIRT ON ROAD REMOVED DAILY BILIZED CONSTRUCTION ENTRANCE
DFFSITE VEH HAU LOAI EXC	IICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIRT ON ROAD REMOVED DAILY BILIZED CONSTRUCTION ENTRANCE
DFFSITE VEH HAU LOAI X STAE PERMITS:	IICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIRT ON ROAD REMOVED DAILY BILIZED CONSTRUCTION ENTRANCE
DFFSITE VEH LOAI EXC STAB PERMITS: REMARKS: LOAI	IICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIRT ON ROAD REMOVED DAILY BILIZED CONSTRUCTION ENTRANCE
DFFSITE VEH LOAI EXCI STAB PERMITS: Waters. Dispos	DISPOSAL areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving
DFFSITE VEH LOAI EXC STAB PERMITS: Waters. Dispose Contractor in a recommendation	DISPOSAL areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving at areas shall not be located in any wetland, waterbody or streambed. Construction staging areas and vehicle maintenance areas shall be constructed by the
DFFSITE VEH LOAI EXC STAB PERMITS: waters. Dispose Contractor in a recommendation	DICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIRT ON ROAD REMOVED DAILY BILIZED CONSTRUCTION ENTRANCE Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving al areas shall not be located in any wetland, waterbody or streambed. Construction staging areas and vehicle maintenance areas shall be constructed by the manner to minimize the runoff of pollutants. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting,
DFFSITE VEH LOAI EXC STAB PERMITS: Waters. Dispose Contractor in a recommendation	DICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIRT ON ROAD REMOVED DAILY BILIZED CONSTRUCTION ENTRANCE Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving al areas shall not be located in any wetland, waterbody or streambed. Construction staging areas and vehicle maintenance areas shall be constructed by the manner to minimize the runoff of pollutants. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting,
DFFSITE VEH LOAI EXC STAB PERMITS: Waters. Dispose Contractor in a recommendation	DICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIRT ON ROAD REMOVED DAILY BILIZED CONSTRUCTION ENTRANCE Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving al areas shall not be located in any wetland, waterbody or streambed. Construction staging areas and vehicle maintenance areas shall be constructed by the manner to minimize the runoff of pollutants. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting,
DFFSITE VEH LOAI EXC STAB PERMITS: Waters. Dispose Contractor in a recommendation	DICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIRT ON ROAD REMOVED DAILY BILIZED CONSTRUCTION ENTRANCE Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving al areas shall not be located in any wetland, waterbody or streambed. Construction staging areas and vehicle maintenance areas shall be constructed by the manner to minimize the runoff of pollutants. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting,
DFFSITE VEH LOAI EXC STAB PERMITS: Waters. Dispose Contractor in a recommendation	DICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIRT ON ROAD REMOVED DAILY BILIZED CONSTRUCTION ENTRANCE Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving al areas shall not be located in any wetland, waterbody or streambed. Construction staging areas and vehicle maintenance areas shall be constructed by the manner to minimize the runoff of pollutants. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting,
DFFSITE VEH LOAI EXC STAB PERMITS: waters. Dispose Contractor in a recommendation	DICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIRT ON ROAD REMOVED DAILY BILIZED CONSTRUCTION ENTRANCE Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving al areas shall not be located in any wetland, waterbody or streambed. Construction staging areas and vehicle maintenance areas shall be constructed by the manner to minimize the runoff of pollutants. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting,
DFFSITE VEH LOAI EXC STAB PERMITS: waters. Dispose Contractor in a recommendation	DICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIRT ON ROAD REMOVED DAILY SILIZED CONSTRUCTION ENTRANCE Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving all areas shall not be located in any wetland, waterbody or streambed, Construction staging areas and vehicle maintenance areas shall be constructed by the manner to minimize the runoff of poliutants. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting, and before or other obstructions placed during construction operations that are not a part of the finished work. OWNERS CERTIFICATION L certify under penalty of law that this document and all attachments were prepared under my direction or supervision in
DFFSITE VEH LOAI EXC STAB PERMITS: waters. Dispose Contractor in a recommendation	DICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIST ON ROAD REMOVED DAILY SILIZED CONSTRUCTION ENTRANCE Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving al areas shall not be located in any wetland, waterbody or streambed. Construction staging areas and vehicle maintenance areas shall be constructed by the manner to minimize the runoff of pollutants. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting, in debris or other obstructions placed during construction operations that are not a part of the finished work. OWNERS CERTIFICATION I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel property gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible
DFFSITE VEH LOAI EXC STAB PERMITS: waters. Dispose Contractor in a recommendation	DICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIRT ON ROAD REMOVED DAILY SILIZED CONSTRUCTION ENTRANCE Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving all areas shall not be located in any wetland, waterbody or streambed. Construction staging areas and vehicle maintenance areas shall be constructed by the manner for minimize the trunoff of pollutants. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting, g, debris or other obstructions placed during construction operations that are not a part of the finished work. OWNERS CERTIFICATION Lectify under penalty of law that this document and all attachments were grepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and overlated the information submitted Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for captering the information is uniformation submitted its, but the sets of my knowledge and belief, true, accurate, and
DFFSITE VEH LOAI EXC STAB PERMITS: waters. Dispose Contractor in a recommendation.	DICLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIST ON ROAD REMOVED DAILY SILIZED CONSTRUCTION ENTRANCE Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving al areas shall not be located in any wetland, waterbody or streambed. Construction staging areas and vehicle maintenance areas shall be constructed by the manner to minimize the runoff of pollutants. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting, in debris or other obstructions placed during construction operations that are not a part of the finished work. OWNERS CERTIFICATION I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel property gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible
DFFSITE VEH LOAI EXC STAB PERMITS: waters. Dispose Contractor in a recommendation	INCLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIST ON ROAD REMOVED DAILY SILIZED CONSTRUCTION ENTRANCE Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sadiment that may enter receiving al areas shall not be located in any wetland, waterbody or streambed. Construction staging areas and vehicle maintenance areas shall be constructed by the manner to minimize the runoff of pollutants. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting, g, debris or other obstructions placed during construction operations that are not a part of the finished work. OWNERS CERTIFICATION I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel property gathered and evaluated the information submitted. Based on my inquity of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalises for submitting false information, including the possibility of fine
DFFSITE VEH LOAI EXC STAB PERMITS: Waters. Dispose Contractor in a recommendation	INCLE TRACKING: L ROADS DAMPENED FOR DUST CONTROL DED HAUL TRUCKS TO BE COVERED WITH TARPAULIN ESS DIST ON ROAD REMOVED DAILY SILIZED CONSTRUCTION ENTRANCE Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sadiment that may enter receiving al areas shall not be located in any wetland, waterbody or streambed. Construction staging areas and vehicle maintenance areas shall be constructed by the manner to minimize the runoff of pollutants. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting, g, debris or other obstructions placed during construction operations that are not a part of the finished work. OWNERS CERTIFICATION I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel property gathered and evaluated the information submitted. Based on my inquity of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalises for submitting false information, including the possibility of fine

CONTRACTOR'S CERTIFICATION

SIGNATURE (CONTRACTOR)

I certify under penalty of law that I understand the terms and conditions of the general Texas Pollutant Discharge Elimination System (TPDES) permit that authorizes the storm water discharges associated with industrial activity from the construction site identified as part of this certification plan.

DATE



DRAFTING:K.P./G.P. CHECK: C.P. DESIGN: L.E. CHECK: M.P.S. SUBMITTAL PHASE: KCI JOB #:




Figure 1-43 Schematics of Concrete Washout Areas

GENERAL NOTES:

- 1. Silt fence material should be polypropylene, polyethylene or polyamide woven or nonwoven fabric. The fabric width should be 36 inches, with a minimum unit weight of 4.5 oz/yd, mullen burst strength exceeding 190 lb/in2, ultraviolet stability exceeding 70%, and minimum apparent opening size of U.S. Sieve No. 30.
- 2. Fence posts should be made of hot rolled steel, at least 4 feet long with Tee or Ybar cross section, surface painted or galvanized, minimum nominal weight 1.25 lb/ft2, and Brindell hardness exceeding
- 3. Woven wire backing to support the fabric should be galvanized 2"x 4" welded wire, 12 gauge minimum. Installation:
- 1. Steel posts, which support the silt fence, should be installed on a slight angle toward the anticipated runoff source. Post must be embedded a minimum of 1—foot deep and spaced not more than 8 feet on center. Where water concentrates, the maximum spacing
- 2. Lay out fencing down—slope of disturbed area, following the contour as closely as possible. The fence should be sited so that the maximum drainage area is 1/4 acre/100 feet of fence.
- 3. The toe of the silt fence should be trenched in with a spade or mechanical trencher, so that the down-slope face of the trench is flat and perpendicular to the line of flow. Where fence cannot be trenched in (e.g., pavement or rock outcrop), weight fabric flap with 3 inches of pea gravel on uphill side to prevent flow from seeping under fence.
- 4. The trench must be a minimum of 6 inches deep and 6 inches wide to allow for the silt fence fabric to be laid in the ground and backfilled with compacted material
- 5. Silt fence should be securely fastened to each steel support post or to woven wire, which is in turn attached to the steel fence post. There should be a 3-foot overlap, securely fastened where ends of
- Silt fence should be removed when the site is completely stabilized so as not to block or impede storm flow or drainage.

SILT FENCE

1.4.6 High Service Rock Berms

A high service rock berm should be designated in areas of important environmental significance such as in steep canyons or above permanent springs, pools, recharge features, or other environmentally sensitive areas that may require a higher level of protection. This type of sediment barrier combines the characteristics of a silt fence and a rock berm to provide a substantial level of sediment reduction and a sturdy enough barrier to withstand higher flows. The drainage area to this device should not exceed 5




Figure 1-29 Schematic Diagram of High Service Rock Berm (LCRA, 1998)

- 1. Silt fence material should be polypropylene, polyethylene or polyamide woven or nonwoven fabric. The fabric width should be 36 inches, with a minimum unit weight of 4.5 oz/yd, mullen burst strength exceeding 190 lb/in2, ultraviolet stability exceeding 70%, and minimum apparent opening size of U.S. Sieve No. 30.
- 2. Fence posts should be made of hot rolled steel, at least 4 feet long with Tee or Ybar cross section, surface painted or galvanized, minimum nominal weight 1.25 lb/ft2, and Brindell hardness exceeding
- 140. Rebar (either #5 or #6) may also be used to anchor the berm. Woven wire backing to support the fabric should be galvanized 2"x 4" welded wire, 12 gauge minimum.
- 4. The berm structure should be secured with a woven wire sheathing having maximum opening of 1 inch and a minimum wire diameter of 20 gauge galvanized and should be secured with shoat rings.
- 5. Clean, open graded 3— to 5—inch diameter rock should be used. except in areas where high velocities or large volumes of flow are expected, where 5- to 8-inch diameter rocks may be used.
- 1. Lay out the woven wire sheathing perpendicular to the flow line. The sneatning snould be 20 gauge woven wire mesn with I— inch openings 2. Install the silt fence along the center of the proposed berm
- placement, as with a normal silt fence described in Section 2.4.3. Place the rock along the sheathing on both sides of the silt fence as shown in the diagram (Figure 1-29), to a height not less than 24inches. Clean, open graded 3 - 5" diameter rock should be used, except in areas where high velocities or large volumes of flow are expected, where 5- to 8- inch diameter rock may be used.
- 4. Wrap the wire sheathing around the rock and secure with tie wire so that the ends of the sheathing overlap at least 2 inches, and the berm retains its shape when walked upon.
- 5. The high service rock berm should be removed when the site is revegetated or otherwise stabilized or it may remain in place as a permanent BMP if drainage is adequate.

HIGH SERVICE ROCK BERM

- 1. The aggregate should consist of 4 to 8 inch washed stone over a stable foundation as specified in the plan. The aggregate should be placed with a minimum thickness of 8 inches.
- 3. The geotextile fabric should be designed specifically for use as a soil filtration media with an approximate weight of 6 oz/yd2, a mullen burst rating of 140 lb/in2, and an equivalent opening size greater than a number 50 sieve.
- 4. If a washing facility is required, a level area with a minimum of 4 inch diameter washed stone or commercial rack should be included in the plans. Divert wastewater to a sediment trap or basin.
- 1. Avoid curves on public roads and steep slopes. Remove vegetation and other objectionable material from the foundation area. Grade crown foundation for positive drainage.
- 2. The minimum width of the entrance/exit should be 12 feet or the full width of exit roadway, whichever is greater. 3. The construction entrance should be at least 50 feet long.
- 4. If the slope toward the road exceeds 2%, construct a ridge, 6 to 8 inches high with 3:1 (H:V) side slopes, across the foundation approximately 15 feet from the entrance to divert runoff away from the public road.
- 5. Place geotextile fabric and grade foundation to improve stability, especially where wet conditions are anticipated.
- 6. Place stone to dimensions and grade shown on plans. Leave surface smooth and slope for drainage.
- Divert all surface runoff and drainage from the stone pad to a sediment trap or basin. 8. Install pipe under pad as needed to maintain proper public road drainage.
- Washing: When necessary, wheels shall be cleaned to remove sediment prior to entrance onto public roadway, when washing is required, it shall be done on an area stabilized basin. all sediment shall be prevented from entering any storm drain, ditch, or watercourse using approved methods.
- Maintenance: The entrance shall be maintained in a condition which will prevent tracking or flowing of sediment onto public roadways. This may require periodic top dressing with additional stone as conditions demand, and repair and/or cleanout of any measures used to trap sediment. All sediment spilled, dropped, washed or tracked onto public roadway must be removed immediately.

CONSTRUCTION EXIT

SHEATHING TO 4 INCHES CROSS SECTION FLOW ISOMETRIC PLAN VIEW


Figure 1-28 Schematic Diagram of a Rock Berm (NCTCOG, 1993)


- The berm structure should be secured with a woven wire sheathing having maximum opening of 1 inch and a minimum wire diameter of 20 gauge galvanized and should be secured
- 2. Clean, open graded 3— to 5—inch diameter rock should be used, except in areas where high velocities or large volumes of flow are expected, where 5— to 8—inch diameter rocks may be Installation:
- 1. Lay out the woven wire sheathing perpendicular to the flow line. The sheathing should be 20 gauge woven wire mesh with 1 inch
- 2. Berm should have a top width of 2 feet minimum with side slopes being 2:1 (H:V) or flatter
- 3. Place the rock along the sheathing as shown in the diagram (Figure 1-28), to a height not less than 18".
- Wrap the wire sheathing around the rock and secure with tie wire so that the ends of the sheathing overlap at least 2 inches, and the berm retains its shape when walked upon.
- Berm should be built along the contour at zero percent grade or as near as possible.
- The ends of the berm should be tied into existing upslope arade and the berm should be buried in a trench approximately 3 to 4 inches deep to prevent failure of the control.

ROCK BERM

FOR EROSION AND SEDIMENT CONTROL OVER THE EDWARDS AQUIFER CONTRIBUTING ZONE, THE RESPECTIVE BMP DETAILS HAVE BEEN SHOWN ON THIS SHEET AND SW1. THE DETAILS ARE EXCERPTS FROM THE EDWARDS AQUIFER TECHNICAL GUIDANCE MANUAL: RG-348. JULY 2005.

REFER TO THE EROSION CONTROL PLAN (SW1), FOR USE LOCATIONS / PARAMETERS OF THE DETAILS SHOWN IN THE PLAN SET.






GENERAL NOTES:

- 1. Attach a continuous piece of wire mesh (30—inch minimum width x inlet throat length plus 4 feet) to the 2-inch x 4-inch wooden weir (with a total length of throat length plus 2 feet) as shown in Figure 1-37. Wood should be "construction grade" lumber.
- 2. Place a piece of approved filter cloth of the same dimensions as the wire mesh over the wire mesh and securely attach to the 2inch x 4- inch weir.
- 3. Securely nail the 2-inch x 4-inch weir to the 9-inch long vertical spacers which are to be located between the weir and inlet face at
- a maximum 6— foot spacing. 4. Place the assembly against the inlet throat and nail 2—foot (minimum) lengths of 2-inch x 4- inch board to the top of the weir at spacer locations. These 2- inch x 4- inch anchors should extend across the inlet tops and be held in place by sandbags or alternate weight.
- 5. The assembly should be placed so that the end spacers are a minimum 1 foot beyond both ends of the throat opening.
- 6. Form the wire mesh and filter cloth to the concrete gutter and against the face of curb on both sides of the inlet. Place coarse aggregate over the wire mesh and filter fabric in such a manner as to prevent water from entering the inlet under or around the filter
- This type of protection should be inspected frequently and the filter cloth and stone replaced when clogged with sediment.
- 8. Assure that storm flow does not bypass inlet by installing temporary earth or asphalt dikes directing flow into inlet.

CURB INLET PROTECTION (WEIR)



- Z X Z WOOD STAKE OR STEEL T-POST ____ ABRIC ANCHORED IN X 6 TRENCH BACK-TILLED WITH COMPACTED I. STANDARD INSTALLATION LEVATION OF STAKE AND FABRIC ORIENTATION DETAIL A PERSPECTIVE VIEW THIS METHOD OF INLET PROTECTION IS APPLICABLE WHERE THE INLET DRAINS A RELATIVELY FLAT AREA (SLOPE NO GREATER THAN 5×) WHERE THE INLET SHEET OR OVER-AND FLOWS (NOT TO EXCEED I C.F.S.) A AT CORNERS TYPICAL. THE METHOD SHALL NOT APPLY TO NLETS RECEIVING CONCENTRATED FLOWS. SUCH AS IN STREETS OR HIGHWAY MEDIANS. II. ALTERNATE INSTALLATION PERSPECTIVE VIEW FILTER FABRIC PROTECTION


Figure 1-33 Filter Fabric Inlet Protection (NCTCOG, 1993)

GENERAL NOTES:

NOTE THAT THE DETAIL ABOVE, ONLY METAL POSTS / STAKES SHOULD BE USED. WOOD POSTS / STAKES ARE NOT ALLOWED

- 1. Filter fabric should be a nylon reinforced polypropylene fabric which meets the following minimum criteria: Tensile Strength, 90 lbs.; Puncture Rating, 60 lbs.; Mullen Burst Rating, 280 psi; Apparent Opening Size, U.S. Sieve No. 70.
- 2. Posts for fabric should be galvanized steel, tubular in cross—section or they may be standard fence "T" posts.
- 3. Concrete blocks should be standard 8"x 8"x 16" concrete masonry
- 4. Wire mesh should be standard hardware cloth or comparable wire mesh with an opening size not to exceed 1/2 inch. Guidelines for installation:
- Silt Fence Drop Inlet Protection 1. Silt fence should conform to the specifications listed above and should be cut from a continuous roll to avoid joints.
- 2. For posts, use metal ones with a minimum length of 3 feet.
- 3. Space stakes evenly around the perimeter of the inlet a maximum of 3 feet apart, and securely drive them into the ground, approximately 18 inches deep (Figure 1-33).
- 4. To provide needed stability to the installation, a frame with 2 x 4inch wood strips around the crest of the overflow area at a maximum of 1½ feet above the drop inlet crest should be provided.

INLET PROTECTION (FABRIC)



GENERAL NOTES:

- 1. Inspection should be made weekly and after each rainfall. Repair or
- replacement should be made promptly as needed by the contractor. 2. Remove sediment when buildup reaches a depth of 3 inches Removed sediment should be deposited in a suitable area and in
- such a manner that it will not erode. 3. Check placement of device to prevent gaps between device and
- 4. Inspect filter fabric and patch or replace if torn or missing. 5. Structures should be removed and the area stabilized only after the remaining drainage area has been properly stabilized.

INLET PROTECTION (GRAVEL FILTER BAGS)

DIVISI B 25 m EDIME S

CI JOB #:

RAFTING: K.P./G.P. CHECK:

SUBMITTAL PHASE:

ESIGN: L.E. CHECK: M.P

762207389