



BID FORM (SCHEDULE OF VALUES)					
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT BID PRICE	EXTENDED AMOUNT
101.1	CLEARING	19	Ac.		\$ -
104.1	LOT EXCAVATION	7,819	C.Y.		\$ -
107.1	LOT EMBANKMENT	15,815	C.Y.		\$ -
520.1	HYDROMULCH DISTURBED OPEN SPACE/CHANNEL (TO INCLUDE IRRIGATION FOR 85% MIN. VEGETATION ESTABLISHMENT)	20,955	S.Y.		\$ -
540.1	ROCK BERM	124	L.F.		\$ -
540.10	BAGGED GRAVEL INLET FILTER	34	L.F.		\$ -
540.11	CONCRETE WASHOUT PIT	1	EA.		\$ -
540.6	CONSTRUCTION EXITS (INSTALL/REMOVE)	1	EA.		\$ -
540.9	TEMPORARY SEDIMENT CONTROL FENCE	3,615	L.F.		\$ -
	RETAINING WALL	493	S.F.		\$ -
SITEWORK SUBTOTAL					\$ -
103.1	REMOVE HEADER CURB & GUARD POST	56	L.F.		\$ -
104.1	STREET EXCAVATION	7,626	C.Y.		\$ -
107.1	STREET EMBANKMENT	2,415	C.Y.		\$ -
108.1	6" CEMENT STABILIZED SUBGRADE (23 LBS/SY)	10,848	S.Y.		\$ -
200.1	FLEXIBLE BASE (12" COMPACTED DEPTH)	10,848	S.Y.		\$ -
200.1	FLEXIBLE BASE (8" COMPACTED DEPTH)	835	S.Y.		\$ -
205.4	HOT MIX ASPHALTIC PAVEMENT, TYPE D (2" COMP. DEPTH)	10,586	S.Y.		\$ -
500.1	CONCRETE CURB	5,491	L.F.		\$ -
500.1	CONCRETE HEADER CURB	28	L.F.		\$ -
502	SINGLE ADA CURB RAMPS (DEVELOPER RESPONSIBILITY)	14	EA.		\$ -
502.1	4" DEPTH CONCRETE SIDEWALKS	289	S.Y.		\$ -
531.3	R1-1 STOP (30")(HIGH INTENSITY)	3	EA.		\$ -

BIDDER SIGNATURE _____



BID FORM (SCHEDULE OF VALUES)					
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT BID PRICE	EXTENDED AMOUNT
531.56	OM4-3 END OF ROAD MARKER (18"X18")	3	EA.		\$ -
531.57	9 INCH [229mm] STREET NAME, BLOCK NUMBER (VARIES x9")(HIGH INTENSITY)	6	EA.		\$ -
531.6	R2-1 SPEED LIMIT (24" X 30")(HIGH INTENSITY)	1	EA.		\$ -
STREET SUBTOTAL					\$ -
105.1	CHANNEL EXCAVATION	2,250	C.Y.		\$ -
107.1	CHANNEL EMBANKMENT	186	C.Y.		\$ -
307.1	CONCRETE STRUCTURE (HEADWALL & BAFFLE BLOCKS)	14.50	C.Y.		\$ -
309.1	4-3'X2' CONCRETE M.B.C.	68	L.F.		\$ -
403.6	5' CONCRETE SIDEWALK BOX	1	EA.		\$ -
403.8	INLET TYPE II (COMPLETE)(20 FT)	1	EA.		\$ -
505.1	CONCRETE RIPRAP (5" THICK)	88	S.Y.		\$ -
522.1	PIPE RAILING	66	L.F.		\$ -
550.1	TRENCH EXCAVATION SAFETY PROTECTION	68	L.F.		\$ -
554.1	GABION MATTRESS	18	S.Y.		\$ -
DRAIN SUBTOTAL					\$ -
550.1	TRENCH EXCAVATION SAFETY PROTECTION	4,830	L.F.		\$ -
848	8" PVC SANITARY SEWER LINE (SDR-26) (8' - 10')	994	L.F.		\$ -
848	8" PVC SANITARY SEWERLINE (SDR-26) (10'-12')	776	L.F.		\$ -
852.1	SANITARY SEWER MANHOLE (0'-6')	8	EA.		\$ -
852.1	ADJUST/RECONSTRUCT EXISTING MANHOLE TOP	3	EA.		\$ -
852.3	EXTRA DEPTH MANHOLES (>6')	33	V.F.		\$ -
854	SANITARY SEWER LATERALS	3,060	L.F.		\$ -
866	SEWER MAIN TELEVISION INSPECTION (8" - 20")	1,770	L.F.		\$ -

BIDDER SIGNATURE _____



BID FORM (SCHEDULE OF VALUES)					
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT BID PRICE	EXTENDED AMOUNT
SANITARY SEWER SUBTOTAL					\$ -
812.0	8" C-900 WATER MAIN	2,570	L.F.		\$ -
812.0	2" HDPE 200 PSI DR 11	687	L.F.		\$ -
828.0	8" GATE VALVE & BOX, COMPLETE	18	EA.		\$ -
834.1	STANDARD F.H. COMPLETE W/ VALVE	5	EA.		\$ -
844.0	2" PERMANENT BLOWOFF	3	EA.		\$ -
844.0	2" TEMPORARY BLOWOFF	2	EA.		\$ -
836.0	CAST IRON FITTINGS	2.45	TON		\$ -
856.3	24" STEEL CASING	19	L.F.		\$ -
824.0	1" DUAL WATER SERVICE - LONG	19	EA.		\$ -
824.0	1" DUAL WATER SERVICE - SHORT	24	EA.		\$ -
824.0	3/4" SINGLE WATER SERVICE - LONG	2	EA.		\$ -
824.0	3/4" SINGLE WATER SERVICE - SHORT	4	EA.		\$ -
824.0	1" SINGLE IRRIGATION SERVICE - SHORT	1	EA.		\$ -
833.0	METER BOXES	93	EA.		\$ -
841.0	DISINFECTION & HYDROSTATIC TESTING	1	EA.		\$ -
550.0	TRENCH EXCAVATION PROTECTION	3,257	L.F.		\$ -
	WATER MAIN TIE-IN	2	EA.		\$ -
WATER SUBTOTAL					\$ -

BIDDER SIGNATURE _____



BID FORM (SCHEDULE OF VALUES)					
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT BID PRICE	EXTENDED AMOUNT
1	1-4" SCH. 80 PVC CONDUIT (CENTRIC GAS)	480	L.F.		\$ -
2	3-6" SCH. 80 PVC CONDUIT (CPS ELEC. & GAS) AND 1-4" SCH. 40 PVC CONDUIT (SPECTRUM) JOINT TRENCH	650	L.F.		\$ -
3	2-6" SCH. 80 PVC CONDUIT (CPS ELEC. & GAS) AND 1-4" SCH. 40 PVC CONDUIT (SPECTRUM) JOINT TRENCH	950	L.F.		\$ -
DRY UTILITY SUBTOTAL					\$ -
TOTAL BID AMOUNT					\$ -

BIDDER SIGNATURE _____