

HIGDON CROSSING UNIT 3 and TURN LANE IMPROVEMENTS

BID QUANTITIES

WATER IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	8" Water Main Tie-In	EA.	4	\$ -	\$ -
2	Trench Excavation Protection	L.F.	4,524	\$ -	\$ -
3	8" Pipe, C900 DR 18 PVC Class 235 (Incl. Restraints)	L.F.	4,524	\$ -	\$ -
4	8" Gate Valve, M.J.	EA.	12	\$ -	\$ -
5	Standard Fire Hydrant (Complete)	EA.	5	\$ -	\$ -
6	2" Permanent Blow-off	EA.	3	\$ -	\$ -
7	2" Temporary Blow-off	EA.	4	\$ -	\$ -
8	3/4" Irrigation Service	EA.	1	\$ -	\$ -
9	3/4" Single Service: Short	EA.	91	\$ -	\$ -
10	3/4" Single Service: Long	EA.	42	\$ -	\$ -
11	D.I. Fittings	TON	1.3	\$ -	\$ -
12	Hydrostatic Testing	EA.	2	\$ -	\$ -
13	Meter Boxes	EA.	134	\$ -	\$ -
TOTAL COST					\$ -

SANITARY SEWER IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
14	Tie Into Existing Sewer Main	EA.	7	\$ -	\$ -
15	Trench Excavation Safety Protection	L.F.	9,645	\$ -	\$ -
16	8" Sanitary Sewer Pipe, SDR-26 (0'-6')	L.F.	1,081	\$ -	\$ -
17	8" Sanitary Sewer Pipe, SDR-26 (6'-10')	L.F.	2,036	\$ -	\$ -
18	12" Sanitary Sewer Pipe, SDR-26 (6'-10')	L.F.	1,660	\$ -	\$ -
19	Standard Sanitary Sewer Manhole	EA.	11	\$ -	\$ -
20	Extra Depth Manhole	V.F.	24.1	\$ -	\$ -
21	Vertical Stack	V.F.	8.2	\$ -	\$ -
22	6" Sanitary Sewer Lateral, SDR-26	L.F.	4,868	\$ -	\$ -
23	8" Sewer Main TV Inspection	L.F.	3,117	\$ -	\$ -
24	12" Sewer Main TV Inspection	L.F.	1,660	\$ -	\$ -
TOTAL COST					\$ -

HIGDON CROSSING UNIT 3 and TURN LANE IMPROVEMENTS

BID QUANTITIES

STREET IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
25	Remove Header Curb	L.F.	152	\$ -	\$ -
26	Street Excavation	C.Y.	16,913	\$ -	\$ -
27	Street Embankment	C.Y.	1,414	\$ -	\$ -
28	Lime Stabilized Subgrade (6" Compacted Depth) (30 lb/S.Y.)	S.Y.	14,581	\$ -	\$ -
29	Lime Stabilized Subgrade (8" Compacted Depth) (40 lb/S.Y.)	S.Y.	4,138	\$ -	\$ -
30	Flexible Base (10.0" Compacted Depth)	S.Y.	14,581	\$ -	\$ -
31	Flexible Base (19.5" Compacted Depth)	S.Y.	4,138	\$ -	\$ -
32	Prime Coat	GAL.	3,334	\$ -	\$ -
33	Tack Coat	GAL.	1,667	\$ -	\$ -
34	Hot Mix Asphalt Pavement, Type D - (2" Comp. Depth)	S.Y.	13,024	\$ -	\$ -
35	Hot Mix Asphalt Pavement, Type D - (3" Comp. Depth)	S.Y.	3,645	\$ -	\$ -
36	Hot Mix Asphalt Pavement, Type C - (3" Comp. Depth)	S.Y.	62	\$ -	\$ -
37	Concrete Curb	L.F.	9,538	\$ -	\$ -
38	Header Curb	L.F.	96	\$ -	\$ -
39	ADA Ramps	EA.	28	\$ -	\$ -
40	Concrete Sidewalks (Developer Responsibility)	S.Y.	1,610	\$ -	\$ -
41	Timber Guard Posts	EA.	11	\$ -	\$ -
42	R1-1 Stop (30")(High Intensity)	EA.	6	\$ -	\$ -
43	OM4-3 End of Road Marker (18"x18")(High Intensity)	EA.	11	\$ -	\$ -
44	9-inch Street Name, Block Number (Varies x9")(High Intensity)	EA.	16	\$ -	\$ -
45	6" Wide Solid Yellow Line	L.F.	1,504	\$ -	\$ -
46	Pavement Marker (Type II) (Blue)	EA.	5	\$ -	\$ -
47	Pavement Marker (Type II A-A)	EA.	38	\$ -	\$ -
48	Rock Filter Dams (Type II) (Install & Remove)	L.F.	50	\$ -	\$ -
49	Construction Exit (Installation)	S.Y.	167	\$ -	\$ -
50	Construction Exit (Removal)	S.Y.	167	\$ -	\$ -
51	Temporary Sediment Control Fence (Phase I - Sitework)	L.F.	4,170	\$ -	\$ -
52	Temporary Sediment Control Fence (Phase II - Homebuilder)	L.F.	7,208	\$ -	\$ -
53	Curb Inlet Gravel Filters	L.F.	780	\$ -	\$ -
				TOTAL COST	\$ -

HIGDON CROSSING UNIT 3 and TURN LANE IMPROVEMENTS

BID QUANTITIES

HIGDON RD - TURN LANE IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
54	Remove Concrete Curb & Gutter	L.F.	498	\$ -	\$ -
55	Remove Concrete Sidewalks	L.S.	1	\$ -	\$ -
56	Asphalt Pavement Demolition (Sawcut and Remove)	S.Y.	334	\$ -	\$ -
57	Excavation (Street)	C.Y.	3,975	\$ -	\$ -
58	Flexible Base (21.5" Compacted Depth)	S.Y.	3,216	\$ -	\$ -
59	Lime Stabilized Subgrade (8" Comp. Depth) (40 lb/S.Y.)	S.Y.	3,216	\$ -	\$ -
60	Prime Coat	GAL.	643	\$ -	\$ -
61	Tack Coat	GAL.	322	\$ -	\$ -
62	Hot Mix Asphalt Pavement, Type D - (3" Comp. Depth)	S.Y.	3,216	\$ -	\$ -
63	Concrete Curb & Gutter	L.F.	304	\$ -	\$ -
64	Concrete Sidewalk	S.Y.	65	\$ -	\$ -
65	ADA Ramps	EA.	10	\$ -	\$ -
66	6-Inch Solid White Thermoplastic Line	L.F.	3,217	\$ -	\$ -
67	6-Inch Solid Double Yellow Thermoplastic Line	L.F.	2,002	\$ -	\$ -
68	6-Inch Solid Yellow w/6" Broken Yellow Thermo. Lines	L.F.	872	\$ -	\$ -
69	8-Inch Broken White Thermoplastic Line	L.F.	100	\$ -	\$ -
70	8-Inch Solid White Thermoplastic Line	L.F.	150	\$ -	\$ -
71	24-Inch Solid Yellow Thermoplastic Line	L.F.	724	\$ -	\$ -
72	Solid Yellow Median Nose	EA.	3	\$ -	\$ -
73	Left White Arrow	EA.	6	\$ -	\$ -
74	Word "ONLY"	EA.	2	\$ -	\$ -
75	Traffic Button (Type II A-A)	EA.	324	\$ -	\$ -
76	Barricades, Signs, and Traffic Handling - Phase A	L.S.	1	\$ -	\$ -
77	Barricades, Signs, and Traffic Handling - Phase B	L.S.	1	\$ -	\$ -
78	Temp. Sediment Control Fence (Install) - Phase A	L.F.	1,690	\$ -	\$ -
79	Temp. Sediment Control Fence (Remove) - Phase A	L.F.	1,690	\$ -	\$ -
80	Temp. Sediment Control Fence (Install) - Phase B	L.F.	1,804	\$ -	\$ -
81	Temp. Sediment Control Fence (Remove) - Phase B	L.F.	1,804	\$ -	\$ -
TOTAL COST					# \$ -

DRAINAGE IMPROVEMENTS (DRAIN A)

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
82	Channel Excavation	C.Y.	3,563	\$ -	\$ -
83	Channel Embankment	C.Y.	33	\$ -	\$ -
84	Concrete Riprap (6" Thick)	S.Y.	784	\$ -	\$ -
85	Hydromulching	S.Y.	4,400	\$ -	\$ -
TOTAL COST					# \$ -

HIGDON CROSSING UNIT 3 and TURN LANE IMPROVEMENTS BID QUANTITIES

DRAINAGE IMPROVEMENTS (DRAIN B)

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
86	Channel Excavation	C.Y.	67	\$ -	\$ -
87	Elevated Concrete Sidewalk	C.Y.	6.25	\$ -	\$ -
88	Concrete Riprap (6" Thick)	S.Y.	126	\$ -	\$ -
89	Sidewalk Pipe Railing	L.F.	41	\$ -	\$ -
90	Hydromulching	S.Y.	310	\$ -	\$ -
				TOTAL COST	# \$ -

DRAINAGE IMPROVEMENTS (DRAIN C)

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
91	24" RCP (Class IV)	L.F.	250	\$ -	\$ -
92	4x4x4 Junction Box	EA.	1	\$ -	\$ -
93	10' Type C Inlet	EA.	2.0	\$ -	\$ -
94	Concrete Headwall	C.Y.	4	\$ -	\$ -
				TOTAL COST	# \$ -

SITE WORK AND ADD ALTERNATES

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
95	Clearing and Grubbing	AC.	24.9	\$ -	\$ -
96	Lot Excavation	C.Y.	875	\$ -	\$ -
97	Lot Embankment	C.Y.	25,197	\$ -	\$ -
98	Import Material	C.Y.	1,251	\$ -	\$ -
99	Conduit Bundle (1-6" PVC)	L.F.	115	\$ -	\$ -
100	Conduit Bundle (1-6" PVC & 2-4" PVC)	L.F.	1,300	\$ -	\$ -
101	Conduit Bundle (2-6" PVC & 2-4" PVC)	L.F.	60	\$ -	\$ -
				TOTAL COST	\$ -

GRAND TOTAL COST: