# HIGHLAND GARDENS UNIT 1A

# NEW BRAUNFELS, TEXAS STREETS, DRAINAGE, WATER AND SANITARY SEWER IMPROVEMENT PROJECT

BEING 10.087 ACRE OF LAND OUT OF A 17.389 ACRE TRACT OF LAND SITUATED IN THE JOHN THOMPSON SURVEY NO. 21, ABSTRACT NO. 608, COMAL COUNTY, TEXAS AS DESCRIBED IN DOCUMENT NO. 2017 OF THE OFFICIAL PUBLIC RECORDS OF COMAL COUNTY, TEXAS AND ALSO BEING OUT OF A 38.063 ACRE TRACT OF LAND SITUATED IN THE WILLIAM H. PATE SURVEY NO. 22, ABSTRACT NO. 259 AND RAFAEL XIMENEZ SURVEY, ABSTRACT NO. 347 AS DESCRIBED IN VOLUME 2773, PAGE 98 OF THE OFFICIAL PUBLIC RECORDS OF GUADALUPE COUNTY, TEXAS.

DESIGN SPEED = 30 MPH

PLEASE NOTE: NBU REQUIRES GPS POINTS FOR CERTAIN ELECTRIC, WATER AND WASTEWATER ATTRIBUTES, SOME OF WHICH MUST BE TAKEN PRIOR TO BACKFILL DURING CONSTRUCTION

GPS POINTS SHALL BE REQUIRED FROM THE DEVELOPER CONTRACTOR'S OR ENGINEER. A MINIMUM OF THREE COORDINATE POINTS FOR GEOREFERENCING SHALL BE REQUIRED. THE WATER AND WASTEWATER GPS POINTS SHALL BE TO SURVEY GRADE.

#### WATER

VERTICAL BENDS AND EDGE OF STEEL CASING (IF APPLICABLE) PRIOR TO BACKFILL HORIZONTAL BENDS PRIOR TO BACKFILL

HORIZONTAL BENDS PRIOR TO BACKFILL TEES PRIOR TO BACKFILL

FITTINGS (REDUCERS AND COUPLINGS) PRIOR TO BACKFILL FIRE HYDRANTS (TOP OF FLANGE)

VALVES
METERS (TOP CENTER OF BOX)

BLOW OFF ASSEMBLY CORNER SLAB OF WATER TANK & GATE VALVE ON WATER TANK

#### <u>WASTEWATER</u> MANHOLES

CLEANOUTS CORNER SLAB OF LIFT STATION

## ELECTRIC

POLES TRANSFORMERS, BOTH ABOVE AND UNDERGROUND (FRONT LOCK)
PULL BOXES

STREET LIGHTS

COORDINATE GPS REQUIREMENTS WITH NBU INSPECTOR


## GENERAL NOTES:

- 1. IF CONSTRUCTION HAS NOT COMMENCED WITHIN ONE—YEAR OF CITY OF NEW BRAUNFELS AND NEW BRAUNFELS UTILITIES (NBU) APPROVAL FOR CONSTRUCTION INSPECTION, THAT APPROVAL IS NO LONGER VALID.
- 2. ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE ENGINEER OF RECORD. IN ACCEPTING THESE PLANS, THE CITY OF NEW BRAUNFELS MUST RELY UPON THE ADEQUACY OF THE WORK OF THE ENGINEER OF RECORD.
- 3. NO PORTION OF THE PROJECT IS LOCATED WITHIN THE EXISTING SPECIAL FLOOD HAZARD ZONE A, 100—YEAR FLOOD BOUNDARY, AS DEFINED BY THE COMAL COUNTY, TEXAS MAP NUMBER 48187CO12OF, AS PREPARED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY, EFFECTIVE DATE NOVEMBER 2, 2007.
- 4. THIS PROJECT IS NOT LOCATED WITHIN THE EAA JURISDICTIONAL BOUNDARY AND IS NOT LOCATED WITHIN ANY EDWARDS AQUIFER RECHARGE ZONES.
- 5. THIS PROJECT IS A RESIDENTIAL SUBDIVISION, DEVELOPMENT TYPE 3.
- BRAUNFELS UTILITIES (NBU) TO SET A PRE—CONSTRUCTION MEETING. A 48—HOUR ADVANCED NOTIFICATION IS REQUIRED.
- 6.1. ALL CONB INSPECTIONS ARE TO BE CALLED IN AT 830-221-4068 (PHONE) 6.2. FAXED IN AT 830-608-2117 (FAX)
- 6.3. EMAILED AT inspections@nbtexas.com (EMAIL). 6.4. NBU INSPECTIONS ARE TO BE CALLED AT 830-608-8971
- 7. THE MOST CURRENT EDITIONS OF THE CITY OF SAN ANTONIO STANDARD SPECIFICATIONS AND THE TEXAS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS AND BRIDGES SHALL FOLLOWED FOR ALL CONSTRUCTION EXCEPT AS AMENDED BY THE CITY OF NEW BRAUNFELS STANDARD DETAILS.
- 3. GAS UTILITIES ARE NOT INCLUDED IN THE CIVIL CONSTRUCTION PLANS. FINAL GAS UTILITY DESIGN SHALL BE APPROVED BY THE CITY FOR ANY WORK WITHIN PUBLIC RIGHT-OF-WAY.

## NOTE TO CONTRACTOR:

BY THE ACT OF SUBMITTING A BID FOR THIS PROPOSED CONTRACT, THE BIDDER WARRANTS THAT THE BIDDER, AND ALL SUBCONTRACTORS AND MATERIAL SUPPLIERS HE INTENDS TO USE HAVE CAREFULLY AND THOROUGHLY REVIEWED THE DRAWINGS, SPECIFICATIONS AND ALL OTHER CONTRACT DOCUMENTS AND HAVE FOUND THEM COMPLETE AND FREE FROM ANY AMBIGUITIES AND SUFFICIENT FOR THE PURPOSE INTENDED. THE BIDDER FURTHER WARRANTS THAT TO THE BEST OF HIS OR HIS SUBCONTRACTORS' AND MATERIAL SUPPLIERS' KNOWLEDGE, ALL MATERIALS AND PRODUCTS SPECIFIED OR INDICATED HEREIN ARE ACCEPTABLE FOR ALL APPLICABLE CODES AND AUTHORITIES.

THE LOCATION OF ALL EXISTING UTILITIES SHOWN ON THESE PLANS HAS BEEN BASED UPON RECORD INFORMATION ONLY AND MAY NOT MATCH LOCATIONS AND/OR DEPTHS AS CONSTRUCTED. THE CONTRACTOR SHALL CONTACT EACH OF THE INDIVIDUAL UTILITIES FOR ASSISTANCE IN DETERMINING EXISTING UTILITY LOCATIONS AND DEPTHS PRIOR TO BEGINNING ANY CONSTRUCTION. CONTRACTOR SHALL FIELD VERIFY LOCATIONS OF ALL UTILITY CROSSINGS PRIOR TO BEGINNING ANY CONSTRUCTION.



Sheet List Table					
SHEET NUMBER	SHEET TITLE				
1	GENERAL NOTES				
2	MASTER PLAN				
3	SUBDIVISION PLAT				
4	SUBDIVISION PLAT II				
5	MONTROSE AND ARALIA LN PLAN & PROFILE				
6	DAISY MEADOW PLAN & PROFILE				
7	STREET SECTIONS AND DETAILS I				
8	STREET SECTIONS AND DETAILS II				
9	TRAFFIC SIGNAGE & SIDEWALK PLAN				
10	TRAFFIC SIGNAGE AND SIDEWALK DETAILS				
11	DRAINAGE AREA MAP - SCS EXISTING				
12	DRAINAGE AREA MAP - SCS PROPOSED				
13	DRAINAGE AREA MAP - RATIONAL PROPOSED				
14	GRADING PLAN				
15	OVERALL UTILITY PLAN				
16	EROSION CONTROL PLAN				
17	EROSION CONTROL DETAILS				

OWNER/DEVELOPER:

TIM PRUSKI

(210) 402-0642

ENGINEER/SURVEYOR: INK CIVIL

(830) 358-7127

5151 W. SH46

(210) 325-0858

BELLA VISTA HOMES

2021 SH 46 W. STE 105.


NEW BRAUNFELS, TX. 78130

2174 N 1604 LOOP, SUITE 105 SAN ANTONIO, TX 78232

JAMES INGALLS, P.E. - ENGINEER


D.A. MAWYER LAND SURVEYING, INC. DREW MAWYER, R.P.L.S. - SURVEYOR

NEW BRAUNFELS, TEXAS 78132





2021 W SH46, STE 105 NEW BRAUNFELS, TX. 78132 PH: 830-358-7127 ink-civil.com TBPE FIRM F-13351





NO	DATE	ISSUES AND REVISIONS
<u> </u>	1-13-2022	UPDATED PER CONB COMMENTS
$\triangle$		

SUBMITTAL DATE: 2-10-2022

#### CITY OF NEW BRAUNFELS - CONSTRUCTION NOTES - REV 3-2020

INSPECTION, THAT APPROVAL IS NO LONGER VALID. 2. THE MOST CURRENT EDITIONS OF THE CITY OF SAN ANTONIO STANDARD SPECIFICATIONS AND THE TEXAS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS,

STREETS AND BRIDGES SHALL BE FOLLOWED FOR ALL CONSTRUCTION EXCEPT AS AMENDED BY TH

- 3. ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE ENGINEER OF RECORD. ACCEPTING THESE PLANS, THE CITY OF NEW BRAUNFELS MUST RELY UPON THE ADEQUACY OF THE 23. THE CONTRACTOR SHALL NOTIFY THE CITY AT LEAST TWENTY-FOUR (24) HOURS PRIOR TO THE WORK OF THE ENGINEER OF RECORD.
- 4. PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL CONTACT THE CITY OF NEW
- BRAUNFELS TO SCHEDULE A PRECONSTRUCTION MEETING.

#### FOR PUBLIC INFRASTRUCTURE PERMIT (SC) OR SITE PREP PERMIT (SD) PROJECTS: 4.1 FOR INSPECTIONS, YOU MUST CALL BEFORE 12:00 P.M., 48 HOURS PRIOR TO YOUR INSPECTION

4.2 EACH INSPECTION WILL BE ALLOTTED 1 HOUR UNLESS YOU REQUEST FOR MORE TIME. 4.3 ONCE YOUR REQUEST HAS BEEN ACCEPTED, YOU WILL RECEIVE A CALL FROM THE CITY OF NEW BRAUNFELS INSPECTOR.

#### FOR COMMERCIAL PERMIT (CP) PROJECTS: 4.4 ALL INSPECTIONS ARE TO BE CALLED IN AT 830-221-4068 OR, 4.5 FAXED IN AT 830-608-2117 OR,

CITY OF NEW BRAUNFELS STANDARD DETAILS.

4.6 E-MAILED AT INSPECTIONS@NBTEXAS.ORG.

- 5. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SEE THAT ALL TEMPORARY AND PERMANENT TRAFFIC CONTROL DEVICES ARE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE PLANS AND LATEST EDITION OF THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES. IF, IN THE OPINION THE ENGINEERING REPRESENTATIVE AND THE CONSTRUCTION INSPECTOR, THE BARRICADES AND SIGNS DO NOT CONFORM TO ESTABLISHED STANDARDS OR ARE INCORRECTLY PLACED OR ARE INSUFFICIENT IN QUANTITY TO PROTECT THE GENERAL PUBLIC THE CONSTRUCTION INSPECTOR SHALL HAVE THE OPTION TO STOP OPERATIONS UNTIL SUCH TIME AS THE CONDITIONS ARE CORRECTED. I THE NEED ARISES, ADDITIONAL TEMPORARY TRAFFIC CONTROL DEVICES MAY BE ORDERED BY THE ENGINEERING REPRESENTATIVE AT THE CONTRACTOR'S EXPENSE.
- 6. A TXDOT TYPE II B-B BLUE REFLECTIVE RAISED PAVEMENT MARKER SHALL BE INSTALLED IN THE CENTER OF THE ROADWAY ADJACENT TO ALL FIRE HYDRANTS. IN LOCATIONS WHERE HYDRANTS ARE SITUATED ON CORNERS, BLUE REFLECTIVE RAISED PAVEMENT MARKERS SHALL BE INSTALLED ON BOTH APPROACHES WHICH FRONT THE HYDRANT. THE RAISED PAVEMENT MARKER SHALL MEET TXDOT MATERIAL, EPOXY AND ADHESIVE SPECIFICATIONS.

#### GROUNDWATER

7. IT SHALL BE THE RESPONSIBILITY OF THE DEVELOPER, CONTRACTOR, SUBCONTRACTORS, BUILDERS, GEO-TECHNICAL ENGINEER, AND PROJECT ENGINEER TO IMMEDIATELY NOTIFY THE OFFICE OF THE CITY ENGINEERAND PROJECT ENGINEER IF THE PRESENCE OF GROUNDWATER WITHIN THE SITE IS EVIDENT. LIPON NOTIFICATION THE PROJECT ENGINEER SHALL RESPOND WITH PLAN REVISIONS FOR THE MITIGATION. OF THE GROUNDWATER ISSUE. THE CITY ENGINEER SHALL RESPOND WITHIN TWO (2) BUSINESS DAYS. UPON RECEIPT OF THE MITIGATION PLAN. ALL CONSTRUCTION ACTIVITY. IMPACTED BY THE DISCOVERY F GROUNDWATER, SHALL BE SUSPENDED UNTIL THE CITY ENGINEER GRANTS A WRITTEN APPROVAL OF THE GROUNDWATER MITIGATION PLAN.

#### RECORD DRAWINGS

8. AS PER PLATTING ORDINANCE SECTION 118-38M.: WHEN ALL OF THE IMPROVEMENTS ARE FOUND TO BE CONSTRUCTED AND COMPLETED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS AND WITH THE CITY'S STANDARDS, AND UPON RECEIPT OF ONE SET OF "RECORD DRAWING" PLANS, AND A DIGITAL COPY OF ALL PLANS (PDF COPY) THE CITY ENGINEER SHALL ACCEPT SUCH IMPROVEMENTS FOR THE CITY OF NEW BRAUNFÈLS, SUBJÉCT TO THE GUARANTY OF MATERIAL AND WORKMANSHIP

#### CONSTRUCTION NOTE

DRAINAGE NOTE

- 9. ENGINEER OF RECORD IS RESPONSIBLE TO ENSURE THAT EROSION CONTROL MEASURES AND STORMWATER CONTROL SUFFICIENT TO MITIGATE OFF SITE IMPACTS ARE IN PLACE AT ALL STAGES OF
- 10. DRAINAGE IMPROVEMENTS SUFFICIENT TO MITIGATE THE IMPACT OF CONSTRUCTION SHALL BE INSTALLED PRIOR TO ADDING IMPERVIOUS COVER.

#### FINISHED FLOOR ELEVATIONS

11. THE ELEVATION OF THE LOWEST FLOOR SHALL BE AT LEAST 10 INCHES ABOVE THE FINISHED GRADE OF THE SURROUNDING GROUND. WHICH SHALL BE SLOPED IN A FASHION SO AS TO DIRECT STORMWATER AWAY FROM THE STRUCTURE, PROPERTIES ADJACENT TO STORMWATER CONVEYANCE STRUCTURES MUST HAVE FLOOR SLAB ELEVATION OR BOTTOM OF FLOOR JOISTS A MINIMUM OF ONE FOOT ABOVE THE 100—YEAR WATER FLOW ELEVATION IN THE STRUCTURE. DRIVEWAYS SERVING HOUSES ON THE DOWNHILI SIDE OF THE STREET SHALL HAVE A PROPERLY SIZED CROSS SWALE PREVENTING RUNOFF FROM ENTERING THE GARAGE.

- 12. PROCTORS SHALL BE SAMPLED FROM ON-SITE MATERIAL (ON-SITE IS DEFINED AS LIMITS OF CONSTRUCTION FOR THIS -PLAN SET) AND A COPY OF THE PROCTOR RESULTS SHALL BE DELIVERED TO THE CITY OF NEW BRAUNFELS STREET INSPECTOR PRIOR TO ANY DENSITY TESTS. ROADWAY
- 13. ALL ROADWAY COMPACTION TESTS SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEOTECHNICAL ENGINEER. FLEXIBLE BASE OR FILL/EMBANKMENT MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED EIGHT INCHES (8") LOOSE. THE REQUIRED DENSITY FOR THE FILL/EMBANKMENT MATERIAL SHALL MEET THE REQUIREMENTS OF TXDOT'S SPECIFICATION ITEM 132. THE REQUIRED DENSITY FOR THE FLEXIBLE BASE MATERIAL SHALL MEET THE REQUIREMENTS OF TXDOT'S SPECIFICATION ITEM 247. EACH LAYER OF MATERIAL, INCLUSIVE OF SUBGRADE, SHALL BE COMPACTED AS SPECIFIED AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEOTECHNICAL ENGINEER AND APPROVED BY THE CITY OF NEW BRAUNFELS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL B TAKEN EVERY 200 LE FOR EACH LIFT, UPON COMPLETION OF TESTING, THE GEOTECHNICAL ENGINEER WILL PROVIDE THE CITY OF NEW BRAUNFELS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FLEXIBLE BASE, AND FILL MATERIAL, ANI SUBGRADE, HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS. ADDITIONAL DENSITY TESTS MAY BE REQUESTED BY THE CITY OF NEW BRAUNFELS INSPECTOR.

- 14. ASPHALTIC CONCRETE PAVEMENT SHALL BE THE TYPE OF HOT MIX ASPHALT AS DEFINED IN TXDOT'S STANDARD SPECIFICATIONS FOR CURRENT TXDOT STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREET AND BRIDGES.
- 15. THE CITY OF NEW BRAUNFELS WILL NOT ACCEPT THE USE OF RECYCLED ASPHALT PAVEMENT (RAP) OR RECYCLED ASPHALT SHINGLES (RAS) IN ASPHALT MIXTURES FOR NEW ROADWAYS. ANY DEBRIS INCLUSIONS WITHIN NEW ASPHALT PAVEMENTS WILL RESULT IN ASPHALT REMOVAL AND REPLACEMENT FROM CURB TO CURB FOR LIMITS TO BE DETERMINED BY THE CITY OF NEW BRAUNFELS.
- 16. THE ASPHALTIC CONCRETE PAVEMENT SURFACE COURSE SHALL BE PLANT MIXED, HOT LAID TYPE 'D MEETING THE SPECIFICATION REQUIREMENTS OF TXDOT ITEM 340. THE ASPHALTIC CONCRETE PAVEMENT SUB-SURFACE COURSES SHALL BE PLANT MIXED. HOT LAID TYPE "B" MEETING THE SPECIFICATION REQUIREMENTS OF TXDOT ITEM 340. THE MIXTURE SHALL BE DESIGNED PER THE DESIGN REQUIREMENTS SPECIFIED IN TXDOT ITEM 340 AND SHALL BE COMPACTED TO BETWEEN 91 AND 95 PERCENT OF THE MAXIMUM THEORETICAL DENSITY AS DETERMINED BY TXDOT TEST METHOD TEX-227-F. PLACE THE MIXTURE WHEN THE ROADWAY SURFACE TEMPERATURE IS AT OR ABOVE 60°F. COMPLETE COMPACTION OPERATIONS BEFORE THE PAVEMENT TEMPERATURE DROPS BELOW 160°F. THE ASPHAL CEMENT CONTENT BY PERCENT OF TOTAL MIXTURE WEIGHT SHALL FALL WITHIN A TOLERANCE OF +0.5

## UTILITY TRENCH COMPACTION (ADDED TO THE CONSTRUCTION PLANS ON ALL UTILITY PLAN SHEETS).

17. ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT/SIDEWALK SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEOTECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. DETERMINE THE MAXIMUM LIFT THICKNESS BASED ON THE ABILITY OF THE COMPACTING OPERATION AND EQUIPMENT USED TO MEET THE REQUIRED DENSITY. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSIT AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEOTECHNICAL ENGINEER AND APPROVED BY THE CITY OF NEW BRAUNFELS STREET INSPECTOR. A $^{\circ}$ A MINIMUM. TESTS SHALL BE TAKEN EVERY 200 LF FOR EACH LIFT AND EVERY OTHER SERVICE LINE UPON COMPLETION OF TESTING THE GEOTECHNICAL ENGINEER SHALL PROVIDE THE CITY OF NEW BRAUNFELS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS. ADDITIONAL DENSITY TESTS MAY BE REQUESTED BY THE CITY OF NEW BRAUNFELS INSPECTOR.

## CURB CUT DUE TO CONSTRUCTION OF NEW RIGHT-OF-WAY CONSTRUCTION

18. CURB CUTS SHALL BE THE FOLLOWING METHODS AND INDICATED ON THE PLANS IN DETAIL WHERE APPLICABLE. 18.1 SAWCUT EXISTING STREET AND MATCH TO NEW CONSTRUCTION 18.2 SAWCUT EXISTING CURB TO TIE INTO EXISTING CONSTRUCTION.

## CONSTRUCTION STABILIZED ENTRANCE

PERCENT FROM A SPECIFIC MIX DESIGN.

## 19. SAWCUT CURB FOR CONSTRUCTION ENTRANCE.

20. STABILIZED CONSTRUCTION AREA SHALL BE CONSTRUCTED OF 3"X5" ROCK TO BE PLACED A MINIMUM LENGTH OF 25-FT. AND MAINTAINED SO THAT CONSTRUCTION DEBRIS DOES NOT FALL WITHIN THE CITY RIGHT-OF-WAY. RIGHT-OF-WAY MUST BE CLEARED FROM MUD, ROCKS, ETC. AT ALL TIMES.

#### SIGNING AND PAVEMENT MARKING PLAN NOTES 1. IF CONSTRUCTION HAS NOT COMMENCED WITHIN ONE-YEAR OF CITY APPROVAL FOR CONSTRUCTION

- THE CONTRACTOR SHALL FURNISH AND INSTALL ALL REGULATORY AND WARNING SIGNS, STREETS NAME SIGNS AND SIGN MOUNTS IN ACCORDANCE WITH APPROVED ENGINEERING PLANS. THE CITY WILL INSPECT ALL SIGNS AT FINAL INSPECTION.
- 22. THE CONTRACTOR SHALL INSTALL ALL PAVEMENT MARKINGS IN ACCORDANCE WITH APPROVED ENGINEERING PLANS.
- INSTALLATION OF ALL SEALER AND FINAL MARKINGS. THE CITY WILL INSPECT ALL MARKINGS AT FINAL

## SEEDING AND ESTABLISHMENT OF VEGETATION WITHIN EARTHEN CHANNELS, STORMWATER BASINS AND

- SEEDING FOR THE PURPOSE OF ESTABLISHING VEGETATION WITHIN CONSTRUCTED EARTHEN CHANNELS, BASINS AND DISTURBED AREAS SHALL BE CONDUCTED IN ACCORDANCE WITH ITEM 164 (SEEDING FOR EROSION CONTROL) OF TXDOT'S STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MAINTENANCE OF HIGHWAYS, STREETS AND BRIDGES MANUAL. ONLY SEED TYPES AND MIXES SPECIFIED FOR THE SAN ANTONIO DISTRICT (DISTRICT 15) IN TABLES 1 AND 2 UNDER ITEM 164 SHALL BE UTILIZED. DURING THE COOL SEASON (SEPT 1-NOV 30), CEREAL RYE AND SEED SPECIES SPECIFIED FOR THE SAN ANTONIO DISTRICT IN TABLE 3 MAY BE USED. FOR COOL SEASON SEEDING APPLICATIONS, COOL SEASON SEED MIXES SHALL BE USED IN CONJUNCTION WITH SEED MIXES FOR THE SAN ANTONIO DISTRICT AS SPECIFIED IN TABLE 1 AND 2 UNDEF
- 2. IT MAY BE DEEMED NECESSARY TO INCORPORATE TOPSOIL AND SOIL AMENDMENTS (I.E. COMPOST/ FERTILIZER) INTO EXISTING SOIL IN ORDER TO FACILITATE VEGETATION GROWTH. TOPSOIL, COMPOST AND FERTILIZER ADDITIONS SHALL BE CONDUCTED ACCORDING TO ITEMS 160, 161 AND 166 OF TXDOT'S STANDARD SPECIFICATIONS MANUAL, RESPECTIVELY.
- AREAS REQUIRING PERMANENT VEGETATION (EARTHEN CHANNELS, PONDS, ETC.) ARE REQUIRED TO MEET TXDOT SPECIFICATIONS FOR ITEM 160 TOPSOIL. TESTING PER TEX-128-E WILL BE REQUIRED AT THE CITY'S
- WATERING MAY ALSO BE NECESSARY TO FACILITATE AND EXPEDITE THE SPROUTING AND GROWTH OF VEGETATION. ITEM 168 OF TXDOT'S STANDARD SPECIFICATIONS MANUAL SHALL BE ADHERED TO FOR
- IF EXTENDED DROUGHT CONDITIONS EXIST THAT HINDER OR PROHIBIT THE GROWTH AND ESTABLISHMENT OF VEGETATION. THE CONTRACT/ DEVELOPER SHALL PROVIDE A PLAN TO THE CITY OF NEW BRAUNFELS DESCRIBING THE MEASURES THAT WILL BE TAKEN TO STABILIZE EARTHEN DRAINAGE INFRASTRUCTURE UNTIL A TIME WHEN GROWING CONDITIONS BECOME MORE FAVORABLE.

#### NEW BRAUNFELS UTILITIES - GENERAL NOTES - REV 4-2020

- ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THE PROJECT SHALL BE 9. HYDROSTATIC TESTING IS DONE FROM VALVE TO VALVE. APPROVED BY NEW BRAUNFELS UTILITIES AND COMPLY WITH THE CURRENT "NEW BRAUNFELS UTILITIES WATER SYSTEMS CONNECTION/CONSTRUCTION POLICY".
- CONTRACTOR SHALL NOT PROCEED WITH ANY PIPE INSTALLATION WORK UNTIL THEY OBTAIN A COPY OF THE PLANS FROM THE CONSULTANT OR ENGINEER AND NOTIFY NBU WATER SYSTEMS ENGINEERING AT 830-608-8971 WITH AT LEAST TWO (2) WORKING DAYS (48 HOURS) NOTICE, WORK COMPLETED BY THE CONTRACTOR, WHICH HAS NOT RECEIVÈÓ A NOTICE TO PROCEED FRÓM NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING WILL BE SUBJECT TO REMOVAL AND REPLACEMENT BY AND AT THE EXPENSE OF THE CONTRACTOR
- THE DEVELOPER DEDICATES THE WATER / WASTEWATER MAINS UPON COMPLETION BY THE CONTRACTOR AND ACCEPTANCE BY THE NEW BRAUNFELS UTILITIES WATER SYSTEM. NBU WILL OWN AND MAINTAIN SAID WATER / WASTEWATER MAINS WHICH ARE LOCATED WITHIN PLATTED UTILITY EASEMENTS OR PUBLIC ROW OF PROPOSED DEVELOPMENTS. (AS APPLICABLE)
- 4. CONTRACTOR AGREES TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY. THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS. THE CONTRACTOR SHALL DEFEND. INDEMNIFY AND HOLD THE OWNERS AND THE ENGINEER AND HIS EMPLOYEES. PARTNERS OFFICERS. DIRECTORS. OR CONSULTANTS HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF THE WORK ON THIS PROJECT, EXCEPTING FROM LIABILITY ARISING FROM SOLE NEGLIGENCE OF THE OWNER OR ENGINEER, ENGINEER'S DIRECTORS, OFFICERS, EMPLOYEES, OR CONSULTANTS.
- 5. CONTRACTOR AND / OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION
- 6. CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING TO ITS ORIGINAL OR BETTER CONDITION, ANY DAMAGES DONE TO EXISTING FENCES, CURBS, STREETS, DRIVEWAYS, LANDSCAPING AND STRUCTURES, AND EXISTING UTILITIES (NOT ADJUSTED ON PLANS). COST OF RESTORATIONS, IF ANY, SHALL BE THE CONTRACTOR'S ENTIRE EXPENSE.
- THE CONTRACTOR SHALL AVOID CUTTING ROOTS LARGER THAN ONE INCH IN DIAMETER WHEN EXCAVATING NEAR EXISTING TREES. EXCAVATION IN VICINITY OF TREES SHALL PROCEED WITH CAUTION. CONTRACTOR SHALL PROCURE ALL PERMITS AND LICENSES, PAY ALL CHARGES, FFFS AND TAXES AND

GIVE ALL NOTICES NECESSARY AND INCIDENTAL TO THE DUE AND LAWFUL PROSECUTION OF THE WORK.

#### 9. NO EXTRA PAYMENT SHALL BE ALLOWED FOR WORK CALLED FOR ON THE PLANS BUT NOT INCLUDED ON THE BID SCHEDULE. THIS INCIDENTAL WORK WILL BE REQUIRED AND SHALL BE INCLUDED UNDER THE PAY ITEM TO WHICH IT RELATES.

- 10. CONTRACTOR IS RESPONSIBLE FOR REMOVAL OF ALL WASTE MATERIALS UPON PROJECT COMPLETION. THE CONTRACTOR SHALL NOT PERMANENTLY PLACE ANY WASTE MATERIALS IN THE 100-YEAR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN DEVELOPMENT PERMIT.
- AQUIFER WITHOUT AN APPROVED WATER POLLUTION ABATEMENT PLAN FROM THE TCEQ 31 TAC 313.4 BARRICADES AND WARNING SIGNS SHALL CONFORM TO THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" AND SHALL BE LOCATED TO PROVIDE MAXIMUM PROTECTION TO THE PUBLIC AS WELL AS CONSTRUCTION PERSONNEL AND FOLLIPMENT WHILE PROVIDING CONTINUOUS TRAFFIC FLOW AT

11. THE CONTRACTOR SHALL NOT PLACE ANY MATERIALS ON THE RECHARGE ZONE OF THE EDWARDS

- ALL TIMES DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ALL DEVICES 13. CONTRACTOR IS REQUIRED TO VERIFY PROJECT ELEVATIONS. THE TERM "MATCH EXISTING" SHALL BE UNDERSTOOD TO SIGNIFY BOTH HORIZONTAL AND VERTICAL ALIGNMENT
- THE LOCATION OF UTILITIES, EITHER UNDERGROUND OR OVERHEAD, SHOWN WITHIN THE RIGHT OF WAY ARE APPROXIMATE AND SHALL BE VERIFIED BY THE CONTRACTOR BEFORE BEGINNING CONSTRUCTION
- OF AN ENERGIZED LINE. WHERE WORKMEN AND/OR EQUIPMENT HAVE TO WORK CLOSE TO AN ENERGIZED ELECTRICAL LINE, THE CONTRACTOR SHALL NOTIFY THE ELECTRICAL POWER COMPANY INVOLVED AND MAKE WHATEVER ADJUSTMENTS NECESSARY TO ENSURE THE SAFETY OF THOSE WORKMEN.
- 16. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO LOCATE UTILITY SERVICE LINES AS REQUIRED FOR CONSTRUCTION. UTILITY COMPANIES ARE ALSO PREVIOUSLY MENTIONED IN "UTILITY COMPACTION
- 17. DUE TO FEDERAL REGULATIONS TITLE 49, PART 192 (8), GAS COMPANIES MUST MAINTAIN ACCESS TO GAS VALVES AT ALL TIMES. THE CONTRACTOR MUST PROTECT AND WORK AROUND ANY GAS VALVES THAT ARE IN THE PROJECT AREA.
- THE CONTRACTOR IS FULLY RESPONSIBLE FOR THE TRAFFIC CONTROL AND WILL BE RESPONSIBLE FOR FURNISHING ALL TRAFFIC CONTROL DEVICES, AND FLAGGERS. THE CONSTRUCTION METHODS SHALL BE TO PROVIDE THE LEAST POSSIBLE INTERFERENCE TO TRAFFIC SO AS TO PERMIT THE CONTINUOUS MOVEMENT OF THE TRAFFIC IN ONE DIRECTION AT ALL TIMES. THE CONTRACTOR SHAL CLEAN UP AND REMOVE FROM THE WORK AREA ANY LOOSE MATERIAL RESULTING FROM CONTRACT OPERATIONS AT THE END OF EACH WORKDAY.
- 19. PRIOR TO ORDERING MATERIALS TO BE USED IN CONSTRUCTION, CONTRACTOR SHALL PROVIDE THE ENGINEER WITH FOUR (4) COPIES OF THE SOURCE, TYPE, GRADATION, MATERIAL SPECIFICATION DATA AND / OR SHOP DRAWINGS, AS APPLICABLE, TO SATISFY THE REQUIREMENTS OF THE FOLLOWING ITEMS AND ALL MATERIAL ITEMS REFERRED TO IN THESE LISTED ITEMS:
- 19.1. WATER MAINS AND SERVICES
- 19.2. SEWER MAINS AND SERVICES
- 20. NO METER BOXES TO BE SET IN DRIVEWAYS. ANY METER BOXES IN DRIVEWAYS WILL BE RELCOCATED AT CONTRACTOR'S AND/OR DEVELOPER'S EXPENSE.
- 21. WHERE THE MINIMUM 9 FOOT SEPARATION DISTANCE BETWEEN WASTEWATER LINES AND WATER LINES / MAINS CANNOT BE MAINTAINED, THE INSTALLATION OF SEWER LINES SHALL BE IN STRICT ACCORDANCE
- 22. CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT. IF ANY. SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF THE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH
- 23. UTILITY TRENCH COMPACTION WITH STREET R.O.W. a. ALL UTILITY TRENCH COMPACTION TEST WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER.
- b. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE.

- c. EACH LAYER OF MATERIAL SHALL BE COMPACTED AS SPECIFIED AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEXT METHODS TEX-113-E, TEX- 114-E, TEX-115-E
- d. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEOTECHNICAL ENGINEER AND APPROVED BY THE CITY OF NEW BRAUNFELS STREET INSPECTOR.
- e. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF NEW BRAUNFELS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS
- 24. WATER IS A PRECIOUS COMMODITY IN THE STATE OF TEXAS AND NEW BRAUNFELS UTILITIES (NBU) IS PASSIONATE ABOUT PROTECTING THE LOCAL RESOURCE. NBU'S CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ACQUIRING A FIRE HYDRANT METER SO THAT ALL WATER USED FOR CONSTRUCTION OR TESTING PURPOSES ARE PROPERLY ACCOUNTED FOR NBU WILL NOT TOLERATE ANY WATER THEF REGARDLESS OF THE AMOUNT IF WATER THEFT IS DISCOVERED NBU'S CONTRACTOR SHALL BE SUBJECT TO MONETARY PENALTIES. CRIMINAL CHARGES. AND STOPPAGE OF ALL CONSTRUCTION ACTIVITIES. RELATED TO THE PROJECT. COSTS ASSOCIATED WITH ANY WORK STOPPAGE RESULTING FROM WATER THEFT SHALL BE AT THE FULL EXPENSE OF THE CONTRACTOR.

#### NBU WATER NOTES - REV 5-2019

2. WATER SERVICES SHALL BE SINGLE 1" COPPER TUBING.

1. ALL WATER MAINS SHALL BE AWWA C900 (CLASS 150 OR GREATER).

- 3. WATER LINE IS TO BE CONSTRUCTED IN ACCORDANCE WITH THE NBU SYSTEMS CONNECTION & CONSTRUCTION POLICY.
- 4. WATER MAIN SHALL HAVE A MINIMUM OF 42 INCHES OF COVER, OTHERWISE CONCRETE ENCASEMENT WILL BE REQUIRED.
- 5. EACH UNIT IN A DUPLEX, TRIPLEX, FOURPLEX, OR CONDOMINIUM SHALL BE PROVIDED WITH AN INDIVIDUAL WATER METER. A MASTER METER CAN BE CONSIDERED FOR SEPARATE BUILDINGS, HOWEVER, THOSE BUILDINGS MUST BE PLUMBED TO ALLOW SEPARATE METERS FOR FUTURE CONSIDERATION.
- 6. CONTRACTOR WILL KEEP THE AREA ON TOP OF AND AROUND THE WATER METER BOX FREE OF ALL
- . INITIAL BACKFILL OF WATER LINES SHALL BE MANUFACTURED SAND OR PEA GRAVEL AS PER NBU SYSTEMS CONNECTION & CONSTRUCTION POLICY.
- 8. SECONDARY BACKFILL OF WATER LINES SHALL GENERALLY CONSIST OF MATERIAL REMOVED FROM THE FRENCH AND SHALL BE FREE FROM BRUSH, DEBRIS AND TRASH OR STONES HAVING ANY DIMENSION LARGER THAN 6" INCHES AT THE LARGEST DIMENSION.

OBJECTS AND DEBRIS.

- 10. NO METER BOXES TO BE SET IN DRIVEWAYS OR SIDEWALKS. ANY METER BOXES SET IN DRIVEWAYS OR SIDEWALKS WILL BE RELOCATED AT CONTRACTOR'S AND/OR DEVELOPER'S EXPENSE.
- 1. METER BOXES MUST BE SET AT THE PROPOSED GRADE. ANY METER BOXES THAT ARE NOT SET AT THE FINAL GRADE WILL BE ADJUSTED AT CONTRACTOR'S AND/OR DEVELOPER'S EXPENSE.
- 12. ACCEPTABLE METER BOXES ARE D13-BAMR AND D15-BAMR. NEW RESIDENTIAL LOTS ARE REQUIRED TO USE THE D15-BAMR METER BOXES (DOUBLE AMR). COMMERCIAL LOTS SHOULD CHOOSE WHICH BOX APPLIES TO THE DOMESTIC AND/OR IRRIGATION METER LAYOUT.
- 13. THRUST BLOCKS WILL NOT BE ALLOWED ON THE SYSTEM WITHOUT SPECIAL APPROVAL. JOINTS WILL BE RESTRAINED WITH RESTRAINING SYSTEMS APPROVED BY NBU AND RESTRAINT LENGTH SHALL B SUBMITTED TO NBU AT THE TIME OF PLAN SUBMITTAL
- 14. CONTRACTOR SHALL PLACE TRACER WIRE ON TOP OF THE WATER MAINS. TRACER WIRE SHOULD RUN 3. BEGIN DEMOLITION ACTIVITIES, IF APPLICABLE. FROM VALVE TO VALVE AND EXIT AT THE VALVE BOX. THE TRACER WIRE SHOULD BE ATTACHED TO THE TOP OF THE PIPE USING TAPE. EXCESS WIRE SHOULD BE LEFT WITHIN VALVE BOXES TO BE PLACED WITHIN LID OF COVER.
- 15. WATER QUALITY SHALL BE PROTECTED WITH APPROPRIATE BACKFLOW PREVENTION ASSEMBLIES INSTALLED ON ALL IRRIGATION SYSTEMS. FIRE SUPPRESSION SYSTEMS AND MULTI-UNIT COMPLEXES. ALONG WITH MULTI-LEVEL PROPERTIES ON DOMESTIC METER CONTAINMENT, NBU CAN ASSIST WITH THE DECISION ON APPROPRIATE BACKFLOW ASSEMBLIES ON A CASE BY CASE BASIS. CONTACT BACKFLOW PREVENTION SPECIALIST FOR MORE DETAILS. EMAIL QUESTIONS TO CROSSCONNECTION@NBUTEXAS.COM.
- 16. ALL BACKFLOW PREVENTION ASSEMBLIES SHALL BE TESTED UPON INSTALLATION AND REPORT SENT TO NBU VIA THE ONLINE TRACKING SYSTEM, CONTACT NBU BACKFLOW PREVENTION SPECIALIST FOR MORE DETAILS. EMAIL QUESTIONS TO CROSSCONNECTION@NBUTEXAS.COM.
- 7. ALL RESIDENTIAL AND COMMERCIAL PROPERTIES SHALL HAVE A CUSTOMER SERVICE INSPECTION CERTIFICATE (CSI INSPECTION ) COMPLETED UPON COMPLETION OF THE BUILDING OR HOME STRUCTURE. CONTACT NBU BACKFLOW PREVENTION SPECIALIST FOR MORE DETAILS. EMAIL QUESTIONS TO CROSSCONECCTION@NBUTEXAS.COM.
- 18. THE ENGINEER OF RECORD MUST ACKNOWLEDGE THAT THE POINT OF DELIVERY FOR AN NBU WATER SYSTEM IS THE MAIN SIDE OF THE SERVICE/LATERAL/LEAD FROM THE CUSTOMER'S METER/BACKFLOW/EASEMENT EDGE, AND THE MAIN SIDE OF THE SERVICE LATERAL FROM THE CUSTOMER'S CLEANOUT OR PROPERTY LINE FOR AN NBU WASTEWATER SYSTEM. THE CUSTOMER IS RESPONSIBLE FOR DESIGN, CONSTRUCTION, OPERATION, AND MAINTENANCE BEYOND THE POINT OF DELIVERY AND HAS SOLE CONTROL AND SUPERVISION OVER THE CUSTOMER'S INSTALLATION INCLUDING REVIEW, PERMITTING, AND COMPLIANCE WITH ALL CITY PLUMBING CODES OR OTHER APPLICABLE CODES

## NBU WASTEWATER NOTES

a. PULL MANDREL

ARE REQUIRED ON NEW INSTALLATION.

- THE CONTRACTOR SHALL MAINTAIN SERVICE TO EXISTING WASTEWATER SYSTEM AT ALL TIMES DURING
- 2. A MINIMUM OF 8" WASTEWATER PIPE AND FITTINGS (P.V.C. SDR-26, ASTM, D- 3034, D-3212, F-477)
- 3. ALL RESIDENTIAL WASTEWATER SERVICE LATERALS SHALL BE EXTENDED TO THE PROPERTY LINE AND A CLEANOUT SHALL BE INSTALLED AT THE PROPERTY LINE. SERVICES TO LOTS WILL EXTEND FOUR (4) FFFT PAST THE UNDERGROUND FLECTRIC CONDUIT IF FLECTRIC IS INSTALLED IN THE FRONT FASEMENT. ALL SEWER CLEANOUTS THAT LEAD TO NBU MAINS SHALL BE INSTALLED WITH A PROTECTIVE UITLITY SHROUD AND PIVOTING MARKER POLE DURING TIME OF CONSTRUCTION.
- 15. OSHA REGULATIONS PROHIBIT OPERATIONS THAT WILL BRING PERSONS OR EQUIPMENT WITHIN 10 FEET 4. PIPE BEDDING OF WASTEWATER LINES SHALL BE MANUFACTURED SAND OR PEA GRAVEL AS PER NBU
  - 5. SECONDARY BACKFILL OF WASTEWATER LINES SHALL GENERALLY CONSIST OF MATERIALS REMOVED FROM THE TRENCH AND SHALL BE FREE FROM BRUSH, DEBRIS AND TRASH, NO ROCKS OR STONES HAVING ANY DIMENSION LARGER THAN 6 INCHES AT THE LARGEST DIMENSION.
  - 6. ALL WASTEWATER PIPES SHALL HAVE COMPRESSION OR MECHANICAL JOINTS AS PER 30 TAC §217.53
  - . FOR WASTEWATER LINES LESS THAN 24" IN DIAMETER, SELECT INITIAL BACKFILL MATERIAL SHALL BE a. THE FIRST LIFT SHALL BE SPREAD UNIFORMLY AND SIMULTANEOUSLY ON EACH SIDE AND UNDER THE SHOULDERS OF THE PIPE TO THE MID POINT OR SPRING LINE OF THE PIPE.
  - b. THE SECOND LIFT SHALL BE PLACED TO A DEPTH AS SHOWN ON THE PIPE BACKFILL DETAIL. FOR PIPES LARGER THAN 24", 12" MAXIMUM LIFTS SHALL BE USED. 8. ALL MANHOLES MUST BE WATER TIGHT, EITHER MONOLITHIC, CAST-IN-PLACE CONCRETE STRUCTURES OR PREFABRICATED MANHOLES SPECIFICALLY APPROVED BY NBU. THE MANHOLES SHALL HAVE WATER-TIGHT RINGS AND COVERS. WHEREVER THEY ARE WITHIN THE 100 YEAR FLOODPLAIN, THE
  - MANHOLE COVERS SHALL BE BOLTED. EVERY THIRD MANHOLE IN SEQUENCE SHALL HAVE AN ALTERNATE MEANS OF VENTING. 30 TAC §213.5 (C) (3) (A) AND 30 TAC §217.55 (O)
  - 9. ALL MANHOLES SHALL BE CONSTRUCTED SO THAT THE TOP OF THE RING IS TWO INCHES (2") ABOVE SURROUNDING GROUND EXCEPT WHEN LOCATED IN PAVED AREA. IN PAVED AREAS, THE MANHÓLE RING SHALL BE FLUSH WITH PAVEMENT
  - 11. WASTEWATER PIPE CONNECTIONS TO PRE-CAST MANHOLES WILL BE COMPRESSION JOINTS OR MECHANICAL "BOOT TYPE" JOINT AS APPROVED BY NBU.

10. ALL NEW MANHOLES, UNLESS APPROVED BY NBU ENGINEERING, ARE TO HAVE COVERS WITH 32"

- 12. WASTEWATER LINES SHALL BE TESTED FROM MANHOLE TO MANHOLE.
- 13. IN AREAS WHERE A NEW WASTEWATER MANHOLE IS TO BE CONSTRUCTED OVER AN EXISTING WASTEWATER SYSTEM, IT SHALL BE THE CONTACTOR'S RESPONSIBILITY TO TEST THE EXISTING MANHOLES BEFORE CONSTRUCTION. AFTER THE PROPOSED MANHOLE(S) HAS BEEN BUILT. THE CONTRACTOR SHALL RE-TEST THE EXISTING SYSTEM TO THE SATISFACTION OF THE CONSTRUCTION INSPECTOR. (NO SEPARATE PAY ITEM).

14. WHERE THE MINIMUM 9 FOOT SEPARATION DISTANCE BETWEEN WASTEWATER LINES AND WATER LINES /

MAINS CANNOT BE MAINTAINED, THE INSTALLATION OF WASTEWATER LINES SHALL BE IN STRICT

ACCORDANCE WITH TCEQ. THE WASTEWATER LINE SHALL BE CONSTRUCTED OF CAST IRON, DUCTILE IRON

OR PVC MEETING THE ASTM SPECIFICATION FOR BOTH PIPES AND JOINTS OF 150 PSI AND SHALL BE IN ACCORDANCE WITH 30 TAC \( \)217.53 (D) (3) (A) (I). 15. NO TESTING WILL BE PERFORMED PRIOR TO 30 DAYS FROM COMPLETE INSTALLATION OF THE WASTEWATER LINES. THE FOLLOWING SEQUENCE WILL BE STRICTLY ADHERED TO:

- b. PERFORM AIR TEST
- c. CLEANING OF ANY DEBRIS
- d. FLUSHING OF SYSTEM
- e. TV INSPECTION (WITHIN 72 HOURS OF FLUSHING)
- 16. A MINIMUM OF 3 FEET OF COVER IS TO BE MAINTAINED OVER THE WASTEWATER MAIN AND LATERALS AT SUBGRADE, OTHERWISE CONCRETE ENCASEMENT WILL BE REQUIRED.
- . WASTEWATER MAIN CONNECTIONS MADE DIRECTLY TO EXISTING MANHOLES WILL REQUIRE SUCCESSFUL TESTING OF THE MANHOLE IN ACCORDANCE WITH NBU CONNECTION & CONSTRUCTION POLICY MANUAL.
- 18. TCEQ AND EPA REQUIRE EROSION AND SEDIMENTATION CONTROL FOR CONSTRUCTION OF WASTEWATER COLLECTION SYSTEMS. DEVELOPER OR AUTHORIZED REPRESENTATIVE SHALL PROVIDE EROSION AND SEDIMENTATION CONTROL AS NOTES ON THE PROJECT'S PLAN AND PROFILE SHEETS. ALL TEMPORARY EROSION AND SEDIMENTATION CONTROLS SHALL BE REMOVED BY THE CONTRACTOR AT FINAL ACCEPTANCE OF THE PROJECT BY NBU WATER SYSTEMS.
- 19. ALL MANHOLES NOT WITHIN PAVED STREETS SHALL HAVE LOCKING CONCRETE COLLAR TO SECURE RING AND COVER TO MANHOLE CONE PER NBU DETAIL DRAWING #329.
- 20. ALL MANHOLES OVER THE EDWARDS AQUIFER RECHARGE ZONE SHALL HAVE LOCKING CONCRETE COLLAR

TO SECURE RING AND COVER TO MANHOLE CONE PER NBU DETAIL DRAWING #329

#### **EROSION / SEDIMENTATION CONTROL:**

- 1. AT A MINIMUM, THESE CONTROLS SHALL CONSIST OF ROCK BERMS AND/OR SILT FENCES CONSTRUCTED. PARALLEL TO AND DOWN GRADIENT FROM THE TRENCHES. THE ROCK BERM OR SILT FENCES SHALL BE INSTALLED IN A MANNER SUCH THAT ANY RAINFALL RUNOFF SHALL BE FILTERED. HAY BALES SHALL NOT BE USED FOR TEMPORARY EROSION AND SEDIMENTATION CONTROLS.
- ALL TEMPORARY FROSION AND SEDIMENTATION CONTROLS MUST BE INSTALLED PRIOR TO CONSTRUCTION AND SHALL BE MAINTAINED DURING CONSTRUCTION BY THE CONTRACTOR. THE CONTRACTOR SHALL REMOVE THE CONTROLS WHEN VEGETATION IS ESTABLISHED AND THE CONSTRUCTION AREA STABILIZED. ADDITIONAL PROTECTION MAY BE REQUIRED IF EXCESSIVE SOLIDS ARE BEING DISCHARGED FROM THE SITE.
- 3. ALL TEMPORARY EROSION AND SEDIMENTATION CONTROLS SHALL BE REMOVED BY THE CONTRACTOR AT FINAL ACCEPTANCE OF THE PROJECT BY THE OWNER/ENGINEER.
- PLACEMENT OF TEMPORARY EROSION AND SEDIMENTATION CONTROLS SHALL BE IN ACCORDANCE WITH HE CONSTRUCTION PLANS. ACTUAL LOCATIONS MAY VARY SLIGHTLY FROM THE PLANS. THE CONTRACTOR SHALL INSPECT THE CONTROLS AT WEEKLY INTERVALS AND AFTER EVERY SIGNIFICANT RAINFALL TO INSURE DISTURBANCE OF THE STRUCTURES HAS NOT OCCURRED. SEDIMENT DEPOSITED AFTER A RAINFALL SHALL BE REMOVED FROM THE SITE OR PLACED IN AN ENGINEER APPROVED DESIGNATED DISPOSAL AREA.
- 5. ADDITIONAL CONTROLS MAY BE REQUIRED FOR PROJECTS OVER THE EDWARDS AQUIFER RECHARGE ZONE. REFERENCE 30 TAC 213 CHAPTER A.
- 6. CONTRACTOR OR CONTRACTOR'S CONSULTANT SHALL HAVE A STORM WATER POLLUTION PREVENTION PLAN PREPARED AND ON-SITE AT ALL TIMES.

#### SEQUENCE OF CONSTRUCTION:

- OBTAIN CITY APPROVED SITE PREPARATION PLANS, AND TPDES PERMIT (NOT A COPY OF THE TPDES APPLICATION TO TCEQ), IF APPLICABLE.
- 2. INSTALL TEMPORARY EROSION AND SEDIMENTATION CONTROLS.
- 4. BEGIN SITE CLEARING AND GRADING. 5. INSTALL SEWER AND WATER IMPROVEMENTS.
- 6. INSTALL ELECTRIC IMPROVEMENTS.

GAUGE

GALVANIZED IRON

GLOBAL POSITION STATION

HIGH DENSITY POLYETHYLENE PIPE

7. INSTALL ROADWAY IMPROVEMENTS (ASPHALT, CURBS, SIDEWALKS, ETC.)

8. RESTORE AND REVEGETATE ALL DISTURBED AREAS NOT UNDER IMPERMEABLE IMPROVEMENTS.

- 9. COMPLETE ANY REMAINING "PUNCH LIST" ITEMS.
- 10. CONTRACTOR SHALL REMOVE TEMPORARY EROSION CONTROLS AFTER PERMANENT STABILIZATION IS AT LEAST 70% EVENLY ESTABLISHED. RYE IS NOT ACCEPTED.

## 

\*PLEASE NOTE: NO DETENTION POND OR EARTHEN CHANNEL IS PROPOSED WITH HIGHLAND GARDENS UNIT 1A. FOR LOCATION, CONSTRUCTION AND MAINTENANCE OF DETENTION POND AND EARTHEN CHANNELS, SEE HIGHLAND GARDENS UNIT 2 PLANS.\*

- ACCESS DRIVE OVER TOP OF CURB FOR MOWING AND MAINTENANCE OF DETENTION POND, CHANNELS AND DRAINAGE LOTS
- INSPECTION BMP FACILITIES MUST BE INSPECTED WEEKLY (ONCE DURING OR IMMEDIATELY FOLLOWING WET WEATHER) TO EVALUATE FACILITY OPERATION. DURING EACH INSPECTION, EROSION AREAS INSIDE AND DOWNSTREAM OF THE BMP MUST BE IDENTIFIED AND REPAIRED OR REVEGETATED IMMEDIATELY. WITH EACH INSPECTION, ANY DAMAGE TO THE STRUCTURAL ELEMENTS OF THE SYSTEM (PIPES, CONCRETE DRAINAGE STRUCTURES, RETAINING WALLS, AERATOR, PUMPS, ETC.) MUST BE IDENTIFIED AND REPAIRED IMMEDIATELY, CRACKS, VOIDS AND UNDERMINING SHOULD BE PATCHED/FILLED TO PREVENT ADDITIONAL STRUCTURAL DAMAGE. TREES AND ROOT SYSTEMS SHOULD BE REMOVÉD TO PREVENT GROWTH IN RACKS AND JOINTS THAT CAN CAUSE STRUCTURAL DAMAGE. ANY DRAINAGE STRUCTURES CONSISTING F GRASS COVER WILL REQUIRE MORE FREQUENT INSPECTIONS DURING THE FIRST FEW YEARS AFTER STABLISHMENT TO DETERMINE IF ANY PROBLEMS ARE DEVELOPING, AND TO PLAN FOR LONG-TERM RESTORATIVE MAINTENANCE NEEDS. BARE SPOTS AND AREAS OF EROSION IDENTIFIED DURING SEMI-ANNUAL INSPECTIONS MUST BE REPLANTED AND RESTORED TO MEET SPECIFICATIONS.
- SEDIMENT REMOVAL REMOVE SEDIMENT FROM THE INLET STRUCTURE, SEDIMENTATION CHAMBER, OR POND BOTTOM WHEN SEDIMENT BUILDUP REACHES A DEPTH OF 6 INCHES OR WHEN THE PROPER FUNCTIONING OF INLET AND OUTLET STRUCTURES IS IMPAIRED. SEDIMENT SHOULD BE CLEARED FROM THE

INLET STRUCTURE AT LEAST EVERY YEAR AND FROM THE SEDIMENTATION BASIN EVERY YEAR

- DEBRIS AND LITTER REMOVAL DEBRIS AND LITTER WILL ACCUMULATE NEAR THE SEDIMENTATION BASIN OUTLET DEVICE AND SHOULD BE REMOVED DURING REGULAR MOWING OPERATIONS AND INSPECTIONS. PARTICULAR ATTENTION SHOULD BE PAID TO FLOATING DEBRIS THAT CAN EVENTUALLY CLOG THE CONTROL DEVICE OR RISER.TRASH TENDS TO ACCUMULATE IN VEGETATED AREAS, PARTICULARLY ALONG ROADWAYS. ANY FILTER STRIP STRUCTURES (I.E. LEVEL SPREADERS) OR VEGETATED AREAS SHOULD BE EPT FREE OF OBSTRUCTIONS TO REDUCE FLOATABLES BEING FLUSHED DOWNSTREAM, AND FOR AESTHETIC REASONS. THE NEED FOR THIS PRACTICE IS DETERMINED THROUGH PERIODIC INSPECTION, BUT SHOULD BE PERFORMED NO LESS THAN 4 TIMES PER YEAR.
- MOWING GRASS AREAS IN AND AROUND SAND FILTERS, INLETS, OUTLETS, DETENTION PONDS. CHANNELS AND VEGETATIVE FILTER STRIPS MUST BE MOWED AT LEAST TWICE ANNUALLY TO LIMIT ÆGETATION HEIGHT TO 18 INCHES. MORE FREQUENT MOWING TO MAINTAIN AESTHETIC APPEAL MAY BE NECESSARY IN LANDSCAPED AREAS. VEGETATION ON THE POND EMBANKMENTS SHOULD BE MOWED AS APPROPRIATE TO PREVENT THE ESTABLISHMENT OF WOODY VEGETATION IE NATIVE GRASSES ARE LISED. THEY MAY REQUIRE LESS FREQUENT MOWING. BUT A MINIMUM OF TWICE ANNUALLY, GRASS CLIPPINGS AND BRUSH DEBRIS SHOULD NOT BE DEPOSITED ON GRASS COVERED DRAINAGE STRUCTURES. REGULAR MOWING SHOULD ALSO INCLUDE WEED CONTROL PRACTICES, HOWEVER HERBICIDE USE SHOULD BE KEPT TO A MINIMUM (URBONAS ET AL., 1992). HEALTHY GRASS CAN BE MAINTAINED WITHOUT USIN FERTILIZERS BECAUSE RUNOFF USUALLY CONTAINS SUFFICIENT NUTRIENTS. IRRIGATION OF THE SITE CAN HELP ASSURE A DENSE AND HEALTHY VEGETATIVE COVER.
- GRASS RESEADING AND MULCHING A HEALTHY DENSE GRASS SHOULD BE MAINTAINED. IF AREAS ARE ERODED, THEY SHOULD BE FILLED, COMPACTED, AND RESEEDED SO THAT THE FINAL GRADE IS LEVEL. GRASS DAMAGED DURING THE SEDIMENT REMOVAL PROCESS SHOULD BE PROMPTLY REPLACED USING THE SAME SEED MIX USED DURING ESTABLISHMENT, IF POSSIBLE, FLOW SHOULD BE DIVERTED FROM THE DAMAGED AREAS UNTIL THE GRASS IS FIRMLY ESTABLISHED. BARE SPOTS AND AREAS OF EROSION IDENTIFIED DURING SEMI-ANNUAL INSPECTIONS MUST BE REPLANTED AND RESTORED TO MEET PECIFICATIONS. CORRECTIVE MAINTENANCE, SUCH AS WEEDING OR REPLANTING SHOULD BE DONE MORE REQUENTLY IN THE FIRST TWO TO THREE YEARS AFTER INSTALLATION TO ENSURE STABILIZATION. DENSE VEGETATION MAY REQUIRE IRRIGATION IMMEDIATELY AFTER PLANTING, AND DURING PARTICULARLY DRY
- STORM DRAIN SYSTEMS JUNCTION BOXES, CURB INLETS, STORM MANHOLES, AND OTHER STRUCTURES SHALL BE INSPECTED TWICE YEARLY AND SHALL BE CLEAR OF OBSTRUCTION AND DEBRIS.

PERIODS. PARTICULARLY AS THE VEGETATION IS INITIALLY ESTABLISHED.

## STANDARD ABBREVIATIONS

		OTA NOTAL PROPERTY	_
ASBESTOS CONCRETE AHEAD ASPHALT BACK TO BACK BACK OF CURB BACK BUILDING SETBACK LINE CAST IRON CENTERLINE	HMAC HRS IAW I.D. IP LF LT L	HOT MIX ASPHALTIC CONCRETE HOURS IN ACCORDANCE WITH INSIDE DIAMETER IRON PIN LINEAR FEET LEFT LENGTH LIGHT POLE	- F F F F F
CONCRETE CONTROL PANEL	MH MAX	MANHOLE MAXIMUM	9
CONCRETE STEEL CYLINDER PIPE CORPORATION	MJ MIN	MECHANICAL JOINT MINIMUM	,
CORRUGATED METAL PIPE COUPLING	N NE	NORTH NORTHEAST	9
DRAWING DUCTILE IRON	NW NA	NORTHWEST NOT APPLICABLE	-

POINT OF INTERSECTION

POLYVINYL CHLORIDE PIPE

POUNDS PER SQUARE INCH

POINT OF VERTICAL INTERSECTION

POINT OF TANGENCY

POWER POLE

CONTRACTOR HAS NOT BEEN SELECTED AT THE TIME OF PLAN SUBMITTAL. ONCE THE CONTRACTOR

ONCE THIS HAS BEEN COMPLETED, THE PLAN WILL BE SUBMITTED TO THE CITY OF NEW BRAUNFELS

HAS BEEN SELECTED, THE GEOTECHNICAL ENGINEER AND THE CONTRACTOR WILL COORDINATE TO

PRODUCE A UTILITY TRENCH COMPACTION PLAN SPECIFIC TO THEIR PROCESSES AND EQUIPMENT

CONTRACTOR TO REFERENCE THE UTILITY TRENCH COMPACTION PLAN REF.

ENGINEERING DEPT. AND THIS NOTE WILL BE UPDATED TO REFERENCE THE PLAN.

- NOT TO SCALE ELEV / EL ELEVATION ON CENTER EDGE OF PAVEMENT EX / EXIST EXISTING OVERHEAD ELECTRICAL EACH WAY EACH FACE OVERHEAD TELEPHONE FACE OF CURB OVERHEAD ELECTRICAL/TELEPHONE/CABLE FIRER OPTIC PVMT PAVEMENT FIRE HYDRANT PLUS OR MINUS FI OWI INF POINT OF CURVATURE FOUND PLAIN END
- PROPERTY LINE RAILROAD REINFORCED CONCRETE PIPE RCP REQUIRED RIGHT-OF-WAY ROW RECYCLE WATER LINE SANITARY SEWER SOUTHEAST SOUTHWEST STATION STANDARD STORM SEWER/DRAINAGE

T/G

TEMPORARY BENCHMARK THREADED TYIPICAL UNDERGROUND UNLESS NOTED UNKNOWN VERT VERTICAL VERTICAL POINT OF INFLECTION VERTICAL POINT OF CURVATURE

WELDED WIRE FABRIC

TEST STATION

VERTICAL POINT OF TANGENCY

TOP OF PIPE

TOP OF GROUND

## SHEET

## ISSUES AND REVISIONS 1-13-2022 UPDATED PER CONB COMMENTS

OF



2021 W SH46, STE 105 NEW BRAUNFELS, TX. 78132 PH: 830-358-7127 ink-civil.com

TBPE FIRM F—13351


JAMES INGALLS 107416 PRESTRESSED CONCRETE CYLINDER PIPE

## 2714 N LOOP 1604 E, SUITE 105 SAN ANTONIO, TX 782332 HIGHLAND GARDENS

**BELLA VISTA HOMES** 

## **UNIT 1A**

## GENERAL NOTES



MASTER PLAN APPROVED 6/14/19



BELLA VISTA HOMES 2714 N LOOP 1604 E, SUITE 105 SAN ANTONIO, TX 782332

HIGHLAND GARDENS UNIT 1A

MASTER PLAN

г

2 of 17

DATE ISSUES AND REVISIONS

1-13-2022 UPDATED PER CONB COMMENTS



2021 W SH46, STE 105 NEW BRAUNFELS, TX. 78132 PH: 830-358-7127 ink-civil.com TBPE FIRM F-13351

## HIGHLAND GARDENS SUBDIVISION UNIT 1A

BEING 10.087 ACRE OF LAND OUT OF A 17.389 ACRE TRACT OF LAND SITUATED IN THE JOHN THOMPSON SURVEY NO. 21, ABSTRACT NO. 608, COMAL COUNTY, TEXAS AS DESCRIBED IN DOCUMENT NO. 2017 OF THE OFFICIAL PUBLIC RECORDS OF COMAL COUNTY, TEXAS AND ALSO BEING OUT OF A 38.063 ACRE TRACT OF LAND SITUATED IN THE WILLIAM H. PATE SURVEY NO. 22, ABSTRACT NO. 259 AND RAFAEL XIMENEZ SURVEY, ABSTRACT NO. 347 AS DESCRIBED IN VOLUME 2773, PAGE 98 OF THE OFFICIAL PUBLIC RECORDS OF GUADALUPE COUNTY, TEXAS.

	STATE OF TEXAS COUNTY OF COMAL
a.o.amii	I, THE UNDERSIGNED OWNER OF THE LAND SHOWN ON THIS PLAT, AND DESIGNATED HEREIN AS THE <u>HIGHLAND GARDENS SUBDIVISION</u> , <u>UNIT 1A SUBDIVISION</u> TO THE CITY OF NEW BRAUNFELS, COUNTY OF COMAL, TEXAS, AND WHOSE NAME IS SUBSCRIBED HERETO, DO HEREBY SUBDIVIDE SUCH PROPERTY AND DEDICATE TO THE USE OF THE PUBLIC ALL STREETS, DRAINS, EASEMENTS, AND PUBLIC PLACES THEREON SHOWN FOR THE PURPOSES AND CONSIDERATION THEREIN EXPRESSED.
7707	BELLA VISTA
JUII 14,	C/O TIM PRUSKI 2174 N LOOP 1604, SUITE 105 SAN ANTONIO, TX 78232
מבור	STATE OF TEXAS COUNTY OF COMAL
pilitariyber	THIS INSTRUMENT WAS ACKNOWLEDGED BEFORE ME ON THISDAY OF20,
USEL DIII	BY
r Latiung	NOTARY PUBLIC, STATE OF TEXAS MY COMMISSION EXPIRES:
=	
IIIIO CN	KNOW ALL MEN BY THESE PRESENTS:
GAINDLING	I, THE UNDERSIGNED, DREW A. MAWYER, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF TEXAS, HEREBY CERTIFY THAT THIS PLAT IS TRUE AND CORRECTLY MADE

UNDER MY SUPERVISION AND IN COMPLIANCE WITH CITY AND STATE SURVEY REGULATIONS AND LAWS AND MADE ON THE GROUND AND THAT THE CORNER MONUMENTS WERE



- 1. ALL LOTS WITHIN THE SUBDIVISION WILL BE PROVIDED WATER, SEWER AND ELECTRICAL BY NEW BRAUNFELS UTILITIES (NBU).
- ALL STREETS ARE PROPOSED TO BE OF A LOCAL TYPE FUNCTIONAL CLASSIFICATION WITH 50 FOOT RIGHT-OF-WAYS UNLESS NOTED OTHERWISE.
- 3.1. FOUR (4) FOOT WIDE SIDEWALKS WILL BE CONSTRUCTED AT THE BACK OF CURB BY THE HOME BUILDER PER CITY STANDARDS AT THE TIME OF BUILDING CONSTRUCTION, UNLESS OTHERWISE NOTED ON THE PLAT, ALONG:
- -DAISY MEADOW, MONTROSE, ARALIA LN 3.2. FOUR (4) FOOT WIDE SIDEWALKS WILL BE CONSTRUCTED AT THE BACK OF CURB BY THE DEVELOPER PER CITY STANDARDS AT THE TIME OF SUBDIVISION STREET CONSTRUCTION ALONG: -MONTROSE - LOT 901, BLOCK 1
- -DAISY MEADOW BOTH SIDES OF 120' ROW DEDICATION
- 4. LOT 901 BLOCK 1 IS A DRAINAGE LOT. THIS LOT IS A NON-BUILDABLE LOT. THIS LOT WILL BE OWNED AND MAINTAINED BY THE PROPERTY OWNER'S ASSOCIATION, THEIR SUCCESSOR'S OR ASSIGNS, AND SHALL NOT BE THE RESPONSIBILITY OF THE CITY OF NEW BRAUNFELS OR COMAL COUNTY.
- 5. THE SUBDIVISION IS WITHIN THE COMAL INDEPENDENT SCHOOL DISTRICT.
- 6. ALL BEARINGS AND COORDINATES SHOWN HEREON ARE IN GRID BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, TEXAS SOUTH CENTRAL ZONE (4204), NORTH AMERICAN DATUM 1983. DISTANCES SHOWN HEREON ARE SURFACE USING COMBINED SCALE FACTOR OF 1.00015.
- 7. MONUMENTS WERE FOUND OR SET AT EACH CORNER OF THE SURVEY BOUNDARY OF THE SUBDIVISION. MONUMENTS AND MARKERS WILL BE SET WITH 1/2" IRON PIN WITH PLASTIC CAP STAMPED "DAM #5348 PROP. COR." IMMEDIATELY AFTER COMPLETION OF UTILITY INSTALLATION AND STREET CONSTRUCTION UNLESS NOTED OTHERWISE.
- 8. <u>HIGHLAND GARDENS SUBDIVISION UNIT 1A.</u> DOES FALL WITHIN THE CITY LIMITS OF THE CITY OF NEW BRAUNFELS.
- 9. THE PROPOSED USE OF THE SUBDIVISION IS FOR SINGLE FAMILY RESIDENTIAL.
- 10. <u>HIGHLAND GARDENS SUBDIVISION UNIT 1A</u>, ESTABLISHING A TOTAL OF 35 LOTS, WITH 34 BEING BUILDABLE.
- 11. THIS SUBDIVISION IS SUBJECT TO THE 2006 CITY OF NEW BRAUNFELS PARK LAND DEDICATION AND DEVELOPMENT ORDINANCE. THIS PLAT IS APPROVED FOR 1 DWELLING UNIT PER BUILDABLE LOT WITH A MAXIMUM OF 34 BUILDABLE LOTS. AT SUCH TIME THAT ADDITIONAL DWELLING UNITS ARE CONSTRUCTED; THE OWNER OF THE LOT SHALL CONTACT THE CITY AND COMPLY WITH THE ORDINANCE FOR EACH DWELLING UNIT.
- 12. NO STRUCTURES, WALLS OR OTHER OBSTRUCTIONS OF ANY KIND SHALL BE PLACED WITHIN THE LIMITS OF THE DRAINAGE EASEMENTS SHOWN ON THIS PLAT, NO LANDSCAPING, FENCES, OR OTHER TYPE OF MODIFICATIONS WHICH ALTER THE CROSS SECTIONS OF THE DRAINAGE EASEMENTS OR DECREASES THE HYDRAULIC CAPACITY OF THE EASEMENT, AS APPROVED, SHALL BE ALLOWED WITHOUT THE APPROVAL OF THE CITY ENGINEER. THE CITY OF NEW BRAUNFELS AND GUADALUPE COUNTY SHALL HAVE THE RIGHT OF INGRESS AND EGRESS OVER GRANTORS ADJACENT PROPERTY TO REMOVE ANY OBSTRUCTIONS PLACED WITHIN THE LIMITS OF SAID DRAINAGE EASEMENTS AND TO MAKE ANY MODIFICATIONS OR IMPROVEMENTS WITHIN SAID DRAINAGE
- 13. THE ELEVATION OF THE LOWEST FLOOR SHALL BE AT LEAST 10 INCHES ABOVE THE FINISHED GRADE OF THE SURROUNDING GROUND, WHICH SHALL BE SLOPED IN A FASHION SO AS TO DIRECT STORMWATER AWAY FROM THE STRUCTURE. PROPERTIES ADJACENT TO STORMWATER CONVEYANCE STRUCTURES MUST HAVE A FLOOR SLAB ELEVATION OR BOTTOM OF FLOOR JOISTS A MINIMUM OF ONE FOOT ABOVE THE 100—YEAR WATER FLOW ELEVATION IN THE STRUCTURE. DRIVEWAYS SERVING HOUSES ON THE DOWNHILL SIDE OF THE STREET SHALL HAVE A PROPERLY SIZED CROSS SWALE PREVENTING RUNOFF FROM ENTERING THE GARAGE AND SHALL PREVENT WATER FROM LEAVING THE STREET. FROM LEAVING THE STREET.

- 14. NO STRUCTURES IN THIS SUBDIVISION SHALL BE OCCUPIED UNTIL CONNECTED TO A PUBLIC WATER AND SEWER SYSTEM WHICH HAS BEEN APPROVED BY NEW BRAUNFELS
- 15. MAINTENANCE OF DRAINAGE EASEMENT DESIGNATED WITHIN A LOT SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNERS ASSOCIATION.


16. NO PORTION OF THE SUBDIVISION IS LOCATED WITHIN THE EXISTING SPECIAL FLOOD

- HAZARD ZONE A, 100-YEAR FLOOD BOUNDARY, AS DEFINED BY THE COMAL COUNTY, TEXAS COMMUNITY PANEL NUMBER 48091C0445F, REVISED SEPTEMBER 2, 2009 AS PREPARED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY.
- 17. EACH LOT OWNER SHALL BE RESPONSIBLE FOR VERIFYING THE DEPTH OF THE SEWER SERVICE STUB OUT AND DETERMINING THE MINIMUM SERVICEABLE FINISH FLOOR
- 18. FUTURE DEVELOPMENT IS SUBJECT TO CHAPTER 114 (STREETS, SIDEWALKS, AND OTHER PUBLIC SPACES) OF THE NEW BRAUNFELS CODE OF ORDINANCES. 19. NO PORTION OF THIS PROPERTY IS WITHIN THE EDWARDS AQUIFER RECHARGE ZONE.
- 20. PERMANENT WATER QUALITY CONTROLS ARE REQUIRED FOR THIS SUBDIVISION PLAT IN ACCORDANCE WITH THE CITY OF NEW BRAUNFELS DRAINAGE AND EROSION CONTROL DESIGN MANUAL.
- 21. 5' CONTOURS ARE SOURCED FROM THE CITY OF NEW BRAUNFELS LIDAR GIS DATABASE AND ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, TEXAS SOUTH
- 22. ALL RESIDENTIAL LOTS MEET THE MINIMUM SQUARE FOOTAGE AS DEFINED IN THE HIGHLAND GARDENS PLANNED DEVELOPMENT DISTRICT STANDARDS.

CENTRAL ZONE (4204), NORTH AMERICAN DATUM 1988.

#### NEW BRAUNFELS UTILITIES NOTES:

- MAINTENANCE OF DEDICATED UTILITY EASEMENTS IS THE RESPONSIBILITY OF THE PROPERTY OWNER. ANY USE OF AN EASEMENT, OR ANY PORTION OF IT, INCLUDING LANDSCAPING OR DRAINAGE FEATURES, IS SUBJECT TO AND SHALL NOT CONFLICT WITH THE TERMS AND CONDITIONS IN THE EASEMENT, MUST NOT ENDANGER OR INTERFERE WITH THE RIGHTS GRANTED BY THE EASEMENT TO NEW BRAUNFELS UTILITIES, ITS SUCCESSORS AND ASSIGNS, AND SHALL BE SUBJECT TO APPLICABLE PERMIT REQUIREMENTS OF THE CITY OF NEW BRAUNFELS OR ANY OTHER GOVERNING BODY. THE PROPERTY OWNER MUST OBTAIN, IN ADVANCE, WRITTEN AGREEMENT WITH THE UTILITIES TO UTILIZE THE EASEMENT, OR ANY PART OF IT.
- 2. UTILITIES WILL POSSESS A 5' WIDE SERVICE EASEMENT TO THE BUILDING STRUCTURE ALONG THE SERVICE LINE TO THE SERVICE ENTRANCE. THIS EASEMENT WILL VARY DEPENDING UPON LOCATION OF DWELLING AND SERVICE.
- 3. UTILITIES SHALL HAVE ACCESS TO THE METER LOCATIONS FROM THE FRONT YARD AND METER LOCATIONS SHALL NOT BE LOCATED WITHIN A FENCED AREA.
- 4. EACH LOT MUST HAVE ITS OWN WATER AND SEWER SERVICE AT THE OWNER'S/DEVELOPER'S EXPENSE.
- 5. DO NOT COMBINE ANY NEW UTILITY EASEMENTS (U.E.) WITH DRAINAGE EASEMENTS (D.E.) OR MAKE CHANGES IN GRADE WITHIN THE UTILITY EASEMENTS (U.E.) WITHOUT WRITTEN APPROVAL FROM NEW BRAUNFELS UTILITIES.



**LOCATION MAP** SCALE: 1"=2,000'

APPROVED THIS THE PLANNING COMMISSION OF THE CITY	DAY OF, 2 OF NEW BRAUNFELS, TEXAS.	20 BY THE
CHAIRMAN		
APPROVED FOR ACCEPTANCE		
DATE	PLANNING DIRECTOR	<del>.</del>
DATE	CITY ENGINEER	<del>.</del>
DATE	NEW BRAUNFELS UTILITIES	<del>.</del>

FOR COMAL COUNTY I, \_\_\_\_\_\_, DO HEREBY CERTIFY THAT THE FOREGOING INSTRUMENT WAS FILED FOR RECORD IN THE MAP AND PLAT RECORDS, DOC# \_\_\_\_\_\_OF COMAL COUNTY THE \_\_\_\_\_ DAY OF \_\_\_\_\_\_\_M. WITNESS MY HAND OFFICIAL SEAL, THIS THE \_\_ DAY OF\_\_\_\_\_\_, 20\_\_\_\_ COUNTY CLERK, COMAL COUNTY, TEXAS

DEPUTY

2021 W SH46, STE 105 NEW BRAUNFELS, TX. 78132 PH: 830-358-7127 ink-civil.com

PROPERLY PLACED UNDER MY SUPERVISION.

REGISTERED PROFESSIONAL LAND SURVEYOR NO. 5348

DREW A. MAWYER

FIRM #10191500

D.A. MAWYER LAND SURVEYING

NEW BRAUNFELS, TEXAS 78132

= POINT OF BEGINNING = BUILDING SETBACK LINE = DRAINAGE EASEMENT = UTILITY EASEMENT R.O.W. = RIGHT-OF-WAY = OPEN SPACE LOT = DRAINAGE LOT —— = PAGE MATCH LINE = 1/2" IRON PIN SET = IRON PIN FOUND

PREPARED: January 14, 2022

PAGE 1 OF 2

PRELIMINARY PLAT **APPROVED 6/14/19** 

FINAL PLAT NOT **APPROVED** 



**BELLA VISTA HOMES** 2714 N LOOP 1604 E, SUITE 105 SAN ANTONIO, TX 782332

HIGHLAND GARDENS UNIT 1A

SUBDIVISION PLAT


SHEET

3 of 17

ISSUES AND REVISIONS UPDATED PER CONB COMMENTS 1-13-2022



2021 W SH46, STE 105 NEW BRAUNFELS, TX. 78132 PH: 830-358-7127 ink-civil.com TBPE FIRM F-13351





## BELLA VISTA HOMES 2714 N LOOP 1604 E, SUITE 105

SAN ANTONIO, TX 782332
HIGHLAND GARDENS

SUBDIVISION PLAT II

UNIT 1A

SHEET

4 of 17

NO DATE ISSUES AND REVISIONS


1-13-2022 UPDATED PER CONB COMMENTS



2021 W SH46, STE 105
NEW BRAUNFELS, TX. 78132
PH: 830-358-7127 ink-civil.com
TBPE FIRM F-13351

PRELIMINARY PLAT APPROVED 6/14/19

OPYRIGHT 2021



#### CONSTRUCTION NOTES:

- 1. DIMENSIONS SHOWN ARE TYPICALLY TO EDGE OF PAVEMENT, UNLESS OTHERWISE NOTED. SEE STREET SECTIONS AND CURB DETAILS FOR
- ADDITIONAL DETAIL.
- 3. SEE SHEET 9 FOR STREET SIGNAGE.


2. SEE SHEET 7 FOR STREET SECTIONS AND DETAILS.

4. SEE SHEET 10 FOR SIDEWALK RAMP DETAILS.


- 3. SEE SHEET 9 FOR STREET SIGNAGE.
- 5. SIDEWALKS AND SIDEWALK RAMPS SHOWN SHALL BE CONSTRUCTED WITH
- STREET CONSTRUCTION.

  6. ALL CURB & GUTTER IS CATCH CURB UNLESS OTHERWISE NOTED.
- 7. ALL RAMPS AND ANY SIDEWALKS THAT DO NOT FRONT PROPOSED RESIDENTIAL LOTS ARE REQUIRED TO BE CONSTRUCTED WITH STREET CONSTRUCTION.


Curve Table						
Curve # Radius Length Delta		Tangent	Chord Length	ength Chord Direction		
C1	125.00	30.471	13°58'00"	15.31'	30.40'	N33° 50′ 48.51″W




KNUCKLE SAC AND PAVEMENT TRANSITION DETAIL



## DAISY MEADOW





VERTICAL PAVEMENT TRANSITION (WASHOUT CROWN)

VALLEY GUTTER



## BELLA VISTA HOMES 2714 N LOOP 1604 E, SUITE 105 SAN ANTONIO, TX 782332

HIGHLAND GARDENS UNIT 1A

DAISY MEADOW PLAN & PROFILE

SHEET

6 of 17

NO DATE ISSUES AND REVISIONS

1-13-2022 UPDATED PER CONB COMMENTS




2021 W SH46, STE 105

NEW BRAUNFELS, TX. 78132

PH: 830-358-7127 ink-civil.com


TBPE FIRM F-13351



\*FOC - FACE OF CURB \*BOC- BACK OF CURB

Scale: 1" = 5'

Scale: 1" = 5'



TYPICAL STREET CROSS SECTIONS

Pavement Constituent	Layer Coefficient (α)	
Lime Treated Subgrade	0.08	
New Crushed Limestone Base (TxDOT Item 247 Type A, Grade 1-2)	0.14	
Type D HMAC	0.44	

The recommended hot mixed asphaltic concrete (HMAC) pavement sections are provided in the following tables:

"ONE AND TWO FAMILY RESIDENTIAL" (Required AASHTO 18-KIP ESAL = 58,000)					
Hot Mix Asphaltic Concrete	2"				
Crushed Limestone Base Material (TxDOT Item 247 Type A; Gr. 2)	6"				
TENSAR Geogrid	TX-5				
Lime Treated Subgrade					
Moisture Conditioned Subgrade	6"				
Calculated AASHTO 18-kip ESAL	99,000				

## Moisture Conditioned Subgrade

After all surface organics and deleterious materials have been removed and the desired subgrade elevation has been achieved, the upper 6-inches of exposed subgrade soils should be compacted to a minimum density of 95-percent of the maximum dry unit weight of the subgrade soils as determined by TEX 114E and at or above the optimum moisture content. Any fill required to achieve the final subgrade elevation shall be placed in maximum 8-inch loose lifts and compacted as specified above.

1. RESIDENTIAL LOCAL PAVEMENT SECTION LIMITS


CONTRACTOR TO REFERENCE GEOTECHNICAL ENGINEERING STUDY FOR THE "PROPOSED HIGHLAND GARDENS SUBDIVISION ROADWAYS UNIT 1, 2 AND 3."

ACCORDING TO THE GEOTECHNICAL ENGINEERING STUDY FOR THE "PROPOSED HIGHLAND GARDENS SUBDIVISION ROADWAYS UNIT 1, 2 AND 3" ROCK ENGINEERING AND TESTING LABORATORY PREPARED BY: RETL PROJECT NO.: G218116 FEBRUARY 27, 2018

- THE SUBGRADE SOILS SHALL BE TESTED AT TIME OF CONSTRUCTION TO DETERMINE THE LIME REQUIREMENT TO ACHIEVE A PH VALUE OF 12.4 OR GREATER.
- 3. SUBGRADE SOILS SHOULD BE TESTED FOR SOLUBLE SULFATE CONTENT PRIOR TO


## STREET SECTION NOTES:

- ALL CONCRETE CURBING SHALL BE CONCRETE CURB AND GUTTER, (I.E. CATCH OR SPILL) UNLESS OTHERWISE SPECIFIED ON THE PLANS (I.E. RIBBON CURB)
- 2. CROSS SLOPE VARIES WITHIN VERTICAL TRANSITIONS. THE TYPICAL CROSS SLOPE SHALL BE 1% UNLESS OTHERWISE SPECIFIED ON PLANS.
- 3. BASE MATERIAL SHALL EXTEND 12" BEHIND BACK OF CURB.
- 4. SEE GRADING PLAN FOR LOT GRADING BEYOND RIGHT OF WAY LINE.



NEW PAVEMENT TO EXISTING

NOTE: PAVEMENT SECTION MEETS THE MINIMUM REQUIREMENTS AS PER Scale: NTS CITY OF NEW BRAUNFELS



#### **CURB RAMP NOTES**

- , <u>ALL SLOPES ARE MAXIMUM ALLOWABLE.</u> THE LEAST POSSIBLE SLOPE THAT WILL STILL DRAIN PROPERLY SHOULD BE USED, ADJUST CURB RAMP LENGTH OR GRADE OF APPROACH SIDEWALKS AS DIRECTED. . THESE DETAILS ARE FOR REFERENCE ONLY, ACTUAL LOCATIONS OF CURB RAMPS ARE TO BE SHOWN ON THE
- . THE MINIMUM STANDARD SIDEWALKS SHALL BE PROVIDED IN ACCORDANCE WITH SECTION 118-49 OF THE
- NEW BRAUNFELS CODE OF ORDINANCES.
- . ALL LANDINGS WHERE REQUIRED SHALL BE 5'X 5' (60"X60") MINIMUM WITH A MAXIMUM 2% SLOPE IN ANY
- RAMP LENGTHS SHALL BE SUFFICIENT TO MAINTAIN A MAXIMUM SLOPE OF 8.33% (1V:12H). MAXIMUM ALLOWABLE CROSS SLOPE ON SIDEWALK AND CURB RAMP SURFACES IS 2% (1V:50H).
- SIDEWALK GRADES SHALL NOT EXCEED THE GRADE ESTABLISHED FOR THE ADJACENT ROADWAY, ANY SIDEWALK CONSTRUCTION THAT DEVIATES FROM THE GRADE OF THE NATURAL GRADE OF THE ROADWAY TO IN ACCORDANCE WITH CURRENT ADA AND TAS REQUIREMENTS.
- PROVIDE FLARED RAMP SIDES WITH A MAXIMUM SLOPE OF 10% (1V:10H) MEASURED ALONG THE CURB LINE. CURB RETURNS MAY BE USED IN-LIEU OF SIDE FLARES IN AREAS NOT NORMALLY WALKED ACROSS BY PEDESTRIANS, BECAUSE THE ADJACENT SURFACE IS VEGETATION OR OTHER NON-WALKING SURFACE OR
- WHERE THE SIDE APPROACH IS SUBSTANTIALLY OBSTRUCTED. . MANEUVERING SPACE AT THE BOTTOM OF CURB RAMPS SHALL BE A MINIMUM OF 4'X 4' (48"X48") WHOLLY CONTAINED WITHIN THE CROSSWALK AND WHOLLY OUTSIDE THE PARALLEL VEHICULAR TRAVEL PATH.
- . CROSSWALK DIMENSIONS, CROSSWALK MARKINGS AND STOP BAR LOCATIONS SHALL BE AS SHOWN
- ELSEWHERE IN THE PLANS. AT INTERSECTIONS WHERE CROSSWALK MARKINGS ARE NOT REQUIRED, CURB RAMPS SHALL BE ALIGNED WITH THEORETICAL CROSSWALKS, OR AS DIRECTED BY THE CITY ENGINEER OR
- O. EXISTING FEATURES THAT COMPLY WITH CURRENT TAS REQUIREMENTS MAY REMAIN IN PLACE UNLESS
- . HANDRAILS ARE NOT REQUIRED ON CURB RAMPS, PROVIDE CURB RAMPS WHEREVER AN ACCESSIBLE ROUTE
- 2. SEPARATE CURB RAMP AND LANDINGS FROM ADJACENT SIDEWALK AND ANY OTHER ELEMENTS WITH PRE-MOLD OR BOARD JOINT OF 1/2" UNLESS OTHERWISE DIRECTED BY THE CITY ENGINEER OR BUILDING
- 3. PROVIDE A SMOOTH TRANSITION WHERE THE CURB RAMPS CONNECT TO THE STREET.
- 4. THE CHANGE OF GRADE BETWEEN ADJACENT SURFACES SHALL BE LESS THAN 11%. THE CHANGE OF GRADE SHALL BE DEFINED AS THE ALGEBRAIC DIFFERENCE OF THE ADJACENT SURFACE SLOPES. IN THE CASE OF A STREET ACCESS RAMP DESIGNED AT THE 8.33% MAXIMUM SLOPE, THE ADJACENT PAVEMENT CROSS SLOPE SHALL BE LESS THAN 2.67% (I.E. 8.33-(-2.67)=11). IN ADDITION, THE ADJACENT PAVEMENT CROSS SLOPE SHALL BE LESS THAN OR EQUAL TO 5%.
- 5. IF THE CHANGE OF GRADE BETWEEN ADJACENT SURFACES IS GREATER THAN OR EQUAL TO 11%. A LEYELING STRIP, 2 FEET IN LENGTH, SHALL BE PROVIDED TO TRANSITION THE ADJACENT SURFACES.
- 6. ADA RAMP SHALL BE CONSTRUCTED WITH 5" CLASS "A" CONCRETE WITH 2" MINIMUM GRAVEL, CRUSHED ROCK OR FLEXIBLE BASE MATERIAL. REINFORCING STEEL SHALL BE #3 BARS AT 18" O.C.E.W. OR 6"x6" -
- 17. THE EXTENTS OF ADA COMPLIANCE IN ALTERATIONS SHALL BE WITHIN THE LIMITS, BOUNDARIES OR SCOPE OF A PLANNED PROJECT AND AS DETERMINED BY THE CITY BUILDING OFFICIAL.

W2.9 X W2.9 WIRE MESH.

## DETECTABLE WARNING NOTES

- . CURB RAMPS OR LANDINGS ABUTTING THE CROSSWALK MUST HAVE A DETECTABLE WARNING SURFACE THAT CONSISTS OF RAISED TRUNCATED DOMES COMPLYING WITH SECTION 705 OF THE TEXAS ACCESSIBILITY STANDARDS (TAS), THE SURFACE MUST CONTRAST VISUALLY WITH ADJOINING SURFACES, INCLUDING SIDE FLARES. FURNISH DARK BROWN OR DARK RED DETECTABLE WARNING SURFACE ADJACENT TO UNCOLORED CONCRETE, UNLESS SPECIFIED ELSEWHERE IN THE PLANS.
- 2. DETECTABLE WARNING SURFACES MUST BE SLIP RESISTANT AND NOT ALLOW WATER TO ACCUMULATE.
- 3. ALIGN TRUNCATED DOMES IN THE DIRECTION OF PEDESTRIAN TRAVEL WHEN ENTERING THE STREET. 4. DETECTABLE WARNING SURFACES SHALL BE A MINIMUM OF 24" IN DEPTH IN THE DIRECTION OF PEDESTRIAN
- TRAVEL, AND EXTEND THE FULL WIDTH OF THE CURB RAMP OR LANDING WHERE THE PEDESTRIAN ACCESS 5. DETECTABLE WARNING SURFACES SHALL BE LOCATED SO THAT THE EDGE NEAREST THE CURB LINE IS AT THE BACK OF CURB. ALIGN THE ROWS OF DOMES TO BE PERPENDICULAR TO THE GRADE BREAK BETWEEN
- THE RAMP RUN AND THE STREET. DETECTABLE WARNING SURFACES MAY BE CURVED ALONG THE CORNER 5. DETECTABLE WARNING MATERIALS MUST MEET TXDOT DEPARTMENTAL MATERIALS SPECIFICATION DMS 4350
- AND BE LISTED ON THE MATERIAL PRODUCER LIST. INSTALL PRODUCTS IN ACCORDANCE WITH
- . DETECTABLE WARNING PAVERS SHALL NOT BE PERMITTED WITHOUT THE APPROVAL BY THE PUBLIC WORKS



**BELLA VISTA HOMES** 2714 N LOOP 1604 E, SUITE 105 SAN ANTONIO, TX 782332

HIGHLAND GARDENS UNIT 1A

STREET SECTIONS AND DETAILS I


SHEET


OF


ISSUES AND REVISIONS 1-13-2022 UPDATED PER CONB COMMENTS





2021 W SH46, STE 105 NEW BRAUNFELS, TX. 78132 PH: 830-358-7127 ink-civil.com TBPE FIRM F-13351
















BELLA VISTA HOMES
2714 N LOOP 1604 E, SUITE 105
SAN ANTONIO, TX 782332

HIGHLAND GARDENS UNIT 1A

STREET SECTIONS AND DETAILS II

SHEET


8 of 17


NO DATE ISSUES AND REVISIONS


1-13-2022 UPDATED PER CONB COMMENTS




2021 W SH46, STE 105 NEW BRAUNFELS, TX. 78132 PH: 830-358-7127 ink-civil.com TBPE FIRM F-13351









- 2. When two sets of street name signs are required (e.g. at "T" intersections), one double-sided street name sign shall be mounted on sign post. The sign assembly shall meet minimum height requirements as required in the Texas Manual on Uniform Traffic Control Devices (TMUTCD). When required, DEAD END (W14-1a) or NO OUTLET (W14-2a) signs shall also be mounted on the sign post.
- 3. Street name signs greater than 36" long and center mounted on top of sign post shall be mounted on post top bracket with 12" slot. All other street name signs center mounted on top of sign post shall be mounted on post top bracket with 5 ½" slot.
- 4. Street name signs mounted on sign post shall be mounted with double-sided round pole brackets. Two holes should be punched in the center of the 9" street name sign blank 1" from edge of the blank with 7"spacing between holes.
- 5. The lettering for names of streets shall be composed of a combination of lower-case letters with initial upper-case letters. Acceptable abbreviations per TMUTCD may be used except for the street name itself.
- 6. Red background (red film over High Intensity Prismatic) should be used for private street name signs.

  Street Sign Detail Ground Mount

  ISSUE DATE: February 2013 DWG. NO: ST-024 SCALE: N.T.S.

  DRAWN BY: RAS CONTACT: GF SHEET: 1 OF 1

  ENGINEERING DIVISION
  424 S. CASTELL AVE.
  NEW BRAUNFELS. TR330 O 221 4020
  FAX: 830 0221 4020
  FAX: 830 026 3600

ERING-AUTOCAD\DETAILS\NB-PUBLIC WORKS DETAILS\NB-UNAPPROVED DETAILS-2013\ST-2013.024 STREET SIGN DETAIL - GROUND MOUNT.D\WG

#### SIGN REQUIREMENTS

TRAFFIC SIGNS SHALL BE USED IN ACCORDANCE WITH THE LATEST REVISION OF THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) AND WHERE JUSTIFIED BY ENGINEERING JUDGMENT OR STUDY. TRAFFIC SIGNS INCLUDE REGULATOR SIGNS, WARNING SIGNS, STREET NAME SIGNS AND OBJECT MARKERS.

2. ALL SIGNS SHALL BE SHOWN IN THE ENGINEERING PLANS FOR REVIEW AND APPROVAL AS PART OF THE PLAN AND PROFILE SHEET OR SEPARATE SIGNING AND PAVEMENT MARKING LAYOUT SHEET. THE ENGINEERING PLANS SHALL INCLUDE SIGN LOCATION, NAME, DESIGNATION AND SIZE. SIGN STANDARDS SHALL BE INCLUDED IN THE ENGINEERING PLANS.

## INSTALLATION

THE CONTRACTOR SHALL FURNISH AND INSTALL ALL
 REGULATORY, WARNING AND STREET NAME SIGNS AND SIGN
 MOUNTS IN ACCORDANCE WITH APPROVED ENGINEERING PLANS.

## MOUNTING

THE WEDGE ANCHOR STEEL SYSTEM AND THIN-WALLED TUBING POST SHALL BE USED FOR SIGNS WITH UP TO 10 SQUARE FEET OF SIGN AREA. MATERIALS AND INSTALLATION SHOULD FOLLOW THE TEXAS DEPARTMENT OF TRANSPORTATION (TXDOT) TRAFFIC STANDARDS SMD(GEN)-08 AND SMD(TWT)-08.


- 2. THE TRIANGULAR SLIP BASE SYSTEM AND 10 BWG TUBING POST SHALL BE USED FOR SIGNS THAT HAVE 10 TO 16 SQUARE FEET OF SIGN AREA. MATERIALS AND INSTALLATION SHOULD FOLLOW THE TXDOT TRAFFIC STANDARDS SMD(GEN)-08 AND SMD(SLIP-1-3)-08.
- OBJECT MARKERS MATERIALS AND INSTALLATION SHOULD FOLLOW THE TXDOT TRAFFIC STANDARDS D&OM(1-5)-10.

## MATERIALS

- SIGN MATERIALS INCLUDING ALUMINUM SING BLANKS AND SIGN FACE MATERIALS SHOULD FOLLOW THE TXDOT TRAFFIC STANDARDS TSR(1-5)-08 AND DEPARTMENTAL MATERIAL SPECIFICATIONS DMS-7110 AND DMS-8300.
- 2. THE CITY OF NEW BRAUNFELS WILL INSPECT ALL SIGNS AT FINAL INSPECTION.

## PAVEMENT MARKING REQUIREMENTS

- PAVEMENT MARKINGS SHALL BE USED IN ACCORDANCE WITH THE LATEST REVISION OF THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) AND WHERE JUSTIFIED BY ENGINEERING JUDGMENT OR STUDY.
- 2. ALL PAVEMENT MARKINGS SHALL BE SHOWN IN THE ENGINEERING PLANS FOR REVIEW AND APPROVAL AS PART OF THE PLAN AND PROFILE SHEET OR SEPARATE SIGNING AND PAVEMENT MARKING LAYOUT SHEET. DESIGN, MATERIALS AND INSTALLATION SHOULD FOLLOW TXDOT TRAFFIC STANDARDS PM(1-4)-12. CITY OF SAN ANTONIO TRAFFIC ENGINEERING STANDARDS FOR PAVEMENT MARKINGS DESIGNATING TRAFFIC LANES, LANE USAGE AND LANE REGULATIONS AND PEDESTRIAN/BICYCLIST ACCOMMODATIONS MAY BE USED FOR ADDITIONAL STANDARD DESIGN DETAILS. MARKING STANDARDS SHALL BE INCLUDED IN THE ENGINEERING PLANS.
- 3. ALL PAVEMENT MARKINGS SHALL BE TYPE I HOT APPLIED THERMOPLASTIC AND MEET TXDOT DEPARTMENTAL MATERIAL SPECIFICATIONS DMS-8200.
- 4. THE CONTRACTOR SHALL NOTIFY THE CITY OF NEW BRAUNFELS AT LEAST TWENTY-FOUR (24) HOURS PRIOR TO THE INSTALLATION OF ALL SEALER AND FINAL MARKINGS. THE CONTRACTOR MAY BE RESPONSIBLE FOR PLACING SPOT TABS BEFORE MARKING APPLICATION. THE CITY WILL INSPECT ALL MARKINGS AT FINAL APPLICATION.





## BELLA VISTA HOMES 2714 N LOOP 1604 E, SUITE 105 SAN ANTONIO, TX 782332

HIGHLAND GARDENS UNIT 1A

TRAFFIC SIGNAGE AND SIDEWALK DETAILS

SHEET

of 17

NO DATE ISSUES AND REVISIONS

1-13-2022 UPDATED PER CONB COMMENTS




2021 W SH46, STE 105


NEW BRAUNFELS, TX. 78132

PH: 830-358-7127 ink-civil.com

TBPE FIRM F-13351


COPYRIGHT 2021





•	Highland Gardens Unit 1A - Proposed Rational Conditions Hydrology Calculations								
	Point	Area (ac)	С	T <sub>c</sub> (min)	Q <sub>2</sub> (cfs)	Q <sub>10</sub> (cfs)	Q <sub>25</sub> (cfs)	Q <sub>100</sub> (cfs)	Location
	A1	7.74	0.75	30.56	16.95	21.23	27.40	40.22	Montrose Curb Inlet & Storm Drain Line A
	A3.1	1.22	0.75	20.21	2.42	4.17	5.36	7.87	Aralia Ln Street Capacity
	DA-23	8.80	0.46	21	14.18	21.74	28.85	42.95	Highland Grove Unit 8

\*NOTE: THE RATIONAL ANALYSIS FOR DRAINAGE AREA 11 & 12 IS PART OF THE HIGHLAND GARDENS UNIT 4A MASTER DRAINAGE PLAN AND REPORT. THE RATIONAL ANALYSIS FOR DRAINAGE AREAS A1 IS PART OF THE HIGHLAND GARDENS UNIT 2 DRAINAGE REPORT.



LIMITS OF DRAINAGE AREA

LIMITS OF SUB-DRAINAGE AREA

TC TC TIME OF CONCENTRATION

EXISTING CONTOURS

- PROPOSED CONTOURS

FLOW ARROWS

A

DRAINAGE BASIN LABEL

BASIN AREA (AC)

SUB-DRAINAGE AREA LABEL
SUB-DRAINAGE AREA (AC)

INLET LABEL

ANALYSIS POINT LABEL



## BELLA VISTA HOMES 2714 N LOOP 1604 E, SUITE 105 SAN ANTONIO, TX 782332

## HIGHLAND GARDENS UNIT 1A

DRAINAGE AREA MAP -RATIONAL PROPOSED

SHEET

13 of 17


DATE ISSUES AND REVISIONS

1-13-2022 UPDATED PER CONB COMMENTS



2021 W SH46, STE 105
NEW BRAUNFELS, TX. 78132
PH: 830-358-7127 ink-civil.com
TBPE FIRM F-13351

COPYRIGHT 2021



#### GENERAL SPECIFICATIONS FOR SITE PREPARATION

GENERAL DESCRIPTION
THIS ITEM SHALL CONSIST OF ALL CLEARING AND PREPARATION OF LAND TOO BE FILLED, FILLING OF THE LAND, SPREADING, COMPACTION TESTING AND INSPECTION OF THE FILL, AND ALL SUBSIDIARY WORK NECESSARY TO COMPLETE THE GRADING OF THE CUT AND FILL AREAS TO CONFORM WITH THE LINES, GRADES AND SLOPES AS SHOWN ON THE APPROVED PLANS.

SCARIFYING THE AREA TO BE FILLED
ALL ORGANIC MATTER SHALL BE REMOVED FROM THE SURFACE UPON WHICH THE FILL MATERIAL
IS TO BE PLACED, AND SURFACE SHALL BE DISKED OR SCARIFIED TO A MINIMUM DEPTH OF SIX INCHES
(6"), ALL SURFACE RUTS OR OTHER UNEVEN FEATURES WILL BE LEVELED PRIOR TO FIELD DENSITY

COMPACTING THE AREA TO BE FILLED FOLLOWING THE CLEARING AND DISKING OR SCARIFYING OF THE FILL AREA, IT SHALL BE BLADED UNTIL IT IS UNIFORM AND FREE FROM LARGE CLODS. THE AREA SHALL BE BROUGHT TO ADEQUATE MOISTURE CONTENT AND COMPACTED (TYPICALLY) TO NOT LESS THAN NINETY PERCENT (90%) OF MAXIMUM DENSITY IN ACCORDANCE WITH THE CURRENT ASTM D 1557 COMPACTION PROCEDURE, OR 95% OF MAXIMUM DENSITY IN ACCORDANCE WITH THE THD—TEX—113—E COMPACTION PROCEDURE. ALL AREAS EXCEEDING (6") SIX INCHES IN DEPTH, MUST MEET WITH FHA/HUD HANDBOOK 4140.30 SPECIFICATIONS FOR LAND DEVELOPMENTS ON CONTROLLED EARTHWORK, DATASHEET 79G.

FILL MATERIALS
THE MATERIALS USED SHALL BE FREE FROM ORGANIC MATTER AND OTHER DELETERIOUS SUBSTANCES, SUCH AS TREES, BRUSH AND RUBBISH.

DEPTH AND MIXING OF FILL LAYERS
THE SELECTED FILL MATERIAL SHALL BE PLACED IN LEVEL, UNIFORM LAYERS WHICH, WHEN COMPACTED, SHALL HAVE A DENSITY CONFORMING TO THE STIPULATED ABOVE.
EACH LAYER SHALL BE THOROUGHLY MIXED DURING THE SPREADING TO ENSURE UNIFORMITY OF MATERIAL IN EACH LAYER. COMPACTED LAYER THICKNESS MAY VARY DEPENDING ON THE COMPACTION EQUIPMENT OF THE DEMONSTRATED CAPABILITY.

ROCK
WHEN FILL MATERIAL INCLUDES ROCK, THE MAXIMUM ROCK SIZE SHALL BE AS APPROVED BY THE
GEOTECHNICAL ENGINEER. NO LARGE ROCKS SHALL BE ALLOWED TO NEST AND ALL VOIDS MUST BE
FILLED WITH SMALL STONES OR SOIL AND ADEQUATELY COMPACTED.

COMPACTION OF FILL LAYER
COMPACTION EQUIPMENT SHALL BE CAPABLE OF COMPACTING THE FILL TO THE SPECIFIED DENSITY.
COMPACTION SHALL BE ACCOMPLISHED WHILE THE FILL MATERIAL IS AT OR NEAR THE APPROPRIATE
MOISTURE CONTENT. COMPACTION OF EACH LAYER SHALL BE CONTINUOUS OVER THE ENTIRE STRUCTURAL
AREA (BENEATH PROPOSED STRUCTURES).

COMPACTION OF SLOPES
THE FACES OF FILL SLOPES SHALL BE COMPACTED. COMPACTING OPERATIONS SHALL BE CONTINUED UNTIL THE SLOPE FACES ARE STABLE BUT NOT TOO DENSE FOR PLANTING ON THE SLOPES. COMPACTION OF THE SLOPE FACE MAY BE DONE PROGRESSIVELY IN INCREMENTS OF THREE TO FIVE FEET (3' TO 5') IN FILL HEIGHT AS THIS FILL PROGRESSES OR AFTER THE FILL HAS BEEN BROUGHT TO ITS TOTAL HEIGHT.

DENSITY TEST
FIELD DENSITY TESTS SHALL BE PERFORMED ON ALL LAYERS OF FILL WHEN THE FILL IS BEING PLACED AS DIRECTED BY THE GEOTECHNICAL ENGINEER. THE MAXIMUM FILL HEIGHT BETWEEN DENSITY TESTING SHALL BE TWELVE INCHES (12"). ALL TESTING SHALL BE REQUESTED BY THE CONTRACTOR TO MEET THE CONTRACTOR'S CONSTRUCTION SCHEDULE. NOTIFICATION BY THE CONTRACTOR TO CONDUCT TESTS SHALL BE AT LEAST THE DAY BEFORE. THIS NOTIFICATION SHALL INCLUDE THE FILL AREA LOCATION (LOT AND BLOCK), THE LIFT OR HEIGHT OF FILL AND APPROXIMATE DESIRED TIME OF TESTING. WHEN THESE TESTS INDICATE THAT THE DENSITY OF ANY LAYER OF FILL OR PORTION THEREOF IS BELOW THE REQUIRED DENSITY, THE PARTICULAR LAYER OR PORTION SHALL BE REWORKED AND RETESTED AT THE EXPENSE OF THE CONTRACTOR UNLESS THE CONTRACTOR CAN SHOW EVIDENCE THAT CIRCUMSTANCES BEYOND HIS CONTROL REQUIRED THE RETESTING. GENERALLY, THE SPECIFIC TESTING WILL BE AS FOLLOWS AND CONDUCTED BY A GEOTECHNICAL ENGINEER OR STAFF.

- 1. THE LAND TO BE FILLED (PREPARED SUBGRADE) SHALL BE PREPARED AND TESTED AT A FREQUENCY AS DETERMINED BY THE GEOTECHNICAL ENGINEER.
- 2.THE FIRST LIFT OF COMPACTED FILL (GENERALLY 8-12 IN.) SHALL BE TESTED AS DETERMINED BY THE GEOTECHNICAL ENGINEER. ANY AREAS SUPPORTING THE PROPOSED STRUCTURES REQUIRING FILL SHALL BE TESTED FOR DENSITY COMPLIANCE.
- 3. FILL AREAS SHALL BE TESTED AT A MAXIMUM OF EACH TWELVE INCHES (12") OF FILL.
- 4.TEST RESULTS WILL BE PROVIDED BY THE FIELD TECHNICIAN TO THE CONTRACTOR WHEN POSSIBLE: HOWEVER, ALL TEST RESULTS ARE TO BE REVIEWED BY THE GEOTECHNICAL ENGINEER FOR COMPLIANCE. THE ENGINEER WILL NOTIFY THE CONTRACTOR OF ALL TEST RESULTS.

  CUT/FILL LOTS

AREAS INVOLVING CUT ON THE PORTION AND FILL ON ANOTHER PORTION OF A SPECIFIC LOT SHALL BE PREPARED TO A MINIMUM DEPTH OF 6 IN., AND WILL BE THE SAME MATERIAL CLASSIFICATION AT THE SAME COMPACTION AND MOISTURE CONTENT. FIELD DENSITY TESTS SHALL BE REQUIRED ON EACH CUT/FILL LOT FOR THE PURPOSE OF DETERMINING UNIFORMITY OF THE AREA SUPPORTING THE PROPOSED STRUCTURES.

HUD 79-G
HUD 79-G REQUIREMENT FOR FILL MATERIAL OF 6 INCHES AND MORE WILL BE CONDUCTED. ALL CUT AREAS WILL ALSO MEET THE REQUIREMENTS FOR HUD 79-G COMPACTION TESTING. IN ADDITION, CONTRACTOR MUST RETAIN A GEOTECHNICAL ENGINEER TO PROVIDE VERIFICATION OF ALL AREAS WHICH DO NOT REQUIRE HUD 79-G. AFTER SITE GRADING IS COMPLETED, CONTRACTOR TO RETAIN GEOTECHNICAL ENGINEER TO PROVIDE THE OWNER A 79-G LETTER.

## GRADING NOTES:

- 1. STRIPPING OF VEGETATION FROM PROJECT SITES SHALL BE PHASED SO AS TO EXPOSE THE MINIMUM AMOUNT OF AREA TO SOIL EROSION FOR THE SHORTEST POSSIBLE PERIOD OF TIME PER THE NEW BRAUNFELS DRAINAGE AND EROSION CONTROL DESIGN MANUAL
- 2. GRADING SHOWN ON THIS GRADING PLAN IS FOR MASS GRADING PURPOSES ONLY. FINAL GRADING AROUND HOMES, SETTING FINISHED FLOOR ELEVATIONS, ETC. WILL BE DONE AS PART OF EACH BUILDING PERMIT PROCESSED FOR THE INDIVIDUAL HOMES.
- 3. IN ALL FILL AREAS, LOOSE OR ORGANIC MATTER SHALL BE STRIPPED AND REMOVED FROM THE SITE UPON WHICH THE FILL IS TO BE PLACED AND THE AREA SHALL BE BROUGHT TO THE PROPER GRADE GRADE WITH ADEQUATE MOISTURE CONTENT AND COMPACTED TO NOT LESS THAN 90% DENSITY.
- 4. CONTRACTOR TO INSURE THAT ALL LOTS FILLED WILL HAVE POSITIVE DRAINAGE TO PREVENT ANY PONDING OF WATER AND PROVIDE A MINIMUM FINAL GRADE OF 1.2% WITHIN THE LOT.
  5. CONTRACTOR TO CONTACT OWNER PRIOR TO ANY LOT FILLING TO DETERMINE IF TREES WITHIN
- 6. ALL LARGE ROCKS 10" OR LARGER SHALL BE KEPT OUT OF THE FILL SITE UNLESS INSTRUCTED BY THE OWNER TO PLACE SUCH ROCKS ON THE SITE.
- 7. CONTRACTOR TO ENSURE POSITIVE DRAINAGE FOR ALL GRADING WITHIN LIMITS OF PROJECT.
- 8. FINISHED FLOOR ELEVATION FOR HOMES WILL BE A MINIMUM OF 12" ABOVE THE TOP OF CURB FRONTING THE LOT, AND ON C LOTS' DRIVEWAY SWALE FLOWLINE WILL BE A MINIMUM OF 6" BELOW THE FINISHED FLOOR OF THE HOUSE.

CONTRACTOR SHALL NOTIFY THE FOLLOWING UTILITY COMPANIES 48 HOURS PRIOR TO EXCAVATION:

New Braunfels Utilities
Spectrum Cable
Centerpoint Gas
Robert Sanders
Damaged Line
AT&T Telephone
Erick White PM

THE FILL AREA CAN BE SAVED.

830-629-8400 830-625-3408 830-643-6434 830-643-6903 888-876-5786 830-303-1333 210-283-1706 210-658-4886

830-545-6005

Erick White PM
Scott McBrearty (Construction)
Texas One Call

C.P.E. LOCATOR

CALL CENTER POINT ENERGY LOCATOR AT 1-800-545-6005, 48HRS BEFORE BEGINNING ANY EXCAVATION. DUE TO FEDERAL REGULATIONS TITLE 49, PART 192.181, CENTER POINT ENERGY MUST MAINTAIN ACCESS TO GAS VALVES AT ALL TIMES. THE CONTRACTOR MUST PROTECT AND WORK AROUND ANY GAS VALVES THAT ARE IN THE PROJECT AREA.

## TELEPHONE LOCATOR


THE EXISTENCE AND LOCATION OF UNDERGROUND CABLE INDICATED ON THE PLANS ARE TAKEN FROM THE BEST RECORDS AVAILABLE AND ARE NOT GUARANTEED TO BE ACCURATE. CONTRACTOR TO CONTACT THE TELEPHONE COMPANY CABLE LOCATOR 48HRS PRIOR TO EXCAVATION AT 1-800-545-6005,, CONTRACTOR HAS THE RESPONSIBILITY TO PROTECT AND SUPPORT TELEPHONE COMPANY DURING CONSTRUCTION.


## TRENCH EXCAVATION SAFETY PROTECTION


CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTORS IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.


THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY


DISCREPANCIES 24-HOURS PRIOR TO COMMENCING CONSTRUCTION.
















# BELLA VISTA HOMES 2714 N LOOP 1604 E, SUITE 105 SAN ANTONIO, TX 782332

## HIGHLAND GARDENS UNIT 1A

## GRADING PLAN

SHEET

of **17** 

NO DATE ISSUES AND REVISIONS

1-13-2022 UPDATED PER CONB COMMENTS



2021 W SH46, STE 105 NEW BRAUNFELS, TX. 78132 PH: 830-358-7127 ink-civil.com TBPE FIRM F-13351

#### CONSTRUCTION NOTES:

- 1. WHERE WATER LINES AND NEW SEWER LINES ARE INSTALLED WITH A SEPARATION DISTANCE CLOSER THAN NINE FEET (I.E., WATER LINES CROSSING WASTEWATER LINES, WATER LINES PARALLELING WASTEWATER LINES, OR WATER LINES NEXT TO MANHOLES) THE INSTALLATION MUST MEET THE REQUIREMENTS OF 30 TAC §217.53(D) (PIPE DESIGN) AND 30 TAC §290.44(E) (WATER DISTRIBUTION).
- 2. WHERE A 9' (NINE FOOT) SEPARATION FROM WATER AND SEWER LINES CROSSING CANNOT BE MAINTAINED, THE NEW WATER LINE SHALL BE ABOVE THE SEWER LINE AS SHOWN ON THE WATER/SEWER LINE CROSSING DETAIL. AT NO TIME SHALL A WATER LINE OR WATER SERVICE BE PLACED UNDER A SEWER LINE OR SEWER SERVICE.
- 3. WHERE A NEW POTABLE WATERLINE CROSSES AN EXISTING, PRESSURE RATED WASTEWATER MAIN OR LATERAL, ONE SEGMENT OF THE WATERLINE PIPE SHALL BE CENTERED OVER THE WASTEWATER MAIN OR LATERAL SUCH THAT THE JOINTS OF THE WATERLINE PIPE ARE EQUIDISTANT AND AT LEAST NINE FEET HORIZONTALLY FROM THE CENTERLINE OF THE WASTEWATER MAIN OR LATERAL. THE POTABLE WATERLINE SHALL BE AT LEAST SIX INCHES ABOVE THE WASTEWATER MAIN OR LATERAL. WHENEVER POSSIBLE, THE CROSSING SHALL BE CENTERED BETWEEN THE JOINTS OF THE WASTEWATER MAIN OR LATERAL. IF THE EXISTING WASTEWATER MAIN OR LATERAL SHOWS SIGNS OF LEAKING, IT SHALL BE REPLACED FOR AT LEAST NINE FEET IN BOTH DIRECTIONS (18 FEET TOTAL) WITH AT LEAST 150 PSI PRESSURE RATED PIPE.
- 4. ALL PRIVATE SERVICE LATERALS MUST BE INSPECTED AND CERTIFIED IN ACCORDANCE WITH 30 TAC \\$213.5(C)(3)(I). AFTER INSTALLATION OF AND, PRIOR TO COVERING AND CONNECTING A PRIVATE SERVICE LATERAL TO AN EXISTING ORGANIZED SEWAGE COLLECTION SYSTEM, A TEXAS LICENSED PROFESSIONAL ENGINEER, TEXAS REGISTERED SANITARIAN, OR APPROPRIATE CITY INSPECTOR MUST VISUALLY INSPECT THE PRIVATE SERVICE LATERAL AND THE CONNECTION TO THE SEWAGE COLLECTION SYSTEM, AND CERTIFY THAT IT IS CONSTRUCTED IN CONFORMITY WITH THE APPLICABLE PROVISIONS OF THIS SECTION. THE OWNER OF THE COLLECTION SYSTEM MUST MAINTAIN SUCH CERTIFICATIONS FOR FIVE YEARS AND FORWARD COPIES TO THE APPROPRIATE REGIONAL OFFICE UPON REQUEST. CONNECTIONS MAY ONLY BE MADE TO AN APPROVED SEWAGE COLLECTION SYSTEM.
- 5. FIRE HYDRANTS SHALL NOT BE INSTALLED WITHIN NINE FEET VERTICALLY OR HORIZONTALLY OF ANY WASTEWATER MAIN, WASTEWATER LATERAL, OR WASTEWATER SERVICE LINE REGARDLESS OF CONSTRUCTION
- 6. METER BOXES MUST BE SET AT PROPOSED FINISHED GRADE. ANY METER BOXES THAT ARE NOT SET AT THE FINAL GRADE WILL BE ADJUSTED BY THE CONTRACTOR AT NO ADDITIONAL COSTS
- 7. CONTRACTOR TO COORDINATE WITH NBU IF EXISTING WATER MAINS WILL BE REMOVED FROM SERVICE AT ANY TIME.
- 8. ALL UTILITIES SHALL BE CONSTRUCTED PRIOR TO STREETS.
- 9. ENSURE ALL DRIVEWAY APPROACHES ARE BUILT IN GENERAL ACCORDANCE WITH A.D.A. SPECIFICATIONS.
- 10. NO VALVES, FIRE HYDRANTS, ETC. SHALL BE CONSTRUCTED WITHIN CURBS, SIDEWALKS OR
- 11. ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO—TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX—113—E, TEX—114—E, TEX—115—E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO— TECHNICAL ENGINEER AND APPROVED BY THE CITY OF NEW BRAUNFELS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO—TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF NEW BRAUNFELS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.
- 12. THIS PROJECT INCLUDES UTILITY INSTALLATIONS GREATER THAN 5-FEET IN DEPTH LOCATED IN PUBLIC RIGHT-OF-WAY OR EASEMENTS. DEEP TRENCHES POSE COMPACTION TESTING AND CONSTRUCTION CHALLENGES AND CITY METHODS FOR TESTING AND COMPACTION MAY NOT BE ACHIEVABLE. A UTILITY COMPACTION PLAN WILL BE REQUIRED AND MUST BE SUBMITTED FOR APPROVAL TO CITY PRIOR TO UTILITY INSTALLATION.

CONTRACTOR SHALL NOTIFY THE FOLLOWING UTILITY COMPANIES 48 HOURS PRIOR TO EXCAVATION:

830-629-8400 830-625-3408 830-643-6434

830-643-6903

888-876-5786

830-303-1333

210-283-1706

210-658-4886

830-545-6005

New Braunfels Utilities
Spectrum Cable
Centerpoint Gas
Robert Sanders
Damaged Line
AT&T Telephone
Erick White PM
Scott McBrearty (Construction)

Texas One Call

P.E. LOCATOR

CALL CENTER POINT ENERGY LOCATOR AT 1-800-545-6005, 48HRS BEFORE BEGINNING ANY EXCAVATION. DUE TO FEDERAL REGULATIONS TITLE 49, PART 192.181, CENTER POINT ENERGY MUST MAINTAIN ACCESS TO GAS VALVES AT ALL TIMES. THE CONTRACTOR MUST PROTECT AND WORK AROUND ANY GAS VALVES THAT ARE IN THE PROJECT AREA.


ELEPHONE LOCATOR


THE EXISTENCE AND LOCATION OF UNDERGROUND CABLE INDICATED ON THE PLANS ARE TAKEN FROM THE BEST RECORDS AVAILABLE AND ARE NOT GUARANTEED TO BE ACCURATE. CONTRACTOR TO CONTACT THE TELEPHONE COMPANY CABLE LOCATOR 48HRS PRIOR TO EXCAVATION AT 1-800-545-6005,, CONTRACTOR HAS THE RESPONSIBILITY TO PROTECT AND SUPPORT TELEPHONE COMPANY DURING CONSTRUCTION.


TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTORS IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.


THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24—HOURS PRIOR TO COMMENCING CONSTRUCTION.







## **LEGEND**





## BELLA VISTA HOMES 2714 N LOOP 1604 E, SUITE 105 SAN ANTONIO, TX 782332

## HIGHLAND GARDENS UNIT 1A

OVERALL UTILITY PLAN

SHEET

OF 17

O DATE ISSUES AND REVISIONS

1-13-2022 UPDATED PER CONB COMMENTS



2021 W SH46, STE 105
NEW BRAUNFELS, TX. 78132
PH: 830-358-7127 ink-civil.com
TBPE FIRM F-13351

COPYRIGHT 2021

#### **SEQUENCE OF CONSTRUCTION:**

- OBTAIN CITY APPROVED SITE PREPARATION PLANS, AND TPDES PERMIT (NOT A COPY OF THE TPDES APPLICATION TO TCEQ), IF APPLICABLE.
- 2. INSTALL TEMPORARY EROSION AND SEDIMENTATION CONTROLS.
- 3. BEGIN DEMOLITION ACTIVITIES, IF APPLICABLE.
- 4. BEGIN SITE CLEARING AND GRADING.
- 5. RESTORE AND REVEGETATE ALL DISTURBED AREAS NOT UNDER IMPERMEABLE IMPROVEMENTS
- 6. COMPLETE ANY REMAINING "PUNCH LIST" ITEMS.
- 7. CONTRACTOR SHALL REMOVE TEMPORARY EROSION CONTROLS AFTER PERMANENT STABILIZATION IS AT LEAST 70% EVENLY ESTABLISHED. RYE IS NOT ACCEPTED.

#### RESIDENTIAL LOT STABILIZATION

- . CURLEX BLANKET (I) (4' MIN WIDTH) OR ENGINEER APPROVED
- 2. CURLEX MUST BE INSTALLED PER MANUFACTURER SPECIFICATIONS.
- 3. MAX SLOPE FOR CURLEX (I) < 2H : 1V

#### SOIL STABILIZATION NOTE

PER TPDES REQUIREMENTS, DISTURBED AREAS ON WHICH CONSTRUCTION ACTIVITIES HAVE CEASED (TEMPORARILY OR PERMANENTLY) SHALL BE STABILIZED WITHIN 14 DAYS UNLESS ACTIVITY RESUMES WITHIN 21 DAYS. SEEDING DOES NOT CONSTITUTE AS STABILIZATION.

SUBSTANTIAL GRADING IS PROPOSED WITH THIS UNIT. PER THE NEW BRAUNFELS DRAINAGE AND EROSION CONTROL DESIGN MANUAL SEC. 13.2(N), STRIPPING OF VEGETATION FROM PROJECT SITES SHALL BE PHASED SO AS TO EXPOSE THE MINIMUM AMOUNT OF AREA TO SOIL EROSION FOR THE SHORTEST POSSIBLE TIME.

#### EROSION CONTROL NOTES:

LIMITS OF CONSTRUCTION AND OTHER EROSION CONTROL IMPROVEMENTS SHOWN OUTSIDE THE PROPERTY ARE SHOWN FOR GRAPHICAL PURPOSE ONLY. IF NEAR PROPERTY LINE, THE INTENT IS TO BE PLACED NEAR THE PROPERTY LINE, NOT ON THE ADJACENT

2. DO NOT DISTURB VEGETATED AREAS (TREES, GRASS, WEEDS, BRUSH, ETC.) ANY MORE THAN NECESSARY FOR CONSTRUCTION. 3. CONSTRUCTION ENTRANCE/EXIT LOCATION, CONCRETE WASH-OUT PIT, AND CONSTRUCTION EQUIPMENT AND MATERIAL STORAGE YARD TO BE DETERMINED IN THE

4. STORM WATER POLLUTION PREVENTION CONTROLS MAY NEED TO BE MODIFIED IN THE FIELD TO ACCOMPLISH THE DESIRED EFFECT. ALL MODIFICATIONS ARE TO BE NOTED IN THE SWPPP DOCUMENTS AND SIGNED AND DATED BY THE RESPONSIBLE PARTY. RESTRICT ENTRY/EXIT TO THE PROJECT SITE TO DESIGNATED LOCATIONS BY USE OF ADEQUATE FENCING, IF NECESSARY.

6. ALL STORM WATER POLLUTION PREVENTION CONTROLS ARE TO BE MAINTAINED AND IN WORKING CONDITIONS AT ALL TIMES. STORM WATER POLLUTION PREVENTION STRUCTURES SHOULD BE CONSTRUCTED WITHIN THE SITE BOUNDARIES. SOME OF THESE FEATURES MAY BE SHOWN OUTSIDE THE SITE

BOUNDARIES ON THIS PLAN FOR VISUAL CLARITY. 8. AS SOON AS PRACTICAL, ALL DISTURBED SOIL THAT WILL NOT BE COVERED BY IMPERVIOUS COVER SUCH AS PARKWAY AREAS, EASEMENT AREAS, EMBANKMENT SLOPES, ETC. WILL BE STABILIZED PER APPLICABLE PROJECT SPECIFICATIONS.

DISTURBANCE OF UP-GRADIENT AREAS. 10. BEST MANAGEMENT PRACTICES MAY BE REMOVED IN STAGES ONCE THE WATERSHED FOR THAT PORTION CONTROLLED BY THE BEST MANAGEMENT PRACTICES HAS BEEN STABILIZED IN ACCORDANCE WITH TPDES REQUIREMENTS.

9. BEST MANAGEMENT PRACTICES MAY BE INSTALLED IN STAGES TO COINCIDE WITH THE

11. UPON COMPLETION OF THE PROJECT, INCLUDING SITE STABILIZATION, AND BEFORE FINAL PAYMENT IS ISSUED, CONTRACTOR SHALL REMOVE ALL SEDIMENT AND EROSION CONTROL MEASURES, PAYING SPECIAL ATTENTION TO ROCK BERMS IN DRAINAGE FEATURES. 12. STRIPPING OF VEGETATION FROM PROJECT SITES SHALL BE PHASED SO AS TO EXPOSE THE MINIMUM AMOUNT OF AREA TO SOIL EROSION FOR THE SHORTEST POSSIBLE PERIOD OF TIME PER THE NEW BRAUNFELS DRAINAGE AND EROSION CONTROL DESIGN MANUAL SEC. 12.2(N).

#### HYDRAULIC MULCH

#### MATERIALS:

HYDRAULIC MULCHES: WOOD FIBER MULCH CAN BE APPLIED ALONE OR AS A COMPONENT OF HYDRAULIC MATRICES. WOOD FIBER APPLIED ALONE IS TYPICALLY APPLIED AT THE RATE OF 2,000 TO 4,000 LB/ACRE. WOOD FIBER MULCH IS MANUFACTURED FROM WOOD OR WOOD WASTE FROM LUMBER MILLS OR FROM URBAN SOURCES.

HYDRAULIC MATRICES: HYDRAULIC MATRICES INCLUDE A MIXTURE OF WOOD FIBER AND ACRYLIC POLYMER OR OTHER TACKIFIER AS BINDER. APPLY AS A LIQUID SLURRY USING A HYDRAULIC APPLICATION MACHINE (I.E., HYDRO SEEDER) AT THE FOLLOWING MINIMUM RATES, OR AS SPECIFIED BY THE MANUFACTURER TO ACHIEVE COMPLETE COVERAGE OF THE TARGET AREA: 2,000 TO 4,000 LB/ACRE WOOD FIBER MULCH, AND 5 TO 10% (BY WEIGHT) OF TACKIFIER (ACRYLIC COPOLYMER, GUAR, PSYLLIUM, ETC.)

BONDED FIBER MATRIX: BONDED FIBER MATRIX (BFM) IS A HYDRAULICALLY APPLIED SYSTEM OF FIBERS AND ADHESIVES THAT UPON DRYING FORMS AN EROSION RESISTANT BLANKET THAT PROMOTES VEGETATION, AND PREVENTS SOIL EROSION. BFMS ARE TYPICALLY APPLIED AT RATES FROM 3,000 LB/ACRE TO 4,000 LB/ACRE BASED ON THE MANUFACTURER'S RECOMMENDATION. A BIODEGRADABLE BFM IS COMPOSED OF MATERIALS THAT ARE 100% BIODEGRADABLE. THE BINDER IN THE BFM SHOULD ALSO BE BIODEGRADABLE AND SHOULD NOT DISSOLVE OR DISPERSE UPON RE-WETTING. TYPICALLY BIODEGRADABLE BEMS SHOULD NOT BE APPLIED IMMEDIATELY BEFORE, DURING OR IMMEDIATELY AFTER RAINFALL IF THE SOIL IS SATURATED. DEPENDING ON THE PRODUCT, BFMS TYPICALLY REQUIRE 12 TO 24 HOURS TO DRY AND BECOME EFFECTIVE.

- . PRIOR TO APPLICATION, ROUGHEN EMBANKMENT AND FILL AREAS BY ROLLING WITH A CRIMPING OR PUNCHING TYPE ROLLER OR BY TRACK WALKING. TRACK WALKING SHALL ONLY BE USED WHERE OTHER METHODS ARE IMPRACTICAL.
- . TO BE EFFECTIVE, HYDRAULIC MATRICES REQUIRE 24 HOURS TO DRY BEFORE RAINFALL 3. AVOID MULCH OVER SPRAY ONTO ROADS, SIDEWALKS, DRAINAGE CHANNELS, EXISTING
- 4. 4" OF TOP SOIL SHALL BE PLACED. INSPECTION AND MAINTENANCE GUIDELINES:
- MULCHED AREAS SHOULD BE INSPECTED WEEKLY AND AFTER EACH RAIN EVENT TO AREAS DAMAGED BY STORMS OR NORMAL CONSTRUCTION ACTIVITIES SHOULD BE REGRADED AND HYDRAULIC MULCH REAPPLIED AS SOON AS PRACTICAL.

CONTRACTOR SHALL NOTIFY THE FOLLOWING UTILITY COMPANIES 48 HOURS PRIOR TO EXCAVATION:

New Braunfels Utilities Spectrum Cable Centerpoint Gas Robert Sanders Damaged Line AT&T Telephone Erick White PM

Texas One Call

Scott McBrearty (Construction)

830-625-3408 830-643-6434 830-643-6903 888-876-5786 210-283-1706 210-658-4886 830-545-6005


C.P.E. LOCATOR
CALL CENTER POINT ENERGY LOCATOR AT 1-800-545-6005, 48HRS BEFORE BEGINNING ANY EXCAVATION. DUE TO FEDERAL REGULATIONS TITLE 49, PART 192.181, CENTER POINT ENERGY MUST MAINTAIN ACCESS TO GAS VALVES AT ALL TIMES. THE CONTRACTOR MUST PROTECT AND WORK AROUND ANY GAS VALVES THAT ARE IN THE PROJECT AREA.

THE EXISTENCE AND LOCATION OF UNDERGROUND CABLE INDICATED ON THE PLANS ARE TAKEN FROM THE BEST RECORDS AVAILABLE AND ARE NOT GUARANTEED TO BE ACCURATE. CONTRACTOR TO CONTACT THE TELEPHONE COMPANY CABLE LOCATOR 48HRS PRIOR TO EXCAVATION AT 1-800-545-6005,, CONTRACTOR HAS THE RESPONSIBILITY TO PROTECT AND SUPPORT TELEPHONE COMPANY DURING CONSTRUCTION.

#### TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTÉCHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. CONTRACTORS IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24—HOURS PRIOR TO COMMENCING CONSTRUCTION.



**LEGEND** 

EXISTING CONTOURS PROPOSED CONTOURS EDGE OF PAVEMENT

FLOW ARROWS

EXISTING UTILITY POLE EXISTING LIGHT POLE EXISTING WATER METER EXISTING WATER VALVE EXISTING FIRE HYDRANT EXISTING TREE

BOUNDARY OF DISTURBED AREA

STABLIZED CONSTRUCTION ENTRANCE/EXIT

TRUCK WASH OUT PIT

CONSTRUCTION STAGING AREA

ROCK BERM

GRAVEL FILTER BAGS



## **BELLA VISTA HOMES** 2714 N LOOP 1604 E, SUITE 105 SAN ANTONIO, TX 782332

## HIGHLAND GARDENS UNIT 1A

**EROSION CONTROL PLAN** 


SHEET


16 of 17


ISSUES AND REVISIONS 1-13-2022 UPDATED PER CONB COMMENTS





2021 W SH46, STE 105 NEW BRAUNFELS, TX. 78132 PH: 830-358-7127 ink-civil.com TBPE FIRM F-13351













BELLA VISTA HOMES 2714 N LOOP 1604 E, SUITE 105 SAN ANTONIO, TX 782332

## HIGHLAND GARDENS UNIT 1A

**EROSION CONTROL DETAILS** 

OF

SHEET

17

NO DATE ISSUES AND REVISIONS

1-13-2022 UPDATED PER CONB COMMENTS



2021 W SH46, STE 105 NEW BRAUNFELS, TX. 78132 PH: 830-358-7127 ink-civil.com TBPE FIRM F-13351