

BID SUMMARY SHEET

Highpoint Unit-2C

NOTE: QUANTITIES ARE PROVIDED FOR REFERENCE ONLY. CONTRACTOR RESPONSIBLE FOR QUANTITY CONFIRMATION.

DESCRIPTION	QTY	UNIT
STREET IMPROVEMENTS		
Clearing	22	AC
Remove Header Curb & Barricade Posts	96	LF
Street Excavation	7538	CY
Street Embankment	8476	CY
Lime Stabilized Subgrade	298	SY
Lime	4	TON
8.5" Flexible Base (Local A)	8820	SY
17" Flexible Base (Local B)	5768	SY
2" Type D Asphalt (Local A)	7926	SY
3" Type D Asphalt (Local B)	5335	SY
7" Standard Curb	6846	LF
9" Header Curb	84	LF
6" Barricade Posts	15	EA
Concrete Sidewalk (Developer Responsibility)	439	SY
ADA Ramps (Developer Responsibility)	8	EA
Signage and Striping	1	LS
SUBTOTAL		
DRAINAGE IMPROVEMENTS		
Channel Excavation	8052	CY
Channel Embankment	71	CY
Baffle Blocks	1.5	CY
6' Sidewalk Box	5	EA
6" Concrete Rip-Rap	41	SY
Sidewalk Pipe Railing	32	LF
Hydromulch (include 6" top soil)	6058	SY
18" Rock Rubble	39	SY
SUBTOTAL		
LOT GRADING		
Lot Excavation	29308	CY
Lot Embankment	38938	CY
SUBTOTAL		
EROSION CONTROL		
TPDES Erosion Control	1	LS
TPDES After Construction Erosion Control Phase II	1	LS
SUBTOTAL		
WATER		
8" C-900 Class 235 PVC (DR18) Pipe	3883	LF
3/4" Single Service, Short w/ 5/8" Meter	59	EA
3/4" Single Service, Long w/ 5/8" Meter	34	EA
24" Steel Casing	41	LF
Standard Fire Hydrant Assembly	5	EA

BID SUMMARY SHEET

8" Gate Valve, MJ w/ Valve Box	14	EA
8" Division Valve, MJ w/ Valve Box	1	EA
2" Blowoff (Temporary)	3	EA
2" Blowoff (Permanent)	3	EA
Ductile Iron Fittings	2.65	TON
Joint Restraints	1	LS
Hydrostatic Testing	3	LS
Trench Excavation Protection	3883	LF
Chlorination	3883	LF
Meter Box	93	EA
SUBTOTAL		
SEWER		
8" Sanitary Sewer Pipe SDR-26 (0-6 Feet)	185	LF
8" Sanitary Sewer Pipe SDR-26 (6-10 Feet)	2023	LF
8" Sanitary Sewer Pipe SDR-26 (10-14 Feet)	800	LF
8" Sanitary Sewer Pipe (160 PSI) SDR-26 (6-10 Feet)	60	LF
8" Sanitary Sewer Pipe (160 PSI) SDR-26 (10-14 Feet)	20	LF
Standard Manhole with Ring Encasement	12	EA
Vertical Stacks	6	VF
Manhole Extra Depth	42.2	VF
Adjust Existing Manhole Top	2	EA
8" x 6" Wye	84	EA
8" x 6" Wye into Existing 8" Main	2	EA
6" Sanitary Sewer Lateral (SDR-26)	3462	LF
Tie into Existing Manhole	1	EA
Trench Excavation Protection	6550	LF
TV Video Sewer Line	3088	LF
SUBTOTAL		
MISC		
CPS Conduit Bundle A	1080	LF
CPS Conduit Bundle B	50	LF
CPS Conduit Bundle C	85	LF
CPS Conduit Bundle D	50	LF
Concrete Mailbox Pad (8'x8')	2	EA
SUBTOTAL		
HIGHPOINT UNIT-2C		
Date: 7/12/24		