

BID SUMMARY SHEET

Highpoint Unit-2I

NOTE: QUANTITIES ARE PROVIDED FOR REFERENCE ONLY. CONTRACTOR RESPONSIBLE FOR QUANTITY CONFIRMATION.

DESCRIPTION	QTY	UNIT
STREET IMPROVEMENTS		
Clearing	33	AC
Remove Header Curb & Barricade Posts	285	LF
Street Excavation	18,090	CY
Street Embankment	4,880	CY
8.5" Flexible Base (Local A)	17,674	SY
17" Flexible Base (Local B)	2,421	SY
18.5" Flexible Base (Collector)	7,371	SY
Prime Coat	5,048	GAL
Tack Coat	2,524	GAL
7" Type B Asphalt (Local B)	177	SY
2" Type D Asphalt (Local A)	15,884	SY
1.5" Type C Asphalt (Local B)	2,366	SY
1.5" Type D Asphalt (Local B)	2,366	SY
1.5" Type C Asphalt (Collector)	6,813	SY
3" Type D Asphalt (Collector)	6,813	SY
7" Standard Curb	12,605	LF
Concrete Sidewalk (Developer Responsibility)	1,208	SY
Barricade Posts	5	EA
ADA Ramps (Developer Responsibility)	4	EA
Signage and Striping	1	LS
SUBTOTAL		
DRAINAGE IMPROVEMENTS		
Channel Excavation	1,900	CY
Channel Embankment	380	CY
Concrete Headwall	2	CY
Baffle Blocks	1.2	CY
24" Reinforced Concrete Pipe	362	LF
42" Reinforced Concrete Pipe	77	LF
48" Reinforced Concrete Pipe	173	LF
Junction Box 6'x6'	1	EA
Curb Inlet 10'	4	EA
Curb Inlet 15'	1	EA
Curb Inlet 20'	2	EA
Grate Inlet 8'x8'	1	EA
Concrete Collars	13	CY
6' Sidewalk Box	3	EA
6" Concrete Rip-Rap	540	SY
Hydromulch	2,303	SY
Sidewalk Pipe Railing	54	LF
9" Rock Rubble	94	SY
SUBTOTAL		
LOT GRADING		
Lot Excavation	25,050	CY

BID SUMMARY SHEET

Lot Embankment	24,000	CY
SUBTOTAL		
EROSION CONTROL		
TPDES Erosion Control	1	LS
TPDES After Construction Erosion Control Phase II	1	LS
SUBTOTAL		
WATER		
8" C-900 Class 235 PVC (DR18) Pipe	5,202	LF
12" C-900 Class 235 PVC (DR18) Pipe	2,416	LF
12" DI Pipe	13	LF
8" DI Pipe	27	LF
3/4" Single Service, Short w/ 5/8" Meter	79	EA
3/4" Single Service, Long w/ 5/8" Meter	39	EA
3/4" Irrigation Service w/ 5/8" Meter	2	EA
1" Irrigation Service w/ 1" Meter	2	EA
Standard Fire Hydrant Assembly	12	EA
8" Gate Valve, MJ w/ Valve Box	15	EA
12" Gate Valve, MJ w/ Valve Box	8	EA
2" Blowoff (Temporary)	3	EA
2" Blowoff (Permanent)	1	EA
24" Steel Casing	27	LF
12"x8" Cut In Tee	1	EA
Ductile Iron Fittings	7.35	TON
Tie Into Existing Water Main	3	EA
Joint Restraints	1	LS
Hydrostatic Testing	1	LS
Trench Excavation Protection	7,658	LF
Chlorination	7,658	LF
Meter Box	122	EA
SUBTOTAL		
SEWER		
8" Sanitary Sewer Pipe (SDR-26) (6-10 ft)	3,285.50	LF
8" Sanitary Sewer Pipe (SDR-26) (10-14 ft)	738	LF
8" Sanitary Sewer Pipe (SDR-26) (14-18 ft)	675	LF
8" Sanitary Sewer Pipe (SDR-26) (18-22 ft)	469	LF
8" Sanitary Sewer Pipe (160 PSI) (SDR-26) (6-10 ft)	60	LF
8" Sanitary Sewer Pipe (160 PSI) (SDR-26) (10-14 ft)	20	LF
Standard Manhole with Ring Encasement	15	EA
Vertical Stack	149	VF
Manhole Extra Depth	95	VF
8" x 6" Wye	110	EA
6" Sanitary Sewer Lateral (SDR-26)	4,279	LF
Tie into Existing Manhole	3	EA
Trench Excavation Protection	5,247.50	LF
TV Video Sewer Line	5,247.50	LF
Adjust Top of Manhole	1	LS
Drop Manhole Structure	1	EA
SUBTOTAL		

BID SUMMARY SHEET

MISC		
CPS Conduit Bundle A	182	LF
CPS Conduit Bundle B	1,415	LF
Concrete Mailbox Pad (8'x8')	2	EA
Export (Lots, Streets, and Drains)	15,780	CY
HIGHPOINT UNIT-2I	DATE:	
7/12/24		