

**LEGACY AT GREEN ENCLAVE UNIT 1
BID QUANTITIES**

SITE IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Mobilization	L.S.	1.0		\$ -
2	Site Clearing	AC.	27.1		\$ -
3	Silt Fence	L.F.	7,650.0		\$ -
4	Gravel Bag Filters	L.F.	850.0		\$ -
5	Rock Berm	L.F.	120.0		\$ -
6	Construction Staging Area	L.S.	1.0		\$ -
7	Concrete Washout Pit	L.S.	1.0		\$ -
8	Stabalized Construction Entrance	L.S.	1.0		\$ -
TOTAL COST					\$ -

SANITARY SEWER IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	TIE INTO EXISTING SANITARY SEWER MAIN	E.A.	1		\$ -
2	TRENCH EXCAVATION SAFETY PROTECTION	L.F.	11,580		\$ -
3	8" SANITARY SEWER PIPE, SDR-26 (0'-6')	L.F.	451		\$ -
4	8" SANITARY SEWER PIPE, SDR-26 (6'-10')	L.F.	5,039		\$ -
5	8" SANITARY SEWER PIPE, SDR-26 (10'-14')	L.F.	471		\$ -
6	8" SANITARY SEWER PIPE, SDR-26 (14'-18')	L.F.	813.0		\$ -
7	STANDARD SANITARY SEWER MANHOLE	EA.	24		\$ -
8	EXTRA DEPTH MANHOLE	V.F.	65		\$ -
9	VERTICAL STACK	V.F.	334		\$ -
10	6" SANITARY SEWER LATERALS, SDR-26	L.F.	4,806		\$ -
11	WYE ONLY	E.A.	54		\$ -
12	ONE-WAY CLEANOUTS	EA.	128		\$ -
13	SEWER MAIN TELEVISION INSPECTION	L.F.	6,774		\$ -
TOTAL COST					\$ -

WATER IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Trench Excavation Protection	L.F.	5,581		\$ -
2	8" Pipe, C900 DR 18 PVC Class 235 (Includes Joint Restraints)	L.F.	2,678		\$ -
3	12" Pipe, C900 DR 18 PVC Class 235 (Includes Joint Restraints)	L.F.	156		\$ -
4	16" Pipe, C900 DR 18 PVC Class 235 (Includes Joint Restraints)	L.F.	2,747		\$ -
5	8" Gate Valve, M.J. w/ Box, Complete	EA.	10		\$ -
6	16" Gate Valve, M.J. w/ Box, Complete	EA.	15		\$ -
7	Standard Fire Hydrant	EA.	7		\$ -
8	2" Permanent Blow-off	EA.	3		\$ -
9	2" Temporary Blow-off	EA.	4		\$ -
10	3/4" Single Service Per Lot: Short	EA.	78		\$ -
11	3/4" Single Service Per Lot: Long (Sleeved w/ 2" PVC)	EA.	50		\$ -
12	1" Irrigation Service	EA.	1		\$ -
13	D.I. Fittings	TON	5.18		\$ -
14	Water Main Tie-in	EA.	4		\$ -
15	Hydrostatic Testing	EA.	1		\$ -

16	Chlorintion & Bacterial Testing	EA.	1		\$	-
17	Meter Boxes	EA.	128		\$	-
TOTAL COST					\$	-

STREET IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Street & Lot Excavation	C.Y.	25,902		\$ -
2	Street & Lot Embankment	C.Y.	14,326		\$ -
3	Saw Cut, Remove, and Replace Existing Pavement	L.F.	175		\$ -
4	Lime Stabalized Subgrade (6.0" 34 lbs/sy)	S.Y.	8,402		\$ -
5	Lime Stabalized Subgrade (8.0" 45 lbs/sy)	S.Y.	12,078		\$ -
6	Flexible Base (11.0" Compacted)	S.Y.	8,402		\$ -
7	Flexible Base (18.5" Compacted)	S.Y.	10,498		\$ -
8	Prime Coat	GAL	3,679		\$ -
9	Tack Coat	GAL	1,839		\$ -
10	HMAC, Type C (2.5" Thickness)	S.Y.	9,462		\$ -
11	HMAC, Type C (9" Thickness)	S.Y.	1,580		\$ -
12	HMAC, Type D (2.0" Thickness)	S.Y.	7,352		\$ -
13	HMAC, Type D (1.5" Thickness)	S.Y.	9,462		\$ -
14	HMAC, Type D (3" Thickness)	S.Y.	1,580		\$ -
15	4" Mountable Curb	L.F.	7,223		\$ -
16	7" Standard Machine Laid Curb	L.F.	1,652		\$ -
17	Header Curb	L.F.	94		\$ -
18	4' Concrete Sidewalks (By Developer)	S.Y.	194		\$ -
19	6' Concrete Sidewalks (By Developer)	S.Y.	95		\$ -
20	ADA Ramps (By Developer)	EA.	27		\$ -
21	Metal Beam Guard Fence	L.F.	125		\$ -
22	R1-1 Stop Sign, 30" x30"	EA.	9		\$ -
23	9" Private Street Name Signs	EA.	20		\$ -
24	W2-1 Warning Sign	EA.	1		\$ -
25	W16-aP "350FT" Plate	EA.	1		\$ -
26	Timber Guard Posts	EA.	20		\$ -
27	End of Road Marker	EA.	9		\$ -
28	Pavement Marker (Type II)(Blue)	EA.	7		\$ -
29	8-inch Solid White Line	L.F.	83		\$ -
30	4-inch Double Yellow Line w/ Type II-AA RPPMS	L.F.	1,094		\$ -
31	Left White Arrow	EA.	1		\$ -
32	Word "ONLY"	EA.	1		\$ -
TOTAL COST				\$	-

DRAIN IMPROVEMENTS

Drain A					
ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Channel Excavation	C.Y.	34.0		\$ -
2	Elevated Concrete Sidewalk	C.Y.	2.5		\$ -
3	6" Concrete Rip Rap	S.Y.	105		\$ -
4	Sidewalk Pipe Railing	L.F.	10.0		\$ -
5	Revegetation	S.Y.	200		\$ -
TOTAL COST					\$ -
Drain B					
ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Demo Existing Headwall & Rip-Rap	L.S.	1.0		\$ -
2	8'x3' S.B.C.	L.F.	14.0		\$ -
3	Concrete Headwall	C.Y.	7.0		\$ -
4	6" Concrete Rip Rap	S.Y.	60		\$ -
5	Sidewalk Pipe Railing	L.F.	38.0		\$ -
6	Revegetation	S.Y.	150		\$ -

TOTAL COST	\$	-
------------	----	---

Additive Alternates

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	1-6"/2-4" PVC BUNDLE (Utility Conduit)	L.F.	1,900		\$ -
2	1-6"/1-4" PVC (IRRIGATION)	L.F.	60		\$ -
3	Stock Pile Excess Material	C.Y.	11,576		\$ -
4	All Weather Access Rd (CPS OH Route)	S.Y.	1,090		\$ -
TOTAL COST					\$ -

SUMMARY:

SITE IMPROVEMENTS	\$	-
SANITARY SEWER IMPROVEMENTS	\$	-
WATER IMPROVEMENTS	\$	-
STREET IMPROVEMENTS	\$	-
DRAIN IMPROVEMENTS	\$	-
BID ADDITIVES	\$	-
TOTAL CONSTRUCTION COST:	\$	-