

**LEGACY AT GREEN ENCLAVE UNIT 2
BID QUANTITIES - Addendum 1**

SITE IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Mobilization	L.S.	1.0		\$ -
2	Site Clearing	AC.	16.4		\$ -
3	Silt Fence	L.F.	6,000		\$ -
4	Gravel Bag Filters	L.F.	668		\$ -
5	Rock Berm	L.F.	60.0		\$ -
6	Construction Staging Area	L.S.	1.0		\$ -
7	Concrete Washout Pit	L.S.	1.0		\$ -
8	Stabalized Construction Entrance	L.S.	1.0		\$ -
TOTAL COST					\$ -

SANITARY SEWER IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	TIE INTO EXISTING SANITARY SEWER MAIN	E.A.	2		\$ -
2	TRENCH EXCAVATION SAFETY PROTECTION	L.F.	3,804		\$ -
3	8" SANITARY SEWER PIPE, SDR-26 (0'-6')	L.F.	343		\$ -
4	8" SANITARY SEWER PIPE, SDR-26 (6'-10')	L.F.	513		\$ -
5	8" SANITARY SEWER PIPE, SDR-26 (10'-14')	L.F.	189		\$ -
6	8" SANITARY SEWER PIPE, SDR-26 (14'-18')	L.F.	69.0		\$ -
7	STANDARD SANITARY SEWER MANHOLE	EA.	5		\$ -
8	EXTRA DEPTH MANHOLE	V.F.	11		\$ -
9	VERTICAL STACK	V.F.	27.2		\$ -
10	6" SANITARY SEWER LATERALS, SDR-26	L.F.	2,690		\$ -
12	TWO-WAY CLEANOUTS	EA.	87		\$ -
13	RE-COAT EXISTING MANHOLE	EA.	2		\$ -
14	SEWER MAIN TELEVISION INSPECTION	L.F.	1,114		\$ -
15	ADJUST EXISTING MANHOLE	EA.	4		\$ -
TOTAL COST					\$ -

WATER IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Trench Excavation Protection	L.F.	4,565		\$ -
2	8" Pipe, C900 DR 18 PVC Class 235 (Includes Joint Restraints)	L.F.	3,030		\$ -
3	16" Pipe, C900 DR 18 PVC Class 235 (Includes Joint Restraints)	L.F.	1,535		\$ -
4	8" Gate Valve, M.J. w/ Box, Complete	EA.	12		\$ -
5	16" Gate Valve, M.J. w/ Box, Complete	EA.	3		\$ -
6	Standard Fire Hydrant	EA.	5		\$ -
7	2" Permanent Blow-off	EA.	1		\$ -
8	2" Temporary Blow-off	EA.	4		\$ -
9	1" Dual Service Short	EA.	21		\$ -
10	1" Dual Service Long	EA.	12		\$ -
11	1" Single Service Short	EA.	3		\$ -
12	1" Single Service Long	EA.	2		\$ -
13	D.I. Fittings	TON	2.8		\$ -

14	Hydrostatic Testing	EA.	1		\$	-
15	Chlorintion & Bacterial Testing	EA.	1		\$	-
16	Meter Boxes	EA.	87		\$	-
17	24" Steel Casing (Offsite)	L.F.	36		\$	-
18	16" Ductile Iron Pipe (Offsite)	L.F.	138		\$	-
19	Remove & Replace Existing Fence (Offsite)	L.F.	950		\$	-
20	Remove & Replace Existing Driveway (Offsite)	S.Y.	80		\$	-
21	Remove & Replace Existing 16" CMP & Rip-Rap (Offsite)	L.S.	1		\$	-
TOTAL COST						\$ -

STREET IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Street & Lot Excavation	C.Y.	14,214		\$ -
2	Street & Lot Embankment	C.Y.	12,770		\$ -
3	Saw Cut, Remove, and Replace Existing Pavement	L.F.	60		\$ -
4	Lime Stabalized Subgrade (6.0" 34 lbs/sy)	S.Y.	10,372		\$ -
5	Lime Stabalized Subgrade (8.0" 45 lbs/sy)	S.Y.	1,744		\$ -
6	Flexible Base (11.0" Compacted)	S.Y.	10,372		\$ -
7	Flexible Base (18.5" Compacted)	S.Y.	1,744		\$ -
8	Prime Coat	GAL	2,158		\$ -
9	Tack Coat	GAL	1,079		\$ -
10	HMAC, Type C (2.5" Thickness)	S.Y.	1,545		\$ -
11	HMAC, Type D (2.0" Thickness)	S.Y.	9,243		\$ -
12	HMAC, Type D (1.5" Thickness)	S.Y.	1,545		\$ -
13	4" Mountable Curb	L.F.	5,336		\$ -
14	7" Standard Machine Laid Curb	L.F.	550		\$ -
15	Header Curb	L.F.	30		\$ -
16	4' Concrete Sidewalks (By Developer)	S.Y.	104		\$ -
17	6' Concrete Sidewalks (By Developer)	S.Y.	0		\$ -
18	ADA Ramps (By Developer)	EA.	15		\$ -
19	R1-1 Stop Sign, 30" x30"	EA.	3		\$ -
20	9" Private Street Name Signs	EA.	12		\$ -
21	W14-2A "NO OUTLET" Plate	EA.	2		\$ -
22	Timber Guard Posts	EA.	6		\$ -
23	End of Road Marker	EA.	3		\$ -
24	Pavement Marker (Type II)(Blue)	EA.	5		\$ -
TOTAL COST					\$ -

DRAIN IMPROVEMENTS

Drain C					
ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Channel Excavation	C.Y.	10.0		\$ -
2	Elevated Concrete Sidewalk	C.Y.	7.0		\$ -
3	6" Concrete Rip Rap	S.Y.	109		\$ -
4	Sidewalk Pipe Railing	L.F.	20.0		\$ -
5	Revegetation	S.Y.	175		\$ -
TOTAL COST					\$ -
Drain D					
ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Channel Excavation	C.Y.	5.0		\$ -
2	Elevated Concrete Sidewalk	C.Y.	4.0		\$ -
3	6" Concrete Rip Rap	S.Y.	103		\$ -
4	Sidewalk Pipe Railing	L.F.	15.0		\$ -
5	Revegetation	S.Y.	250		\$ -
TOTAL COST					\$ -

Additive Alternates

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	1-6"/2-4" PVC BUNDLE (Utility Conduit)	L.F.	1,000		\$ -
2	2-6"/2-4" PVC BUNDLE (Utility Conduit)	L.F.	90		\$ -
3	Export Material	C.Y.	13,020		\$ -
4	All Weather Access Rd (CPS OH Route - 6" Flex Base)	S.Y.	1,590		\$ -
5	Additional 25% Lime & Remix (High Sulfates Onsite)	S.Y.	12,116		\$ -
6	Construction Staking	L.S.	1		\$ -
7	Sewer & Water Trench Compaction Testing	L.S.	1		\$ -
8	Lot Compaction Testing	L.S.	1		\$ -
9	Concrete Compressive Testing (Drains)	L.S.	1		\$ -
10	3rd Party SWPPP Inspections	L.S.	1		\$ -
TOTAL COST					\$ -

SUMMARY:

SITE IMPROVEMENTS	\$	-
SANITARY SEWER IMPROVEMENTS	\$	-
WATER IMPROVEMENTS	\$	-
STREET IMPROVEMENTS	\$	-
DRAIN IMPROVEMENTS	\$	-
BID ADDITIVES	\$	-
TOTAL CONSTRUCTION COST:	\$	-