

LONESOME DOVE HILLS UNIT 3 BID QUANTITIES

WATER IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	8" Water Main Tie-In	EA.	4	\$ -	\$ -
2	Trench Excavation Protection	L.F.	3,204	\$ -	\$ -
3	8" Pipe, C900 DR 18 PVC Class 235 (Incl. Restraints)	L.F.	3,179	\$ -	\$ -
4	24" Steel Casing	L.F.	10		
5	8" Pipe, D.I.	L.F.	25	\$ -	\$ -
6	8" Gate Valve, M.J.	EA.	8	\$ -	\$ -
7	Standard Fire Hydrant (Complete)	EA.	7	\$ -	\$ -
8	2" Permanent Blow-off	EA.	1	\$ -	\$ -
9	2" Temporary Blow-off	EA.	3	\$ -	\$ -
10	3/4" Irrigation Service	EA.	1	\$ -	\$ -
11	3/4" Single Service: Short	EA.	55	\$ -	\$ -
12	3/4" Single Service: Long	EA.	59	\$ -	\$ -
13	D.I. Fittings	TON	2.0	\$ -	\$ -
14	Hydrostatic Testing	EA.	1	\$ -	\$ -
15	Meter Boxes	EA.	115	\$ -	\$ -
TOTAL COST					\$ -

SANITARY SEWER IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
16	Tie Into Existing Sewer Main	EA.	4	\$ -	\$ -
17	Reconstruct Existing Manholes	EA.	4	\$ -	\$ -
18	Trench Excavation Safety Protection	L.F.	1,213	\$ -	\$ -
19	8" Sanitary Sewer Pipe, SDR-26 (6'-10')	L.F.	1,213	\$ -	\$ -
20	Standard Sanitary Sewer Manhole	EA.	2	\$ -	\$ -
21	Extra Depth Manhole	V.F.	2.6	\$ -	\$ -
22	Vertical Stack	V.F.	36	\$ -	\$ -
23	6" Sanitary Sewer Lateral, SDR-26	L.F.	2,413	\$ -	\$ -
24	One-Way Cleanouts	EA.	69	\$ -	\$ -
TOTAL COST					\$ -

LONESOME DOVE HILLS UNIT 3 BID QUANTITIES

STREET IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
25	Remove Header Curb	L.F.	56	\$ -	\$ -
26	Remove Timber Guard Posts	EA.	19	\$ -	\$ -
27	Remove Temporary Turnaround	EA.	1	\$ -	\$ -
28	Street Excavation	C.Y.	8,108	\$ -	\$ -
29	Street Embankment	C.Y.	1,912	\$ -	\$ -
30	Lime Stabilized Subgrade (6" Compacted Depth) (30 lb/S.Y.)	S.Y.	12,435	\$ -	\$ -
31	Flexible Base (10.0" Compacted Depth)	S.Y.	11,862	\$ -	\$ -
32	Flexible Base (19.5" Compacted Depth)	S.Y.	573	\$ -	\$ -
33	Prime Coat	GAL.	2,225	\$ -	\$ -
34	Tack Coat	GAL.	1,112	\$ -	\$ -
35	Hot Mix Asphalt Pavement, Type D - (2" Comp. Depth)	S.Y.	10,615	\$ -	\$ -
36	Hot Mix Asphalt Pavement, Type D - (3" Comp. Depth)	S.Y.	508	\$ -	\$ -
37	Concrete Curb	L.F.	6,374	\$ -	\$ -
38	Header Curb	L.F.	28	\$ -	\$ -
39	ADA Ramps	EA.	14	\$ -	\$ -
40	Concrete Sidewalks (Developer Responsibility)	S.Y.	240	\$ -	\$ -
41	Timber Guard Posts	EA.	5	\$ -	\$ -
42	R1-1 Stop (30")(High Intensity)	EA.	3	\$ -	\$ -
43	OM4-3 End of Road Marker (18"x18")(High Intensity)	EA.	3	\$ -	\$ -
44	9-inch Street Name, Block Number (Varies x9")(High Intensity)	EA.	6	\$ -	\$ -
45	Pavement Marker (Type II) (Blue)	EA.	7	\$ -	\$ -
46	Rock Filter Dams (Type II) (Install & Remove)	L.F.	172	\$ -	\$ -
47	Construction Exit (Installation)	S.Y.	264	\$ -	\$ -
48	Construction Exit (Removal)	S.Y.	264	\$ -	\$ -
49	Temporary Sediment Control Fence (Phase I - Sitework)	L.F.	3,306	\$ -	\$ -
50	Temporary Sediment Control Fence (Phase II - Homebuilder)	L.F.	6,245	\$ -	\$ -
51	Curb Inlet Gravel Filters	L.F.	48	\$ -	\$ -
				TOTAL COST	\$ -

DRAINAGE IMPROVEMENTS (DRAIN A)

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
52	Channel Excavation	C.Y.	344	\$ -	\$ -
53	Channel Embankment	C.Y.	56	\$ -	\$ -
				TOTAL COST	\$ -

LONESOME DOVE HILLS UNIT 3 BID QUANTITIES

DRAINAGE IMPROVEMENTS (DRAIN B)

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
54	Channel Excavation	C.Y.	19	\$ -	\$ -
55	Channel Embankment	C.Y.	38	\$ -	\$ -
56	Elevated Concrete Sidewalk	C.Y.	2.25	\$ -	\$ -
57	Concrete Riprap (6" Thick)	S.Y.	76	\$ -	\$ -
58	Sidewalk Pipe Railing	L.F.	13	\$ -	\$ -
TOTAL COST					\$ -

DRAINAGE IMPROVEMENTS (DRAIN C)

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
59	Channel Excavation	C.Y.	9	\$ -	\$ -
60	Channel Embankment	C.Y.	95	\$ -	\$ -
61	Elevated Concrete Sidewalk	C.Y.	3	\$ -	\$ -
62	Concrete Riprap (6" Thick)	S.Y.	64	\$ -	\$ -
63	Sidewalk Pipe Railing	L.F.	13.0	\$ -	\$ -
TOTAL COST					\$ -

DRAINAGE IMPROVEMENTS (DRAIN D)

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
64	Channel Excavation	C.Y.	31	\$ -	\$ -
65	Channel Embankment	C.Y.	80	\$ -	\$ -
66	24" RCP (Class IV)	L.F.	178.5	\$ -	\$ -
67	Concrete Riprap (6" Thick)	S.Y.	168	\$ -	\$ -
68	Concrete Collar	S.Y.	0.5	\$ -	\$ -
69	Concrete Headwall	EA.	2	\$ -	\$ -
70	Sidewalk Pipe Railing	L.F.	78.0	\$ -	\$ -
TOTAL COST					\$ -

SITE WORK AND ADD ALTERNATES

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
71	Clearing and Grubbing	AC.	20.8	\$ -	\$ -
72	Lot Excavation	C.Y.	17,569	\$ -	\$ -
73	Lot Embankment	C.Y.	28,730	\$ -	\$ -
74	Import Material	C.Y.	4,831	\$ -	\$ -
75	Conduit Bundle (1-6" PVC & 2-4" PVC)	L.F.	1,350	\$ -	\$ -
76	Conduit Bundle (2-6" PVC & 2-4" PVC)	L.F.	140	\$ -	\$ -
77	Conduit Bundle (4-6" PVC & 2-4" PVC)	L.F.	50	\$ -	\$ -
78	Conduit Bundle (6-6" PVC & 2-4" PVC)	L.F.	20	\$ -	\$ -
79	Conduit Bundle (7-6" PVC & 2-4" PVC)	L.F.	6	\$ -	\$ -
TOTAL COST					\$ -

GRAND TOTAL COST: \$ -