

LUCERO AT LUCKEY RANCH, UNIT 1A
BID FORM

ITEM	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
<u>STREET IMPROVEMENTS</u>					
1.	Mobilization	LS	1	\$ _____	\$ _____
2.	Clearing & Grubbing	AC	4.8	\$ _____	\$ _____
3.	Earthwork			\$ _____	\$ _____
	a. Excavation	CY	91	\$ _____	\$ _____
	b. Embankment	CY	18,974	\$ _____	\$ _____
	c. Import Offsite (Scraper)	CY	18,883	\$ _____	\$ _____
4.	1.5" Type D Asphalt (Secondary Arterial)	SY	12,100	\$ _____	\$ _____
5.	2.5" Type C Asphalt (Secondary Arterial)	SY	12,100	\$ _____	\$ _____
6.	2.5" Type C Asphalt (Temporary Turnaround)	SY	832	\$ _____	\$ _____
7.	8.0" Flexible Base (Temporary Turnaround)	SY	832	\$ _____	\$ _____
8.	14.0" Flexible Base (Modified Road Section)	SY	438	\$ _____	\$ _____
9.	18.0" Flexible Base (Secondary Arterial)	SY	11,662	\$ _____	\$ _____
10.	12.0" Lime Stabilized Subgrade (Secondary Arterial) (53 lb/sy)	SY	12,100	\$ _____	\$ _____
11.	Geogrid (Tensor TX-5) (Modified Road Section)	SY	438	\$ _____	\$ _____
12.	7" Concrete Curb	LF	3,230	\$ _____	\$ _____
13.	4' Concrete Sidewalk	SY	50	\$ _____	\$ _____
14.	6' Concrete Sidewalk	SY	1,028	\$ _____	\$ _____
15.	12' Concrete Sidewalk (Multi-Use Path)	SY	1,926	\$ _____	\$ _____
16.	Signage, Traffic Control & Pavement Striping	LS	1	\$ _____	\$ _____
17.	Header Curb	LF	230	\$ _____	\$ _____
18.	Barricade Post	EA	46	\$ _____	\$ _____
19.	Streetscape (Medium Size Trees)	EA	64	\$ _____	\$ _____
20.	Saw-Cut, Remove & Tie-In to Existing Pavement (WT Montgomery Rd)	LF	175	\$ _____	\$ _____
21.	TPDES (Stage I)	LS	1	\$ _____	\$ _____
22.	Sleeves/Conduits				
	a. Major Crossing (Electric)				
	3-6" Conduit, 2-4" Conduit (3ea)	LF	294	\$ _____	\$ _____
	b. Major Crossing (Gas) (2ea)				
	1-12" Conduit	LF	150	\$ _____	\$ _____
	c. Developer Crossing				
	3-4" Conduit (3 ea)	LF	294	\$ _____	\$ _____
				SUBTOTAL	\$ _____

**LUCERO AT LUCKEY RANCH, UNIT 1A
BID FORM**

ITEM	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
<u>DRAINAGE IMPROVEMENTS</u>					
1.	Reinforced Concrete Class 'A'				
	a. Curb Inlets	CY	20	\$ _____	\$ _____
	b. Headwall/Wingwall (CIP)	CY	8	\$ _____	\$ _____
2.	Junction Box				
	a. 4'x4' Junction Box (w/ 4-Way Inlet)	EA	1	\$ _____	\$ _____
	b. 4'x4' Junction Box	EA	1	\$ _____	\$ _____
	c. 6'x6' Junction Box	EA	1	\$ _____	\$ _____
	d. 7'x7' Junction Box	EA	2	\$ _____	\$ _____
3.	24" RCP (Class IV)	LF	316	\$ _____	\$ _____
4.	30" RCP (Class IV)	LF	92	\$ _____	\$ _____
5.	24" CMP (Ultraflow)	LF	44	\$ _____	\$ _____
6.	4'x2' SBC (PC)	LF	38	\$ _____	\$ _____
7.	5'x2' SBC (PC)	LF	809	\$ _____	\$ _____
8.	Concrete Collars	EA	14	\$ _____	\$ _____
9.	6" Concrete Rip Rap	SY	95	\$ _____	\$ _____
10.	6"-8" Rock Rubble at 12" Deep	SY	16	\$ _____	\$ _____
11.	Pipe Handrail	LF	52	\$ _____	\$ _____
12.	Existing Bar Ditch Improvements (WT Montgomery Rd) (Placeholder)	LS	1	\$ _____	\$ _____
13.	Bar Ditch Revegetation (Sod/Seed) (Placeholder)	SY	100	\$ _____	\$ _____
				SUBTOTAL	\$ _____

**LUCERO AT LUCKEY RANCH, UNIT 1A
BID FORM**

ITEM	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
<u>SANITARY SEWER IMPROVEMENTS</u>					
1.	8" Sanitary Sewer Pipe (SDR 26)				
	a. (6'-8')	LF	187	\$ _____	\$ _____
	b. (20'-22')	LF	323	\$ _____	\$ _____
2.	Fiberglass Sanitary Sewer Manhole	EA	2	\$ _____	\$ _____
3.	Standard Manhole Extra Depth	VF	28	\$ _____	\$ _____
4.	Sewer Cap & Cleanout	EA	5	\$ _____	\$ _____
5.	Trench Excavation Protection	LF	510	\$ _____	\$ _____
6.	TV Video Sewer Line	LF	510	\$ _____	\$ _____
7.	Dewatering (Placeholder)	LS	1	\$25,000.00	\$25,000.00
				SUBTOTAL	\$ _____
<u>WATER IMPROVEMENTS</u>					
1.	12" PVC C-900, Class 235, DR 18	LF	1,689	\$ _____	\$ _____
2.	8" PVC C-900, Class 235, DR 18	LF	149	\$ _____	\$ _____
3.	12" Gate Valve, MJ w/Valve Box	EA	6	\$ _____	\$ _____
4.	8" Gate Valve, MJ w/Valve Box	EA	2	\$ _____	\$ _____
5.	Standard Fire Hydrant Assembly	EA	4	\$ _____	\$ _____
6.	D.I. Fittings (Restrained)	TON	1.5	\$ _____	\$ _____
7.	¾" Irrigation Service (5/8" Meter)	EA	3	\$ _____	\$ _____
8.	2" Blowoff Assembly (Temporary)	EA	1	\$ _____	\$ _____
9.	2" Blowoff Assembly (Permanent)	EA	5	\$ _____	\$ _____
10.	Joint Restraints	LS	1	\$ _____	\$ _____
11.	Hydrostatic Pressure Test	EA	2	\$ _____	\$ _____
12.	Trench Excavation Protection	LF	1,838	\$ _____	\$ _____
13.	Chlorination	LF	1,838	\$ _____	\$ _____
14.	Meter Box	EA	3	\$ _____	\$ _____
				SUBTOTAL	\$ _____
				TOTAL	\$ _____

Notes:

1. Contractor is to perform an independent quantity take-off prior to signing the contract, to verify that the quantities given in the bid proposal are within three percent (3%) of the actual quantities required to complete the construction represented by the plans and specifications. If any quantity is found to be in error of more than three percent (3%), the Contractor shall notify the Engineer forty-eight (48) hours prior to signing the contract.
2. Bids shall include all Unit Price costs as indicated by the Contract Documents and Bid Form. The bid price submitted by the Contractor shall be the sum of the unit prices times the estimated quantity of each item shown in the bid form. However, the Contractor shall guarantee himself of the accuracy of the quantities shown in the bid form. The quantities shown are estimates only and indicate only the magnitude of the project and a basis for bid comparison. Any discrepancies in quantity or work necessary to fulfill the intent of the plans shall be included, whether a bid item is included or not. Any work required for which a bid item is not shown shall be considered subsidiary to other work items.
3. All construction staking will be performed by the contractor. Engineer will set all final pins for the project.