

MAYFAIR - PARCEL E-9N

UNIT PRICES

Date _____

BIDDER'S FULL NAME _____

Address _____

City, State, Zip _____

Milestone #1-Substantial Completion (days): _____

BASE BID: \$ _____ -

Milestone #2-Final Completion (days): _____

1. The Undersigned proposes to furnish all labor, services, materials, tools and necessary equipment for the construction of various improvements and to perform the work required at the locations set out by the Plans and Specifications, in strict accordance with the Contract Documents.
2. In submitting this Bid, it is understood that this Bid may not be altered or withdrawn for a minimum of 90 calendar days, and that the Owner has reserved the right to reject any and all Bids.
3. The Undersigned certifies that this Bid is made in good faith, without collusion or connection with any other person, persons, partnership, company, firm, association, or corporation offering Bids on this work, for the following sum or prices to wit:

SIGNATURES _____

Authorized Signing Officer, Title

SIGNATURES _____

Authorized Signing Officer, Title

ITEM	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
STREET IMPROVEMENTS					
1.	Local A & B, 50' & 60' ROW				
	a. 3" Type C/D HMAC (Gutter to Gutter)	SY	24,389	\$ -	\$ -
	b. 12" Flexible (Granular) Base (1' behind back of curb)	SY	30,750	\$ -	\$ -
	c. 6" Lime Treated Subgrade	SY	30,750	\$ -	\$ -
2.	Minor Collector				
	a. 2.5" Type C/D HMAC (Gutter to Gutter)	SY	7,121	\$ -	\$ -
	b. 3.5" Type C HMAC (Gutter to Gutter)	SY	7,121	\$ -	\$ -
	c. 17" Flexible (Granular) Base (1' behind back of curb)	SY	8,255	\$ -	\$ -
	d. 6" Lime Treated Subgrade	SY	8,255	\$ -	\$ -
3.	Temporary Cul-de-sac/Turnaround, Access Road				
	a. 1.5" Type D HMAC	SY	895	\$ -	\$ -
	b. 8" Flexible (Granular) Base	SY	895	\$ -	\$ -
4.	Sidewalk	SY	4,490	\$ -	\$ -
5.	7" Concrete Curb and Gutter	LF	17,003	\$ -	\$ -
6.	Barricade Posts	EA	6	\$ -	\$ -
7.	Revegetation (Hydromulch) Parkways	SY	11,796	\$ -	\$ -
8.	Header Curb	LF	1,256	\$ -	\$ -
9.	Concrete Valley Gutter	SY	84	\$ -	\$ -
10.	Demo Existing Road	SY	5,577	\$ -	\$ -

SUBTOTAL \$ -

DRAINAGE IMPROVEMENTS

1.	Rock Rubble	SY	58	\$ -	\$ -
2.	Channel Revegetation (Hydromulch)	SY	828	\$ -	\$ -
3.	Curlex Single Net Erosion Control Blanket	SY	324	\$ -	\$ -
4.	6'x6' Junction Box	EA	1	\$ -	\$ -
5.	4'x4' Junction Box	EA	1	\$ -	\$ -
6.	Reinforced Concrete Class 'A'				
	a. 10' Type CI Curb Inlet	EA	8	\$ -	\$ -
	b. 15' Type CI Curb Inlet	EA	5	\$ -	\$ -
	c. 20' Type CI Curb Inlet	EA	1	\$ -	\$ -
	d. 25' Type CI Curb Inlet	EA	1	\$ -	\$ -
	e. 30' Type CI Curb Inlet	EA	3	\$ -	\$ -
	f. Baffle Blocks	CY	1.1	\$ -	\$ -
	g. FW-0 Headwall	CY	15.8	\$ -	\$ -
7.	Remove Existing Concrete	SY	66	\$ -	\$ -
8.	6" Concrete Rip-rap	SY	92	\$ -	\$ -
9.	Concrete Collars	CY	11.53	\$ -	\$ -
10.	24" RCP	LF	850.46	\$ -	\$ -
11.	30" RCP	LF	244.4	\$ -	\$ -
12.	48" RCP	LF	175.21	\$ -	\$ -
13.	4'X3' SBC	LF	170.49	\$ -	\$ -
14.	Trench Excavation Protection	LF	1,440.56	\$ -	\$ -
				SUBTOTAL	\$ -

SANITARY SEWER IMPROVEMENTS

1.	8" Sanitary Sewer Pipe				
	a. 8'-10' Depth	LF	2,390.13	\$ -	\$ -
	b. 10'-12' Depth	LF	1,875.48	\$ -	\$ -
	c. 12-14' Depth	LF	833.36	\$ -	\$ -
	d. 14'-16' Depth	LF	154.57	\$ -	\$ -
	e. 16'-18' Depth	LF	89.50	\$ -	\$ -
2.	Standard Manhole	EA	23	\$ -	\$ -
3.	Drop Manhole	EA	1	\$ -	\$ -
4.	Manhole Extra Depth	VF	93.09	\$ -	\$ -
5.	Wye	EA	169	\$ -	\$ -
6.	6" Lateral (SDR-26)	LF	8,535	\$ -	\$ -
7.	Trench Excavation Protection	LF	13,878.04	\$ -	\$ -
8.	Camera Testing	LF	5,343.04	\$ -	\$ -
9.	Tie to Existing Manhole	EA	2	\$ -	\$ -
				SUBTOTAL	\$ -

WATER DISTRIBUTION IMPROVEMENTS

1.	8" PVC C-900 Class 150, CDR-(4)	LF	7,518	\$	-	\$	-
2.	8" Gate Valve, MJ w/Valve Box	EA	30	\$	-	\$	-
3.	12" PVC C-900 Class 150, CDR-(4)	LF	1,616	\$	-	\$	-
4.	12" Gate Valve, MJ w/Valve Box	EA	4	\$	-	\$	-
5.	Standard Fire Hydrant Assembly	EA	22	\$	-	\$	-
6.	Joint Restraints	LS	1	\$	-	\$	-
7.	Ductile Iron Fittings	TON	6.23	\$	-	\$	-
8.	1" Single Service, Long	EA	97	\$	-	\$	-
9.	1" Single Service, Short	EA	85	\$	-	\$	-
10.	1" Irrigation Service	EA	2	\$	-	\$	-
11.	Hydrostatic Testing	LS	1	\$	-	\$	-
12.	Trench Excavation Protection	LF	9,133	\$	-	\$	-
13.	Meter Box with lid	EA	184	\$	-	\$	-
14.	2" Permanent Blowoff	EA	3	\$	-	\$	-
15.	2" Temporary Blowoff	EA	5	\$	-	\$	-
16.	Landscape Conduit	LF	176	\$	-	\$	-
				SUBTOTAL		\$	-

GRADING, CLEARING, TPDES & SIGNAGE

1.	Excavation (Streets)	CY	33,703	\$	-	\$	-
2.	Embankment (Streets)	CY	9,143	\$	-	\$	-
3.	Excavation (Lots & Drainage)	CY	58,683	\$	-	\$	-
4.	Embankment (Lots & Drainage)	CY	78,011	\$	-	\$	-
5.	Export	CY	5,232	\$	-	\$	-
6.	Clearing	AC	38.99	\$	-	\$	-
7.	TPDES	LS	1	\$	-	\$	-
8.	Signage/Striping	LS	1	\$	-	\$	-
9.	Retainage Wall	SF	24,060	\$	-	\$	-
				SUBTOTAL		\$	-

ELECTRICAL IMPROVEMENTS

1.	3~3" PVC Primary Conduit	LF	2,309	\$	-	\$	-
2.	1~3" PVC Primary Conduit	LF	5,966	\$	-	\$	-
3.	1~3" PVC Secondary Conduit	LF	5,092	\$	-	\$	-
4.	1~1-1/4" PVC Streetlight Conduit	LF	3,203	\$	-	\$	-
5.	Primary Pull Box	EA	8	\$	-	\$	-
6.	Secondary Pull Box	EA	85	\$	-	\$	-
7.	Stubout Trench (assume 5lf/stubout)	EA	186	\$	-	\$	-
8.	Streetlight Foundation Pad	EA	34	\$	-	\$	-
9.	Transformer Pad	EA	29	\$	-	\$	-
				SUBTOTAL		\$	-

MAYFAIR - PARCEL E-9N - BASE BID: \$ -

ALTERNATE

1.	Stair steps	EA	34	\$	-	\$	-
ALTERNATE TOTAL						\$	-