

**BID QUANTITIES**  
**MEADOWS AT OAK CREEK**  
**4/5/2024**

| DESCRIPTION                                 | UNIT | QTY   |
|---------------------------------------------|------|-------|
| <b>STREET IMPROVEMENTS</b>                  |      |       |
| Mobilization                                | LS   | 1     |
| Clearing                                    | AC   | 10.0  |
| Tree Protection                             | LS   | 1     |
| Street Excavation                           | CY   | 2,963 |
| Street Embankment                           | CY   | 291   |
| 5" Concrete PVMT                            | SY   | 6,905 |
| 6" Concrete Curb                            | LF   | 1,254 |
| 4" Mountable Curb                           | LF   | 2,781 |
| TXDOT Sidewalk Ramps                        | EA   | 4     |
| Signage and Striping                        | LS   | 1     |
| TPDES Storm Water Pollution Prevention Plan | LS   | 1     |

|                              |    |       |
|------------------------------|----|-------|
| <b>DRAINAGE IMPROVEMENTS</b> |    |       |
| Drainage Excavation          | CY | 1,297 |
| Drainage Embankment          | CY | 716   |
| 24" RCP                      | LF | 56    |
| 36" RCP                      | LF | 24    |
| 12" HDPE                     | LF | 9     |
| 18" HDPE                     | LF | 467   |
| 24" HDPE                     | LF | 185   |
| 36" HDPE                     | LF | 23    |
| 24" CMP ULTRA FLOW           | LF | 212   |
| Trench Excavation Protection | LF | 976   |
| 3' x 3' Junction Box         | EA | 5     |
| 4' x 4' Junction Box         | EA | 2     |
| 4' x 4' 4-Way Inlet          | EA | 3     |
| 5' Curb Inlet                | EA | 1     |
| 10' Curb Inlet               | EA | 2     |
| 15' Curb Inlet               | EA | 1     |
| Detention Basin              | LS | 2     |
| RH-15 Headwall               | EA | 1     |
| Rock Rubble                  | SY | 119   |
| Sidewalk Drain               | EA | 1     |

|                                                 |     |       |
|-------------------------------------------------|-----|-------|
| <b>WATER</b>                                    |     |       |
| 12" x 8" Cut In Tee                             | EA  | 1     |
| 16" x 8" Cut In Tee                             | EA  | 1     |
| 16" X 3/4" Tap in Tee                           | EA  | 1     |
| 3/4" Irrigation Service                         | EA  | 1     |
| 8" C-900 PVC (DR18) Class 235                   | LF  | 2,103 |
| Standard Fire Hydrant Assembly                  | EA  | 4     |
| 8" Gate valve (MJ) with 6" Valve Box, Complete  | EA  | 10    |
| 12" Gate valve (MJ) with 6" Valve Box, Complete | EA  | 1     |
| 16" Gate valve (MJ) with 6" Valve Box, Complete | EA  | 1     |
| Fittings                                        | TON | 1.20  |
| 3/4" Single Service, Long w/ 5/8" Meter & Box   | EA  | 40    |
| 3/4" Single Service, Short w/ 5/8" Meter & Box  | EA  | 49    |
| Hydrostatic Testing                             | LS  | 1     |
| Trench Excavation Safety Protection             | LF  | 2,103 |
| Chlorination                                    | LF  | 2,103 |

|                                         |    |       |
|-----------------------------------------|----|-------|
| <b>SEWER</b>                            |    |       |
| Tie Into Existing Sewer Manhole         | EA | 1     |
| 8" Sanitary Sewer Pipe (SDR 26 160 PSI) |    |       |
| a. (6' - 10')                           | LF | 952   |
| b. (10' - 14')                          | LF | 818   |
| c. (sub 14')                            | LF | 574   |
| 6" Sanitary Sewer Lateral (SDR 26)      | LF | 3,115 |
| 8" x 6" Wye                             | EA | 88    |
| Standard Manhole w/ Ring Encasement     | EA | 13    |
| Vertical Stack                          | VF | 186   |
| Manhole Extra Depth                     | VF | 81    |
| Trench Excavation Protection            | LF | 2,344 |
| TV Video Sewer Line                     | LF | 2,344 |

|                |    |        |
|----------------|----|--------|
| <b>GRADING</b> |    |        |
| Lot Excavation | CY | 11,535 |
| Lot Embankment | CY | 15,142 |
| Export         | CY | 354    |
| Retaining Wall | FF | 6,315  |

|                                                     |    |       |
|-----------------------------------------------------|----|-------|
| <b>MISC</b>                                         |    |       |
| Construction Staking                                | LS | 1     |
| Testing                                             | LS | 1     |
| CPS Conduits (2 ~ 6" SCH 80 PVC, 2 ~ 4" SCH 40 PVC) | LF | 1,176 |
| CPS Conduits (4 ~ 4" SCH 40 PVC) Landscape Conduits | LF | 108   |