GENERAL INFORMATION

- ALL CONSTRUCTION SHALL CONFORM TO THE CITY OF SAN ANTONIO STANDARD SPECIFICATIONS FOR CONSTRUCTION
- NO EXTRA PAYMENT SHALL BE ALLOWED FOR WORK CALLED FOR ON THE PLANS. BUT NOT INCLUDED IN THE BID
- THE CONTRACTOR SHALL PROVIDE ACCESS FOR THE DELIVERY OF MAIL BY THE U.S. POSTAL SERVICE. 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING TO ITS ORIGINAL OR BETTER CONDITION ANY DAMAGE DONE TO EXISTING FENCES, CONCRETE ISLANDS, STREET PAVING, CURBS, SHRUBS, BUSHES OR DRIVEWAYS. (NO SEPARATE PAY

PROPOSAL. THIS INCIDENTAL WORK WILL BE REQUIRED AND SHALL BE INCLUDED IN THE PAY ITEM TO WHICH IT RELATES

- IT IS THE CONTRACTOR'S RESPONSIBILITY TO SEE THAT ALL SIGNS AND BARRICADES ARE PROPERLY INSTALLED AND MAINTAINED. ALL LOCATIONS AND DISTANCES WILL BE DECIDED UPON IN THE FIELD BY THE CONTRACTOR, USING THE NGINEERING REPRESENTATIVE WILL ONLY BE RESPONSIBLE TO INSPECT BARRICADES AND SIGNS. IF, IN THE OPINION C THE TRAFFIC ENGINEERING REPRESENTATIVE AND THE CONSTRUCTION INSPECTOR, THE BARRICADES AND SIGNS DO NO $^\circ$ CONFORM TO ESTABLISHED STANDARDS OR ARE INCORRECTLY PLACED OR ARE INSUFFICIENT IN QUANTITY TO PROTECT
- IF THE NEED ARISES, ADDITIONAL BARRICADES AND DIRECTIONAL DEVICES MAY BE ORDERED BY THE TRAFFIC ENGINEERING REPRESENTATIVE AT THE CONTRACTOR'S EXPENSE.
- DUE TO FEDERAL REGULATIONS TITLE 49, PART 192.171 C.P.S. MUST MAINTAIN ACCESS TO GAS VALVES AT ALL TIMES. THE CONTRACTOR MUST PROTECT AND WORK AROUND ANY GAS VALVES THAT ARE IN THE PROJECT AREA.
- CONTRACTOR SHALL NOTIFY THE CITY INSPECTOR TWENTY FOUR (24) HOURS PRIOR TO BACKFILL OF ANY UTILITY TRENCHES TO SCHEDULE FOR DENSITY TEST AS REQUIRED
- CONTRACTOR SHALL PRESERVE ALL CONSTRUCTION STAKES, MARKS, ETC. IF ANY ARE DESTROYED OR REMOVED BY TH CONTRACTOR OR HIS EMPLOYEES, THEY SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
- CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES PRIOR TO CONSTRUCTION TO DETERMINE THE LOCATION OF EXISTING UTILITIES. CONTRACTOR SHALL NOTIFY THE FOLLOWING AT LEAST FORTY-EIGHT (48) HOURS PRIOR TO

SAN ANTONIO WATER SYSTEM (SAWS)

TEXAS STATE WIDE ONE CALL LOCATOR CITY PUBLIC SERVICE ENERGY - TIME WARNER - AT&T - MCI

- THE EXISTENCE AND LOCATION OF UNDERGROUND UTILITIES INDICATED ON THE PLANS ARE TAKEN FROM AVAILABLE RECORDS AND ARE NOT GUARANTEED, BUT SHALL BE INVESTIGATED AND VERIFIED BY THE CONTRACTOR BEFORE STARTING WORK, THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY DAMAGE TO AND FOR THE MAINTENANCE AN PROTECTION OF THE EXISTING UTILITIES EVEN IF THEY ARE NOT SHOWN ON THE PLANS. LOCATION AND DEPTH OF EXISTING UTILITIES SHOWN HERE ARE APPROXIMATE ONLY, ACTUAL LOCATIONS AND DEPTHS MUST BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION AND HE SHALL BE RESPONSIBLE FOR PROTECTION OF SAME DURING
- ALL WASTE MATERIAL SHALL BECOME PROPERTY OF THE CONTRACTOR AND SHALL BE HIS SOLE RESPONSIBILITY TO DISPOSE OF THIS MATERIAL OFF THE LIMITS OF THE PROJECT. NO WASTE MATE-RIAL SHALL BE PLACED IN EXISTING LOV THAT WILL BLOCK OR ALTER FLOW LIMITS OF EXISTING ARTIFICIAL OR NATURAL DRAINAGE.
- THE CONTRACTOR SHALL NOT PLACE ANY WASTE MATERIAL IN THE 100-YEAR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN DEVELOPMENT PERMIT.
- THE CONTRACTOR SHALL MAINTAIN ALL ADJOINING STREETS AND TRAVELED ROUTES FREE FROM SPILLED AND / OR
- IF THE CONTRACTOR ENCOUNTERS ANY ARCHAEOLOGICAL DEPOSITS DURING CONSTRUCTION OPERATIONS, THE CONTRACTOR MUST STOP EXCAVATION IMMEDIATELY, CONTACT THE CITY INSPECTOR, AND CALL THE CITY HISTORIC PRESERVATION OFFICE AT 207-7306 OR 207-3327 FOR AN ARCHAEOLOGICAL INVESTIGATION. THE CONTRACTOR CANNOT BEGIN EXCAVATION AGAIN WITHOUT WRITTEN PERMISSION FROM THE CITY. IF MORE THAN THREE (3) DAYS ARE REQUIRED FOR INVESTIGATION (NOT INCLUDING HOLIDAY AND WEEKENDS) AND IF THE CONTRACTOR IS UNABLE TO WOR IN OTHER AREAS. THEN THE CONTRACTOR WILL BE ALLOWED TO NEGOTIATE FOR ADDITIONAL CONSTRUCTION TIME UPON WRITTEN REQUEST WITHIN TEN (10) DAYS AFTER THE FIRST NOTICE TO THE CITY OF ARCHAEOLOGICAL INVESTIGATION FOR EACH EVENT. IF THE TIME REQUIRED FOR INVESTIGATION IS LESS THAN OR EQUAL TO THREE (3) DAYS FOR EACH EVENT, CONTRACT DURATION WILL NOT BE EXTENDED
- IMMEDIATELY WHEN CONTAMINATED SOILS AND / OR GROUNDWATER ARE ENCOUNTERED AT LOCATIONS NOT IDENTIFIED CONTAMINATED SOIL AND / OR GROUNDWATER SHALL NOT BE REMOVED FROM THE LOCATION WITHOUT PRIOR C.O.S.A. APPROVAL. THE CONTRACTOR MUST STOP THE EXCAVATION IMMEDIATELY AND CONTACT THE C.O.S.A. INSPECTOR. THE CONTRACTOR CANNOT BEGIN EXCAVATION ACTIVITIES WITHOUT WRITTEN PERMISSION FROM THE CITY.
- CONTRACTOR IS TO INCLUDE A MAILBOX POST BLOCKOUT FOR VACANT LOTS AND ALL RESIDENCES WHICH DO NOT HAVE MAILBOXES AT THE CURB. BLOCKOUTS ARE PROVIDED FOR FUTURE USE BY THE POST OFFICE.
- CONTRACTOR SHALL NOT REMOVE OR ADJUST ANY VIA FACILITIES. THE CONTRACTOR MUST CONTACT VIA FOURTEEN DAYS PRIOR, FOR THE REMOVAL OF BENCHES, STOP POLES OR ANY OTHER VIA FACILITIES THAT MAY BE PRESENT. PLEASE PROVIDE THIRTY DAYS PRIOR NOTICE FOR SHELTER REMOVAL (TELEPHONE NOS: (210) 362-2155 OR (210) 362-2096). THE CONTRACT- OR WILL BE LIABLE FOR ANY DAMAGES TO VIA FACILITIES NOT REMOVED BY VIA. THE CON-TRACTOR IS REQUIRED TO REPLACE ALL FLATWORK REMOVED OR DAMAGED IN THE COURSE OF EXFCLITING THE CONTRACT UNLESS OTHERWISE NOTED BY VIA. THE CONTRACTOR WILL BE RESPONSIBLE FOR PROTECTING VIA FACILITIES IF ADJACENT TO WORK AREA.

<u>REE PROTECTION AND PRESERVATION GENERAL NOTES</u>

- NO UTILITY OR STREET EXCAVATION WORK SHALL BEGIN IN AREAS WHERE TREE PRESERVATION AND TREATMENT MEASURES HAVE NOT BEEN COMPLETED AND APPROVED
- TREE PROTECTION FENCING SHALL BE REQUIRED. TREE PROTECTION FENCING SHALL BE INSTALLED, MAINTAINED AND REPAIRED BY THE CONTRACTOR DURING SITE CONSTRUCTION. DURING CONSTRUCTION ACTIVITY, AT LEAST A SIX-INCH LAYER OF COARSE MULCH SHALL BE PLACED AND MAINTAINED OVER THE ROOT PROTECTION ZONE (NO SEPARATE PAY
- THE CONTRACTOR SHALL AVOID CUTTING ROOTS LARGER THAN ONE INCH IN DIAMETER WHEN EXCAVATING NEAR EXISTIN TREES. EXCAVATION IN THE VICINITY OF TREES SHALL PROCEED WITH CAUTION. THE CONTRACTOR SHALL CONTACT THE
- ROOTS WILL BE CUT WITH A ROCK SAW OR BY HAND, NOT BY AN EXCAVATOR OR OTHER ROAD CONSTRUCTION EQUIPMENT.
- ALL CURB AND SIDEWALK WORK SHALL USE ALTERNATIVE CONSTRUCTION METHODS TO MINIMIZE EXTENSIVE ROOT
- EXPOSED ROOTS SHALL BE COVERED AT THE END OF THE DAY USING TECHNIQUES SUCH AS COVERING WITH SOIL, MULCI-
- NO EQUIPMENT. VEHICLES OR MATERIALS SHALL OPERATE OR BE STORED WITHIN THE ROOT PROTECTION ZONE OF ANY TREE NEAR THE PROJECT. ROOT PROTECTION ZONE IS 1 FOOT OF RADIUS PER INCH OF TREE'S DIAMETER. A 10-INCH DIAMETER TREE WOULD HAVE A 10 FOOT RADIUS ROOT PROTECTION ZONE AROUND THE TREE. ROOTS OR BRANCHES IN CONFLICT WITH THE CONSTRUCTION SHALL BE CUT CLEANLY ACCORDING TO PROPER PRUNING METHODS. OAK WOUNDS SHALL BE PAINTED OVER WITHIN 30 MINUTES TO PREVENT OAK WILT.
- SAPLINGS, SHRUBS OR BUSHES TO BE CLEARED FROM THE PROTECTED ROOT ZONE AREA OF A LARGE TREE SHALL BE REMOVED BY HAND AS DESIGNATED BY THE INSPECTOR.
- NO WIRES, NAILS OR OTHER MATERIAL MAY BE ATTACHED TO PROTECTED TREES.
- TREES, TREE LIMBS, BUSHES AND SHRUBS LOCATED IN THE CITY STREET OR ALLEY RIGHT-OF-WAY OR PERMANENT EASEMENTS WHICH INTERFERE WITH PROPOSED CONSTRUCTION ACTIVITIES SHALL BE PROPERLY PRUNED FOLLOWING THE ANSI A-300 STANDARDS FOR PRUNING. ALL TREE PRUNING SHALL BE COMPLETED BY A CITY OF SAN ANTONIO TREE MAINTENANCE LICENSED CONTRACTOR (ARTICLE 21-171, CITY CODE) ONLY AFTER APPROVAL FROM THE CAPITAL PROJECTS MANAGEMENT THROUGH THE INSPECTOR.
- NO EXCESSIVE TREE TRIMMING WILL BE PERMITTED
- ALL DEBRIS GENERATED BY THE PRUNING AND TRIMMING OF THE TREES AND / OR BUSHES SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF PROPERLY (NO SEPARATE PAY ITEM).
- TREES MUST BE MAINTAINED IN GOOD HEALTH THROUGHOUT THE CONSTRUCTION PROCESS. MAINTENANCE MAY INCLUDE BUT NOT LIMITED TO: WATERING THE ROOT PROTECTION ZONE, WASHING FOLIAGE, FERTILIZATION, PRUNING, ADDITIONAL MULCH APPLICATIONS AND OTHER MAINTENANCE AS NEEDED ON THE PROJECT.
- ANY TREE REMOVAL SHALL BE APPROVED BY THE CITY ARBORIST. (207-0278).
- TREES WHICH ARE DAMAGED OR LOST DUE TO THE CONTRACTOR'S NEGLIGENCE DURING CONSTRUCTION SHALL BE
- TREE PLANTING FOR MITIGATION OR ENHANCEMENT: ALL PLANTED TREES SHALL BE MAINTAINED IN A HEALTHY CONDITION AT ALL TIMES. THIS INCLUDES IRRIGATION, FERTILIZING, PRUNING AND OTHER MAINTENANCE AS NEEDED ON THE PROJECT. TREES THAT DIE WITHIN TWELVE (12) MONTHS SHALL BE REPLACED WITH A TREE OF EQUAL SIZE AND

<u>CCESSIBILITY REQUIREMENTS</u>

- THE CONTRACTOR SHALL PROVIDE AND MAINTAIN VEHICULAR AND PEDESTRIAN ACCESS AT ALL TIMES TO LOCAL RESIDENCES AND BUSINESSES.
- WHEN THE WORK REQUIRES THE EXCAVATION OF THE STREET AND THE REMOVAL OF THE EXISTING DRIVEWAY APPROACHES AND SIDEWALKS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING TEMPORARY ALL-WEATHER ACCESS TO THE BUSINESSES AND RESIDENCES. THE TEMPORARY DRIVEWAY APPROACHES SHALL BE CONSTRUCTED WITH FLEXIBLE BASE OR GRAVEL MATERIAL AT NO SEPARATE COST TO THE CITY.
- PRIOR TO INITIATING THE CONSTRUCTION OF NEW DRIVEWAY APPROACHES, THE CONTRACTOR SHALL GIVE ADVANCE WARNING IN PERSON, OR IN WRITING, OF AT LEAST 48 HOURS TO EACH RESIDENCE THAT WILL BE IMMEDIATELY AFFECTED SO THAT ALTERNATE PLANS MAY BE MADE BY THE RESIDENTS.
- FOR BUSINESSES WITH MORE THAN ONE DRIVEWAY. AT LEAST ONE DRIVEWAY SHALL REMAIN OPEN WHILE THE OTHER NEW DRIVEWAY APPROACHES ARE CONSTRUCTED. FOR BUSINESSES WITH ONLY ONE DRIVEWAY, THE NEW DRIVEWAY APPROACH SHALL BE CONSTRUCTED IN HALF WIDTHS, UNLESS A TEMPORARY ASPHALT DRIVEWAY IS FIRST INSTALLED A NO SEPARATE COST TO THE CITY.

MORGAN HEIGHTS PHASE 2B

BEXAR COUNTY, TEXAS

STREET, DRAINAGE, WATER, SANITARY SEWER, AND UTILITY IMPROVEMENTS



LOCATION MAP


OWNER/DEVELOPER TALLEY EXTENSION REVITALIZATION INITIATIVE, LLC. 5210 THOUSAND OAKS, STE. 1318 SAN ANTONIO, TEXAS 78233

INDEX


DESCRIPTION	SHEET NO.
COVER SHEET	0.0
OVERALL UTILITY PLAN	1.0
OVERALL UTILITY PLAN	
MASTER DRAINAGE PLAN (1 OF 2)	2.0
MASTER DRAINAGE PLAN (2 OF 2)	2.1
OVERALL GRADING PLAN	3.0
OVERALL GRADING PLAN	3.1
DRAIN "A" PLAN & PROFILE	4.0
DRAIN "B" PLAN & PROFILE	
DRAIN "C" PLAN & PROFILE	4.2
DRAIN "D" PLAN & PROFILE	4.3
SBC DRAIN DETAILS	
WONDERLAND WAY PLAN & PROFILE	5.0
AUGUSTUS BRKS & BRANDY GLEN PLAN & PROFILE	
WHIRLING PLACE & CLARNELLA GRVS PLAN & PROFILE	5.2
MERRY MAKER PLAN & PROFILE	5.3
STREET DETAIL SHEET	
CONCRETE DRIVEWAY DETAILS	
WHEELCHAIR RAMP DETAILS	5.6
TXDOT PED-18 DETAILS	5.7
TRAFFIC SIGNAGE PLAN	5.8
TRAFFIC SIGNAGE PLAN	5.9
PAVEMENT MARKING DETAILS (1 of 2)	
PAVEMENT MARKING DETAILS (2 of 2)	
SIGN MOUNTING DETAILS (1 of 2)	5.12
SIGN MOUNTING DETAILS (2 of 2)	5.13
LEFT TURN LANE (1 OF 2)	5.14
LEFT TURN LANE (2 OF 2)	
SANITARY SEWER COVER SHEET	6.0
OVERALL SANITARY SEWER PLAN	6.1
OVERALL SANITARY SEWER PLAN	6.2
LINE "A" & LINE "D" PLAN AND PROFILE	6.3
LINE "B" PLAN AND PROFILE	6.4
LINE "C" PLAN AND PROFILE	6.5
WATER DISTRIBUTION COVER SHEET	7.0
WATER DISTRIBUTION PLAN	7.1
WATER DISTRIBUTION PLAN	7.2
STORMWATER POLLUTION PREVENTION PLAN	8.0
STORMWATER POLLUTION PREVENTION PLAN	8.1
STORMWATER POLLUTION PREVENTION DETAILS	8.2

www.colliersengineering.com

hom the services were contracted or to whom it is certified. This drawing ma e copied, reused, disclosed, distributed or relied upon for any other pur without the express written consent of Colliers Engineering & Design



FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW CALL811 COM



PRELIMINARY


MORGAN HEIGHTS PHASE 2B PLAT# 23-11800386


> SAN ANTONIO BEXAR COUNTY


& Design

SAN ANTONIO (KFW) San Antonio, TX 78231 Phone: 210.979.8444

COVER SHEET







Proposed/Ulti mate Conditions:														
Study Point	AREA	(Acres)	С	Tovrl (min)		Tsc (min)	Tch (min)	Ttot (min)	l5 (in/hr)	l25 (in/hr)	l100 (in/hr)	Q5 (ft3/s)	Q25 (ft3/s)	Q100 (ft3/s)
1	A-1	3.26	0.77	10.00		1.00	2.00	13	5.662	7.888	9.854	14.21	19.80	24.73
2	A-2	4.41	0.77	10.00		1.00	3.00	14	5.468	7.600	9.480	18.57	25.81	32.19
3	A-3	5.95	0.77	10.00	ļ	2.00	2.00	14	5.468	7.600	9.480	25.05	34.82	43.43
4	A-4	6.96	0.77	10.00		1.00	3.00	14	5.468	7.600	9.480	29.30	40.73	50.81
5	A-5	8.83	0.77	10.00		1.00	2.00	13	5.662	7.888	9.854	38.50	53.63	67.00
	A-6	2.01	0.77		CARRYOVER									
6	PT.5 + PT. 7 + A-6	17.15	0.77	18.00	FROM PT. 7	0.00	2.00	20	4.543	6.277	7.789	60.00	82.89	102.86
	A-6a	3.20	0.77											
6a	PT.2 + PT. 3 + PT.4 +	37.67	0.77	20.00	CARRYOVER	0.00	1.00	21	4.432	6.120	7.591	128.55	177.52	220.18
6b	PT.6 + A-6a PT. 6a	38.88	0.77		FROM PT. 6	EPOM HVD	ROGRAPH DETENT	ION POND "A" CAL	CULATIONS			56.54	80.38	102.32
00	A-7	5.29	0.77			FROMITID	ROGRAFITELIEN	ION FOND A CAL	COLATIONS			30.34	00.30	102.32
					CARRYOVER									
7	PT. OS4 + A-7	6.31	0.76	15.00	FROM PT. OS4	1.00	2.00	18	4.796	6.633	8.241	23.00	31.81	39.52
8	A-8	4.14	0.77	10.00		2.00	1.00	13	5.662	7.888	9.854	18.05	25.15	31.41
9a	A-9a	8.52	0.84	10.00		1.00	3.00	14	5.468	7.600	9.480	38.96	54.15	67.54
9b	A-9b	6.10	0.77	10.00		1.00	3.00	14	5.468	7.600	9.480	25.68	35.70	44.53
	A-9c-1	0.45	0.96											
9c-1	PT. 9b + A-9c-1	6.55	0.78	14.00	CARRYOVER FROM PT. 9b	0.00	1.00	15	5.280	7.320	9.115	27.08	37.54	46.75
9c-2	A-9c-2	2.92	0.77	10.00	11(0)(111.35	1.00	2.00	13	5.662	7.888	9.854	12.73	17.74	22.16
							1			1.000	1			
	A-9c	0.16	0.96				<u> </u>							
9c	PT.9c-1 + PT. 9c-2 + A-9c	9.63	0.78	15.00	CARRYOVER FROM PT. 9c-1	0.00	0.00	15	5.280	7.320	9.115	39.76	55.13	68.65
	A-90 A-10	8.11	0.77				<u> </u>				 	1		
40				45.00	CARRYOVER	4.00	2.00	40	4.004	C 447	0.005	20.00	A4 F0	E4 50
10	PT. OS3 + A-10	8.36	0.77	15.00	FROM PT. OS3	1.00	3.00	19	4.664	6.447	8.005	30.02	41.50	51.53
11	A-11	6.78	0.77	10.00		2.00	2.00	14	5.468	7.600	9.480	28.55	39.68	49.49
	A-12	7.05	0.70											
12	PT. 11 + PT. 22 + PT.23 + A-12	95.55	0.71	26.00	CARRYOVER FROM PT. 22	4.00	9.00	39	3.217	4.440	5.502	218.24	301.19	373.23
12a					<u></u>	Ş	SEE MORGAN HEIG	HTS PHASE 5 SWM	<u>•</u> ∕IP	•	•	125.74	274.78	434.62
	A-12b	1.86	0.77			<u> </u>	1.2.3	1 2						
12b	PT. 12a +A-12b	97.41	0.77	39.00		0.00	0.00	39	3.217	4.440	5.502	241.31	333.03	412.69
12c	PT12b	97.41	0.77	39.00			0.00	39	3.217	4.440	5.502	241.31	333.03	412.69
						0.00								
13	A-13	6.65	0.77	10.00		2.00	2.00	14	5.468	7.600	9.480	28.00	38.92	48.54
	A-13a	2.81	0.77		OARDY (C)		 		<u> </u>		 	-	<u> </u>	
13a	PT. 8 + PT. 9+A-13a	15.47	0.77	14.00	CARRYOVER FROM PT. 9	0.00	1.00	15	5.280	7.320	9.115	62.89	87.20	108.58
13b	A-13b	1.34	0.82	10.00		3.00	0.00	13	5.662	7.888	9.854	6.22	8.67	10.83
	A-14	0.83	0.53				1		ì	1	1			
14	PT.OS2C + A-14	9.78	0.66	17.00	CARRYOVER	0.00	0.00	17	4.941	6.838	8.501	31.80	44.01	54.72
					FROM PT.OS2C				ļ					
15	A-15	11.85	0.67	14.00		3.00	2.00	19	4.664	6.447	8.005	37.03	51.19	63.55
	A-15a	1.37	0.67											
15a	PT.15 + DA-15a	13.22	0.67	19.00	CARRYOVER	0.00	0.00	19	4.664	6.447	8.005	41.31	57.10	70.90
			***	10100	FROM PT. 15									
	A-16	11.23	0.67											
16	PT.26 + A-16	13.07	0.63	17.00	CARRYOVER	0.00	5.00	22	4.329	5.975	7.408	35.84	49.47	61.33
10				17.00	FROM PT. 26	0.00	3.00	22	4.020	3.373	7.400	33.04	45.47	01.55
	A-16a	0.89	0.67		CARRYOVER									
16a	PT.16 + DA-16a	13.96	0.67	22.00	CARRYOVER FROM PT. 16	0.00	0.00	22	4.329	5.975	7.408	40.49	55.89	69.29
17a	A-17a	0.44	0.41	14.00		3.00	0.00	17	4.941	6.838	8.501	0.89	1.23	1.53
	17b	0.95	0.41											
			• • • • • • • • • • • • • • • • • • • •		CARRYOVER									
17b	PT.OS1 + PT.OS2A + PT.17A + A-17b	10.99	0.64	22.00	CARRYOVER FROM PT.OS1	0.00	0.00	22	4.329	5.975	7.408	30.31	41.84	51.87
	A-18	3.28	0.67											
			***		CARRYOVER									
18	PT.OS2B + PT.14 + PT.17b + A-18	26.48	0.65	22.00	CARRYOVER FROM PT.17b	0.00	1.00	23	4.233	5.841	7.239	73.08	100.83	124.97
	A-18a	0.49	0.67											
18a	PT.10 + PT.15a +	48.55	0.67	23.00	CARRYOVER	0.00	1.00	24	4.143	5.715	7.081	134.77	185.90	230.34
	PT.18 +DA-18a				FROM PT. 18									
19	A-19	10.34	0.77	5.00		0.00	0.00	5	7.884	11.004	13.785	62.77	87.61	109.75
	A-20	1.40	0.67			<u> </u>	<u> </u>	<u></u>			<u></u>			
20	PT.16a + PT.18a +	63.91	0.67	24.00	CARRYOVER	0.00	1.00	25	4.059	5.597	6.934	173.79	239.68	296.90
*	DA-20			<u> </u>	FROM PT. 18a	I	<u> </u>	<u> </u>			1		11.00	33.30
	A-21	0.59	0.77				<u> </u>	<u></u>			<u></u>	<u></u>		
21	PT.19 + DA-21	10.93	0.77	5.00	CARRYOVER	0.00	0.00	5	7.884	11.004	13.785	66.35	92.61	116.02
	A-22	0.85	0.77	<u>.</u>	FROM PT. 19	<u> </u>	·			·	+		<u> </u>	
	A-22 PT.20 + PT.21 +				CARRYOVER		 		 	 	 	 	 	
22	P1.20 + P1.21 + DA-22	75.69	0.69	25.00	FROM PT. 20	0.00	1.00	26	3.979	5.487	6.795	206.48	284.70	352.61
23	A-23	6.03	0.96	14.00		12.00	0.00	26	3.979	5.487	6.795	23.03	31.76	39.34
24a	A-24a	14.26	0.77	14.00		5.00	3.00	22	4.329	5.975	7.408	47.53	65.61	81.35
24b	A-24b	1.89	0.77	10.00		3.00	0.00	13	5.662	7.888	9.854	8.24	11.48	14.34
25	A-25	4.66	0.41	14.00		7.00	1.00	22	4.329	5.975	7.408	8.27	11.42	14.15
26	A-26	1.84	0.41	14.00		3.00	0.00	17	4.941	6.838	8.501	3.73	5.16	6.41
27	A-27	5.53	0.67	14.00		6.00	0.00	20	4.543	6.277	7.789	16.83	23.26	28.86
28	A-28	10.38	0.67	14.00		4.00	3.00	21	4.432	6.120	7.591	30.82	42.56	52.79
>					<u> </u>			<u> </u>		J., 120		33.02	50	<u> </u>
_	A-29	0.96	0.41			_		_						
29	PT.27 + A-29	6.49	0.63	20.00	CARRYOVER FROM PT. 27	0.00	2.00	22	4.329	5.975	7.408	17.74	24.49	30.36
	A 00	0.5:	2 2-				†		 					
	A-30	3.04	0.67											_
30	PT.28 + PT.29 + A-30	19.91	0.66	22.00		0.00	2.00	24	4.143	5.715	7.081	54.23	74.81	92.69
		^ ·-	2		 		†		 	 	 			
	A-31	0.47	0.41	_										
31	PT.OS5 + A-31	1.49	0.59	14.00	CARRYOVER FROM PT. 9	1.00	0.00	15	5.280	7.320	9.115	4.63	6.41	7.99
	A-32	12.55	0.77		FROW P1.9		 				 	-	 	
			 		CARRYOVER									
32	PT.30 + PT.31+ A-32	33.95	0.70	24.00	FROM PT. 30	0.00	1.00	25	4.059	5.597	6.934	95.91	132.26	163.84
OS-1	A-OS1	4.79	0.67	17.00		5.00	0.00	22	4.329	5.975	7.408	13.89	19.18	23.78
OS-2A	A-OS2A	4.81	0.67	9.00		3.00	0.00	12	5.864	8.186	10.238	18.90	26.38	32.99
OS-2B	A-OS2B	2.43	0.67	14.00		2.00	0.00	16	5.101	7.066	8.791	8.31	11.50	14.31
OS-2C	A-OS2C	8.95	0.67	10.00		7.00	0.00	17	4.941	6.838	8.501	29.63	41.01	50.98
	A-OS3	0.25	0.67	14.00		1.00	0.00	15	5.280	7.320	9.115	0.88	1.23	1.53
OS-3	_ !			1	1	4.00	0.00	 	 	•	-	1	4.40	5.56
OS-3	A-OS4	0.91	0.67	14.00		1.00	0.00	15	5.280	7.320	9.115	3.22	4.46	0.50
	A-OS4 A-OS5	0.91	0.67	14.00 14.00		1.00	0.00	15 15	5.280	7.320	9.115 9.115	3.22 3.61	5.00	6.23



Engineering & Design


www.colliersengineering.com

Copyright © 2023. Colliers Engineering & Design All Rights Reserved. This drawing and all the information contained herein is authorized for use only by the party for whom the services were contracted or to whom it is certified. This drawing may not be copied, reused, disclosed, distributed or relied upon for any other purpose without the express written consent of Colliers Engineering & Design.

Formerly Known as



FOR STATE SPECIFIC DIRECT PHONE NUMBERS
VISIT: WWW.CALL811.COM



PRELIMINARY

FOR
MORGAN HEIGHTS
PHASE 2B
PLAT# 23-11800386

SAN ANTONIO BEXAR COUNTY TEXAS

Collices

Engineering
& Design

SAN ANTONIO (KFW)

3421 Paesanos
Parkway
San Antonio, TX 78231
Phone: 210.979.8444


COLLIERS ENGINEERING & DESIGN, INC.
TBPE Firm#: F-14909
TBPLS Firm#: 10194550

CALE: DATE: DRAWN BY:
AS SHOWN 07/20/2023 SD

ROJECT NUMBER: DRAWING NAME:

MASTER DRAINAGE PLAN
(2 OF 2)

2.1





GENERAL NOTES: COUNTY FINISHED FLOOR ELEVATION - RELATIVE TO FLOOD PLAIN: BEXAR COUNTY R.O.W. NOTE 1. ELEVATION SHOWN ON FOUNDATION IS FOR FINISHED FLOOR. FINISHED FLOOR ELEVATIONS FOR STRUCTURES ON LOTS CONTAINING 2. CONTRACTOR SHALL PROVIDE OWNER ALL NECESSARY DENSITY TESTS FOR FILL LOTS AS A BEXAR COUNTY PERMIT SETBACK SETBACK FLOOD PLAIN OR ADJACENT TO THE FLOOD PLAIN SHALL BE IN REQUIRED BY HUD SPECIFICATIONS. MUST BE OBTAINED BEFORE COMPLIANCE WITH THE FLOOD PLAIN REGULATION IN EFFECT AT THE 3. HOME BUILDER SHALL REFER TO THE APPROVED SUBDIVISION PLAT TO CONFIRM ALL BUILDING **WORKING IN BEXAR COUNTY** TIME OF CONSTRUCTION. CONTACT BEXAR COUNTY PUBLIC WORKS FOR SETBACKS PRIOR TO ANY FOUNDATION WORK. R.O.W. 4. AS SOON AS PRACTICAL HOME BUILDER SHALL ESTABLISH VEGETATION (HYDROMULCH. MORE INFORMATION. (F-142(a) & (b)(1)) SEEDING, SODDING, ETC...) TO PREVENT EROSION FROM OCCURRING. 5. CONTRACTOR SHALL CONTACT ENGINEER REGARDING ANY QUESTIONS ON THE INTENT OF 6. POSITIVE DRAINAGE SHALL BE MAINTAINED ON ALL SURFACE AREAS WITHIN THE SCOPE OF THIS PROJECT. DRAINAGE SHALL BE DIRECTED AWAY FROM ALL BUILDING FOUNDATIONS AND TOWARDS THE PROPER DRAINAGE EASEMENT OR STREET RIGHT OF WAY ACCORDING TO THE FOUNDATION F.F. MATCH LINE "B" SEE THIS SHEET MASTER DRAINAGE PLAN FOR THE PROJECT. CONTRACTOR SHOULD TAKE PRECAUTIONS NOT FOUNDATION F.F. TO ALLOW PONDING OF WATER. 7. ALL ELEVATIONS AND CONTOURS SHOWN ON THIS GRADING PLAN REFLECT FINISHED GRADES. THE THICKNESS OF PAVEMENT, CURBS, AND SIDEWALKS MUST BE SUBTRACTED TO OBTAIN SUBGRADE ELEVATIONS. 8. GRADING PLAN IS INTENDED FOR USE IN LOT GRADING ONLY. CONTRACTOR SHOULD REFER WONDERLAND WAY (VARIABLE WIDTH R.O.W.) TO CONSTRUCTION DRAWINGS FOR ALL OTHER GRADES, INCLUDING, BUT NOT LIMITED TO, CHANNELS, ROADS, AND DETENTION PONDS. 9. CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE ALL SWALES. ormerly Known as TYPICAL SIDE YARD GRADING N.T.S. LOCATION MAP MATCH LINE "A" SEE SHEET 3.0 SCALE : 1" = 50' Linear unit of measure: US Survey Foot (1 ft = 1200/3937 m) LEGEND E, G, T, & TV. E. = GAS, ELECTRIC, TELEPHONE, CABLE T.V. EASEMENT = FLOW ARROW = LOT GRADE TYPE OFF-LOT 55' RADIUS ELECTRIC, GAS, TELEPHONE, CABLE TV, WATER, SANITARY SEWER, DRAINAGE & TURNAROUND EASEMENT (ENTIRE EASEMENT TO EXPIRE UPON INCORPORATION INTO PLATTED PUBLIC STREET R.O.W.) TYPE 'A' LOT GRADING

WONDERLAND WA (VARIABLE WIDTH R.O.W

MATCH LINE "B" SEE THIS SHEET

VISION EASEMENT BRANDY GLEN BRANDY GLEN (50' R.O.W.) 10' E.G.T.TV. TYPE 'B' LOT GRADING TAMARON SUBDIVISION UNIT 1 (VOLUME 9533, PAGE 126 D.P.R.)





TYPE 'C' LOT GRADING


Colliers Engineering & Design

www.colliersengineering.com ppyright © 2024. Colliers Engineering & Design All Rights Reserved. This drawin

whom the services were contracted or to whom it is certified. This drawing may be copied, reused, disclosed, distributed or relied upon for any other purpo without the express written consent of Colliers Engineering & Design.

PROTECT YOURSELF
ALL STATES REQUIRE NOTIFICATION OF
EXCAVATORS, DESIGNERS, OR ANY PERSO
PREPARING TO DISTURB THE EARTH'S
SURFACE ANYWHERE IN ANY STATE

FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM



PRELIMINARY

MORGAN HEIGHTS PHASE 2B PLAT# 23-11800386

> SAN ANTONIO BEXAR COUNTY **TEXAS**

& Design

SAN ANTONIO (KFW) 3421 Paesanos San Antonio, TX 78231 Phone: 210.979.8444

OVERALL GRADING PLAN

TRENCH EXCAVATION SAFETY PROTECTION

WORKING IN AND AROUND TRENCH EXCAVATION.

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE THE CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S

AND SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S

AND SPECIFICALLY OF THE VEHICLE OF THE V INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS

OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF


ANY OLDER DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY


OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT

LEGEND


— — —735— = EXISTING CONTOUR


= PROPOSED CONTOUR = FLOW ARROW





BAFFLE BLOCK CALCULATIONS






FACE OF CURB -


BEXAR COUNTY R.O.W. NOTE:


COUNTY R.O.W.


A BEXAR COUNTY PERMIT MUST BE

OBTAINED BEFORE WORKING IN BEXAR









PRELIMINARY

FOR **MORGAN HEIGHTS** PHASE 2B PLAT# 23-11800386

> SAN ANTONIO BEXAR COUNTY **TEXAS**


Colliers Engineering & Design


3421 Paesanos Parkway San Antonio, TX 78231 Phone: 210.979.8444 COLLIERS ENGINEERING & DESIGN, INC TBPE Firm#: F-14909 TBPLS Firm#: 10194550


SAN ANTONIO (KFW)


AS SHOWN DP2054004 - DRAIN A


DRAIN "A" PLAN & PROFILE

















Colliers

Engineering & Design

www.colliersengineering.com

Copyright © 2023. Colliers Engineering & Design All Rights Reserved. This draw and all the information contained herein is authorized for use only by the party whom the services were contracted or to whom it is certified. This drawing may be copied, reused, disclosed, distributed or relied upon for any other purp without the express written consent of Colliers Engineering & Design.

Formerly Known as

PROTECT YOURSELF

ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE

PROTECT PROCESS OF THE STATE SPECIFIC DIRECT PHONE NUMBERS.

FOR STATE SPECIFIC DIRECT PHONE NUMBERS
VISIT: WWW.CALL811.COM

JEFFREY W. MARTIN

139094

CENSE
ONAL

12/19/23

PRELIMINARY

FOR
MORGAN HEIGHTS
PHASE 2B
PLAT# 23-11800386

SAN ANTONIO BEXAR COUNTY TEXAS

Colliers

Engineering
& Design

SAN ANTONIO (KFW)

3421 Paesanos
Parkway
San Antonio, TX 78231
Phone: 210.979.8444
COLLIERS ENGINEERING & DESIGN, INC

Phone: 210.979.8444


COLLIERS ENGINEERING & DESIGN, IN TBPE Firm#: F-14909
TBPLS Firm#: 10194550


CALE: DATE: DRAWN BY: CHECKED
AS SHOWN 07/20/2023 SD SC


ROJECT NUMBER: DRAWING NAME:
205-40-04 DRDT2054004

SBC DRAIN DETAILS


NUMBER:









TRENCH EXCAVATION SAFETY PROTECTION









= SIDEWALK TO BE CONSTRUCTED

OF HOME CONSTRUCTION

= PROPOSED DRIVEWAY LOCATION

BY DEVELOPER

= SIDEWALK TO BE BUILT AT THE TIME

R.O.W. = RIGHT OF WAY

E.G.T.TV.E. = ELECTRIC, GAS, TELEPHONE &

E.G.T.TV.E. = ELECTRIC, GAS, TELEPHONE

CABLE EASEMENT

& CABLE EASEMENT

V.N.A.E. = VEHICULAR NON-ACCESS EASEMENT

WHEELCHAIR RAMPS

S.D.W.C.R. = SINGLE DIRECTIONAL WHEEL CHAIR RAMP

SEE SHEET 5.6

SEE SHEET 5.6

BEXAR COUNTY R.O.W. NOTE

A BEXAR COUNTY PERMIT MUST

BE OBTAINED BEFORE WORKING IN BEXAR COUNTY R.O.W.

Engineering & Design

www.colliersengineering.com

opyright © 2024. Colliers Engineering & Design All Rights Reserved. This drawin whom the services were contracted or to whom it is certified. This drawing may i

be copied, reused, disclosed, distributed or relied upon for any other purpo without the express written consent of Colliers Engineering & Design.

Formerly Known as

ALL STATES REQUIRE NOTIFICATION C EXCAVATORS, DESIGNERS, OR ANY PERS PREPARING TO DISTURB THE EARTH! SURFACE ANYWHERE IN ANY STATE

FOR STATE SPECIFIC DIRECT PHONE NUMBERS

VISIT: WWW.CALL811.COM



PRELIMINARY

MORGAN HEIGHTS PHASE 2B PLAT# 23-11800386

> SAN ANTONIO BEXAR COUNTY **TEXAS**

Engineering & Design


3421 Paesanos San Antonio, TX 78231 Phone: 210.979.8444 COLLIERS ENGINEERING & DESIGN, IN TBPE Firm#: F-14909 TBPLS Firm#: 10194550


SAN ANTONIO (KFW)


AS SHOWN

TPP2054004 WHIRLING PLACE &

> **CLARNELLA GRVS** PLAN & PROFILE








TYPICAL RESIDENTIAL DRIVEWAY SECTION

WHERE PROPERTY IS LOWER THAN STREET & SIDEWALK IS ABUTTING CURB ITEM 503.1



TYPICAL COMMERCIAL DRIVEWAY SECTION

WITH SIDEWALK ABUTTING CURB

ITEM 503.2

#3 BARS 12" O.C. BOTH WAYS

W/ D5 WELDED WIRE FLAT

(ITEM 301) OR 6" x 6" W/ D5 x

CONCRETE DRIVEWAY NOTES

1. DRIVEWAY PENETRATION REFERS TO A PORTION OF THE DRIVEWAY THAT MAY BE NECESSARY TO RECONSTRUCT WITHIN PRIVATE PROPERTY TO COMPLY WITH A MAXIMUM DRIVEWAY SLOPE. THIS PORTION OF THE DRIVEWAY SHALL BE PAID FOR UNDER THE FOLLOWING ITEMS AS MAY APPLY: A.) CONCRETE DRIVEWAY PAID FOR UNDER ITEM NO. 503.1 OR 503.2.

2" MINIMUM FLEXIBLE BASE

MATERIAL, CEMENT TREATED BASE


OR ASPHALTIC CONCRETE BASE

(2) THE ALGEBRAIC DIFFERENCE OF G1 & G2 SHALL BE 14% OR LESS

- B.) ASPHALTIC CONCRETE DRIVEWAY PAID FOR UNDER ITEM NO. 503.4 AND SHALL INCLUDE A MINIMUM OF 1" ASPHALT TYPE 'D' & 6" FLEXIBLE BASE
- C.) GRAVEL DRIVEWAY PAID FOR UNDER ITEM NO. 503.5 AND SHALL INCLUDE A MINIMUM OF 6" FLEXIBLE BASE
- 2. 7" MINIMUM HEIGHT WILL NOT NECESSARILY OCCUR AT THE PROPERTY LINE. IT MAY OCCUR WITHIN THE RIGHT OF WAY OR WITHIN THE DRIVEWAY PENETRATION ON PRIVATE PROPERTY.
- 3. THE PROPOSED DRIVEWAY SHOULD MATCH THE EXISTING WIDTH AT THE PROPERTY LINE BUT UNLESS AUTHORIZED BY THE CITY TRAFFIC ENGINEER, THE WIDTH SHALL BE WITHIN THE FOLLOWING VALUES:


TYPE	MINIMUM	MAXIMUM
RESIDENTIAL	10'	20'
COMMERCIAL - ONE WAY	12'	20'
COMMERCIAL - TWO WAY	24'	30'

- 4. FOR LOCAL TYPE "A" STREETS, SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 4' AND IF SEPARATED FROM THE CURB, THE SIDEWALK SHALL BE LOCATED A MINIMUM OF 3' FROM THE BACK OF CURB.
- 5. FOR OTHER THAN LOCAL TYPE "A" STREETS, THE SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 4' AND SEPARATED A MINIMUM OF 3' FROM THE BACK OF CURB OR, AS AN OPTION, THE SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 6' WHEN LOCATED AT THE BACK OF CURB.
- 6. DUMMY JOINTS PARALLEL TO THE CURB SHALL BE PLACED WHERE THE SIDEWALK MEETS THE DRIVEWAY. DUMMY JOINTS PERPENDICULAR TO THE CURB, AND WITHIN THE BOUNDARIES OF THE PARALLEL DUMMY JOINTS, SHALL BE PLACED AT INTERVALS EQUAL TO THE WIDTH OF THE SIDEWALK.
- 7. A MINIMUM OF TWO ROUND AND SMOOTH DOWEL BARS 3 /8" IN DIAMETER AND 18" IN LENGTH SHALL BE SPACED 18" APART AT EACH EXPANSION JOINT.
- 8. SIDEWALK RAMP LENGTHS SHALL BE OF SUFFICIENT LENGTH TO MAINTAIN 8.33% (1:12) MAXIMUM SLOPE. WHERE SIDEWALKS CROSS DRIVEWAYS, SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2%.
- 9. SIDEWALK RAMP SURFACE SHALL BE BRUSH FINISHED.



TYPICAL RESIDENTIAL DRIVEWAY SECTION


WITH SIDEWALK SEPARATED FROM CURB ITEM 503.1



② THE ALGEBRAIC DIFFERENCE OF G1 & G2 SHALL BE 14% OR LESS

TYPICAL RESIDENTIAL DRIVEWAY SECTION

WHERE PROPERTY IS LOWER THAN STREET & SIDEWALK IS SEPARATED FROM CURB



TYPICAL COMMERCIAL DRIVEWAY SECTION WITH SIDEWALK SEPARATED FROM CURB

ITEM 503.2


_ 3 / 4" CHAMFER 3 / 4" CHAMFER 6" MINIMUM - 12" MAXIMUM-ASPHALT OR GRAVEL DRIVEWAY --- 2 - #4 BARS CONTINUOUS 2 - #4 BARS CONTINUOUS 12" MINIMUM - 18" MAXIMUM BELOW FINISHED GRADE 12"

1. COST OF REINFORCEMENT TO BE INCLUDED IN UNIT COST OF ITEM 307.1. 2. CONCRETE RETAINING WALL COMBINATION TYPE SHALL BE USED FOR

DRIVEWAY - CONCRETE RETAINING WALL


ON COMPACTED SUBGRADE ITEM 307.1

CONCRETE DRIVEWAYS.




② RESIDENTIAL : 2' MAXIMUM; COMMERCIAL: SEE PLAN VIEW

CURB PROFILE AT DRIVEWAY WITH SIDEWALK ABUTTING CURB



TYPICAL DRIVEWAY PLAN VIEW


WITH SIDEWALK ABUTTING CURB



② RESIDENTIAL : 2' MAXIMUM; COMMERCIAL: SEE PLAN VIEW

CURB PROFILE AT DRIVEWAY

WITH SIDEWALK SEPARATED FROM CURB



② 45 FOR COMMERCIAL DRIVEWAY

TYPICAL DRIVEWAY PLAN VIEW

WITH SIDEWALK SEPARATED FROM CURB

MAY 2009

CITY OF SAN ANTONIO CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

CONCRETE DRIVEWAY STANDARDS

CHKD. BY: R.S. HOSSEINI, P.E. SHEET NO.: OF

_% SUBMITTAL | PROJECT NO.:

DRWN. BY: V. VASQUEZ DSGN. BY:

Colliers Engineering & Design

3421 Paesanos San Antonio, TX 78231 Phone: 210.979.8444 DLLIERS ENGINEERING & DESIGN, IN TBPE Firm#: F-14909 TBPLS Firm#: 10194550

SAN ANTONIO (KFW)

Colliers

Engineering & Design

www.colliersengineering.com

pyright © 2023. Colliers Engineering & Design All Rights Reserved. This drav

hom the services were contracted or to whom it is certified. This drawing may i

e copied, reused, disclosed, distributed or relied upon for any other pur

without the express written consent of Colliers Engineering & Design.

FOR STATE SPECIFIC DIRECT PHONE NUMBERS

VISIT: WWW.CALL811.COM

JEFFREY W. MARTI

139094

PRELIMINARY

MORGAN HEIGHTS

PHASE 2B

PLAT# 23-11800386

SAN ANTONIO

BEXAR COUNTY


TEXAS


PROTECT YOURSELF ALL STATES REQUIRE NOTIFICATION C EXCAVATORS, DESIGNERS, OR ANY PERS PREPARING TO DISTURB THE EARTH! SURFACE ANYWHERE IN ANY STATE


Formerly Known as


AS SHOWN SD TDT2054004 205-40-04


CONCRETE DRIVEWAY DETAILS















MORGAN HEIGHTS PHASE 2B PLAT# 23-11800386


> SAN ANTONIO **BEXAR COUNTY TEXAS**


		SAN ANTONIO (KFW)					
Colli	ers		3421 Paesanos Parkway				
			San Antonio, 1	TX 78231			
Enginee & Des		Phone: 210.979.8444 COLLIERS ENGINEERING & DESIGN, IN TBPE Firm#: F-14909 TBPLS Firm#: 10194550					
SCALE:	DATE:		DRAWN BY:	CHECKED B			
AS SHOWN	07/20/2023		SD	SC			
DDOLECT NUMBER	.D. [DAMA	IC NAME.	•			

STDT2054004 205-40-04

TXDOT PED-18 DETAILS







opyright © 2023. Colliers Engineering & Design All Rights Reserved. This drawin




FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM


MORGAN HEIGHTS


SAN ANTONIO (KFW) 3421 Paesanos San Antonio, TX 78231 Phone: 210.979.8444 COLLIERS ENGINEERING & DESIGN, INC. TBPE Firm#: F-14909 TBPLS Firm#: 10194550


DETAILS (1 OF 2)

5.10









PRELIMINARY

12/19/23

MORGAN HEIGHTS PHASE 2B PLAT# 23-11800386

> SAN ANTONIO **BEXAR COUNTY TEXAS**

TBPE Firm#: F-14909


	SAN ANTONIO (KFW)
Colliers	3421 Paesanos
	Parkway
	San Antonio, TX 78231
Engineering	Phone: 210.979.8444
& Design	COLLIERS ENGINEERING & DESIGN, IN TBPE Firm#: F-14909

TBPLS Firm#: 10194550 AS SHOWN SD SDT2054004 205-40-04

PAVEMENT MARKING


DETAILS (2 OF 2)


5.11



SM RD SGN ASSM TY XXXXX(X)SB(X-XXXX)

IST CUUNTY







Engineering & Design

www.colliersengineering.com

pyright © 2023. Colliers Engineering & Design All Rights Reserved. This draw hom the services were contracted or to whom it is certified. This drawing may e copied, reused, disclosed, distributed or relied upon for any other purp without the express written consent of Colliers Engineering & Design.

Formerly Known as

ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH! SURFACE ANYWHERE IN ANY STATE

FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM



PRELIMINARY

FOR **MORGAN HEIGHTS** PHASE 2B PLAT# 23-11800386

> SAN ANTONIO **BEXAR COUNTY TEXAS**

> > 3421 Paesanos

Parkway


SAN ANTONIO (KFW) **Colliers** San Antonio, TX 78231 Engineering


Phone: 210.979.8444 COLLIERS ENGINEERING & DESIGN, IN & Design TBPE Firm#: F-14909 TBPLS Firm#: 10194550

AS SHOWN SD WING NAME: SDT2054004 205-40-04

SIGN MOUNTING DETAILS (1 OF 2)

5.12








Engineering & Design

www.colliersengineering.com


Copyright © 2023. Colliers Engineering & Design All Rights Reserved. This draw and all the information contained herein is authorized for use only by the party whom the services were contracted or to whom it is certified. This drawing may use copied, reused, disclosed, distributed or relied upon for any other purpowithout the express written consent of Colliers Engineering & Design.

ormerly Known as



ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE

FOR STATE SPECIFIC DIRECT PHONE NUMBERS
VISIT: WWW.CALL811.COM





PRELIMINARY

FOR MORGAN HEIGHTS PHASE 2B

PLAT# 23-11800386

SAN ANTONIO BEXAR COUNTY TEXAS

ColliersEngineering

& Design

SAN ANTONIO (KFW)

3421 Paesanos
Parkway
San Antonio, TX 78231
Phone: 210.979.8444

COLLIERS ENGINEERING & DESIGN, ING
TBPE Firm#: F-14909
TBPLS Firm#: 10194550


CALE: DATE: DRAWN BY: CHAPTER OF THE PROJECT NUMBER: DRAWING NAME: 205-40-04 TSDT2054004


SIGN MOUNTING DETAILS

(2 OF 2)

SHEET NUMBER:

5.13





GENERAL INFORMATION

SAWS STANDARD GENERAL CONSTRUCTION NOTES
ASSOCIATED WITH 2021 SAWS STANDARD SPECS
Updated December 14, 2021

General Section

- All materials and construction procedures within the scope of this contract shall be approved by the San Antonio Water System (SAWS) and comply with the Plans, Specifications, General Conditions and with the following as applicable:
- A. Current Texas Commission on Environmental Quality (TCEQ) "Design Criteria for Domestic Wastewater System", Texas Administrative Code (TAC) Title 30 Part 1 Chapter 217 and "Public Drinking Water", TAC
- B. Current TXDOT "Standard Specifications for Construction of Highways, Streets and Drainage".
- C. Current "San Antonio Water System Standard Specifications for Water and Sanitary Sewer Construction".
- D. Current City of San Antonio "Standard Specifications for Public Works Construction".

 E. Current City of San Antonio "Utility Excavation Criteria Manual" (UECM).
- 2. The contractor shall not proceed with any pipe installation work until they obtain a copy of the approved Counter Permit or General Construction Permit (GCP) from the consultant and has been notified by SAWS Construction Inspection Division to proceed with the work and has arranged a meeting with the inspector and consultant for the work requirements. Work completed by the contractor without an approved Counter Permit and/or a GCP will be subject to removal and replacement at the expense of the contractors and/or the developer.
- 3. The Contractor shall obtain the SAWS Standard Details from the SAWS website, http://www.saws.org/business_center/specs. Unless otherwise noted within the design plans.
- 4. The Contractor is to make arrangements with the SAWS Construction Inspection Division at (210) 233-2973, on notification procedures that will be used to notify affected home residents and/or property owners 48 hours prior to beginning any work.
- 5. Location and depth of existing utilities and service laterals shown on the plans are understood to be approximate. Actual locations and depths must be field verified by the Contractor at least 1 week prior to construction. It shall be the Contractor's responsibility to locate utility service lines as required for construction and to protect them during construction at no cost to SAWS.
- 6. The Contractor shall verify the exact location of underground utilities and drainage structures at least 1-2 weeks prior to construction whether shown on plans or not. Please allow up to 7 business days for locates requesting pipe location markers on SAWS facilities. The following contact information are supplied for verification purposes: SAWS Utility Locates: http://www.saws.org/Service/Locates
 - COSA Drainage (210) 207-0724 or (210) 207-6026 COSA Traffic Signal Operations (210) 206-8480 COSA Traffic Signal Damages (210) 207-3951 Texas State Wide One Call Locator 1-800-545-6005 or 811
- 7. The Contractor shall be responsible for restoring existing fences, curbs, streets, driveways, sidewalks, landscaping and structures to its original or better condition if damages are made as a result of the project's construction.
- All work in Texas Department of Transportation (TxDOT) and/or Bexar County right-of-way shall be done in accordance with respective construction specifications and permit requirements
- 9. The Contractor shall comply with City of San Antonio or other governing municipality's tree ordinances when excavating near trees.
- The Contractor shall not place any waste materials in the 100-year Flood Plain without first obtaining an approved Flood Plain Permit.
- 11. Holiday Work: Contractors will not be allowed to perform SAWS work on SAWS recognized holidays. Request should be sent to constworkreq@saws.org. Weekend Work: Contractors are required to notify the SAWS Inspection Construction Department 48 hours in advance to request weekend work. Request should be sent to constworkreq@saws.org. Any and all SAWS utility work installed without holiday/weekend approval will be subject to be uncovered for proper inspection.
- 12. Compaction note (Item 804): The contractor shall be responsible for meeting the compaction requirements on all trench backfill and for paying for the tests performed by a third party. Compaction tests will be done at one location point randomly selected, or as indicated by the SAWS Inspector and/or the test administrator, per each 12-inch loose lift per 400 linear feet at a minimum. This project will not be accepted and finalized by SAWS without this requirement being met and verified by providing all necessary documented test results.
- 13. A copy of all testing reports shall be forwarded to SAWS Construction Inspection Division.

Sewer Note

- 1. The Contractor is responsible for ensuring that no Sanitary Sewer Overflow (SSO) occurs as a result of their work. All contractor personnel responsible for SSO prevention and control shall be trained on proper response. Should an SSO occur, the contractor shall:
- Identify the source of the SSO and notify SAWS Emergency Operations Center (EOC) immediately at (210) 233-2014. Provide the address of the spill and an estimated volume or flow.
- B. Attempt to eliminate the source of the SSO.C. Contain sewage from the SSO to the extent of preventing a possible contamination of
- waterways.

 D. Clean up spill site (return contained sewage to the collection system if possible) and properly dispose of contaminated soil/materials.
- E. Clean the affected sewer mains and remove any debris.
 F. Meet all post-SSO requirements as per the EPA Consent Decree, including line cleaning and televising the affected sewer mains (at SAWS direction) within 24 hours. Should the Contractor fail to address an SSO immediately and to SAWS satisfaction, they will be responsible for all costs incurred by SAWS, including any fines from EPA, TCEQ and/or any other Federal, State or Local Agencies. No separate measurement or payment shall be made for this work. All work shall be done according to guidelines set by the TCEQ and SAWS.
- 2. If bypass pumping is required, the Contractor shall perform such work in accordance with SAWS Standard Specification for Water and Sanitary Sewer Construction, Item No. 864, "Bypass Pumping".
- 3. Prior to tie-ins, any shutdowns of existing force mains of any size must be coordinated with the SAWS Construction Inspection Division at (210) 233-2973 at least one week in advance of the shutdown. The Contractor must also provide a sequence of work as related to the tie-ins; this is at no additional cost to SAWS or the project and it is the responsibility of the Contractor to sequence the work accordingly.
- D2241, TAC 217.53 and TCEQ 290.44(e)(4)(B). Contractor shall center a 20' joint of 160 psi pressure rated PVC at the proposed water crossing.

 5. FLEVATIONS POSTED FOR TOP OF MANHOLES ARE FOR REFERENCE ONLY: It shall

4. Sewer pipe where water line crosses shall be 160 psi and meet the requirements of ASTM

- ELEVATIONS POSTED FOR TOP OF MANHOLES ARE FOR REFERENCE ONLY: It shall be the responsibility of the Contractor to make allowances and adjustments for top of manholes to match the finished grade of the project's improvements. (NSPI)
- 6. Spills, Overflows, or Discharges of Wastewater: All spills, overflows, or discharges of wastewater, recycled water, petroleum products, or chemicals must be reported immediately to the SAWS Inspector assigned to the Counter Permit or General Construction Permit (GCP). This requirement applies to every spill, overflow, or discharge regardless of size.
- 7. Manhole and all pipe testing (including the TV inspection) must be performed and passed prior to Final Field Acceptance by SAWS Construction Inspection Division, as per the SAWS Specifications For Water and Sanitary Sewer Construction.
- 8. All PVC pipe over 14 feet of cover shall be extra strength with minimum pipe stiffness of 115

MORGAN HEIGHTS PHASE 2B

BEXAR COUNTY, TEXAS SANITARY SEWER IMPROVEMENTS




LOCATION MAP

N.T.S.

OWNER/DEVELOPER
TALLEY EXTENSION REVITALIZATION INITIATIVE, LLC.
5210 THOUSAND OAKS, STE. 1318
SAN ANTONIO, TEXAS 78233

INDEX

DESCRIPTION	SHEET NO
SANITARY SEWER COVER SHEET	6.0
OVERALL SANITARY SEWER PLAN	6.
OVERALL SANITARY SEWER PLAN	6.2
LINE "A" & LINE "D" PLAN AND PROFILE	6.3
LINE "B" PLAN AND PROFILE	6.4
LINE "C" PLAN AND PROFILE	6.5



Engineering


& Design

www.colliersengineering.com

opyright © 2023. Colliers Engineering & Design All Rights Reserved. This drav

whom the services were contracted or to whom it is certified. This drawing may be copied, reused, disclosed, distributed or relied upon for any other purp

without the express written consent of Colliers Engineering & Design.



PRELIMINARY

FOR
MORGAN HEIGHTS
PHASE 2B
PLAT# 23-11800386

SAN ANTONIO BEXAR COUNTY TEXAS

> SAN ANTONIO (KFW) 3421 Paesanos

San Antonio, TX 78231

ColliersEngineering & Design

SEWER - FAR WEST SEWERSHED - MEDIO CREEK W.R.C.

STATE: TEXAS

SAWS JOB#: 23-1644

TOTAL LINEAR FOOTAGE OF PIPE: 2,410 LF OF 8" SDR 26 PLAT NO.: 23-11800386

TOTAL ACREAGE: 14.10 ACRES

TOTAL EDU'S: 72

DEVELOPER'S NAME: TALLEY EXTENSION REVITALIZATION INITIATIVE, LLC

DEVELOPER'S ADDRESS: 1202 W. BITTERS RD., BLD 1, SUITE 1200

CITY: SAN ANTONIO

PHONE#: (210) 490-1798

NUMBER OF LOTS: 72

SAWS BLOCK MAP#: 064600

pineering Phone: 210.979.8444


Design COLLIERS ENGINEERING & DESIGN, II
TBPE Firm#: F-14909
TBPLS Firm#: 10194550

CALE: DATE: DRAWN BY: CHECKED B
AS SHOWN 07/20/2023 SD SC

ROJECT NUMBER: DRAWING NAME:
205-40-04 CVOS2054004

SANITARY SEWER
COVER SHEET

6.0



RENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY

WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

- NOTE:

 1. SEWER PIPE WHERE WATER LINE CROSSES SHALL BE MEET THE REQUIREMENTS OF ASTM D2241. CONTRACTOR SHALL CENTER A 20 FOOT JOINT OF 160 P.S.I. PRESSURE RATED P.V.C. AT THE PROPOSED WATER CROSSING (NO SEPARATE PAY ITEM). REFERENCE SHEET 6.0, SANITARY SEWER GENERAL NOTES, S.A.W.S. CRITERIA FOR SEWER MAIN CONSTRUCTION IN THE VICINITY OF WATER MAINS.
- 2. SEE SHEET 6.1 FOR BENCHMARK INFORMATION. 3. PIPE TYPE DESIGNATIONS ARE SDR 26.
- 4. SEE THIS SHEET FOR TYPICAL SANITARY SEWER / WATER CROSSING DETAIL.
- 5. ALL MANHOLES SHALL HAVE CONCRETE RING ENCASEMENT AND A WATER TIGHT RING AND COVER. 6. ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL BE IN ACCORDANCE WITH THE SAN ANTONIO WATER SYSTEM (SAWS) STANDARD SPECIFICATIONS.

<u>COMPACTION NOTE:</u> THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEETING 98% COMPACTION ON ALL TRENCH BACKFILL

AND PAYING FOR THE TESTS TO BE PERFORMED BY A THIRD PARTY. COMPACTION TESTS WILL BE DONE AT ONE LOCATION POINT RANDOMLY SELECTED OR AS INDICATED BY THE SAWS INSPECTOR/TEST ADMINISTRATOR, PER EACH 12 INCH LOOSE LIFT PER 400 LINEAR FEET AT A MINIMUM. PERMITS AND/OR WILL NOT BE ACCEPTED AND FINALIZED BY SAWS WITHOUT THIS REQUIREMENT BEING MET AND VERIFIED BY PROVIDING ALL NECESSARY DOCUMENTED TEST RESULTS.

DRY UTILITY CONDUIT NOTE:

OFF-LOT 55' RADIUS ELECTRIC, GAS, TELEPHONE,

CABLE TV. WATER, SANITARY SEWER, DRAINAGE

& TURNAROUND EASEMENT (ENTIRE EASEMENT 🗸

TO EXPIRE UPON INCORPORATION INTO

PLATTED PUBLIC STREET R.O.W.)

CONDUIT LOCATIONS SHOWN ON PLAN ARE FOR GEOGRAPHICAL PURPOSES ONLY AND ARE APPROXIMATE. CONTRACTOR TO INSTALL PROPOSED CONDUITS IN ACCORDANCE WITH DRY UTILITY PURVEYOR'S SPECIFICATIONS. CONTRACTOR TO VERIFY THE CONDUIT LOCATIONS AND SIZES BASED ON THE DRY UTILITY PURVEYOR'S PLAN.

CAUTION!!:
THE CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING U BUT NOT LIMITED TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.

MANHOLE NOTE:

10' E.G.T.TV.E —

M.H. "C2"

10' E.G.T.TV.E

STA: 14+14.01 LINE D

BLOCK 5

M.H. "D5"

*C.B. 440*4

WATER CROSSING STA: 2+56.60 LINE "D" REF. WATER CROSSING

DETAIL THIS SHEET

LINE "D"

10' E.G.T.TV.L

BLOCK 1 C.B. 4404

TAMARON SUBDIVISION UNIT 1

(VOLUME 9533, PAGE 126 D.P.R.)

STA: 16+57.64 LINE D

150

-BRANDY GLEN

149

__1008 -

д М.Н. "D6"

END LINE D

STA: 6+95.95 LINE (

ALL MANHOLES MUST BE WATERTIGHT, WITH WATERTIGHT RINGS AND COVERS. THESE MANHOLES MUST BE VENTED PER SAWS DETAIL DD852-02.

MATCH LINE "A" SEE SHEET 6.1

10' E.G.T.TV.E ____

10' E.G.T.TV.E

STA: 10+75.95 LINE C

VARIABLE WIDTH CLEAR

BRANDY GLĘN 🛭

(50' R.O.W!)3+00

/ 180°0'0'

10' E.G.T.TV.E

BRANDY GLEN

(50' R.O.W.)

— — →E8"W— — -

¹ 10′ E,G.T.TV.E |

140

VISION EASEMENT

M.H. "C3"

END LINE C

143

STA: 12+77.32 LINE D


CONTRACTOR TO TIE-IN TO EXISTING MANHOLE

S.A.W.S. JOB# 22-1510

EXISTING MH


BEGIN LINE D

LOCATION MAP



LEGEND


PROPOSED WATER MAIN = ----8"W-----PROPOSED FIRE HYDRANT PROPOSED WATER VALVE PROPOSED SANITARY SEWER MAIN = -8"SS-----PROPOSED SANITARY SEWER MANHOLE = ----PROPOSED SANITARY SEWER LATERAL = ► → ω PROPOSED SANITARY SEWER LATERAL = WITH VERTICAL STACK ELECTRIC, GAS, TELE., & CABLE TV = E.G.T.TV.E. VEHICULAR NON-ACCESS EASEMENT = V.N.A.E. EXISTING WATER MAIN = — — —E.8"W— — — = EXISTING FIRE HYDRANT EXISTING WATER VALVE = 🖂 = *─E.8*"SS- <u></u> — EXISTING SANITARY SEWER MAIN



EXISTING STREETLIGHT (UG, 250 WATT) =


SEWER - FAR WEST SEWERSHED - MEDIO CREEK W.R.C.

DEVELOPER'S NAME: TALLEY EXTENSION REVITALIZATION INITIATIVE, LLC DEVELOPER'S ADDRESS: 1202 W. BITTERS RD., BLD 1, SUITE 1200 CITY: SAN ANTONIO ZIP: 78216 STATE: TEXAS TOTAL ACREAGE: 14.10 ACRES PHONE#: (210) 490-1798 SAWS BLOCK MAP#: 064600 TOTAL EDU'S: 72 TOTAL LINEAR FOOTAGE OF PIPE: 2,410 LF OF 8" SDR 26 PLAT NO.: 23-11800386 NUMBER OF LOTS: 72 SAWS JOB#: 23-1644



ormerly Known as PROTECT YOURSELF ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE

FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM



PRELIMINARY

MORGAN HEIGHTS PHASE 2B PLAT# 23-11800386

> SAN ANTONIO BEXAR COUNTY **TEXAS**


SAN ANTONIO (KFW) Engineering & Design


San Antonio, TX 78231 Phone: 210.979.8444 COLLIERS ENGINEERING & DESIGN, IN TBPE Firm#: F-14909 TBPLS Firm#: 10194550


3421 Paesanos Parkway

AS SHOWN S2054004 205-40-04 **OVERALL SANITARY SEWER**

PLAN







GENERAL INFORMATION

SAWS CONSTRUCTION NOTES COUNTER PERMIT AND GENERAL CONSTRUCTION PERMIT

- 1. All materials and construction procedures within the scope of this contract shall be approved by the San Antonio Water System (SAWS) and comply with the Plans, Specifications, General
- Conditions and with the following as applicable: A. Current Texas Commission on Environmental Quality (TCEQ) "Design Criteria for Domestic Wastewater System", Texas Administrative Code (TAC) Title 30 Part 1
- Chapter 217 and "Public Drinking Water", TAC Title 30 Part 1 Chapter 290. B. Current TXDOT "Standard Specifications for Construction of Highways, Streets
- C. Current "San Antonio Water System Standard Specifications for Water and Sanitary Sewer Construction".
- D. Current City of San Antonio "Standard Specifications for Public Works Construction"
- E. Current City of San Antonio "Utility Excavation Criteria Manual" (UECM). The contractor shall not proceed with any pipe installation work until they obtain a copy of the approved Counter Permit or General Construction Permit (GCP) from the consultant and has been notified by SAWS Construction Inspection Division to proceed with the work and has arranged a meeting with the inspector and consultant for the work requirements. Work completed by the contractor without an approved Counter Permit and/or a GCP will be subject to removal and replacement at the expense of
- the contractors and/or the developer. The Contractor shall obtain the SAWS Standard Details from the SAWS website,
- http://www.saws.org/business_center/specs. Unless otherwise noted within the design plans. 4. The Contractor is to make arrangements with the SAWS Construction Inspection Division at (210) 233-2973, on notification procedures that will be used to notify affected home residents
- and/or property owners 48 hours prior to beginning any work. 5. Location and depth of existing utilities and service laterals shown on the plans are understood to be approximate. Actual locations and depths must be field verified by the Contractor at least 1 week prior to
- construction and to protect them during construction at no cost to SAWS. 6. The Contractor shall verify the exact location of underground utilities and drainage structures at least 1-2 weeks prior to construction whether shown on plans or not. Please allow up to 7 business days for locates requesting pipe location markers on SAWS facilities. The following contact information are

construction. It shall be the Contractor's responsibility to locate utility service lines as required for

- SAWS Utility Locates: http://www.saws.org/Service/Locates
- COSA Drainage (210) 207-0724 or (210) 207-6026
- COSA Traffic Signal Operations (210) 206-8480 COSA Traffic Signal Damages (210) 207-3951 Texas State Wide One Call Locator 1-800-545-6005 or 811
- 7. The Contractor shall be responsible for restoring existing fences, curbs, streets, driveways, sidewalks, landscaping and structures to its original or better condition if damages are made as a result
- 8. All work in Texas Department of Transportation (TxDOT) and/or Bexar County right-of-way shall be done in accordance with respective construction specifications and permit requirements.
- 9. The Contractor shall comply with City of San Antonio or other governing municipality's tree
- ordinances when excavating near trees.
- 10. The Contractor shall not place any waste materials in the 100-year Flood Plain without first obtaining an approved Flood Plain Permit.
- 11. Holiday Work: Contractors will not be allowed to perform SAWS work on SAWS recognized holidays. Request should be sent to constworkreq@saws.org. Weekend Work: Contractors are required to notify the SAWS Inspection Construction Department 48 hours in advance to request weekend work. Request should be sent to constworkreq@saws.org. Any and all SAWS utility work installed without holiday/weekend approval will be subject to be uncovered
- for proper inspection. 12. Compaction note (Item 804): The contractor shall be responsible for meeting the compaction requirements on all trench backfill and for paying for the tests performed by a third party. Compaction tests will be done at one location point randomly selected, or as indicated by the SAWS Inspector and/or the test administrator, per each 12-inch loose lift per 400 linear feet at a minimum. This project will not be accepted and finalized by SAWS without this requirement being met and verified by providing all necessary documented test results.
- 13. A copy of all testing reports shall be forwarded to SAWS Construction Inspection Division.

- Prior to tie-ins, any shutdowns of existing mains of any size must be coordinated with the SAWS Construction Inspection Division at least one week in advance of the shutdown. The Contractor must also provide a sequence of work as related to the tie-ins; this is at no additional cost to SAWS or the project and it is the responsibility of the Contractor to sequence the work accordingly.
- For water mains 12" or higher: SAWS Emergency Operations Center (210) 233-2014 2. Asbestos Cement (AC) pipe, also known as transite pipe which is known to contain asbestos containing material (ACM), may be located within the project limits. Special waste management procedures and health and safety requirements will be applicable when removal and/or disturbance of this pipe occurs. Such work is to be made under Special Specification Item No. 3000, "Special Specification for Handling Asbestos Cement Pipe".
- Valve removal: Where the contractor is to abandon a water main, the control valve located on the abandoning branch will be removed and replaced with a cap/plug. (NSPI)
- 4. Suitable anchorage/thrust blocking or joint restraint shall be provided at all of the following main locations: dead ends, plugs, caps, tees, crosses, valves, and bends, in accordance with the Standard Drawings DD-839 Series and Item No. 839, in the SAWS Standard
- Specifications for Construction. 5. All valves shall read "open right"
- 985 feet where the static pressure will normally exceed 80 PSI. At all such locations where the ground level is below <u>985</u> feet, the Developer or Builder shall install at each lot, on the customer's side of the meter, an approved type pressure regulator in conformance with the Plumbing Code of the City of San Antonio. No dual services allowed for any lot(s) if *PRV is/are required for such lot(s), only single service connections shall be allowed. *Note: A pressure regulator is also known as a pressure reducing valve (PRV).
- Pipe Disinfection with Dry HTH for Projects less than 800 linear feet. (Item No. 847.3): Mains shall be disinfected with dry HTH where shown in the contract documents or as directed by the Inspector, and shall not exceed a total length of 800 feet. This method of disinfection will also be followed for main repairs. The Contractor shall utilize all appropriate safety measure to protect his personnel during disinfection operations
- **Backflow Prevention Devices:**
- All commercial backflow prevention devices must be approved by SAWS prior to installation
- Final connection to the existing water main shall not be made until the water main has been pressure tested, chlorinated, and SAWS has released the main for tie-in and use. 10. Division Valves: Division Valves shown on plans or not shown on plans but found in the field shall only be operated by SAWS Distribution and Collection staff and only with prior written approval of the SAWS Director of Production and Operations and proper coordination with all SAWS departments. Contractor shall provide written notification to the inspector a minimum of two weeks in advance to start the coordination process and will be informed by the Inspector when the division valve will be operated by the SAWS Distribution and Collection staff. The Division Valve can only be operated by SAWS Distribution and Collection staff member not the inspector or the contractor. Operation of a Division Valve without the express prior written approval of the SAWS Distribution and Collection staff will constitute a material breach of any written SAWS contract or permit in addition to subjecting the Contractor to liability for any and all fines, fees, or other damages, direct or consequential, that may arise from or be caused by the operation of the valve without prior written permission. Please be informed that the approval of the operation or opening or closing of a division valve can take several weeks for approval. Division Valves will also have a valve lid labeled Division Valve and a locking mechanism installed with a key. The lock and key mechanism will be paid for by the contractor but will be installed by SAWS Distribution and Collection staff.

VISION VALVES:. DIVISION VALVES SHOWN ON PLANS OR NOT SHOWN ON PLANS BUT FOUND IN THE FIELD SHALI NLY BE OPERATED BY SAWS DISTRIBUTION AND COLLECTION STAFF AND ONLY WITH PRIOR WRITTEN APPROVAL F THE SAWS DIRECTOR OF PRODUCTION AND OPERATIONS AND PROPER COORDINATION WITH ALL SAWS EPARTMENTS. CONTRACTOR SHALL PROVIDE WRITTEN NOTIFICATION TO THE INSPECTOR A MINIMUM OF TWO VEEKS IN ADVANCE TO START THE COORDINATION PROCESS AND WILL BE INFORMED BY THE INSPECTOR WHEN HE DIVISION VALVE WILL BE OPERATED BY THE SAWS DISTRIBUTION AND COLLECTION STAFF. THE DIVISION R THE CONTRACTOR. OPERATION OF A DIVISION VALVE WITHOUT THE EXPRESS PRIOR WRITTEN APPROVAL OF HE SAWS DISTRIBUTION AND COLLECTION STAFF WILL CONSTITUTE A MATERIAL BREACH OF ANY WRITTEN SAWS ONTRACT OR PERMIT IN ADDITION TO SUBJECTING THE CONTRACTOR TO LIABILITY FOR ANY AND ALL FINES, EES, OR OTHER DAMAGES, DIRECT OR CONSEQUENTIAL, THAT MAY ARISE FROM OR BE CAUSED BY THE PERATION OF THE VALVE WITHOUT PRIOR WRITTEN PERMISSION. PLEASE BE INFORMED THAT THE APPROVAL O E OPERATION OR OPENING OR CLOSING OF A DIVISION VALVE CAN TAKE SEVERAL WEEKS FOR APPROVAL. VISION VALVES WILL ALSO HAVE A VALVE LID LABELED DIVISION VALVE AND A LOCKING MECHANISM INSTALLED WITH A KEY. THE LOCK AND KEY MECHANISM WILL BE PAID FOR THE CONTRACTOR BUT WILL BE INSTALLED BY

MORGAN HEIGHTS PHASE 2B

BEXAR COUNTY, TEXAS WATER IMPROVEMENTS




LOCATION MAP

N.T.S.

OWNER/DEVELOPER TALLEY EXTENSION REVITALIZATION INITIATIVE, LLC. 5210 THOUSAND OAKS, STE. 1318 SAN ANTONIO, TEXAS 78233

INDEX

DESCRIPTION	SHEET NO.
WATER DISTRIBUTION COVER SHEET	7.0
WATER DISTRIBUTION PLAN	7.1
WATER DISTRIBUTION PLAN	7.2



Engineering

& Design

www.colliersengineering.com opyright © 2023. Colliers Engineering & Design All Rights Reserved. This drav

PRELIMINARY

MORGAN HEIGHTS PHASE 2B PLAT# 23-11800386

> SAN ANTONIO BEXAR COUNTY TEXAS

> > SAN ANTONIO (KFW) 3421 Paesanos

San Antonio, TX 78231 Phone: 210.979.8444


Engineering & Design

SAWS PRESSURE ZONE 8 SERVICE AREA: FAR WEST

DEVELOPER'S NAME: TALLEY EXTENSION REVITALIZATION INITIATIVE, LLC DEVELOPER'S ADDRESS: 1202 W. BITTERS RD., BLD 1, SUITE 1200 CITY: SAN ANTONIO TOTAL ACREAGE: 13.87 ACRES PHONE#: (210) 490-1798 TOTAL EDU'S: 72 SAWS BLOCK MAP#: 064600 TOTAL LINEAR FOOTAGE OF PIPE: 2,395 LF ~ 8" C-900 NUMBER OF LOTS: 72 SAWS JOB#: 23-1175

WATER DISTRIBUTION COVER SHEET

VOW2054004




RENCH EXCAVATION SAFETY PROTECTION

ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

ONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND

JOINT RESTRAINT NOTE:

CONTRACTOR SHALL INSTALL RETAINER GLANDS AT ALL FITTINGS AND PROVIDE JOINT RESTRAINING HARNESS OR FIELD LOCK GASKETS AT ALL JOINTS WITHIN THE LENGTH SHOWN. CONTRACTOR SHALL INSURE THAT ALL TEES. BENDS. VALVES. ETC. HAVE A MINIMUM OF 5 FT OF PIPE WITH NO JOINTS ON EACH SIDE OF THE FITTING. JOINT RESTRAINTS AND RETAINER GLANDS SHALL BE CALCULATED BY SAWS APPROVED PROGRAMS. THERE WILL BE NO SEPARATE PAY ITEM FOR RETAINER GLANDS AND OTHER JOINT RESTRAINING HARNESS AND GASKETS, BUT SHALL BE SUBSIDIARY TO THE UNIT COST PER LINEAL FOOT OF PIPE INSTALLED.



IN AN EFFORT TO MEET THE CITY OF SAN ANTONIO'S FIRE FLOW REQUIREMENTS FOR THE PROPOSED RESIDENTIAL DEVELOPMENT, THE PUBLIC WATER MAIN SYSTEM HAS BEEN DESIGNED FOR A MINIMUM FIRE FLOW DEMAND OF 1,500 GPM AT 25 PSI RESIDUAL PRESSURE. THE FIRE FLOW REQUIREMENTS FOR INDIVIDUAL STRUCTURES WILL BE REVIEWED DURING THE BUILDING PERMIT PROCESS IN ACCORDANCE WITH THE PROCEDURES SET FORTH BY THE CITY OF SAN ANTONIO DIRECTOR OF DEVELOPMENT SERVICES DEPARTMENT AND THE SAN ANTONIO FIRE DEPARTMENT FIRE MARSHAL.

PRESSURE REDUCING VALVE (PRV) NOTE.

CONTRACTOR TO VERIFY THAT NO PORTION OF THE TRACT IS BELOW GROUND ELEVATION OF 985 FEET WHERE THE STATIC PRESSURE WILL NORMALLY EXCEED 80 PSI. AT ALL SUCH LOCATIONS WHERE THE GROUND LEVEL IS BELOW 985 FEET, THE DEVELOPER OR BUILDER SHALL INSTALL AT EACH LOT, ON THE CUSTOMER'S SIDE OF THE METER, AN APPROVED TYPE PRESSURE REGULATOR IN CONFORMANCE WITH THE PLUMBING CODE OF THE CITY OF SAN ANTONIO. NO DUAL SERVICES ALLOWED FOR ANY LOT(S) IF *PRV IS / ARE REQUIRED FOR SUCH LOT(S), ONLY SINGLE SERVICE CONNECTIONS SHALL BE ALLOWED. WATER SERVICES WHERE PRV'S REQUIRED ARE DESIGNATED BY AN ASTERISK (*).


*NOTE: A PRESSURE REGULATOR IS ALSO KNOWN AS A PRESSURE REDUCING VALVE(PRV)


. ALL VALVES SHALL READ "OPEN RIGHT" 2. ALL PVC PIPE TO BE C-900 CLASS 235 (DR 18)

. "SAWS REQUIRES GCPs AND COUNTER PERMIT TO USE LEAD FREE (<0.25% LEAD) FIRE HYDRANTS." 2. ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL BE IN ACCORDANCE WITH THE SAN ANTONIO WATER SYSTEM (SAWS) STANDARD SPECIFICATIONS.

CAUTION!!:

THE CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITED TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.






Linear unit of measure: US Survey Foot (1 ft = 1200/3937 m)

LEGEND

PROPOSED WATER MAIN PROPOSED 3/4" WATER SERVICE WITH 5/8" METER & BOX PROPOSED WATER 3/4" IRRIGATION SERVICE WITH 3/4" METER & BOX PROPOSED FIRE HYDRANT M PROPOSED WATER VALVE PROPOSED SANITARY SEWER MAIN PROPOSED SANITARY SEWER MANHOLE PROPOSED ELECTRIC, GAS, TELEPHONE = E.G.T.TV.E & CABLE TV EASEMENT PROPOSED VEHICULAR NON-ACCESS **EASEMENT** PROPOSED CLEAR VISION EASEMENT = C.V.E = — — EW — — — EXISTING WATER MAIN EXISTING FIRE HYDRANT = 000 EXISTING WATER VALVE EXISTING SANITARY SEWER MAIN




EXISTING SANITARY SEWER MANHOLE

EXISTING OVERHEAD ELECTRIC

EXISTING GUY WIRE/OVERHEAD

W/POWER POLE



SAWS PRESSURE ZONE 8 SERVICE AREA: FAR WEST

= −OHE---⊜---OHE-


DEVELOPER'S NAME: TALLEY EXTENSION REVITALIZATION INITIATIVE, LLC						
DEVELOPER'S ADDRESS: 1202 W. BITTERS RD., BLD 1, SUITE 1200						
CITY: SAN ANTONIO		STATE: TEXAS	ZIP:	78216		
PHONE#: (210) 490-1798	FAX#:		TOTAL ACREAGE:	13.87 ACRE		
SAWS BLOCK MAP#: 064600			TOTAL EDU'S	S: 72		
TOTAL LINEAR FOOTAGE OF F	PIPE: 2,39	95 LF ~ 8" C-900	PLAT NO.: 23	-11800386		


SAWS JOB#: 23-1175

NUMBER OF LOTS: 72

TBPE Firm#: F-14909 TBPLS Firm#: 10194550 W2054004

PLAN





JEFFREY W. MARTIN

PRELIMINARY

12/19/23

FOR MORGAN HEIGHTS PHASE 2B

PLAT# 23-11800386

SAN ANTONIO **BEXAR COUNTY**

TEXAS

SAN ANTONIO (KFW) 3421 Paesanos Parkway San Antonio, TX 78231 Phone: 210.979.8444 Engineering COLLIERS ENGINEERING & DESIGN, IN & Design

WATER DISTRIBUTION

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS. PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEETING 98% COMPACTION ON ALL TRENCH BACKFILL AND PAYING FOR THE TESTS TO BE PERFORMED BY A THIRD PARTY. COMPACTION TESTS WILL BE DONE AT ONE LOCATION POINT RANDOMLY SELECTED OR AS INDICATED BY THE SAWS INSPECTOR/TEST ADMINISTRATOR, PER EACH 12 INCH LOOSE LIFT PER 400 LINEAR FEET AT A MINIMUM. PERMITS AND/OR WILL NOT BE ACCEPTED AND FINALIZED BY SAWS WITHOUT THIS REQUIREMENT BEING MET AND VERIFIED BY PROVIDING ALL NECESSARY DOCUMENTED TEST RESULTS.

DRY UTILITY CONDUIT NOTE:

CONDUIT LOCATIONS SHOWN ON PLAN ARE FOR GEOGRAPHICAL PURPOSES ONLY AND ARE APPROXIMATE. CONTRACTOR TO INSTALL PROPOSED CONDUITS IN ACCORDANCE WITH DRY UTILITY PURVEYOR'S SPECIFICATIONS. CONTRACTOR TO VERIFY THE CONDUIT LOCATIONS AND SIZES BASED ON THE DRY UTILITY PURVEYOR'S PLAN.

SEWER EASEMENT

OFF-LOT VARIABLE WIDTH ACCESS, SANITARY SEWER, WATER, DRAINAGE,

EXPIRE UPON INCORPORATION INTO

UNPLATTED

180.88 ACRE TRACT OWNER: TALLEY EXTENSION REVITALIZATION INITIATIVE LLC

(DOC# 20190108872)

OFF-LOT VARIABLE WIDTH ACCESS,

EASEMENT (ENTIRE EASEMENT TO EXPIRE UPON INCORPORATION INTO

PLATTED STREET R.O.W.)__

OFF-LOT 30' SANITARY SEWER

PLATTED STREET R.O.W.)

LIMITS OF CONSTRUCTION

PHASE I

MATCH LINE "A" SEE SHEET 8.1

EASEMENT (ENTIRE EASEMENT TO EXPIRE UPON INCORPORATION INTO

SANITARY SEWER, WATER, DRAINAGE,

ELECTRIC, GAS, TELEPHONE & CABLE TV-

PLATTED STREET R.O.W.)

LIMITS OF

VARIABĹE WIDTH CLEAF

CONSTRUCTION

ELECTRIC, GAS, TELEPHONE & CABLE TV EASEMENT (ENTIRE EASEMENT TO

PROJECT COMPLETION:

- 1. ALL DISTURBED AREAS ARES NOT COVERED BY IMPERVIOUS COVER ARE TO BE STABILIZED PER THE SWPPP AND PROJECT SPECIFICATIONS PRIOR TO REMOVAL OF ANY BMP'S AND/OR PRIOR TO FILING A NOTICE OF TERMINATION (NOT).
- 2. BEST MANAGEMENT PRACTICES MAY BE REMOVED IN PHASES IF ALL UPGRADIENT AREAS HAVE BEEN STABILIZED PER SWPPP AND PROJECT SPECIFICATIONS. THIS PHASING SHOULD BE NOTED WITHIN THE MODIFICATIONS SECTION WITH THE SIGNATURE AND DATE OF THE RESPONSIBLE PARTY.
- 3. CONTRACTOR TO ENSURE THEY HAVE MET ALL REQUIREMENTS OF THE SWPPP BEFORE FILING A NOTICE OF TERMINATION

INLET WITH PROTECTION RAVEL FILTER BAGS)

- 1. THIS EXHIBIT IS TO BE USED FOR THE PURPOSES OF STORMWATER POLLUTION PREVENTION ONLY. ALL OTHER CIVIL ENGINEERING INFORMATION SHOULD BE OBTAINED FROM THE APPROPRIATE CONSTRUCTION DOCUMENTS.
- 2. THE PURPOSE OF THE SIGNATURE AND SEAL OF THE ENGINEER ON THIS DOCUMENT IS TO DEMONSTRATE COMPLIANCE WITH THE TPDES STORMWATER POLLUTION PREVENTION PLAN REGULATIONS ONLY.
- 3. ALL OWNERS/OPERATORS ARE RESPONSIBLE FOR FAMILIARIZING THEMSELVES WITH THE STORMWATER POLLUTION PREVENTION PLAN AND COMPLYING WITH THE REGULATIONS CONTAINED WITHIN IT.

100 YR FLOOD PLAIN (ZONE "AE" AS SCALED FROM LOMR 13-06-150P9, — DATED: JANUARY 9, 2014)

INSTALLATION:

LOT 902 BLOCK 13 C.B. 4404 OPEN SPACE / PUBLIC DRAINAGE EASEMENT

VEHICLE, & MATERIAL

CONSTRUCTION

(GRAVEL FILTER BAGS)

- 1. ALL OPERATORS SHALL SUBMIT A NOTICE OF INTENT (NOI) AT LEAST 48 HOURS IN ADVANCE AND ALL BEST MANAGEMENT PRACTICES (BMP'S) SHALL BE IN PLACE PRIOR TO STARTING CONSTRUCTION ACTIVITIES.
- 2. CONTRACTOR TO ENSURE THAT STRUCTURAL BMP'S ARE INSTALLED WITHIN THE LIMITS OF THE SITE BOUNDARY.
- 3. CONTRACTOR MAY INSTALL THE BEST MANAGEMENT PRACTICES IN PHASES THAT COINCIDE WITH THE DISTURBANCE OF UP GRADIENT AREAS. THIS PHASING SHOULD BE NOTED WITHIN THE MODIFICATIONS SECTION WITH THE SIGNATURE AND DATE OF THE RESPONSIBLE PARTY.
- 4. CONTRACTOR TO VERIFY SUFFICIENT VEGETATION IN AREAS DENOTED AS VEGETATED FILTER STRIP. IF INSUFFICIENT VEGETATION EXISTS, CONTRACTOR SHALL IMPLEMENT A DIFFERENT BEST MANAGEMENT PRACTICE AND WILL SHOW IT ON THIS PLAN WITH NOTATION IN THE MODIFICATIONS SECTION WITH THE SIGNATURE AND DATE OF THE RESPONSIBLE PARTY.

MAINTENANCE AND INSPECTION:

- 1. CONTRACTOR SHOULD LIMIT CONSTRUCTION ACTIVITIES TO ONLY THOSE AREAS SHOWN TO BE DISTURBED ON THIS PLAN. IF ADDITIONAL VEGETATED AREAS ARE DISTURBED, THEY SHOULD BE PROTECTED WITH APPROPRIATE BEST MANAGEMENT PRACTICES UNTIL THE AREAS HAVE BEEN STABILIZED AS PER THE SPECIFICATIONS OF THE SWPPP. THE AREAS OF THIS ADDITIONAL SOIL DISTURBANCE AND THE MEASURES USED SHOULD BE SHOWN ON THE SITE PLAN AND NOTED WITHIN THE MODIFICATIONS SECTION WITH THE SIGNATURE AND DATE OF THE RESPONSIBLE PARTY.
- 2. CONTRACTOR IS RESPONSIBLE FOR MAINTENANCE AND INSPECTION OF BMP'S AS PER THE SPECIFICATIONS OF THE SWPPP. THE CONTRACTOR MAY MODIFY THE CONTROLS AS NECESSARY TO PREVENT SEDIMENT RUNOFF. THESE MODIFICATIONS SHOULD BE SHOWN AND THE SITE PLAN AND NOTED WITHIN THE MODIFICATIONS SECTION WITH THE SIGNATURE AND DATE OF THE RESPONSIBLE PARTY.
- 3. LOCATION OF CONSTRUCTION ENTRANCE/EXIT, CONCRETE WASHOUT PIT, AND EQUIPMENT AND STORAGE ARE TO BE FIELD DETERMINED. LOCATIONS SHALL

DRAIN "B"

100 YR FLOOD PLAIN (ZONE "AE" AS

DATED: JANUARY 9, 2014)

BEXAR COUNTY R.O.W. NOTE: A BEXAR COUNY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY R.O.W.


ONDERLAND WAY RIABLE WIDTH R.O.W.)

1 3' LANDSCAPE EASEMENT


10RGAN HEIGHTS PHASE 1B


(CONCURRENT PLAT

NUMBER 21-11800244)



LOCATION MAP










DISTURBED AREA







INLET WITH PROTECTION (GRAVEL FILTERS BAGS)

EARTHEN CHECK BERM

COORDINATION NOTE:

- 1. CONTACT TIME WARNER TO COORDINATE CABLE TV SERVICE. (210) 244-0500
- 2. CONDUIT FOR ELECTRICAL SERVICE. CONFIRM REQUIREMENTS AND COORDINATE WITH CPS FOR INSPECTION. (210) 353-2246.
- 3. CONTACT AT&T TO COORDINATE TELEPHONE SERVICE. 1-800-449-7928.
- 4. CONTRACTOR TO COORDINATE WITH CPS PRIOR TO CONSTRUCTION TO PLAN ELECTRIC SERVICE.
- 5. CONTRACTOR TO COORDINATE WITH SAWS TO PLAN WATER AND SANITARY SEWER SERVICES (210) 704-7297
- 6. CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION.

SW3P MODIFICATIONS

DATE	SIGNATURE	DESCRIPTION

JEFFREY W. MARTII

Engineering

& Design

www.colliersengineering.com

pyright © 2023. Colliers Engineering & Design All Rights Reserved. This draw

hom the services were contracted or to whom it is certified. This drawing may

e copied, reused, disclosed, distributed or relied upon for any other purp

without the express written consent of Colliers Engineering & Design.

FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE

Formerly Known as

PRELIMINARY

12/19/23

MORGAN HEIGHTS PHASE 2B PLAT# 23-11800386

> SAN ANTONIO **BEXAR COUNTY**

> > **TEXAS**

	SAN ANTONIO (KFW)
Colliers	3421 Paesanos Parkway San Antonio, TX 78231
Engineering	Phone: 210.979.8444
& Design	COLLIERS ENGINEERING & DESIGN, IN TBPE Firm#: F-14909 TBPLS Firm#: 10194550

one: 210.979.8444 ENGINEERING & DESIGN, IN TBPE Firm#: F-14909

SW3P2054004 205-40-04

STORMWATER POLLUTION PREVENTION PLAN

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

COMPACTION NOTE:
THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEETING 98% COMPACTION ON ALL TRENCH BACKFILL AND PAYING FOR THE TESTS TO BE PERFORMED BY A THIRD PARTY. COMPACTION TESTS WILL BE DONE AT ONE LOCATION POINT RANDOMLY SELECTED OR AS INDICATED BY THE SAWS INSPECTOR/TEST ADMINISTRATOR, PER EACH 12 INCH LOOSE LIFT PER 400 LINEAR FEET AT A MINIMUM. PERMITS AND/OR WILL NOT BE ACCEPTED AND FINALIZED BY SAWS WITHOUT THIS REQUIREMENT BEING MET AND VERIFIED BY PROVIDING ALL NECESSARY DOCUMENTED TEST RESULTS.

DRY UTILITY CONDUIT NOTE:

CONDUIT LOCATIONS SHOWN ON PLAN ARE FOR GEOGRAPHICAL PURPOSES ONLY AND ARE APPROXIMATE. CONTRACTOR TO INSTALL PROPOSED CONDUITS IN ACCORDANCE WITH DRY UTILITY PURVEYOR'S SPECIFICATIONS. CONTRACTOR TO VERIFY THE CONDUIT LOCATIONS AND SIZES BASED ON THE DRY UTILITY PURVEYOR'S PLAN.

1. THIS EXHIBIT IS TO BE USED FOR THE PURPOSES OF STORMWATER POLLUTION PREVENTION ONLY. ALL OTHER CIVIL ENGINEERING INFORMATION SHOULD BE OBTAINED FROM THE APPROPRIATE CONSTRUCTION DOCUMENTS.

- 2. THE PURPOSE OF THE SIGNATURE AND SEAL OF THE ENGINEER ON THIS DOCUMENT IS TO DEMONSTRATE COMPLIANCE WITH THE TPDES STORMWATER POLLUTION PREVENTION PLAN
- 3. ALL OWNERS/OPERATORS ARE RESPONSIBLE FOR FAMILIARIZING THEMSELVES WITH THE STORMWATER POLLUTION PREVENTION PLAN AND COMPLYING WITH THE REGULATIONS CONTAINED WITHIN IT.

CONSTRUCTION WONDERLAND WAY (VARIABLE WIDTH R.O.W

SW3P MODIFICATIONS

MATCH LINE "B" SEE THIS SHEET

DATE	SIGNATURE	DESCRIPTION

PROJECT COMPLETION:

- 1. ALL DISTURBED AREAS ARES NOT COVERED BY IMPERVIOUS COVER ARE TO BE STABILIZED PER THE SWPPP AND PROJECT SPECIFICATIONS PRIOR TO REMOVAL OF ANY BMP'S AND/OR PRIOR TO FILING A NOTICE OF TERMINATION (NOT).
- 2. BEST MANAGEMENT PRACTICES MAY BE REMOVED IN PHASES IF ALL UPGRADIENT AREAS HAVE BEEN STABILIZED PER SWPPP AND PROJECT SPECIFICATIONS. THIS PHASING SHOULD BE NOTED WITHIN THE MODIFICATIONS SECTION WITH THE SIGNATURE AND DATE OF THE RESPONSIBLE PARTY.
- 3. CONTRACTOR TO ENSURE THEY HAVE MET ALL REQUIREMENTS OF THE SWPPP BEFORE FILING A NOTICE OF TERMINATION

MATCH LINE "B" SEE THIS SHEET WONDERLAND WAY (VARIABLE WIDTH R.O.W.)

LIMITS OF

CONSTRUCTION


INSTALLATION:

- 1. ALL OPERATORS SHALL SUBMIT A NOTICE OF INTENT (NOI) AT LEAST 48 HOURS IN ADVANCE AND ALL BEST MANAGEMENT PRACTICES (BMP'S) SHALL BE IN PLACE PRIOR TO STARTING CONSTRUCTION ACTIVITIES.
- 2. CONTRACTOR TO ENSURE THAT STRUCTURAL BMP'S ARE INSTALLED WITHIN THE LIMITS OF THE SITE BOUNDARY.
- 3. CONTRACTOR MAY INSTALL THE BEST MANAGEMENT PRACTICES IN PHASES THAT COINCIDE WITH THE DISTURBANCE OF UP GRADIENT AREAS. THIS PHASING SHOULD BE NOTED WITHIN THE MODIFICATIONS SECTION WITH THE SIGNATURE AND DATE OF THE RESPONSIBLE PARTY.
- 4. CONTRACTOR TO VERIFY SUFFICIENT VEGETATION IN AREAS DENOTED AS VEGETATED FILTER STRIP. IF INSUFFICIENT VEGETATION EXISTS, CONTRACTOR SHALL IMPLEMENT A DIFFERENT BEST MANAGEMENT PRACTICE AND WILL SHOW IT ON THIS PLAN WITH NOTATION IN THE MODIFICATIONS SECTION WITH THE SIGNATURE AND DATE OF THE RESPONSIBLE PARTY.


MAINTENANCE AND INSPECTION:


- 1. CONTRACTOR SHOULD LIMIT CONSTRUCTION ACTIVITIES TO ONLY THOSE AREAS SHOWN TO BE DISTURBED ON THIS PLAN. IF ADDITIONAL VEGETATED AREAS ARE DISTURBED, THEY SHOULD BE PROTECTED WITH APPROPRIATE BEST MANAGEMENT PRACTICES UNTIL THE AREAS HAVE BEEN STABILIZED AS PER THE SPECIFICATIONS OF THE SWPPP. THE AREAS OF THIS ADDITIONAL SOIL DISTURBANCE AND THE MEASURES USED SHOULD BE SHOWN ON THE SITE PLAN AND NOTED WITHIN THE MODIFICATIONS SECTION WITH THE SIGNATURE AND DATE OF THE RESPONSIBLE PARTY.
- 2. CONTRACTOR IS RESPONSIBLE FOR MAINTENANCE AND INSPECTION OF BMP'S AS PER THE SPECIFICATIONS OF THE SWPPP. THE CONTRACTOR MAY MODIFY THE CONTROLS AS NECESSARY TO PREVENT SEDIMENT RUNOFF. THESE MODIFICATIONS SHOULD BE SHOWN AND THE SITE PLAN AND NOTED WITHIN THE MODIFICATIONS SECTION WITH THE SIGNATURE AND DATE OF THE RESPONSIBLE PARTY.
- 3. LOCATION OF CONSTRUCTION ENTRANCE/EXIT, CONCRETE WASHOUT PIT, AND EQUIPMENT AND STORAGE ARE TO BE FIELD DETERMINED. LOCATIONS SHALL


BEXAR COUNTY R.O.W. NOTE: A BEXAR COUNY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY R.O.W.




LOCATION MAP











EARTHEN CHECK BERM

CONTACT TIME WARNER TO COORDINATE CABLE

COORDINATION NOTE:


- TV SERVICE. (210) 244-0500 CONDUIT FOR ELECTRICAL SERVICE. CONFIRM
- CONTACT AT&T TO COORDINATE TELEPHONE SERVICE. 1-800-449-7928.


INSPECTION. (210) 353-2246.

4. CONTRACTOR TO COORDINATE WITH CPS PRIOR TO CONSTRUCTION TO PLAN ELECTRIC SERVICE.

REQUIREMENTS AND COORDINATE WITH CPS FOR

- CONTRACTOR TO COORDINATE WITH SAWS TO
- PLAN WATER AND SANITARY SEWER SERVICES (210) 704-7297
- CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION.





Engineering

& Design

www.colliersengineering.com

pyright © 2023. Colliers Engineering & Design All Rights Reserved. This drawin

hom the services were contracted or to whom it is certified. This drawing may

e copied, reused, disclosed, distributed or relied upon for any other purp

without the express written consent of Colliers Engineering & Design.

ALL STATES REQUIRE NOTIFICATION OF

PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE

Formerly Known as

PRELIMINARY

MORGAN HEIGHTS PHASE 2B

PLAT# 23-11800386

SAN ANTONIO **BEXAR COUNTY**

TEXAS


	Colliers	
I	Engineering & Design	


3421 Paesanos San Antonio, TX 78231 Phone: 210.979.8444 COLLIERS ENGINEERING & DESIGN, IN TBPLS Firm#: 10194550


SAN ANTONIO (KFW)

SW3P2054004

STORMWATER POLLUTION PREVENTION PLAN







TYPE 4 SACK GABIONS

FIBER ROLL

Install fiber roll

Vertical spacing

face of the slope

varies between

10' and 20'

measured along the

along a level contour

slope where it transitions

into a steeper slope

TYPICAL FIBER ROLL INSTALLATION

ENTRENCHMENT DETAIL

max 4'

THE TOP OF THE SACK GABIONS SHOULD BE LEVEL AND ORIENTED PERPENDICULAR TO THE DIRECTION OF FLOW. FILTER FABRIC MATERIAL SHALL BE FASTENED TO WOVEN WIRE FILTER FABRIC MATERIAL SHOULD MEET THE FOLLOWING SPECIFICATIONS: RESISTANT TO ULTRAVIOLET LIGHT. FABRIC DUNCES PER SQUARE YARD. MINIMUM MULLEN BURST STRENGTH OF POUNDS PER SQUARE INCH AND A FLOW THRU RATE OF 120 GALLONS PER MINUTE PER SQUARE FOOT OF FRONTAL AREA. STONE SIZE: ±4"-8" OPEN GRADED CRUSHED LIMESTONE. NSPECT WEEKLY OR AFTER EACH RAINFALL EVENT AND REPAIR OR WHEN SILT REACHES A DEPTH OF 6 INCHES OR MORE ABOVE NATURAL GROUND, SILT SHALL BE REMOVED AND DISPOSED IN AN APPROVED MANNER THAT WILL NOT CONTRIBUTE TO RESILTATION. CONTAMINATED SEDIMENT MUST BE REMOVED AND DISPOSED OF FF-SITE IN ACCORDANCE WITH APPLICABLE REGULATIONS.

THE MATERIAL, INSTALLATION, INSPECTION, AND MAINTENANCE OF

(1) Core material: Core material should be biodegradable or recyclable. Material

FIBER ROLLS WILL BE PER THE MANUFACTURE'S SPECIFICATIONS

AND SHALL ALSO COMPLY WITH THE TEXAS COMMISSION OF

may be compost, mulch, aspen wood fibers, chipped site vegetation, agricultural rice or wheat straw, coconut fiber, 100% recyclable fibers, or

(2) Containment Mesh: Containment mesh should be 100% biodegradable,

photodegradable or recyclable such as burlap, twine, UV photodegradable

plastic, polyester, or similar material. When the fiber role will remain in place

as part of a vegetative system use biodegradable or photodegradable mesh.

Slope inclination of 4:1 (H:V) or flatter: Fiber rolls should be placed at a

Slope inclination 2:1 (H:V) or greater: Fiber Rolls should be placed at a

Slope inclination between 4:1 and 2:1 (H:V): Fiber Rolls should be placed at a

(2) Turn the ends of the fiber roll up slope to prevent runoff from going around the

(4) Drive stakes at the end of each fiber roll and spaced 4 ft maximum on center.

(5) Use wood stakes with a nominal classification of 0.75 by 0.75 in. and minimum

(6) If more than one fiber roll is placed in a row, the rolls should be overlapped, not

(3) If the fiber roll is used as a sediment capture device, or as an erosion control device to maintain sheet flows, sediment that accumulates behind the role must be

periodically removed in order to maintain its effectiveness. Sediment should be

incorporated into earthwork on the site or disposed of at an appropriate location.

depth, usually one-half the distance between the top of the fiber roll and the adjacent ground surface. Sediment removed during maintenance may be

removed when the accumulation reaches one-half the designated sediment storage

(3) Stake fiber rolls into a 2 to 4 in. deep trench with a width equal to the diameter of

BEST MANAGEMENT PRACTICES" AS NOTED BELOW.

For temporary installation recyclable mesh is recommended.

(1) Locate fiber rolls on level contours spaced as follows:

maximum interval of 15 ft. (a closer spacing is more effective).

maximum interval of 10 ft. (a closer spacing is more effective).

(2) Repair or replace split, torn, unraveling, or slumping fiber rolls.

similar materials.

maximum interval of 20 ft.


Inspection and Maintenance Guidelines:

the fiber roll.

abutted.

(1) Inspect weekly

ENVIRONMENTAL QUALITY CURRENT "TECHNICAL GUIDANCE ON



SEOTEXTILE. FABRIC CROSS-SECTION OF A CONSTRUCTION ENTRANCE/EXIT

Installation: (North Carolina, 1993)

area. Grade crown foundation for positive drainage.

(1) The aggregate should consist of 4 to 8 inch washed stone over a stable foundation as specified in the plan. PUBLIC ROAD (2) The aggregate should be placed with a minimum thickness of 8 inches (3) The geotextile fabric should be designed specifically for use as a soil filtration media with an approximate weight of 6 oz/yd2, a mullen burst rating of 140 lb/in2, and an equivalent opening size greater than a number

(4) If a washing facility is required, a level area with a minimum of 4 inch diameter washed stone or commercial rack should be included in the plans. Divert wastewater to a sediment trap or basin.

hom the services were contracted or to whom it is certified. This drawing may e copied, reused, disclosed, distributed or relied upon for any other purp without the express written consent of Colliers Engineering & Design. (1) Avoid curves on public roads and steep slopes. Remove vegetation and other objectionable material from the foundation


(2) The minimum width of the entrance/exit should be 12 feet or the full width of exit roadway, whichever is greater. (3) The construction entrance should be at least 50 feet long. (4) If the slope toward the road exceeds 2%, construct a ridge, 6 to 8 inches high with 3:1 (H:V) side slopes, across the foundation approximately 15 feet from the entrance to divert runoff away from the public road. (5) Place geotextile fabric and grade foundation to improve stability, especially where wet conditions are anticipated. (6) Place stone to dimensions and grade shown on plans. Leave surface smooth and slope for drainage. (7) Divert all surface runoff and drainage from the stone pad to a sediment trap or basin. (8) Install pipe under pad as needed to maintain proper public road drainage.

The entrance should be maintained in a condition, which will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repair andlor cleanout of any measures used to trap sediment. (2) All sediment spilled, dropped, washed or tracked onto public rights-of-way should be removed immediately by contractor.

(4) When washing is required, it should be done on an area stabilized with crushed stone that drains into an approved sedimen trap or sediment basin. CONSTRUCTION ENTRANCE/EXIT (5) All sediment should be prevented from entering any storm drain, ditch or water course by using approved methods.

(3) When necessary, wheels should be cleaned to remove sediment prior to entrance onto public right-of-way.

STABILIZED CONSTRUCTION ENTRANCE / EXIT



GEOTEXTILE FABRIC

TO STABILIZE FOUNDATION

(1) The berm structure should be. secured with a woven wire sheathing having maximum opening of 1 inch and a minimum wire diameter of 20 gauge galvanized and should be secured with shoat rings. (2) Clean, open graded 3- to 5-inch diameter rock should be used, except in areas where high velocities or large volumes of flow are expected, where 5- to 8-inch diameter rocks may be used.

(1) Lay out the woven wire sheathing perpendicular to the flow line. The sheathing should be 20 gauge woven wire mesh with 1 inch openings. (2) Berm should have a top width of 2 feet minimum with side slopes being 2:1 (H:V) or flatter. (3) Place the rock along the sheathing as shown in the diagram Figure 1-28), to a height not less than

(4) Wrap the wire sheathing around the rock and secure with tie wire so that the ends of the sheathing overlap at least 2 inches, airl the berm retains its shape when walked upon (5) Berm should be built along the contour at zero percent grade or as near as possible. (6) The ends of the berm should be tied into existing upslope grade and the berm should be buried in a trench approximately 3 to 4 inches deep to prevent failure of the control.

Inspection and Maintenance Guidelines:

(1) Inspection should be made weekly by the responsible party. For installations


in streambeds, additional daily inspections should be made. (2) Remove sediment and other debris when buildup reaches 6 inches and dispose of the accumulated silt in an approved manner that will not cause any additional siltation.

(3) Repair any loose wire sheathing. (4) The berm should be reshaped as needed during inspection.

(5) The berm should be replaced when the structure ceases to function as intended due to silt accumulation among the rocks, washout, construction traffic damage, etc.

(6) The rock berm should be left in place until all upstream areas are stabilized and accumulated silt

ROCK BERM



(1) SILT FENCE MATERIAL SHOULD BE POLYPROPYLENE, POLYETHYLENE OR POLYAMIDE WOVEN OR NONWOVEN FABRIC. THE FABRIC WIDTH SHOULD BE 36 INCHES, WITH A MINIMUM UNIT WEIGHT OF 4.5 OZ/YD, MULLEN BURST STRENGTH EXCEEDING 190 LB/IN2, ULTRAVIOLET STABILITY EXCEEDING 70%, AND MINIMUM APPARENT OPENING SIZE OF U.S. SIEVE NO. 30. (2) FENCE POSTS SHOULD BE MADE OF HOT ROLLED STEEL, AT LEAST 4 FEET LONG WITH TEE OR YBAR CROSS SECTION, SURFACE PAINTED OR GALVANIZED, MINIMUM NOMINAL WEIGHT 1.25 LB/FL2, AND BRINDELL HARDNESS EXCEEDING 140. REBAR (EITHER #5 OR #6) MAY ALSO BE

USED TO ANCHOR THE BERM. (3) WOVEN WIRE BACKING TO SUPPORT THE FABRIC SHOULD BE GALVANIZED 2" X 4" WELDED WIRE, 12 GAUGE MINIMUM. (4) THE BERM STRUCTURE SHOULD BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM OPENING OF 1 INCH. AND A MINIMUM WIRE DIAMETER OF 20 GAUGE GALVANIZED AND SHOULD BE SECURED WITH SHOAT RINGS.

(5) CLEAN, OPEN GRADED 3- TO 5-INCH DIAMETER ROCK SHOULD BE USED, EXCEPT IN AREAS WHERE HIGH VELOCITIES OR LARGE VOLUMES OF FLOW ARE EXPECTED, WHERE 5- TO 8-INCH DIAMETER ROCKS MAY BE USED.

INSTALLATION:
(1) LAY OUT THE WOVEN WIRE SHEATHING PERPENDICULAR TO THE FLOW LINE. THE SHEATHING SHOULD BE 20 GAUGE WOVEN WIRE MESH WITH 1-INCH OPENINGS

(2) INSTALL THE SILT FENCE ALONG THE CENTER OF THE PROPOSED BERM PLACEMENT, AS WITH A NORMAL SILT FENCE DESCRIBED IN SECTION 2.4.3. (3) PLACE THE ROCK ALONG THE SHEATHING ON BOTH SIDES OF THE SILT FENCE AS SHOWN IN THE DIAGRAM (FIGURE 1-29), TO A HEIGHT NOT LESS THAN 24 INCHES. CLEAN, OPEN GRADED 3- 5" DIAMETER ROCK SHOULD BE USED, EXCEPT IN AREAS WHERE HIGH VELOCITIES OR LARGE VOLUMES OF FLOW ARE EXPECTED, WHERE 5- TO 8-INCH DIAMETER ROCK MAY BE USED. (4) WRAP THE WIRE SHEATHING AROUND THE ROCK AND SECURE WITH TIE WIRE SO THAT THE ENDS OF THE SHEATHING OVERLAP AT LEAST 2

INCHES, AND THE BERM RETAINS ITS SHAPE WHEN WALKED UPON. (5) THE HIGH SERVICE ROCK BERM SHOULD BE REMOVED WHEN THE SITE IS REVEGETATED OR OTHERWISE STABILIZED OR IT MAY REMAIN IN PLACE AS A PERMANENT BMP IF DRAINAGE IS ADEQUATE.

INSPECTION AND MAINTENANCE GUIDELINES:
(1) INSPECTION SHOULD BE MADE WEEKLY BY THE RESPONSIBLE PARTY. FOR INSTALLATIONS IN STREAMBEDS, ADDITIONAL DAILY INSPECTIONS SHOULD BE MADE ON ROCK BERM. (2) REMOVE SEDIMENT AND OTHER DEBRIS WHEN BUILDUP REACHES 6 INCHES AND DISPOSE OF THE ACCUMULATED SILT OF IN AN APPROVED

(3) REPAIR ANY LOOSE WIRE SHEATHING. (4) THE BERM SHOULD BE RESHAPED AS NEEDED DURING INSPECTION. (5) THE BERM SHOULD BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED DUE TO SILT ACCUMULATION AMONG THE

ROCKS, WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC. (6) THE ROCK BERM SHOULD BE LEFT IN PLACE UNTIL ALL UPSTREAM AREAS ARE STABILIZED AND ACCUMULATED SILT REMOVED.

HIGH SERVICE ROCK BERM

Engineering

& Design

www.colliersengineering.com

pyright © 2023. Colliers Engineering & Design All Rights Reserved. This draw

FOR STATE SPECIFIC DIRECT PHONE NUMBERS

VISIT: WWW.CALL811.COM

ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON

PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE

Formerly Known as

PRELIMINARY

12/19/23

JEFFREY W. MARTI

MORGAN HEIGHTS PHASE 2B PLAT# 23-11800386

> SAN ANTONIO **BEXAR COUNTY**


SAN ANTONIO (KFW) 3421 Paesanos San Antonio, TX 78231 Phone: 210.979.8444 Engineering OLLIERS ENGINEERING & DESIGN, II & Design TBPE Firm#: F-14909 TBPLS Firm#: 10194550

TEXAS

AS SHOWN SW3P-DT3145104

STORMWATER POLLUTION PREVENTION DETAILS


NOTE: DO NOT SCALE DRAWINGS FOR CONSTRUCTION.



SECTION A-A WIRE MESH COVERED -**GENERAL NOTES:** WITH FILTER FABRIC - FILTERED RUNOF THE FILTER BAG MATERIAL SHALL BE MADE OF POLYPROPYLENE, POLYETHYLENE OR POLYAMIDE WOVEN FABRIC, MIN UNIT WEIGHT OF 4 OUNCES/SY, MULLEN BURST STRENGTH EXCEEDING 300 PSI AND ULTRAVIOLET SECTION A-A THE FILTER BAG SHALL BE FILLED WITH CLEAN, MEDIUM TO COARSE GRAVEL (0.31 TO 0.75 INCH DIAMETER). DETAIL-A

GRAVEL FILTER BAG DETAIL

CURB INLET PROTECTION (ALTERNATE)



TYPICAL CONSTRUCTION STAGING AREA

FLOW ARROWS

- WIRE MESH COVERED WIRE MESH COVERED WITH FILTER FABRIC