#### **GENERAL INFORMATION**

- ALL CONSTRUCTION SHALL CONFORM TO THE CITY OF SAN ANTONIO STANDARD SPECIFICATIONS FOR CONSTRUCTION
- NO EXTRA PAYMENT SHALL BE ALLOWED FOR WORK CALLED FOR ON THE PLANS, BUT NOT INCLUDED IN THE BID
- THE CONTRACTOR SHALL PROVIDE ACCESS FOR THE DELIVERY OF MAIL BY THE U.S. POSTAL SERVICE. 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING TO ITS ORIGINAL OR BETTER CONDITION ANY DAMAGE DONE TO EXISTING FENCES, CONCRETE ISLANDS, STREET PAVING, CURBS, SHRUBS, BUSHES OR DRIVEWAYS. (NO SEPARATE PAY

PROPOSAL. THIS INCIDENTAL WORK WILL BE REQUIRED AND SHALL BE INCLUDED IN THE PAY ITEM TO WHICH IT RELATES

- IT IS THE CONTRACTOR'S RESPONSIBILITY TO SEE THAT ALL SIGNS AND BARRICADES ARE PROPERLY INSTALLED AND MAINTAINED. ALL LOCATIONS AND DISTANCES WILL BE DECIDED UPON IN THE FIELD BY THE CONTRACTOR, USING THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES". THE CITY'S CONSTRUCTION INSPECTOR AND TRAFFIC ENGINEERING REPRESENTATIVE WILL ONLY BE RESPONSIBLE TO INSPECT BARRICADES AND SIGNS. IF, IN THE OPINION O CONFORM TO ESTABLISHED STANDARDS OR ARE INCORRECTLY PLACED OR ARE INSUFFICIENT IN QUANTITY TO PROTECT
- IF THE NEED ARISES, ADDITIONAL BARRICADES AND DIRECTIONAL DEVICES MAY BE ORDERED BY THE TRAFFIC ENGINEERING REPRESENTATIVE AT THE CONTRACTOR'S EXPENSE.
- DUE TO FEDERAL REGULATIONS TITLE 49, PART 192.171 C.P.S. MUST MAINTAIN ACCESS TO GAS VALVES AT ALL TIMES. THE CONTRACTOR MUST PROTECT AND WORK AROUND ANY GAS VALVES THAT ARE IN THE PROJECT AREA.
- CONTRACTOR SHALL NOTIFY THE CITY INSPECTOR TWENTY FOUR (24) HOURS PRIOR TO BACKFILL OF ANY UTILITY TRENCHES TO SCHEDULE FOR DENSITY TEST AS REQUIRED.
- CONTRACTOR SHALL PRESERVE ALL CONSTRUCTION STAKES. MARKS, ETC. IF ANY ARE DESTROYED OR REMOVED BY TH CONTRACTOR OR HIS EMPLOYEES, THEY SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
- CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES PRIOR TO CONSTRUCTION TO DETERMINE THE LOCATION OF EXISTING UTILITIES. CONTRACTOR SHALL NOTIFY THE FOLLOWING AT LEAST FORTY-EIGHT (48) HOURS PRIOR TO

SAN ANTONIO WATER SYSTEM (SAWS) BEXAR METROPOLITAN WATER DISTRICT (BEXAR MET)

TEXAS STATE WIDE ONE CALL LOCATOR CITY PUBLIC SERVICE ENERGY - TIME WARNER - AT&T - MCI THE EXISTENCE AND LOCATION OF UNDERGROUND UTILITIES INDICATED ON THE PLANS ARE TAKEN FROM AVAILABLE RECORDS AND ARE NOT GUARANTEED, BUT SHALL BE INVESTIGATED AND VERIFIED BY THE CONTRACTOR BEFORE STARTING WORK. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY DAMAGE TO AND FOR THE MAINTENANCE AN PROTECTION OF THE EXISTING UTILITIES EVEN IF THEY ARE NOT SHOWN ON THE PLANS. LOCATION AND DEPTH OF

THAT WILL BLOCK OR ALTER FLOW LIMITS OF EXISTING ARTIFICIAL OR NATURAL DRAINAGE.

ALL WASTE MATERIAL SHALL BECOME PROPERTY OF THE CONTRACTOR AND SHALL BE HIS SOLE RESPONSIBILITY TO DISPOSE OF THIS MATERIAL OFF THE LIMITS OF THE PROJECT. NO WASTE MATE- RIAL SHALL BE PLACED IN EXISTING LOW

EXISTING UTILITIES SHOWN HERE ARE APPROXIMATE ONLY, ACTUAL LOCATIONS AND DEPTHS MUST BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION AND HE SHALL BE RESPONSIBLE FOR PROTECTION OF SAME DURING

- THE CONTRACTOR SHALL NOT PLACE ANY WASTE MATERIAL IN THE 100-YEAR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN DEVELOPMENT PERMIT.
- THE CONTRACTOR SHALL MAINTAIN ALL ADJOINING STREETS AND TRAVELED ROUTES FREE FROM SPILLED AND / OR
- IF THE CONTRACTOR ENCOUNTERS ANY ARCHAEOLOGICAL DEPOSITS DURING CONSTRUCTION OPERATIONS, THE CONTRACTOR MUST STOP EXCAVATION IMMEDIATELY, CONTACT THE CITY INSPECTOR, AND CALL THE CITY HISTORIC PRESERVATION OFFICE AT 207-7306 OR 207-3327 FOR AN ARCHAEOLOGICAL INVESTIGATION. THE CONTRACTOR CANNOT BEGIN EXCAVATION AGAIN WITHOUT WRITTEN PERMISSION FROM THE CITY. IF MORE THAN THREE (3) DAYS ARE REQUIRED FOR INVESTIGATION (NOT INCLUDING HOLIDAY AND WEEKENDS) AND IF THE CONTRACTOR IS UNABLE TO WOR IN OTHER AREAS. THEN THE CONTRACTOR WILL BE ALLOWED TO NEGOTIATE FOR ADDITIONAL CONSTRUCTION TIME UPON WRITTEN REQUEST WITHIN TEN (10) DAYS AFTER THE FIRST NOTICE TO THE CITY OF ARCHAEOLOGICAL INVESTIGATION FOR EACH EVENT. IF THE TIME REQUIRED FOR INVESTIGATION IS LESS THAN OR EQUAL TO THREE (3) DAYS FOR EACH EVENT. CONTRACT DURATION WILL NOT BE EXTENDED.
- IMMEDIATELY WHEN CONTAMINATED SOILS AND / OR GROUNDWATER ARE ENCOUNTERED AT LOCATIONS NOT IDENTIFIED CONTAMINATED SOIL AND / OR GROUNDWATER SHALL NOT BE REMOVED FROM THE LOCATION WITHOUT PRIOR C.O.S.A. APPROVAL.  $\,\,$  THE CONTRACTOR MUST STOP THE EXCAVATION IMMEDIATELY AND CONTACT THE C.O.S.A. INSPECTOR.  $\,$  THE CONTRACTOR CANNOT BEGIN EXCAVATION ACTIVITIES WITHOUT WRITTEN PERMISSION FROM THE CITY.
- CONTRACTOR IS TO INCLUDE A MAILBOX POST BLOCKOUT FOR VACANT LOTS AND ALL RESIDENCES WHICH DO NOT HAVE MAILBOXES AT THE CURB. BLOCKOUTS ARE PROVIDED FOR FUTURE USE BY THE POST OFFICE.
- CONTRACTOR SHALL NOT REMOVE OR ADJUST ANY VIA FACILITIES. THE CONTRACTOR MUST. CONTACT VIA FOURTEEN DAYS PRIOR, FOR THE REMOVAL OF BENCHES, STOP POLES OR ANY OTHER VIA FACILITIES THAT MAY BE PRESENT. PLEASE PROVIDE THIRTY DAYS PRIOR NOTICE FOR SHELTER REMOVAL (TELEPHONE NOS. (210) 362-2155 OR (210) 362-2096). THE CONTRACT- OR WILL BE LIABLE FOR ANY DAMAGES TO VIA FACILITIES NOT REMOVED BY VIA. THE CON-TRACTOR IS REQUIRED TO REPLACE ALL FLATWORK REMOVED OR DAMAGED IN THE COURSE OF EXECUTING THE CONTRACT UNLESS OTHERWISE NOTED BY VIA. THE CONTRACTOR WILL BE RESPONSIBLE FOR PROTECTING VIA

#### REE PROTECTION AND PRESERVATION GENERAL NOTES

FACILITIES IF ADJACENT TO WORK AREA.

- NO UTILITY OR STREET EXCAVATION WORK SHALL BEGIN IN AREAS WHERE TREE PRESERVATION AND TREATMENT MEASURES HAVE NOT BEEN COMPLETED AND APPROVED
- TREE PROTECTION FENCING SHALL BE REQUIRED. TREE PROTECTION FENCING SHALL BE INSTALLED, MAINTAINED AND REPAIRED BY THE CONTRACTOR DURING SITE CONSTRUCTION. DURING CONSTRUCTION ACTIVITY. AT LEAST A SIX-INCH LAYER OF COARSE MULCH SHALL BE PLACED AND MAINTAINED OVER THE ROOT PROTECTION ZONE (NO SEPARATE PAY
- THE CONTRACTOR SHALL AVOID CUTTING ROOTS LARGER THAN ONE INCH IN DIAMETER WHEN EXCAVATING NEAR EXISTING TREES. EXCAVATION IN THE VICINITY OF TREES SHALL PROCEED WITH CAUTION. THE CONTRACTOR SHALL CONTACT THE
- ROOTS WILL BE CUT WITH A ROCK SAW OR BY HAND, NOT BY AN EXCAVATOR OR OTHER ROAD CONSTRUCTION EQUIPMENT.
- ALL CURB AND SIDEWALK WORK SHALL USE ALTERNATIVE CONSTRUCTION METHODS TO MINIMIZE EXTENSIVE ROOT
- EXPOSED ROOTS SHALL BE COVERED AT THE END OF THE DAY USING TECHNIQUES SUCH AS COVERING WITH SOIL, MULCH
- NO EQUIPMENT. VEHICLES OR MATERIALS SHALL OPERATE OR BE STORED WITHIN THE ROOT PROTECTION ZONE OF ANY TREE NEAR THE PROJECT, ROOT PROTECTION ZONE IS 1 FOOT OF RADIUS PER INCH OF TREE'S DIAMETER. A 10-INCH DIAMETER TREE WOULD HAVE A 10 FOOT RADIUS ROOT PROTECTION ZONE AROUND THE TREE. ROOTS OR BRANCHES IN CONFLICT WITH THE CONSTRUCTION SHALL BE CUT CLEANLY ACCORDING TO PROPER PRUNING METHODS. OAK WOUNDS SHALL BE PAINTED OVER WITHIN 30 MINUTES TO PREVENT OAK WILT.
- SAPLINGS, SHRUBS OR BUSHES TO BE CLEARED FROM THE PROTECTED ROOT ZONE AREA OF A LARGE TREE SHALL BE REMOVED BY HAND AS DESIGNATED BY THE INSPECTOR.
- NO WIRES, NAILS OR OTHER MATERIAL MAY BE ATTACHED TO PROTECTED TREES.
- TREES, TREE LIMBS, BUSHES AND SHRUBS LOCATED IN THE CITY STREET OR ALLEY RIGHT-OF-WAY OR PERMANENT EASEMENTS WHICH INTERFERE WITH PROPOSED CONSTRUCTION ACTIVITIES SHALL BE PROPERLY PRUNED FOLLOWING THE ANSI A-300 STANDARDS FOR PRUNING. ALL TREE PRUNING SHALL BE COMPLETED BY A CITY OF SAN ANTONIO TREE MAINTENANCE LICENSED CONTRACTOR (ARTICLE 21-171, CITY CODE) ONLY AFTER APPROVAL FROM THE CAPITAL PROJECTS MANAGEMENT THROUGH THE INSPECTOR.
- NO EXCESSIVE TREE TRIMMING WILL BE PERMITTED.
- ALL DEBRIS GENERATED BY THE PRUNING AND TRIMMING OF THE TREES AND / OR BUSHES SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF PROPERLY (NO SEPARATE PAY ITEM)
- TREES MUST BE MAINTAINED IN GOOD HEALTH THROUGHOUT THE CONSTRUCTION PROCESS. MAINTENANCE MAY INCLUDE BUT NOT LIMITED TO: WATERING THE ROOT PROTECTION ZONE, WASHING FOLIAGE, FERTILIZATION, PRUNING, ADDITIONAL MULCH APPLICATIONS AND OTHER MAINTENANCE AS NEEDED ON THE PROJECT.
- ANY TREE REMOVAL SHALL BE APPROVED BY THE CITY ARBORIST. (207-0278).
- TREES WHICH ARE DAMAGED OR LOST DUE TO THE CONTRACTOR'S NEGLIGENCE DURING CONSTRUCTION SHALL BE MITIGATED TO THE CITY'S SATISFACTION.
- TREE PLANTING FOR MITIGATION OR ENHANCEMENT: ALL PLANTED TREES SHALL BE MAINTAINED IN A HEALTHY CONDITION AT ALL TIMES. THIS INCLUDES IRRIGATION, FERTILIZING, PRUNING AND OTHER MAINTENANCE AS NEEDED ON THE PROJECT. TREES THAT DIE WITHIN TWELVE (12) MONTHS SHALL BE REPLACED WITH A TREE OF EQUAL SIZE AND


- THE CONTRACTOR SHALL PROVIDE AND MAINTAIN VEHICULAR AND PEDESTRIAN ACCESS AT ALL TIMES TO LOCAL RESIDENCES AND BUSINESSES.
- WHEN THE WORK REQUIRES THE EXCAVATION OF THE STREET AND THE REMOVAL OF THE EXISTING DRIVEWAY APPROACHES AND SIDEWALKS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING TEMPORARY ALL-WEATHER ACCESS TO THE BUSINESSES AND RESIDENCES. THE TEMPORARY DRIVEWAY APPROACHES SHALL BE CONSTRUCTED WIT. FLEXIBLE BASE OR GRAVEL MATERIAL AT NO SEPARATE COST TO THE CITY.
- PRIOR TO INITIATING THE CONSTRUCTION OF NEW DRIVEWAY APPROACHES, THE CONTRACTOR SHALL GIVE ADVANCE WARNING IN PERSON, OR IN WRITING, OF AT LEAST 48 HOURS TO EACH RESIDENCE THAT WILL BE IMMEDIATELY AFFECTED SO THAT ALTERNATE PLANS MAY BE MADE BY THE RESIDENTS.
- FOR BUSINESSES WITH MORE THAN ONE DRIVEWAY, AT LEAST ONE DRIVEWAY SHALL REMAIN OPEN WHILE THE OTHER NEW DRIVEWAY APPROACHES ARE CONSTRUCTED. FOR BUSINESSES WITH ONLY ONE DRIVEWAY, THE NEW DRIVEWAY APPROACH SHALL BE CONSTRUCTED IN HALF WIDTHS, UNLESS A TEMPORARY ASPHALT DRIVEWAY IS FIRST INSTALLED AT

RESIDENTIAL LOTS = 79

# MORGAN HEIGHTS PHASE 6

# BEXAR COUNTY, TEXAS

# STREET, DRAINAGE, WATER, SANITARY SEWER, AND UTILITY IMPROVEMENTS




LOCATION MAP

N.T.S.

OWNER/DEVELOPER TALLEY EXTENSION REVITALIZATION INITIATIVE, LLC. 5210 THOUSAND OAKS, SUITE 1318 SAN ANTONIO, TEXAS 78233

#### INDEX

DESCRIPTION	SHEET NO.
COVER SHEET	0.0
OVERALL UTILITY PLAN	1.0
MASTER DRAINAGE PLAN (1 OF 2)	2.0
MASTER DRAINAGE PLAN (2 OF 2)	2.1
OVERALL GRADING PLAN	3.0
DRAIN "A" PLAN & PROFILE (1 OF 2)	4.0
DRAIN "A" PLAN & PROFILE (2 OF 2)	4.1
DRAIN "B" PLAN & PROFILE (1 OF 4)	4.2
DRAIN "B" PLAN & PROFILE (2 OF 4)	4.3
DRAIN "B" PLAN & PROFILE (3 OF 4)	4.4
DRAIN "B" PLAN & PROFILE (4 0F 4)	4.5
DRAIN "C" PLAN & PROFILE (1 OF 2)	4.6
DRAIN "C" PLAN & PROFILE (2 OF 2)	
DRAIN DETAILS (1 OF 2)	4.8
DRAIN DETAILS ( 2 OF 2)	4.9
FROZEN VLG PLAN & PROFILE	5.0
TAZ WAY PLAN & PROFILE	5.1
TAMARON PARK	5.2
STREET DETAIL SHEET	5.3
CONCRETE DRIVEWAY DETAILS	5.4
WHEELCHAIR RAMP DETAILS	5.5
TXDOT PED-18 DETAILS	5.6
TRAFFIC SIGNAGE & PEDESTRIAN ACCESSIBILITY PLAN	5.7
PAVEMENT MARKING DETAILS	5.8
SIGN MOUNTING DETAILS (1 of 2)	5.9
SIGN MOUNTING DETAILS (2 of 2)	5.10
SANITARY SEWER COVER SHEET	6.0
OVERALL SANITARY SEWER PLAN	6.1
LINE "C" PLAN & PROFILE	6.2
LINE "D" PLAN & PROFILE	6.3
LINE "E" PLAN & PROFILE	6.4
WATER DISTRIBUTION COVER SHEET	7.0
WATER DISTRIBUTION PLAN	7.1
STORMWATER POLLUTION PREVENTION PLAN	8.0
STORMWATER POLLUTION PREVENTION DETAILS	8.1



hom the services were contracted or to whom it is certified. This drawing m

e copied, reused, disclosed, distributed or relied upon for any other pur

without the express written consent of Colliers Engineering & Design

FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW CALL811 COM

**PRELIMINARY** 

MORGAN HEIGHTS PHASE 6 PLAT# 23-11800391


> SAN ANTONIO BEXAR COUNTY TEXAS


& Design

SAN ANTONIO (KFW) San Antonio, TX 78231 Phone: 210.979.8444 TBPLS Firm#; 10194550

V2054006 205-40-06

COVER SHEET





oposed/Ultimate Conditions:												1		
Study Point	AREA	(Acres)	С	Tovrl (min)		Tsc (min)	Tch (min)	Ttot (min)	l5 (in/hr)	l25 (in/hr)	I100 (in/hr)	Q5 (ft3/s)	Q25 (ft3/s)	Q100 (ft3/s)
1	A-1	3.26	0.77	10.00		1.00	7.00	18	4.796	6.633	8.241	12.04	16.65	20.69
2	A-2	4.41	0.77	10.00		2.00	10.00	22	4.329	5.975	7.408	14.70	20.29	25.16
3	A-3	5.95	0.77	10.00		3.00	9.00	22	4.329	5.975	7.408	19.83	27.38	33.94
4	A-4	6.96	0.77	10.00		2.00	10.00	22	4.329	5.975	7.408	23.20	32.02	39.70
5	A-5	8.83	0.77	10.00		2.00	5.00	17	4.941	6.838	8.501	33.59	46.50	57.80
<u> </u>	A-6	2.01	0.77	10.00		2.00	3.00	17	4.541	0.030	0.501	33.39	40.50	37.80
_					CARRYOVER FROM									
6	PT.5 + PT. 7 + A-6	17.15	0.77	25.00	PT. 7	0.00	10.00	35	3.413	4.707	5.828	45.07	62.15	76.97
	A-6a	3.20	0.77											
6a	PT.2 + PT. 3 + PT.4 + PT.6 + A-6a	37.67	0.77	35.00	CARRYOVER FROM PT. 6	0.00	10.00	45	2.960	4.093	5.082	85.86	118.73	147.40
6b		38.88	0.77			YDROGRAPH D	ETENTION DO		NIII ATIONS			56.54	80.38	102.32
OD	PT. 6a				1 IXOIVITI	TDROGRAFITD	LILINIION FO	OND A CALC	JOLATIONS			30.34	00.30	102.52
	A-7	5.29	0.77	-	CARRYOVER FROM							<b></b>		<b></b>
7	PT. OS4 + A-7	6.31	0.76	16.00	PT. OS4	2.00	7.00	25	4.059	5.597	6.934	19.46	26.84	33.25
8	A-8	4.14	0.77	10.00		3.00	3.00	16	5.101	7.066	8.791	16.26	22.52	28.02
9a	A-9a	8.52	0.84	10.00		1.00	13.00	24	4.143	5.715	7.081	29.52	40.72	50.45
9b	A-9b	6.10	0.77	10.00		1.00	6.00	17	4.941	6.838	8.501	23.21	32.12	39.93
	A-9c-1	0.45	0.96											
9c-1	PT. 9b + A-9c-1	6.55	0.78	17.00	CARRYOVER FROM	0.00	4.00	21	4.432	6.120	7.591	22.73	31.39	38.93
90-1	P1. 90 + A-90-1	0.00	0.76	17.00	PT. 9b	0.00	4.00	21	4.432	0.120	7.591	22.13	31.39	36.93
9c-2	A-9c-2	2.92	0.77	10.00		1.00	7.00	18	4.796	6.633	8.241	10.78	14.91	18.53
	A-9c	0.16	0.96											
9c	PT.9c-1 + PT. 9c-2 + A-9c	9.63	0.78	21.00	CARRYOVER FROM PT. 9c-1	0.00	1.00	22	4.329	5.975	7.408	32.60	45.00	55.79
		6.72	0.77		F1.90-1	0.00	1.00	22	4.329	5.975	7.400	32.00	45.00	55.79
	A-10			<del>                                     </del>	CARRYOVER FROM							<u> </u>	$\vdash$	
10	PT. OS3 + A-10	6.97	0.77	15.00	PT. OS3	4.00	11.00	30	3.700	5.100	6.314	19.86	27.37	33.89
11	A-11	6.78	0.77	10.00		3.00	9.00	22	4.329	5.975	7.408	22.60	31.19	38.68
	A-12	7.05	0.70											
12	PT. 11 + PT. 22 +	•-		37.00	CARRYOVER FROM	6.00	0.00							
	PT.23 + A-12	95.32	0.71	07.00	PT. 22			43	3.042	4.203	5.214	205.87	284.47	352.91
12a		4 = 1		<b></b>	-	SEE MORGAN	HEIGHTS PH	ASE 5 SWMI	,			125.74	274.78	434.62
. =:	A-12b	1.86	0.77							<u> </u>		<u> </u>		
12b	PT. 12a +A-12b	97.18	0.77	44.00		0.00	1.00	45	2.960	4.093	5.082	221.49	306.30	380.25
12c	PT12b	97.18	0.77	45.00		0.00	0.00	45	2.960	4.093	5.082	221.49	306.30	380.25
13	A-13	6.65	0.77	10.00		3.00	6.00	19	4.664	6.447	8.005	23.88	33.01	40.99
	A-13a	2.81	0.77											
13a	PT. 8 + PT. 9+A-13a	15.47	0.77	22.00	CARRYOVER FROM PT. 9	0.00	8.00	30	3.700	5.100	6.314	44.07	60.75	75.21
13b	A-13b	1.34	0.82	10.00	11.0	4.00	0.00	14	5.468	7.600	9.480	6.01	8.35	10.42
105	A-14	0.83	0.53	10.00		1.00	0.00	,,	0.100	7.000	0.100	0.01	0.00	10.12
	A-14				CARRYOVER FROM									
14	PT.OS2C + A-14	9.78	0.66	21.00	PT.OS2C	0.00	0.00	21	4.432	6.120	7.591	28.53	39.39	48.86
15	A-15	11.85	0.67	14.00		3.00	5.00	22	4.329	5.975	7.408	34.37	47.44	58.82
	A-15a	1.37	0.67											
15a	DT 45 : 5 : 1	13.22	0.67	22.00	CARRYOVER FROM	0.00	1.00	23	4.233	5.841	7.239	37.49	51.73	64.12
	PT.15 + DA-15a				PT. 15	55					55		- · · · · ·	
	A-16	11.23	0.67	<del>                                     </del>	CARRYOVER							<u> </u>	<del>                                     </del>	
16	PT.26 + A-16	13.07	0.63	17.00	CARRYOVER FROM PT. 26	0.00	14.00	31	3.638	5.015	6.208	30.12	41.51	51.39
	A-16a	0.89	0.67											
16a		13.96	0.67	31.00	CARRYOVER FROM	0.00	1.00	32	3.579	4.933	6.107	33.47	46.14	57.12
10a	PT.16 + DA-16a	13.90	0.67	31.00	PT. 16	0.00	1.00	32	3.379	4.933	0.107	33.47	40.14	
17a	A-17a	0.44	0.41	14.00		3.00	0.00	17	4.941	6.838	8.501	0.89	1.23	1.53
	17b	0.95	0.41											
17b	PT.OS1 + PT.OS2A + PT.17A + A-17b	10.99	0.64	22.00	CARRYOVER FROM PT.OS1	0.00	0.00	22	4.329	5.975	7.408	30.31	41.84	51.87
	A-18	3.28	0.67	<del>                                     </del>	1 1.001									<del>                                     </del>
	PT.OS2B + PT.14 +				CARRYOVER FROM									
18	PT 17b + A-18	26.48	0.65	22.00	PT.17b	0.00	3.00	25	4.059	5.597	6.934	70.07	96.63	119.70
	A-18a	1.65	0.67											
18a	PT.10 + PT.15a +	48.32	0.67	25.00	CARRYOVER FROM	0.00	5.00	30	3.700	5.100	6.314	119.79	165.11	204.41
	PT.18 +DA-18a				PT. 18									
19	A-19	10.34	0.77	14.00		3.00	7.00	24	4.143	5.715	7.081	32.99	45.50	56.38
	A-20	1.40	0.67	<del>                                     </del>	CARRYOVER EDG:							<b></b> '	<b>├</b> ──	
20	PT.16a + PT.18a + DA-20	63.68	0.67	30.00	CARRYOVER FROM PT. 18a	0.00	4.00	34	3.466	4.779	5.918	147.90	203.91	252.48
	A-21	0.59	0.77	Ī										
21		10.93	0.77	24.00	CARRYOVER FROM	0.00	2.00	26	3.979	5.487	6.795	33.49	46.18	57.19
	PT.19 + DA-21			<u> </u>	PT. 19	0.00		_~	2.270	201	200	33.10		20
	A-22	0.85	0.77	<del>                                     </del>	CARRYOVER ET ST							<b></b> '		
22	PT.20 + PT.21 + DA-22	75.46	0.69	34.00	CARRYOVER FROM PT. 20	0.00	3.00	37	3.312	4.569	5.660	171.37	236.38	292.81
23	A-23	6.03	0.96	17.00		9.00	0.00	26	3.979	5.487	6.795	23.03	31.76	39.34
24a	A-24a	14.26	0.77	14.00		4.00	11.00	29	3.765	5.189	6.425	41.34	56.98	70.55
24b	A-24b	1.89	0.77	14.00		2.00	0.00	16	5.101	7.066	8.791	7.42	10.28	12.79
25	A-25	4.66	0.41	14.00		3.00	5.00	22	4.329	5.975	7.408	8.27	11.42	14.15
26	A-26	1.84	0.41	14.00		3.00	0.00	17	4.941	6.838	8.501	3.73	5.16	6.41
27	A-27	5.53	0.41	14.00		6.00	0.00	20	4.543	6.277	7.789	16.83	23.26	28.86
28	A-28	10.38	0.67	14.00		4.00	3.00	21	4.432	6.120	7.703 7.591	30.82	42.56	52.79
	A-28 A-29	0.96	0.67	17.00		7.00	0.00	<u>- 1</u>	1.702	5.120	7.001	55.52	,2.00	<u> </u>
		0.80	0.41		CARRYOVER FROM									
29	PT.27 + A-29	6.49	0.63	20.00	PT. 27	0.00	2.00	22	4.329	5.975	7.408	17.74	24.49	30.36
	A-30	3.04	0.67											
30	PT.28 + PT.29 + A-30	19.91	0.66	22.00		0.00	2.00	24	4.143	5.715	7.081	54.23	74.81	92.69
	A-31	0.47	0.41											
31	PT.OS5 + A-31	1.49	0.59	14.00	CARRYOVER FROM	1.00	0.00	15	5.280	7.320	9.115	4.63	6.41	7.99
O I				17.00	PT. 9	1.00	0.00	13	0.200	1.520	0,110	7.00	J.71	1.33
	A-32	12.55	0.77	ļ								<b></b> '		
32	PT.30 + PT.31+ A-32	33.95	0.70	24.00	CARRYOVER FROM PT. 30	0.00	1.00	25	4.059	5.597	6.934	95.91	132.26	163.84
OS-1	A-OS1	4.79	0.67	17.00	, 1. 50	5.00	0.00	22	4.329	5.975	7.408	13.89	19.18	23.78
OS-2A	A-OS1 A-OS2A	4.79	0.67	9.00		3.00	0.00	12	5.864	8.186	10.238	18.90	26.38	32.99
OS-2B	A-OS2A A-OS2B	2.43	0.67	14.00		3.00	0.00	17	4.941	6.838	8.501	8.04	11.13	13.84
UU-ZD				<del> </del>										
	A-OS2C	8.95	0.67	10.00		11.00	0.00	21	4.432	6.120	7.591	26.58	36.70	45.52
OS-2C	A 000		0.67	14.00	ī	1.00	0.00	15	5.280	7.320	9.115	0.88	1.23	1.53
OS-2C OS-3	A-OS3	0.25		44.44	1	2 2 2	^ ^ -			7 ~ ~ ~ .	^ -c ·	~	4 ~ .	
OS-2C	A-OS3 A-OS4 A-OS5	0.25 0.91 1.02	0.67 0.67	14.00 14.00		2.00 3.00	0.00	16 17	5.101 4.941	7.066 6.838	8.791 8.501	3.11 3.38	4.31 4.67	5.36 5.81




www.colliersengineering.com

Copyright © 2025. Colliers Engineering & Design All Rights Reserved. This drawing and all the information contained herein is authorized for use only by the party for whom the services were contracted or to whom it is certified. This drawing may not be copied, reused, disclosed, distributed or relied upon for any other purpose without the express written consent of Colliers Engineering & Design.

Formerly Known as



FOR STATE SPECIFIC DIRECT PHONE NUMBERS
VISIT: WWW.CALL811.COM



PRELIMINARY

FOR MORGAN HEIGHTS PHASE 6 PLAT# 23-11800391

> SAN ANTONIO BEXAR COUNTY TEXAS

**Colliers**Engineering & Design

SAN ANTONIO (KFW)

3421 Paesanos
Parkway
San Antonio, TX 78231
Phone: 210.979.8444

COLLIERS ENGINEERING & DESIGN, INC.
TBPE Firm#: F-14909
TBPLS Firm#: 10194550

ALE: DATE: DRAWN BY: CHECK
S SHOWN 07/20/2023 SD S

DJECT NUMBER: DRAWING NAME:
205-40-06 MD2054006


205-40-06 MD2054006


ET TITLE:


MASTER DRAINAGE PLAN (2 OF 2)


HEET NUMBER:


<u>Z.I</u>



































PRELIMINARY

FOR MORGAN HEIGHTS PHASE 6 PLAT# 23-11800391

> SAN ANTONIO BEXAR COUNTY TEXAS

**Colliers**Engineering & Design

3421 Paesanos
Parkway
San Antonio, TX 78231
Phone: 210.979.8444
COLLIERS ENGINEERING & DESIGN, INC.
TBPE Firm#: 10194550

SAN ANTONIO (KFW)


SSHOWN 07/20/2023 SD SC

OJECT NUMBER: DRAWING NAME:

205-40-06 DR2054006 - C

DRAIN "C" PLAN & PROFILE (2 OF 2)

CHEET NUMBER:






TABLE 9.3.8.1 - RETARDATION CLASS FOR LINING MATERIALS

Retardance Class	Cover	Condition
В	Bermuda grass	Good stand, tall (average 12 in. or 305 mm)
-	Native grass mixture little bluestem, bluestem, blue gamma, other short and long stem midwest grasses	Good stand, unmowed
-	Lespedeza sericea	Good stand, not woody, tall (average 19 in. or 480 mm)
-	Alfalfa	Good stand, uncut (average 11 in or 280 mm)
-	Blue gamma	Good stand, uncut (average 13 in. or 330 mm)
-	Crabgrass	Fair stand, uncut (10-to-48 in. or 55-to-1220 mm)
C	Bermuda grass	Good stand, mowed (average 6 in. or 150 mm)
-	Common lespedeza	Good stand, uncut (average 11 in. or 280 mm)
-	Grass-legume mixture: summer (orchard grass redtop, Italian ryegrass, and common lespedeza)	Good stand, uncut (6-8 in. or 150- 200 mm)
-	Centipede grass	Very dense cover (average 6 in. or 150 mm)
-	Kentucky bluegrass	Good stand, headed (6-12 in. or 150-305 mm)
D	Bermuda grass	Good stand, cut to 2.5 in. or 65 mm
-	Common lespedeza	Excellent stand, uncut (average 4.5 in. or 115 mm)
-	Buffalo grass	Good stand, uncut (3-6 in. or 75- 150 mm)
-	Grass-legume mixture: fall, spring (orchard grass Italian ryegrass, and common lespedeza	Good Stand, uncut (4-5 in. or 100- 125 mm)
-	Lespedeza sericea	After cutting to 2 in. or 50 mm (very good before cutting)
E	Bermuda grass	Good stand, cut to 1.5 in. or 40 mm
-	Bermuda grass	Burned stubble

Retardance Class C Vegetation (See the "Retardation Class for Lining Materials" table above)  Retardance Class D Vegetation (See the "Retardation Class for Lining Materials" table above)  Retardance Class E Vegetation (See the "Retardation Class for Lining Materials" table above)  Retardance Class E Vegetation (See the "Retardation Class for Lining Materials" table above)  Woven Paper  0.15  7	
Vegetation (See the "Retardation Class for Lining Materials" table above)  Retardance Class E Vegetation (See the "Retardation Class for Lining Materials" table above)  17	
"Retardation Class for Lining Materials" table above)	
Woven Paper         0.15         7	
Jute Net 0.45 22	
Single Fiberglass 0.6 29	
Double Fiberglass 0.85 41	
Straw W/Net         1.45         69	
Curled Wood Mat 1.55 74	
Synthetic Mat 2 96	
Gravel, D50 = 1 in. or 25 mm 0.4 19	
Gravel, D50 = 2 in. or 50 mm 0.8 38	
Rock, D50 = 6 in. or 150 mm 2.5	
Rock, D50 = 12 in. or 300 5 239 mm	
6-in. or 50-mm Gabions 35 1675	
4-in. or 100-mm Geoweb 10 479	
Soil Cement (8% cement)         >45         >2154	
Dycel w/out Grass >7 >335	
Petraflex w/out Grass >32 >1532	
Armorflex w/out Grass         12-20         574-957	
Erikamat w/3-in or 75-mm         13-16         622-766           Asphalt         622-766	
Erikamat w/1-in. or 25 mm <5 <239 Asphalt	
Armorflex Class 30 with longitudinal and lateral cables, no grass >5 >1628	

Retardance Class B

Dycel 100, longitudinal

cables, cells filled with mortar

Concrete construction blocks, granular filter underlayer

Wedge-shaped blocks with

drainage slot



**Product Data** 

LANDLOK 300® high performance turf reinforcement mat (HPTRM) is a three-dimensional, lofty, woven polypropylene geotextile that is available in green or tan which is specially designed for erosion control applications on steep slopes and vegetated waterways. The matrix is composed of polypropylene monofilament yarns featuring X3® technology woven into a uniform configuration of resilient pyramid-like projections. The material exhibits very high interlock and reinforcement capacity with both soil and root systems, demonstrates superior UV resistance, and enhances seedling emergence.

LANDLOK 300® conforms to the property values listed below¹ and is manufactured at a Propex facility having achieved ISO 9001:2000 certification. Propex performs internal Manufacturing Quality Control (MQC) tests that have been accredited by the Geosynthetic Accreditation Institute - Laboratory Accreditation Program (GAI-LAP).

MARV <sup>2</sup>				
PROPERTY	TEST METHOD	ENGLISH	METRIC	
ORIGIN OF MATERIALS	1	1		
% U.S. Manufactured Inputs		100%	100%	
% U.S. Manufactured		100%	100%	
PHYSICAL				
Mass/Unit Area	ASTM D-6566	7.5 oz/yd <sup>2</sup>	254.3 g/m <sup>2</sup>	
Thickness	ASTM D-6525	0.25 in	6.35 mm	
Light Penetration (% Passing)	ASTM D-6567	50% (Max)	50%	
Color	Visual	Green or Tan		
MECHANICAL				
Tensile Strength (Grab)	ASTM D-6818	2000 x 1800 lb/ft	29.2 x 26.3 kN/m	
Elongation	ASTM D-6818	50% (max)	50% (max)	
Resiliency	ASTM D-6524	70%	70%	
Flexibility	ASTM D-6575	0.195 in-lb (avg)	10.8 mg-cm (avg)	
ENDURANCE				
UV Resistance	ASTM D-4355	90%	90%	
% Retained 3000 hrs	ASTIVI D-4333	90%	9070	
PERFORMANCE				
Velocity <sup>3</sup> (Vegetated)	Large Scale	20 ft/sec	6.10 m/sec	
Shear Stress <sup>3</sup> (Vegetated)	Large Scale	12 lb/ft <sup>2</sup>	575 Pa	
Manning's "n" 4 (Unvegetated)	Calculated	0.030	0.030	
Seedling Emergence <sup>4</sup>	ECTC Draft Method #4	-	-	
ROLL SIZES		8.5 ft x 106 ft	2.6 m x 32.3 m	

2. MARV indicates minimum average roll value calculated as the typical minus two standard deviations. Statistically, it yields a 97.7% degree of confidence that any sample taken during quality assurance testing will exceed the value reported.

3. Maximum permissible velocity and shear stress has been obtained through vegetated testing programs featuring specific soil types, vegetation classes, flow conditions, and failure criteria. These conditions may not be relevant to every project nor are they replicated by other manufacturers. Please contact Propex for further information. 4. Calculated as typical values from large-scale flexible channel lining test programs with a flow depth of 6 to 12 inches.



ENGINEERING EARTH www.geotextile.com

Propex Operating Company, LLC · 6025 Lee Highway, Suite 425 · PO Box 22788 · Chattanooga, TN 37422 ph 423 899 0444 · ph 800 621 1273 · fax 423 899 7619

Geotex®, Landlok®, Pyramat®, X3®, SuperGro®, Petromat® and Petrotac® are registered trademarks of Propex Operating Company, LLC. This publication should not be construed as engineering advice. While information contained in this publication is accurate to the best of our knowledge, Propex does not warrant its accuracy or completeness. The ultimate customer and user of the products should assume sole responsibility for the final determination of the suitability of the information and the product, or such other written warranty as may be agreed by Propex and individual customers. Propex specifically disclaims all other warranties, express or implied, including without limitation, warranties of merchantability or fitness for a particular purpose, or arising from provision of samples, a course of dealing or usage of trade.

© 2011 Propex Operating Company, LLC



Engineering & Design


www.colliersengineering.com

pyright © 2025. Colliers Engineering & Design All Rights Reserved. This draw hom the services were contracted or to whom it is certified. This drawing may pe copied, reused, disclosed, distributed or relied upon for any other purp without the express written consent of Colliers Engineering & Design.

ormerly Known as

PROTECT YOURSELF
ALL STATES REQUIRE NOTIFICATION OF
EXCAVATORS, DESIGNERS, OR ANY PERSO
PREPARING TO DISTURB THE EARTH'S
SURFACE ANYWHERE IN ANY STATE FOR STATE SPECIFIC DIRECT PHONE NUMBERS

VISIT: WWW.CALL811.COM



PRELIMINARY

**MORGAN HEIGHTS** PHASE 6 PLAT# 23-11800391

> SAN ANTONIO BEXAR COUNTY TEXAS


	Colliers
ı	Engineering & Design


3421 Paesanos San Antonio, TX 78231 Phone: 210.979.8444 COLLIERS ENGINEERING & DESIGN, INC TBPE Firm#: F-14909 TBPLS Firm#: 10194550


SAN ANTONIO (KFW)

AS SHOWN 205-40-06 DRDT2054006

DRAIN DETAILS ( 1 OF 2)









www.colliersengineering.com

Formerly Known as


opyright © 2025. Colliers Engineering & Design All Rights Reserved. This drawing nd all the information contained herein is authorized for use only by the party for shom the services were contracted or to whom it is certified. This drawing may no e copied, reused, disclosed, distributed or relied upon for any other purpose without the express written consent of Colliers Engineering & Design.

PROTECT YOURSELF

ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSO PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE

FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

NOI AIPTION



PRELIMINARY

FOR
MORGAN HEIGHTS
PHASE 6
PLAT# 23-11800391

SAN ANTONIO BEXAR COUNTY TEXAS

**Colliers**Engineering & Design

SAN ANTONIO (KFW)

3421 Paesanos
Parkway
San Antonio, TX 78231
Phone: 210.979.8444

COLLIERS ENGINEERING & DESIGN, INI
TBPE Firm#: F-14909
TBPLS Firm#: 10194550

CALE: DATE: DRAWN BY: CHECKE


AS SHOWN 07/20/2023 SD S0


ROJECT NUMBER: DRAWING NAME:


205-40-06 DRDT2054006


DRAIN DETAILS ( 2 OF 2)

BER:










#### TYPICAL LOCAL "A" STREET SECTION

USE LOCAL "A" STREET SECTION FOR STREETS BELOW:

TAZ WAY - STA: 5+52.25 TO END FROZEN VLG - STA: 9+89.02 TO STA: 11+78.81 SNOW VW - STA: 11+78.81 TO STA: 17+37.35 PRINCESS WAY - STA: 17+37.35 TO STA: 28+23.06 TAMARON PARK - STA: 28+23.06 TO END

Pavement Section 2.0" HMAC Type "D" 8.50" Aggregate Base (Type B, Grade 1) 6" LIME STABILIZED SUBGRADE (32 LBS/SY) Total: 16.50" Structural No: 2.55 CBR: 3.0



#### GENERAL NOTES:

1. THE SUBGRADE SOILS SHOULD BE TESTED FOR SOLUBLE SULPHATE CONTENT PRIOR TO INSTALLATION OF THE LIME OR CEMENT.

2. THE APPLICATION RATE OF LIME SHALL BE DETERMINED BASED ON LABORATORY TESTING AND SHALL BE THE LOWEST PERCENTAGE OF LIME THAT PROVIDES AN UNCONFINED COMPRESSIVE STRENGTH (UCS) AT 7-DAYS OF AT LEAST 160 PSI IN ACCORDANCE WITH ASTM D5102 STANDARD TEST METHODS FOR UNCONFINED COMPRESSIVE STRENGTH OF COMPACTED SOIL-LIME MIXTURES (PROCEDURE B) (IN ADDITION, CURING SHOULD OCCUR FOR 7 DAYS AT 40° AND SPECIMENS SHOULD BE SUBJECT TO 24-HR CAPILLARY SOAK PRIOR TO TESTING.


#### ASPHALT PAVEMENT DETAIL NOT-TO-SCALE DETAIL FOR ALL LOCAL TYPE A

1. PAVEMENT DESIGN THICKNESS BASED ON GEOTECHNICAL REPORT BY INTEC, L.P., PROJECT NO. S231271 DATED NOVEMBER 18, 2023 (SIGNED & SEALED: NOVEMBER 23, 2023)


2. REFERENCE PROJECT GEOTECHNICAL REPORT AND PROJECT SPECIFICATION FOR ADDITIONAL REQUIREMENTS AND ALTERNATE PAVEMENT SECTIONS.

3. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING MATERIAL TESTING. TESTING TO BE PAID BY OWNER.


4. CONTRACTOR MAY LEAVE VERTICAL CUT BANKS AT R.O.W. LINE AND MEDIANS PROVIDED PROJECT GEOTECHNICAL ENGINEER DETERMINES ROCK IS COMPETENT TO STAND ON ITS OWN.




NOT TO SCALE











TIMBER GUARD POST DETAIL NOT-TO-SCALE




CONCRETE CURB ITEM 500 ON ASPHALT TREATED BASE OR ASPHALTIC CONCRETE BASE NOT TO SCALE



FOR CONSTRUCTION VERIFICATION THE FOLLOWING SHALL BE CONDUCTED IN THE

- 1. AFTER INITIAL MIXING THE SOIL-LIME MIXTURE SHALL MELLOW FOR A PERIOD OF TWO TO THREE (2 - 3) DAYS. MAINTAIN MOISTURE DURING MELLOWING;
- 2. AFTER MELLOWING AND FINAL MIXING, THE PULVERIZATION SHALL BE CHECKED USING THE FOLLOWING CRITERIA (REMOVE NON-SLAKING AGGREGATES RETAINED ON THE 3/4 INCH SIEVE FROM THE SAMPLE): MINIMUM PASSING 1 ¾" SIEVE MINIMUM PASSING 3/4" SIEVE MINIMUM PASSING NO. 4 SIEVE
- 3. SAMPLE SOIL-LIME MIXTURE FOR DETERMINATION OF MAXIMUM DRY DENSITY (MDD). IN THE LABORATORY, MOLD SPECIMENS TO 95% OF MDD AT OPTIMUM MOISTURE CONTENT AND VERIFY UCS TO BE AT LEAST 160 PSI IN ACCORDANCE WITH PROCEDURE OUTLINED ABOVE FOR MIXTURE DESIGN.
- 4. COMPACT AND CHECK FIELD DENSITY (MINIMUM OF 95% OF MDD REQUIRED)
- 5. CURE FOR AN ADDITIONAL 2 TO 5 DAYS (TOTAL MELLOWING AND CURING TIME SHOULD TOTAL AT LEAST 5 DAYS).
- 6. VERIFY DEPTH OF LIME STABILIZED LAYER TO DEPTH AS NOTED ON PLAN TO WITHIN ± 1.0 INCH.

- ANY FILL USED TO RAISE THE SUBGRADE: SHOULD NOT CONTAIN ANY DELETERIOUS MATERIAL. SHOULD HAVE A CBR VALUE OF 3.0 OR GREATER
- SHOULD NOT HAVE GRAVELS LARGER THAN 3 INCH IN SIZE PI SHOULD BE LESS THAN 55




**Colliers** 

Engineering & Design

www.colliersengineering.com

opyright © 2024. Colliers Engineering & Design All Rights Reserved. This draw and all the information contained herein is authorized for use only by the party fo whom the services were contracted or to whom it is certified. This drawing may n be copied, reused, disclosed, distributed or relied upon for any other purpo

without the express written consent of Colliers Engineering & Design.



**PRELIMINARY** 

FOR **MORGAN HEIGHTS** PHASE 6 PLAT# 23-11800391


> SAN ANTONIO **BEXAR COUNTY** TEXAS

Colliers Engineering & Design

SAN ANTONIO (KFW) 3421 Paesanos Parkway San Antonio, TX 78231 Phone: 210.979.8444 COLLIERS ENGINEERING & DESIGN, INC TBPE Firm#: F-14909 TBPLS Firm#: 10194550


AS SHOWN TDT2054006 205-40-06

STREET DETAIL SHEET




#### TYPICAL RESIDENTIAL DRIVEWAY SECTION

WITH SIDEWALK ABUTTING CURB ITEM 503.1



### TYPICAL RESIDENTIAL DRIVEWAY SECTION

WHERE PROPERTY IS LOWER THAN STREET & SIDEWALK IS ABUTTING CURB ITEM 503.1



## TYPICAL COMMERCIAL DRIVEWAY SECTION

WITH SIDEWALK ABUTTING CURB


ITEM 503.2

### CONCRETE DRIVEWAY NOTES

- 1. DRIVEWAY PENETRATION REFERS TO A PORTION OF THE DRIVEWAY THAT MAY BE NECESSARY TO RECONSTRUCT WITHIN PRIVATE PROPERTY TO COMPLY WITH A MAXIMUM DRIVEWAY SLOPE. THIS PORTION OF THE DRIVEWAY SHALL BE PAID FOR UNDER THE FOLLOWING ITEMS AS MAY APPLY: A.) CONCRETE DRIVEWAY PAID FOR UNDER ITEM NO. 503.1 OR 503.2.
- B.) ASPHALTIC CONCRETE DRIVEWAY PAID FOR UNDER ITEM NO. 503.4 AND SHALL INCLUDE A MINIMUM OF 1" ASPHALT TYPE 'D' & 6" FLEXIBLE BASE C.) GRAVEL DRIVEWAY PAID FOR UNDER ITEM NO. 503.5 AND SHALL INCLUDE A MINIMUM OF 6" FLEXIBLE BASE
- 2. 7" MINIMUM HEIGHT WILL NOT NECESSARILY OCCUR AT THE PROPERTY LINE. IT MAY OCCUR WITHIN THE RIGHT OF WAY OR WITHIN THE DRIVEWAY PENETRATION ON PRIVATE PROPERTY.
- 3. THE PROPOSED DRIVEWAY SHOULD MATCH THE EXISTING WIDTH AT THE PROPERTY LINE BUT UNLESS AUTHORIZED BY THE CITY TRAFFIC ENGINEER, THE WIDTH SHALL BE WITHIN THE FOLLOWING VALUES:


TYPE	мінімим	MAXIMUM
RESIDENTIAL	10'	20'
COMMERCIAL - ONE WAY	12'	20'
COMMERCIAL - TWO WAY	24'	30'

- 4. FOR LOCAL TYPE "A" STREETS, SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 4' AND IF SEPARATED FROM THE CURB, THE SIDEWALK SHALL BE LOCATED A MINIMUM OF 3' FROM THE BACK OF CURB.
- 5. FOR OTHER THAN LOCAL TYPE "A" STREETS, THE SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 4' AND SEPARATED A MINIMUM OF 3' FROM THE BACK OF CURB OR, AS AN OPTION, THE SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 6' WHEN LOCATED AT THE BACK OF CURB.
- 6. DUMMY JOINTS PARALLEL TO THE CURB SHALL BE PLACED WHERE THE SIDEWALK MEETS THE DRIVEWAY. DUMMY JOINTS PERPENDICULAR TO THE CURB, AND WITHIN THE BOUNDARIES OF THE PARALLEL DUMMY JOINTS, SHALL BE PLACED AT INTERVALS EQUAL TO THE WIDTH OF THE SIDEWALK.
- 7. A MINIMUM OF TWO ROUND AND SMOOTH DOWEL BARS 3 /8" IN DIAMETER AND 18" IN LENGTH SHALL BE SPACED 18" APART AT EACH EXPANSION JOINT.
- 8. SIDEWALK RAMP LENGTHS SHALL BE OF SUFFICIENT LENGTH TO MAINTAIN 8.33% (1:12) MAXIMUM SLOPE. WHERE SIDEWALKS CROSS DRIVEWAYS, SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2%.
- 9. SIDEWALK RAMP SURFACE SHALL BE BRUSH FINISHED.



### TYPICAL RESIDENTIAL DRIVEWAY SECTION


WITH SIDEWALK SEPARATED FROM CURB ITEM 503.1



2 THE ALGEBRAIC DIFFERENCE OF G1 & G2 SHALL BE 14% OR LESS

#### TYPICAL RESIDENTIAL DRIVEWAY SECTION


WHERE PROPERTY IS LOWER THAN STREET & SIDEWALK IS SEPARATED FROM CURB



#### TYPICAL COMMERCIAL DRIVEWAY SECTION

WITH SIDEWALK SEPARATED FROM CURB

ITEM 503.2




1. COST OF REINFORCEMENT TO BE INCLUDED IN UNIT COST OF ITEM 307.1. 2. CONCRETE RETAINING WALL COMBINATION TYPE SHALL BE USED FOR

# DRIVEWAY - CONCRETE RETAINING WALL

ON COMPACTED SUBGRADE ITEM 307.1


CONCRETE DRIVEWAYS.



② RESIDENTIAL : 2' MAXIMUM; COMMERCIAL: SEE PLAN VIEW


## CURB PROFILE AT DRIVEWAY

WITH SIDEWALK ABUTTING CURB




#### TYPICAL DRIVEWAY PLAN VIEW

WITH SIDEWALK ABUTTING CURB



② RESIDENTIAL : 2' MAXIMUM; COMMERCIAL: SEE PLAN VIEW

#### CURB PROFILE AT DRIVEWAY



① 8% MAX. TO THE EDGE OF THE SIDEWALK IF SIDEWALK SEPARATION IS 4' OR GREATER.

② 45 FOR COMMERCIAL DRIVEWAY

TYPICAL DRIVEWAY PLAN VIEW

WITH SIDEWALK SEPARATED FROM CURB

#### MAY 2009

## CITY OF SAN ANTONIO

CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

#### CONCRETE DRIVEWAY STANDARDS

% SUBMITTAL PROJECT NO.: DRWN. BY: V. VASQUEZ DSGN. BY: CHKD. BY: R.S. HOSSEINI, P.E. SHEET NO.: OF Colliers

Engineering & Design

www.colliersengineering.com

pyright © 2024. Colliers Engineering & Design All Rights Reserved. This drav nd all the information contained herein is authorized for use only by the party


without the express written consent of Colliers Engineering & Design.

hom the services were contracted or to whom it is certified. This drawing may

e copied, reused, disclosed, distributed or relied upon for any other pure



FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM



**PRELIMINARY** 

MORGAN HEIGHTS PHASE 6

SAN ANTONIO


PLAT# 23-11800391


BEXAR COUNTY TEXAS SAN ANTONIO (KFW)


3421 Paesanos Colliers San Antonio, TX 78231 Phone: 210.979.8444 Engineering COLLIERS ENGINEERING & DESIGN, INC & Design TBPE Firm#; F-14909 TBPLS Firm#; 10194550


AS SHOWN 205-40-06 ГDT2054006


CONCRETE DRIVEWAY DETAILS


















**TXDOT PED-18 DETAILS** 











PRELIMINARY

FOR
MORGAN HEIGHTS
PHASE 6
PLAT# 23-11800391

SAN ANTONIO BEXAR COUNTY TEXAS

Colliers

Engineering
& Design

SAN ANTONIO (KFW)

3421 Paesanos
Parkway
San Antonio, TX 78231
Phone: 210.979.8444

COLLIERS ENGINEERING & DESIGN, INC.
TBPE Firm#: F-14909
TBPLS Firm#: 10194550


 CALE:
 DATE:
 DRAWN BY:
 CHECKEE


 AS SHOWN
 07/20/2023
 SD
 SC


 PROJECT NUMBER:
 DRAWING NAME:
 TSDT2054006
 TSDT2054006


PAVEMENT MARKING

DETAILS











www.colliersengineering.com


pyright © 2025. Colliers Engineering & Design All Rights Reserved. This drav hom the services were contracted or to whom it is certified. This drawing ma e copied, reused, disclosed, distributed or relied upon for any other pure

without the express written consent of Colliers Engineering & Design.

Formerly Known as



FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM



**PRELIMINARY** 

FOR **MORGAN HEIGHTS** PHASE 6 PLAT# 23-11800391

> SAN ANTONIO **BEXAR COUNTY** TEXAS


SAN ANTONIO (KFW) **Colliers** Engineering & Design

Parkway San Antonio, TX 78231 Phone: 210.979.8444 COLLIERS ENGINEERING & DESIGN, INC TBPE Firm#; F-14909 TBPLS Firm#; 10194550

3421 Paesanos

AS SHOWN SD WING NAME: SDT2054006 205-40-06

SIGN MOUNTING DETAILS (1 OF 2)







www.colliersengineering.com

iopyright © 2025. Colliers Engineering & Design All Rights Reserved. This drawi and all the information contained herein is authorized for use only by the party the whom the services were contracted or to whom it is certified. This drawing may relected, reused, disclosed, distributed or relied upon for any other purpowithout the express written consent of Colliers Engineering & Design.

Formerly Known as



FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM



PRELIMINARY

FOR
MORGAN HEIGHTS
PHASE 6

PLAT# 23-11800391

SAN ANTONIO BEXAR COUNTY

TEXAS

**Colliers**Engineering

3421 Paesanos Parkway San Antonio, TX 78231 Phone: 210.979.8444 COLLIERS ENGINEERING & DESIGN, INC TBPE Firm#: F-14909

SAN ANTONIO (KFW)

& Design

COLLIERS ENGINEERING & DESIGN
TBPE Firm#: F-14909
TBPLS Firm#: 10194550

CALE: DATE: DRAWN BY: CHECK!

AS SHOWN 07/20/2023 SD S

JECT NUMBER: DRAWING NAME:
205-40-06 CVOS2054006

ET TITLE:

SIGN MOUNTING DETAILS (2 of 2)

#### GENERAL INFORMATION

GENERAL SEWER NOTES (REVISED JULY 2017)

1. All materials and construction procedures within the scope of this contract shall be approved by the San Antonio Water System (SAWS) and comply with the Plans, Specifications, General Conditions and with the following as applicable:

- A. Current Texas Commission on Environmental Quality (TCEQ) "Design Criteria for Domestic Waste water System", Texas Administrative Code (TAC) Title 30 Part 1 Chapter 217 and "Public Drinking Water", TAC Title 30 Part 1 Chapter 290.
- B. Current TXDOT "Standard Specifications for Construction of Highways, Streets and Drainage".
  C. Current "San Antonio Water System Standard Specifications for Water and Sanitary Sewer
- Construction .

  Current City of San Antonio "Standard Specifications for Public Works Construction".

  Current City of San Antonio "Utility Excavation Criteria Manual" (UECM).

2. The contractor shall not proceed with any pipe installation work until they obtain a copy of the approved Counter Permit or General Construction Permit (GCP) from the consultant and has been notified by SAWS Construction I nspection Division to proceed with the work and has arranged a meeting with the inspector and consultant for the work requirements. Work completed by the contractor without an approved Counter Permit and/or a GCP will be subject to removal and replacement at the expense of the contractors and/or the developer.

3. The Contractor shall obtain the SAWS Standard Details from the SAWS website,

http://www.saws.org/business\_center/specs. Unless otherwise noted within the design plans.

4. The Contractor is to make arrangements with the SAWS Construction Inspection Division at (210) 233-2973, on notification procedures that will be used to notify affected home residents and/or property owners 48 hours prior to beginning any work.

5. Location and depth of existing utilities and service laterals shown on the plans are understood to be approximate. Actual locations and depths must be field verified by the Contractor at least 1 week prior to construction. It shall be the Contractor's responsibility to locate utility service lines as required for construction and to protect them during construction at no cost to SAWS.

6. The Contractor shall verify the exact location of underground utilities and drainage structures at least 1-2 weeks prior to construction whether shown on plans or not. Please allow up to 7 business days for locates requesting pipe location markers on SAWS facilities. The following contact information are supplied for verification purposes:

SAWS Utility Locates: http://www.saws.org/Service/Locates COSA Drainage (210) 207-0724 or (210) 207-6026 COSA Traffic Signal Operations (210) 206-8480 COSA Traffic Signal Damages (210) 207-3951 Texas State Wide One Call Locator 1-800-545-6005 or 811

7. The Contractor shall be responsible for restoring existing fences, curbs, streets, driveways, sidewalks, landscaping and structures to its original or better condition if damages are made as a result of the project's

8. All work in Texas Department of Transportation (TxDOT) and/or Bexar County right-of-way shall be done in accordance with respective construction specifications and permit requirements.

9. The Contractor shall comply with City of San Antonio or other governing municipality's tree ordinances when excavating near trees.

10. The Contractor shall not place any waste materials in the 100-year Flood Plain without first obtaining an approved Flood Plain Permit.

11. Holiday Work: Contractors will not be allowed to perform SAWS work on SAWS recognized holidays. Request should be sent to constworkreq@saws.org. Weekend Work: Contractors are required to notify the SAWS Inspection Construction Department 48 hours in advance to request weekend work. Request should be sent to constworkreq@saws.org. Any and all SAWS utility work installed without holiday/weekend approval will be subject to be uncovered for proper inspection.

12. Compaction note (Item 804): The contractor shall be responsible for meeting the compaction requirements on all trench backfill and for paying for the tests performed by a third party. Compaction tests will be done at one location point randomly selected, or as indicated by the SAWS Inspector and/or the test administrator, per each 12-inch loose lift per 400 linear feet at a minimum. This project will not be accepted and finalized by SAWS without this requirement being met and verified by providing all necessary documented test results.

13. A copy of all testing reports shall be forwarded to SAWS Construction Inspection Division.

#### Sewer No

1. The Contractor is responsible for ensuring that no Sanitary Sewer Overflow (SSO) occurs as a result of their work. All contractor personnel responsible for SSO prevention and control shall be trained on proper response. Should an SSO occur, the contractor shall:

- A. Identify the soruce of the SSO and notify SAWS Emergency Operations Center (EOC) immediately at (210) 233-2014. Provide the address of the spill and en estimated volume or flow.
- B. Attempt to eliminate the source of the SSO
- C. Contain sewage from the SSO to the extent of preventing a possible contamination of waterways.
   D. Clean up spill site (return contained sewage to the collection system if possible) and properly
- dispose of contaminated soil/materials.

  E. Clean the affected sewer mains and remove any debris.
- F. Meet all post-SSO requirements as per the EPA Consent Decree, including line cleaning and televising the affected sewer mains (at SAWS direction) within 24 hours.

Should the Contractor fail to address an SSO immediately and to SAWS satisfaction, they will be responsible for all cost incurred by SAWS, including any fines from EPA, TCEQ and/or any other Federal, State or Local Agencies.

No separate measurement or payment shall be made for this work. All work shall be done according to guidelines set by TCEQ and SAWS.

2. If bypass pumping is required, the Contractor shall perform such work in accordance with SAWS Standard

Specification for Water and Sanitary Sewer Construction, Item No. 864, "Bypass Pumping".

3. Prior to tie-ins, any shutdowns of existing force mains of any size must be coordinated with the SAWS Construction Inspection Division at (210) 233-2973 at least one week in advance of the shutdown. The Contractor must also provide a sequence of work as related to the tie-ins: this is at no additional cost to SAWS or the project and it is the responsibility of the Contractor sequence the work accordingly.

4. Sewer pipe where water line crosses shall be 160 psi and meet the requirements of ASTM D2241, TAC 217.53 and TCEQ 290.44(Ee)(4)(B). Contractor shall center a 20' joint of 160 psi pressure rated PVC at the proposed water crossing.

5. ELEVATIONS POSTED FOR TOP OF MANHOLES ARE FOR REFERENCE ONLY: It shall be the responsibility of the Contractor to make allowances and adjustments for top of manholes to match the finished grade of the project's improvements. (NSPI).


6. Spills, Overflows, or Discharges of Wastewater: All Spills, overflows, or discharges of wastewater, recycled water, petroleum products, or chemicals must be reported immediately to the SAWS Inspector assigned to the Counter Permit or GEneral Construction Permit (GCP). This requirement applies to every spill, overflow, or discharge regardless of size.

7. Manhole and all pipe testing (including the TV inspection) must be performed and passed prior to Final Field Acceptance by SAWS Construction Inspection Division, as per SAWS Specifications For Water and Sanitary Sewer Construction

8. All PVC pipe over 14 feet of cover shall be extra strength with minimum pipe stiffness of 115 psi.

# MORGAN HEIGHTS PHASE 6

# BEXAR COUNTY, TEXAS SANITARY SEWER IMPROVEMENTS



LOCATION MAP

N.T.S.

OWNER/DEVELOPER
TALLEY EXTENSION REVITALIZATION INITIATIVE, LLC.
5210 THOUSAND OAKS, SUITE 1318
SAN ANTONIO, TEXAS 78233

### *INDEX*

DESCRIPTION	SHEET NO.
SANITARY SEWER COVER SHEET	6.0
OVERALL SANITARY SEWER PLAN	6.1
LINE "C" PLAN & PROFILE	6.2
LINE "D" PLAN & PROFILE	6.3
LINE "E" PLAN & PROFILE	6.4

Copyright © 2024 Collers Engineering & Design All Rights Reserved. This drawing and all the Information contained them is subtrieted for such by the party for whom the services were contracted or to whom it is critified. This drawing may not be copied, extended, distributed or rolled upon for any other purpose without the express written consent of Colliers Engineering & Design.

Formerly Known as


PROTECT YOURSELF
ALL STATES REQUIRE NOTHINGATION OF EXCANATIONS, DESIGNARS, OR ANY PERSON PREPARING TO DISTURE THE EARTH'S SURFACE ANYWHERE IN ANY STATE

FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

NOTE: WWW.CALL811.COM

JEFFREY W. MARTIN
120004

Engineering & Design



PRELIMINARY

FOR
MORGAN HEIGHTS
PHASE 6
PLAT# 23-11800391

SAN ANTONIO BEXAR COUNTY TEXAS

Engineering & Design

SEWER - FAR WEST SEWERSHED - MEDIO CREEK W.R.C

TOTAL ACREAGE: 16.66 ACRES

DEVELOPER'S NAME: TALLEY EXTENSION REVITALIZATION INITIATIVE, LLC

TOTAL LINEAR FOOTAGE OF PIPE: 2,264 LF OF 8" SDR 26 PLAT NO.: 23-11800391

DEVELOPER'S ADDRESS: 5210 THOUSAND OAKS, SUITE 1318

SAWS BLOCK MAP#: 062600, 064600, 062598, 064598

CITY: SAN ANTONIO

PHONE#: (210) 490-1798

SAN ANTONIO (KFW)


3421 Paesanos
Parkway
San Antonio, TX 78231
Phone: 210.979.8444


COLLIERS ENGINEERING & DESIGN, IN
TBPE Firm#: F-14909
TBPLS Firm#: 10194550

DRAWING NAME:
0-06 CVOS2054006

SANITARY SEWER COVER SHEET

6.0





CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL

PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY

PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE

AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE

DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY

CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR

TRENCH EXCAVATION SAFETY PROTECTION

NOTES:

1. SEWER PIPE WHERE WATER LINE CROSSES SHALL BE MEET THE REQUIREMENTS OF ASTM D2241. CONTRACTOR SHALL CENTER A 20 FOOT JOINT OF 160 P.S.I. PRESSURE RATED P.V.C. AT THE PROPOSED WATER CROSSING (NO SEPARATE PAY ITEM). REFERENCE SHEET 6.0, SANITARY SEWER GENERAL NOTES, S.A.W.S. CRITERIA FOR SEWER MAIN CONSTRUCTION IN THE VICINITY OF WATER

REF. SHEET 6.1 FOR BENCHMARK INFORMATION.

PIPE TYPE DESIGNATIONS ARE SDR 26. REF. THIS SHEET FOR TYPICAL SANITARY SEWER / WATER CROSSING DETAIL. ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL BE IN ACCORDANCE WITH THE SAN ANTONIO WATER SYSTEM (SAWS) STANDARD SPECIFICATIONS.

CAUTION!!: THE CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITED TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION  $\uparrow$  FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE

MANHOLE NOTE: ALL MANHOLES MUST BE WATERTIGHT, WITH WATERTIGHT RINGS AND COVERS. THESE MANHOLES MUST BE VENTED PER SAWS DETAIL DD852-02.

SEWER - FAR WEST SEWERSHED - MEDIO CREEK W.R.C. DEVELOPER'S NAME: TALLEY EXTENSION REVITALIZATION INITIATIVE, LLC

DEVELOPER'S ADDRESS: 5210 THOUSAND OAKS, SUITE 1318 CITY: SAN ANTONIO STATE: TEXAS PHONE#: (210) 490-1798 FAX#: TOTAL ACREAGE: 16.66 ACRES

SAWS BLOCK MAP#: 062600, 064600, 062598, 064598 TOTAL EDU'S: 79 TOTAL LINEAR FOOTAGE OF PIPE: 2,264 LF OF 8" SDR 26 PLAT NO.: 23-11800391

> without the express written consent of Colliers Engineering & Design. Formerly Known as PROTECT YOURSELF
>
> ALL STATES REQUIRE NOTIFICATION OF
> EXCAVATORS, DESIGNERS, OR ANY PERSO
> PREPARING TO DISTURB THE EARTH'S
> SURFACE ANYWHERE IN ANY STATE FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

**Colliers** 

Engineering

& Design

www.colliersengineering.com pyright © 2024. Colliers Engineering & Design All Rights Reserved. This draw whom the services were contracted or to whom it is certified. This drawing may

be copied, reused, disclosed, distributed or relied upon for any other purp

JEFFREY W. MARTIN

**PRELIMINARY** 

FOR **MORGAN HEIGHTS** PHASE 6 PLAT# 23-11800391


> SAN ANTONIO **BEXAR COUNTY TEXAS**


Colliers Engineering & Design

SAN ANTONIO (KFW) 3421 Paesanos San Antonio, TX 78231 Phone: 210.979.8444 COLLIERS ENGINEERING & DESIGN, INC TBPE Firm#: F-14909 TBPLS Firm#: 10194550

AS SHOWN 205-40-06 SPP2054006\_C

LINE "C" PLAN & PROFILE





**Colliers** 

& Design


www.colliersengineering.com

hom the services were contracted or to whom it is certified. This drawing may

PROTECT YOURSELF

ALL STATES REQUIRE NOTIFICATION OF
EXCAVATORS, DESIGNERS, OR ANY PERSO
PREPARING TO DISTURB THE EARTH'S
SURFACE ANYWHERE IN ANY STATE

FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM




**PRELIMINARY** 

**MORGAN HEIGHTS** PHASE 6 PLAT# 23-11800391

> SAN ANTONIO **BEXAR COUNTY TEXAS**

> > 3421 Paesanos Parkway San Antonio, TX 78231 Phone: 210.979.8444 COLLIERS ENGINEERING & DESIGN, INC TBPE Firm#: F-14909 TBPLS Firm#: 10194550

LINE "D" PLAN & PROFILE



1+00

2+00

3+00

4+00

5+00

7+00

8+00

9+00

6+00

**Colliers** 

Engineering & Design

www.colliersengineering.com

hom the services were contracted or to whom it is certified. This drawing may be copied, reused, disclosed, distributed or relied upon for any other purp without the express written consent of Colliers Engineering & Design.

PROTECT YOURSELF

ALL STATES REQUIRE NOTIFICATION OF
EXCAVATORS, DESIGNERS, OR ANY PERSO
PREPARING TO DISTURB THE EARTH'S
SURFACE ANYWHERE IN ANY STATE

FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM



**PRELIMINARY** 

FOR **MORGAN HEIGHTS** PHASE 6 PLAT# 23-11800391

> SAN ANTONIO **BEXAR COUNTY TEXAS**

3421 Paesanos Parkway San Antonio, TX 78231 Phone: 210.979.8444 COLLIERS ENGINEERING & DESIGN, INC TBPE Firm#: F-14909 TBPLS Firm#: 10194550

LINE "E" PLAN & PROFILE

NOTE: DO NOT SCALE DRAWINGS FOR CONSTRUCTION.

10+00

#### GENERAL INFORMATION

#### GENERAL WATER NOTES

1. All materials and construction procedures within the scope of this contract shall be approved by the San Antonio Water System (SAWS) and comply with the Plans, Specifications, General Conditions and with the following as applicable:

- A. Current Texas Commission on Environmental Quality (TCEQ) "Design Criteria for Domestic Waste water System", Texas Administrative Code (TAC) Title 30 Part 1 Chapter 217 and "Public Drinking Water", TAC Title 30 Part 1 Chapter 290.
- B. Current TXDOT "Standard Specifications for Construction of Highways, Streets and Drainage".
   C. Current "San Antonio Water System Standard Specifications for Water and Sanitary Sewer Construction".
- D. Current City of San Antonio "Standard Specifications for Public Works Construction".
  E. Current City of San Antonio "Utility Excavation Criteria Manual" (UECM).

2. The contractor shall not proceed with any pipe installation work until they obtain a copy of the approved Counter Permit or General Construction Permit (GCP) from the consultant and has been notified by SAWS Construction I nspection Division to proceed with the work and has arranged a meeting with the inspector and consultant for the work requirements. Work completed by the contractor without an approved Counter Permit and/or a GCP will be subject to removal and replacement at the expense of the contractors and/or the developer.

3. The Contractor shall obtain the SAWS Standard Details from the SAWS website, http://www.saws.org/business\_center/specs. Unless otherwise noted within the design plans.

4. The Contractor is to make arrangements with the SAWS Construction Inspection Division at (210) 233-2973, on notification procedures that will be used to notify affected home residents and/or property owners 48 hours prior to beginning any work.

5. Location and depth of existing utilities and service laterals shown on the plans are understood to be approximate.

Actual locations and depths must be field verified by the Contractor at least 1 week prior to construction. It shall be the Contractor's responsibility to locate utility service lines as required for construction and to protect them during construction at no cost to SAWS

6. The Contractor shall verify the exact location of underground utilities and drainage structures at least 1-2 weeks prior to construction whether shown on plans or not. Please allow up to 7 business days for locates requesting pipe location markers on SAWS facilities. The following contact information are supplied for verification purposes:

SAWS Utility Locates: http://www.saws.org/Service/Locates COSA Drainage (210) 207-0724 or (210) 207-6026 COSA Traffic Signal Operations (210) 206-8480 COSA Traffic Signal Damages (210) 207-3951 Texas State Wide One Call Locator 1-800-545-6005 or 811

7. The Contractor shall be responsible for restoring existing fences, curbs, streets, driveways, sidewalks, landscaping and structures to its original or better condition if damages are made as a result of the project's construction.

8. All work in Texas Department of Transportation (TxDOT) and/or Bexar County right-of-way shall be done in accordance with respective construction specifications and permit requirements.

9. The Contractor shall comply with City of San Antonio or other governing municipality's tree ordinances when excavating near trees.

10. The Contractor shall not place any waste materials in the 100-year Flood Plain without first obtaining an approved Flood Plain Permit.

11. Holiday Work: Contractors will not be allowed to perform SAWS work on SAWS recognized holidays. Request should be sent to constworkreq@saws.org. Weekend Work: Contractors are required to notify the SAWS Inspection Construction Department 48 hours in advance to request weekend work. Request should be sent to constworkreq@saws.org. Any and all SAWS utility work installed without holiday/weekend approval will be subject to be uncovered for proper inspection.

12. Compaction note (Item 804): The contractor shall be responsible for meeting the compaction requirements on all trench backfill and for paying for the tests performed by a third party. Compaction tests will be done at one location point randomly selected, or as indicated by the SAWS Inspector and/or the test administrator, per each 12-inch loose lift per 400 linear feet at a minimum. This project will not be accepted and finalized by SAWS without this requirement being met and verified by providing all necessary documented test results.

13. A copy of all testing reports shall be forwarded to SAWS Construction Inspection Division.

#### Water Section

1. Prior to tie-ins, any shutdowns of existing mains of any size must be coordinated with the SAWS Construction Inspection Division at least one week in advance of the shutdown. The Contractor must also provide a sequence of work as related to the tie-ins; this is at no additional cost to SAWS or the project and it is the responsibility of the Contractor to sequence the work accordingly.

■ For water mains 12" or higher: SAWS Emergency Operations Center (210) 233-2014

2. Asbestos Cement (AC) pipe, also known as transite pipe which is known to contain asbestos containing material (ACM), may be located within the project limits. Special waste management procedures and health and safety requirements will be applicable when removal and/or disturbance of this pipe occurs. Such work is to be made under Special Specification Item No. 3000, "Special Specification for Handling Asbestos Cement Pipe".

3. Valve removal: Where the contractor is to abandon a water main, the control valve located on the abandoning branch will be removed and replaced with a cap/plug. (NSPI)

4. Suitable anchorage/thrust blocking or joint restraint shall be provided at all of the following main locations: dead ends, plugs, caps, tees, crosses, valves, and bends, in accordance with the Standard Drawings DD-839 Series and Item No. 839, in the SAWS Standard Specifications for Construction.

5. All valves shall read "open right".

6. PRVs Required: Contractor to verify that no portion of the tract is below ground elevation of \_\_\_985\_\_ feet where the static pressure will normally exceed 80 PSI. At all such locations where the ground level is below \_\_985\_\_ feet, the Developer or Builder shall install at each lot, on the customer's side of the meter, an approved type pressure regulator in conformance with the Plumbing Code of the City of San Antonio. No dual services allowed for any lot(s) if \*PRV is/are required for such lot(s), only single service connections shall be allowed. \*Note: A pressure regulator is also known as a pressure reducing valve (PRV).

7. Pipe Disinfection with Dry HTH for Projects less than 800 linear feet. (Item No. 847.3): Mains shall be disinfected with dry HTH where shown in the contract documents or as directed by the Inspector, and shall not exceed a total length of 800 feet. This method

of disinfection will also be followed for main repairs. The Contractor shall utilize all appropriate safety measure to protect his personnel during disinfection operations.

8. Backflow Prevention Device

■ All irrigation services within residential areas are required to have backflow prevention devices.
■ All commercial backflow prevention devices must be approved by SAWS prior to installation.


9. Final connection to the existing water main shall not be made until the water main has been pressure tested, chlorinated, and SAWS has released the main for tie-in and use.

#### SAWS NOTES:

DIVISION VALVES:. DIVISION VALVES SHOWN ON PLANS OR NOT SHOWN ON PLANS BUT FOUND IN THE FIELD SHALI ONLY BE OPERATED BY SAWS DISTRIBUTION AND COLLECTION STAFF AND ONLY WITH PRIOR WRITTEN APPROVAL F THE SAWS DIRECTOR OF PRODUCTION AND OPERATIONS AND PROPER COORDINATION WITH ALL SAWS DEPARTMENTS. CONTRACTOR SHALL PROVIDE WRITTEN NOTIFICATION TO THE INSPECTOR A MINIMUM OF TWO WEEKS IN ADVANCE TO START THE COORDINATION PROCESS AND WILL BE INFORMED BY THE INSPECTOR WHEN HE DIVISION VALVE WILL BE OPERATED BY THE SAWS DISTRIBUTION AND COLLECTION STAFF. THE DIVISION ALVE CAN ONLY BE OPERATED BY SAWS DISTRIBUTION AND COLLECTION STAFF MEMBER NOT THE INSPECTOR R THE CONTRACTOR. OPERATION OF A DIVISION VALVE WITHOUT THE EXPRESS PRIOR WRITTEN APPROVAL OF HE SAWS DISTRIBUTION AND COLLECTION STAFF WILL CONSTITUTE A MATERIAL BREACH OF ANY WRITTEN SAW CONTRACT OR PERMIT IN ADDITION TO SUBJECTING THE CONTRACTOR TO LIABILITY FOR ANY AND ALL FINES, FEES, OR OTHER DAMAGES, DIRECT OR CONSEQUENTIAL, THAT MAY ARISE FROM OR BE CAUSED BY THE PERATION OF THE VALVE WITHOUT PRIOR WRITTEN PERMISSION. PLEASE BE INFORMED THAT THE APPROVAL O IE OPERATION OR OPENING OR CLOSING OF A DIVISION VALVE CAN TAKE SEVERAL WEEKS FOR APPROVAL. IVISION VALVES WILL ALSO HAVE A VALVE LID LABELED DIVISION VALVE AND A LOCKING MECHANISM INSTALLED WITH A KEY. THE LOCK AND KEY MECHANISM WILL BE PAID FOR THE CONTRACTOR BUT WILL BE INSTALLED BY SAWS DISTRIBUTION AND COLLECTION STAFF.

# MORGAN HEIGHTS PHASE 6

# BEXAR COUNTY, TEXAS WATER IMPROVEMENTS




LOCATION MAP

N.T.S.

OWNER/DEVELOPER
TALLEY EXTENSION REVITALIZATION INITIATIVE, LLC.
5210 THOUSAND OAKS, SUITE 1318
SAN ANTONIO, TEXAS 78233

#### INDEX

DESCRIPTION	SHEET NO.
WATER DISTRIBUTION COVER SHEET	7.0
WATER DISTRIBUTION PLAN	



& Design

www.colliersengineering.com

opyright © 2023. Colliers Engineering & Design All Rights Reserved. This drav

rhom the services were contracted or to whom it is certified. This drawing may e copied, reused, disclosed, distributed or relied upon for any other pure

without the express written consent of Colliers Engineering & Design.

JEFFREY W. MARTIN

139094

CENSE

JONAL

1/24/25

PRELIMINARY

FOR
MORGAN HEIGHTS
PHASE 6
PLAT# 23-11800391

SAN ANTONIO BEXAR COUNTY

TEXAS

SAN ANTONIO (KFW)

3421 Paesanos

San Antonio, TX 78231

**Collicrs**Engineering & Design

SAWS PRESSURE ZONE 8 SERVICE AREA: FAR WEST

 DEVELOPER'S NAME: TALLEY EXTENSION REVITALIZATION INITIATIVE, LLC

 DEVELOPER'S ADDRESS: 5210 THOUSAND OAKS, SUITE 1318

 CITY: SAN ANTONIO
 STATE: TEXAS
 ZIP: 78216

 PHONE#: (210) 490-1798
 FAX#:
 TOTAL ACREAGE: 16.66 ACRES

 SAWS BLOCK MAP#: 062600, 064600, 062598, 064598
 TOTAL EDU'S: 79

 TOTAL LINEAR FOOTAGE OF PIPE: 897 LF ~ 8" C-900
 PLAT NO.: 23-11800391

SAWS JOB#: 23-XXXX

NUMBER OF LOTS: 79

Engineering Phone: 210.979.8444

& Design COLLIERS ENGINEERING & DESIGN, I
TBPE Firm#: F-14909
TBPLS Firm#: 10194550


SCALE: DATE: DRAWN BY: CHECKED


O772072023 3D 3C


JMBER: DRAWING NAME:
40-06 CVOW2054006


E:

WATER DISTRIBUTION COVER SHEET









FIBER ROLL

Install fiber roll

Vertical spacing

varies between

10' and 20'

measured along the

along a level contour

slope where it transitions

into a steeper slope

TYPICAL FIBER ROLL INSTALLATION

ENTRENCHMENT DETAIL

max 4'

THE TOP OF THE SACK GABIONS SHOULD BE LEVEL AND ORIENTED PERPENDICULAR TO THE DIRECTION OF FLOW. FILTER FABRIC MATERIAL SHALL BE FASTENED TO WOVEN WIRE FILTER FABRIC MATERIAL SHOULD MEET THE FOLLOWING SPECIFICATIONS: RESISTANT TO ULTRAVIOLET LIGHT. FABRIC DUNCES PER SQUARE YARD. MINIMUM MULLEN BURST STRENGTH OF POUNDS PER SQUARE INCH AND A FLOW THRU RATE OF 120 GALLONS PER MINUTE PER SQUARE FOOT OF FRONTAL AREA. STONE SIZE: ±4"-8" OPEN GRADED CRUSHED LIMESTONE. NSPECT WEEKLY OR AFTER EACH RAINFALL EVENT AND REPAIR OR WHEN SILT REACHES A DEPTH OF 6 INCHES OR MORE ABOVE NATURAL GROUND, SILT SHALL BE REMOVED AND DISPOSED IN AN APPROVED MANNER THAT WILL NOT CONTRIBUTE TO RESILTATION. CONTAMINATED SEDIMENT MUST BE REMOVED AND DISPOSED OF FF-SITE IN ACCORDANCE WITH APPLICABLE REGULATIONS.

THE MATERIAL, INSTALLATION, INSPECTION, AND MAINTENANCE OF

(1) Core material: Core material should be biodegradable or recyclable. Material

FIBER ROLLS WILL BE PER THE MANUFACTURE'S SPECIFICATIONS

AND SHALL ALSO COMPLY WITH THE TEXAS COMMISSION OF

may be compost, mulch, aspen wood fibers, chipped site vegetation, agricultural rice or wheat straw, coconut fiber, 100% recyclable fibers, or

(2) Containment Mesh: Containment mesh should be 100% biodegradable,

photodegradable or recyclable such as burlap, twine, UV photodegradable

plastic, polyester, or similar material. When the fiber role will remain in place

as part of a vegetative system use biodegradable or photodegradable mesh.

Slope inclination of 4:1 (H:V) or flatter: Fiber rolls should be placed at a

Slope inclination 2:1 (H:V) or greater: Fiber Rolls should be placed at a

Slope inclination between 4:1 and 2:1 (H:V): Fiber Rolls should be placed at a

(2) Turn the ends of the fiber roll up slope to prevent runoff from going around the

(4) Drive stakes at the end of each fiber roll and spaced 4 ft maximum on center.

(5) Use wood stakes with a nominal classification of 0.75 by 0.75 in. and minimum

(6) If more than one fiber roll is placed in a row, the rolls should be overlapped, not

(3) If the fiber roll is used as a sediment capture device, or as an erosion control device to maintain sheet flows, sediment that accumulates behind the role must be

periodically removed in order to maintain its effectiveness. Sediment should be

incorporated into earthwork on the site or disposed of at an appropriate location.

depth, usually one-half the distance between the top of the fiber roll and the adjacent ground surface. Sediment removed during maintenance may be

removed when the accumulation reaches one-half the designated sediment storage

(3) Stake fiber rolls into a 2 to 4 in. deep trench with a width equal to the diameter of

BEST MANAGEMENT PRACTICES" AS NOTED BELOW.

For temporary installation recyclable mesh is recommended.

(1) Locate fiber rolls on level contours spaced as follows:

maximum interval of 15 ft. (a closer spacing is more effective).

maximum interval of 10 ft. (a closer spacing is more effective).

(2) Repair or replace split, torn, unraveling, or slumping fiber rolls.

similar materials.

maximum interval of 20 ft.


Inspection and Maintenance Guidelines:


the fiber roll.

abutted.

(1) Inspect weekly

ENVIRONMENTAL QUALITY CURRENT "TECHNICAL GUIDANCE ON





Installation: (North Carolina, 1993)

(1) The aggregate should consist of 4 to 8 inch washed stone over a stable foundation as specified in the plan. PUBLIC ROAD (2) The aggregate should be placed with a minimum thickness of 8 inches (3) The geotextile fabric should be designed specifically for use as a soil filtration media with an approximate weight of 6 oz/yd2, a mullen burst rating of 140 lb/in2, and an equivalent opening size greater than a number

(4) If a washing facility is required, a level area with a minimum of 4 inch diameter washed stone or commercial rack should be included in the plans. Divert wastewater to a sediment trap or basin.

hom the services were contracted or to whom it is certified. This drawing may e copied, reused, disclosed, distributed or relied upon for any other purp without the express written consent of Colliers Engineering & Design. (1) Avoid curves on public roads and steep slopes. Remove vegetation and other objectionable material from the foundation

Formerly Known as

Engineering

& Design

www.colliersengineering.com

pyright © 2024. Colliers Engineering & Design All Rights Reserved. This draw

FOR STATE SPECIFIC DIRECT PHONE NUMBERS

VISIT: WWW.CALL811.COM

ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON


PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE

area. Grade crown foundation for positive drainage. (2) The minimum width of the entrance/exit should be 12 feet or the full width of exit roadway, whichever is greater. (3) The construction entrance should be at least 50 feet long. (4) If the slope toward the road exceeds 2%, construct a ridge, 6 to 8 inches high with 3:1 (H:V) side slopes, across the foundation approximately 15 feet from the entrance to divert runoff away from the public road. (5) Place geotextile fabric and grade foundation to improve stability, especially where wet conditions are anticipated. (6) Place stone to dimensions and grade shown on plans. Leave surface smooth and slope for drainage. (7) Divert all surface runoff and drainage from the stone pad to a sediment trap or basin. (8) Install pipe under pad as needed to maintain proper public road drainage.

The entrance should be maintained in a condition, which will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repair andlor cleanout of any measures used to trap sediment.

(2) All sediment spilled, dropped, washed or tracked onto public rights-of-way should be removed immediately by contractor. (3) When necessary, wheels should be cleaned to remove sediment prior to entrance onto public right-of-way. (4) When washing is required, it should be done on an area stabilized with crushed stone that drains into an approved sedimen trap or sediment basin. CONSTRUCTION ENTRANCE/EXIT (5) All sediment should be prevented from entering any storm drain, ditch or water course by using approved methods.

STABILIZED CONSTRUCTION ENTRANCE / EXIT



GEOTEXTILE FABRIC

TO STABILIZE FOUNDATION

(1) The berm structure should be. secured with a woven wire sheathing having maximum opening of 1 inch and a minimum wire diameter of 20 gauge galvanized and should be secured with shoat rings. (2) Clean, open graded 3- to 5-inch diameter rock should be used, except in areas where high velocities or large volumes of flow are expected, where 5- to 8-inch diameter rocks may be used.

(1) Lay out the woven wire sheathing perpendicular to the flow line. The sheathing should be 20 gauge woven wire mesh with 1 inch openings. (2) Berm should have a top width of 2 feet minimum with side slopes being 2:1 (H:V) or flatter. (3) Place the rock along the sheathing as shown in the diagram Figure 1-28), to a height not less than

(4) Wrap the wire sheathing around the rock and secure with tie wire so that the ends of the sheathing overlap at least 2 inches, airl the berm retains its shape when walked upon (5) Berm should be built along the contour at zero percent grade or as near as possible. (6) The ends of the berm should be tied into existing upslope grade and the berm should be buried in a trench approximately 3 to 4 inches deep to prevent failure of the control.

Inspection and Maintenance Guidelines:

(1) Inspection should be made weekly by the responsible party. For installations


in streambeds, additional daily inspections should be made. (2) Remove sediment and other debris when buildup reaches 6 inches and dispose of the accumulated silt in an approved manner that will not cause any additional siltation.

(3) Repair any loose wire sheathing. (4) The berm should be reshaped as needed during inspection.

(5) The berm should be replaced when the structure ceases to function as intended due to silt accumulation among the rocks, washout, construction traffic damage, etc.

(6) The rock berm should be left in place until all upstream areas are stabilized and accumulated silt

**ROCK BERM** 



(1) SILT FENCE MATERIAL SHOULD BE POLYPROPYLENE, POLYETHYLENE OR POLYAMIDE WOVEN OR NONWOVEN FABRIC. THE FABRIC WIDTH SHOULD BE 36 INCHES, WITH A MINIMUM UNIT WEIGHT OF 4.5 OZ/YD, MULLEN BURST STRENGTH EXCEEDING 190 LB/IN2, ULTRAVIOLET STABILITY EXCEEDING 70%, AND MINIMUM APPARENT OPENING SIZE OF U.S. SIEVE NO. 30. (2) FENCE POSTS SHOULD BE MADE OF HOT ROLLED STEEL, AT LEAST 4 FEET LONG WITH TEE OR YBAR CROSS SECTION, SURFACE PAINTED OR GALVANIZED, MINIMUM NOMINAL WEIGHT 1.25 LB/FL2, AND BRINDELL HARDNESS EXCEEDING 140. REBAR (EITHER #5 OR #6) MAY ALSO BE

USED TO ANCHOR THE BERM. (3) WOVEN WIRE BACKING TO SUPPORT THE FABRIC SHOULD BE GALVANIZED 2" X 4" WELDED WIRE, 12 GAUGE MINIMUM. (4) THE BERM STRUCTURE SHOULD BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM OPENING OF 1 INCH. AND A MINIMUM WIRE DIAMETER OF 20 GAUGE GALVANIZED AND SHOULD BE SECURED WITH SHOAT RINGS.

(5) CLEAN, OPEN GRADED 3- TO 5-INCH DIAMETER ROCK SHOULD BE USED, EXCEPT IN AREAS WHERE HIGH VELOCITIES OR LARGE VOLUMES OF FLOW ARE EXPECTED, WHERE 5- TO 8-INCH DIAMETER ROCKS MAY BE USED.

INSTALLATION:
(1) LAY OUT THE WOVEN WIRE SHEATHING PERPENDICULAR TO THE FLOW LINE. THE SHEATHING SHOULD BE 20 GAUGE WOVEN WIRE MESH WITH 1-INCH OPENINGS

(2) INSTALL THE SILT FENCE ALONG THE CENTER OF THE PROPOSED BERM PLACEMENT, AS WITH A NORMAL SILT FENCE DESCRIBED IN SECTION 2.4.3. (3) PLACE THE ROCK ALONG THE SHEATHING ON BOTH SIDES OF THE SILT FENCE AS SHOWN IN THE DIAGRAM (FIGURE 1-29), TO A HEIGHT NOT LESS THAN 24 INCHES. CLEAN, OPEN GRADED 3- 5" DIAMETER ROCK SHOULD BE USED, EXCEPT IN AREAS WHERE HIGH VELOCITIES OR LARGE VOLUMES OF FLOW ARE EXPECTED, WHERE 5- TO 8-INCH DIAMETER ROCK MAY BE USED. (4) WRAP THE WIRE SHEATHING AROUND THE ROCK AND SECURE WITH TIE WIRE SO THAT THE ENDS OF THE SHEATHING OVERLAP AT LEAST 2

INCHES, AND THE BERM RETAINS ITS SHAPE WHEN WALKED UPON. (5) THE HIGH SERVICE ROCK BERM SHOULD BE REMOVED WHEN THE SITE IS REVEGETATED OR OTHERWISE STABILIZED OR IT MAY REMAIN IN PLACE AS A PERMANENT BMP IF DRAINAGE IS ADEQUATE.

INSPECTION AND MAINTENANCE GUIDELINES:
(1) INSPECTION SHOULD BE MADE WEEKLY BY THE RESPONSIBLE PARTY. FOR INSTALLATIONS IN STREAMBEDS, ADDITIONAL DAILY

INSPECTIONS SHOULD BE MADE ON ROCK BERM. (2) REMOVE SEDIMENT AND OTHER DEBRIS WHEN BUILDUP REACHES 6 INCHES AND DISPOSE OF THE ACCUMULATED SILT OF IN AN APPROVED (3) REPAIR ANY LOOSE WIRE SHEATHING.

(4) THE BERM SHOULD BE RESHAPED AS NEEDED DURING INSPECTION. (5) THE BERM SHOULD BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED DUE TO SILT ACCUMULATION AMONG THE ROCKS, WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC. (6) THE ROCK BERM SHOULD BE LEFT IN PLACE UNTIL ALL UPSTREAM AREAS ARE STABILIZED AND ACCUMULATED SILT REMOVED.

JEFFREY W. MARTI

**PRELIMINARY** 

**MORGAN HEIGHTS** PHASE 6 PLAT# 23-11800391


> SAN ANTONIO **BEXAR COUNTY**

SAN ANTONIO (KFW) 3421 Paesanos San Antonio, TX 78231 Phone: 210.979.8444 Engineering OLLIERS ENGINEERING & DESIGN, II & Design TBPE Firm#: F-14909 TBPLS Firm#: 10194550


AS SHOWN SW3P2054006


STORMWATER POLLUTION PREVENTION DETAILS


8.1



GENERAL NOTES:







CURB INLET PROTECTION (ALTERNATE)

SILT FENCE FLOW ARROWS

TYPICAL CONSTRUCTION STAGING AREA

HIGH SERVICE ROCK BERM