

BID PROPOSAL SCHEDULE  
NORTHLAKE, PHASE 4  
BID SUMMARY

BIDDER'S NAME: \_\_\_\_\_

**NORTHLAKE, PHASE 4**

LOT GRADING IMPROVEMENTS	\$ _____
DRAINAGE IMPROVEMENTS	\$ _____
STREET IMPROVEMENTS	\$ _____
SANITARY SEWER IMPROVEMENTS*	\$ _____
WATER IMPROVEMENTS*	\$ _____
SEDIMENTATION AND EROSION CONTROL	\$ _____
MISC. IMPROVEMENTS	\$ _____

**TOTAL BASE BID:** \$ \_\_\_\_\_

**Note to Bidders:**

- \* Includes Warranty Assignments or Bonds, per AHJ General Construction Permit requirements.
- \* Contractor is to perform an independent quantity take-off prior to signing the contract, to verify that the quantities given in the bid proposal are within three percent (3%) of the actual quantities required to complete the construction represented by the plans and specifications. If any quantity is found to be in error of more than three percent (3%), the Contractor shall notify the Engineer forty-eight (48) hours prior to signing the contract.
- \* Bids shall include all Unit Price costs as indicated by the Contract Documents and Bid Form. The bid price submitted by the Contractor shall be the sum of the unit prices times the estimated quantity of each item shown in the bid form. However, the Contractor shall guarantee himself of the accuracy of the quantities shown in the bid form. The quantities shown are estimates only and indicate only the magnitude of the project and a basis for bid comparison. Any discrepancies in quantity or work necessary to fulfill the intent of the plans shall be included, whether a bid item is included or not. Any work required for which a bid item is not shown shall be considered subsidiary to other work items.
- \* Establish vegetation per specifications noted in construction plans.

**Bidders Initials** \_\_\_\_\_  
**Date** \_\_\_\_\_

**BID PROPOSAL SCHEDULE  
 NORTHLAKE, PHASE 4  
 LOT GRADING IMPROVEMENTS**

NO.	DESCRIPTION	UNIT OF MEASURE	APPROX. QUANTITIES	UNIT PRICES	COST
1.	LOT CLEARING & GRUBBING	AC	29.67	\$ _____	\$ _____
2.	ESTABLISH VEGETATION	SY	164,748	\$ _____	\$ _____
<b>TOTAL COST</b>					\$ _____

**Note to Bidders:**

- \* All final lot grading shall be compacted in accordance with notes on the Lot Grading Plan
- \* Contractor shall account for any shrinkage/swelling of soil material within bid price for excavation/embankment.
- \* Contractor to field verify and survey the existing site topography and submit information to engineer prior to submitting final bid for verification. No shrinkage or swelling factor is accounted for in the engineering excavation and embankment quantities. Contractor to adjust unit price as he deems necessary to account for shrinkage and swelling.
- \* Contractor is to perform an independent quantity take-off prior to signing the contract, to verify that the quantities given in the bid proposal are within three percent (3%) of the actual quantities required to complete the construction represented by the plans and specifications. If any quantity is found to be in error of more than three percent (3%), the Contractor shall notify the Engineer forty-eight (48) hours prior to signing the contract.
- \* Bids shall include all Unit Price costs as indicated by the Contract Documents and Bid Form. The bid price submitted by the Contractor shall be the sum of the unit prices times the estimated quantity of each item shown in the bid form. However, the Contractor shall guarantee himself of the accuracy of the quantities shown in the bid form. The quantities shown are estimates only and indicate only the magnitude of the project and a basis for bid comparison. Any discrepancies in quantity or work necessary to fulfill the intent of the plans shall be included, whether a bid item is included or not. Any work required for which a bid item is not shown shall be considered subsidiary to other work items.
- \* Establish vegetation per specifications noted in construction plans.

**Bidders Initials** \_\_\_\_\_  
**Date** \_\_\_\_\_

**BID PROPOSAL SCHEDULE  
NORTHLAKE, PHASE 4  
DRAINAGE IMPROVEMENTS**

NO.	DESCRIPTION	UNIT OF MEASURE	APPROX. QUANTITIES	UNIT PRICES	COST
<b>Drain "A"</b>					
1.	DRAIN CLEARING	AC	0.89	\$ _____	\$ _____
2.	DRAINAGE EXCAVATION	CY	2,418	\$ _____	\$ _____
3.	DRAINAGE EMBANKMENT	CY	30	\$ _____	\$ _____
4.	4'x2' BOX CULVERT	LF	175	\$ _____	\$ _____
5.	15' TYPE C CURB INLET	EA	2	\$ _____	\$ _____
6.	PIPE HANDRAIL	LF	162.0	\$ _____	\$ _____
7.	6" CONCRETE RIP-RAP	SY	396	\$ _____	\$ _____
8.	12" ROCK RUBBLE (18" DEEP)	SY	48	\$ _____	\$ _____
9.	BAFFLE BLOCKS	CY	1	\$ _____	\$ _____
10.	CONCRETE COLLAR	EA	6	\$ _____	\$ _____
11.	HEADWALL	CY	4	\$ _____	\$ _____
12.	CONCRETE SIDEWALK BOX	CY	10	\$ _____	\$ _____
13.	TURF REINFORCEMENT	SF	10,009	\$ _____	\$ _____
14.	ESTABLISH VEGETATION	SY	4,164	\$ _____	\$ _____
<b>Drain "B"</b>					
1.	DRAIN CLEARING	AC	0.13	\$ _____	\$ _____
2.	DRAINAGE EXCAVATION	CY	51	\$ _____	\$ _____
3.	DRAINAGE EMBANKMENT	CY	271	\$ _____	\$ _____
4.	PIPE HANDRAIL	LF	31.0	\$ _____	\$ _____
5.	6" CONCRETE RIP-RAP	SY	225	\$ _____	\$ _____
6.	12" ROCK RUBBLE (18" DEEP)	SY	17	\$ _____	\$ _____
7.	CONCRETE SIDEWALK BOX	CY	5	\$ _____	\$ _____
<b>Drain "G1"</b>					
1.	DRAIN CLEARING	AC	0.91	\$ _____	\$ _____
2.	DRAINAGE EXCAVATION	CY	3,204	\$ _____	\$ _____
3.	DRAINAGE EMBANKMENT	CY	280	\$ _____	\$ _____
4.	30" R.C.P.	LF	82	\$ _____	\$ _____
5.	PIPE HANDRAIL	LF	66.5	\$ _____	\$ _____
6.	6" CONCRETE RIP-RAP	SY	220	\$ _____	\$ _____
7.	12" ROCK RUBBLE (18" DEEP)	SY	17	\$ _____	\$ _____
8.	HEADWALL	CY	4	\$ _____	\$ _____
9.	CONCRETE COLLAR	EA	2	\$ _____	\$ _____
10.	TIE INTO EXISTING DRAIN	EA	1	\$ _____	\$ _____
11.	TURF REINFORCEMENT	SY	3,142	\$ _____	\$ _____
12.	DEMO EXISTING 6" CONCRETE RIP RAP	SY	6	\$ _____	\$ _____
13.	ESTABLISH VEGETATION	SY	4,442	\$ _____	\$ _____
<b>Drain "C"</b>					
1.	DRAIN CLEARING	AC	0.08	\$ _____	\$ _____
2.	DRAINAGE EXCAVATION	CY	34	\$ _____	\$ _____
3.	DRAINAGE EMBANKMENT	CY	156	\$ _____	\$ _____
4.	PIPE HANDRAIL	LF	36.0	\$ _____	\$ _____
5.	6" CONCRETE RIP-RAP	SY	176	\$ _____	\$ _____
6.	12" ROCK RUBBLE (18" DEEP)	SY	16	\$ _____	\$ _____
7.	CONCRETE SIDEWALK BOX	CY	5	\$ _____	\$ _____
8.	ESTABLISH VEGETATION	SY	243	\$ _____	\$ _____
<b>TOTAL COST</b>					<b>\$ _____</b>

**Note to Bidders:**

\* Contractor is to perform an independent quantity take-off prior to signing the contract, to verify that the quantities given in the bid proposal are within three percent (3%) of the actual quantities required to complete the construction represented by the plans and specifications. If any quantity is found to be in error of more than three percent (3%), the Contractor shall notify the Engineer forty-eight (48) hours prior to signing the contract.

\* Bids shall include all Unit Price costs as indicated by the Contract Documents and Bid Form. The bid price submitted by the Contractor shall be the sum of the unit prices times the estimated quantity of each item shown in the bid form. However, the Contractor shall guarantee himself of the accuracy of the quantities shown in the bid form. The quantities shown are estimates only and indicate only the magnitude of the project and a basis for bid comparison. Any discrepancies in quantity or work necessary to fulfill the intent of the plans shall be included, whether a bid item is included or not. Any work required for which a bid item is not shown shall be considered subsidiary to other work items.

\* Establish vegetation per specifications noted in construction plans.

**Bidders Initials** \_\_\_\_\_  
**Date** \_\_\_\_\_

**BID PROPOSAL SCHEDULE  
 NORTHLAKE, PHASE 4  
 STREET IMPROVEMENTS**

NO.	DESCRIPTION	UNIT OF MEASURE	APPROX. QUANTITIES	UNIT PRICES	COST
1.	CLEARING & GRUBBING (Streets & Easements)	AC	14.4	\$ _____	\$ _____
2.	EXCAVATION	CY	54,715	\$ _____	\$ _____
3.	EMBANKMENT	CY	48,832	\$ _____	\$ _____
4.	3" HMAC, TYPE C	SY	23,782	\$ _____	\$ _____
5.	4" HMAC, TYPE C	SY	5,002	\$ _____	\$ _____
6.	8" FLEX BASE (TYPE A, GRADE 1)	SY	23,782	\$ _____	\$ _____
7.	16" FLEX BASE (TYPE A, GRADE 1)	SY	5,002	\$ _____	\$ _____
8.	6" LIME STABILIZATION - 24LB/SY	SY	28,784	\$ _____	\$ _____
9.	CONCRETE CURB	LF	15,331	\$ _____	\$ _____
10.	REMOVE HEADER CURB	LF	128	\$ _____	\$ _____
11.	HEADER CURB	LF	68	\$ _____	\$ _____
12.	REMOVE TIMBER GUARD POST	EA	20	\$ _____	\$ _____
13.	TIMBER GUARD POST	EA	10	\$ _____	\$ _____
14.	4' SIDEWALK	SY	321	\$ _____	\$ _____
15.	6' SIDEWALK	SY	225	\$ _____	\$ _____
16.	TIE INTO EXISTING PAVEMENT	EA	4	\$ _____	\$ _____
17.	STRIPING	LS	1	\$ _____	\$ _____
18.	SIGNAGE	LS	1	\$ _____	\$ _____

**TOTAL COST \$ \_\_\_\_\_**

**Note to Bidders:**

- \* Contractor is to perform an independent quantity take-off prior to signing the contract, to verify that the quantities given in the bid proposal are within three percent (3%) of the actual quantities required to complete the construction represented by the plans and specifications. If any quantity is found to be in error of more than three percent (3%), the Contractor shall notify the Engineer forty-eight (48) hours prior to signing the contract.
- \* Bids shall include all Unit Price costs as indicated by the Contract Documents and Bid Form. The bid price submitted by the Contractor shall be the sum of the unit prices times the estimated quantity of each item shown in the bid form. However, the Contractor shall guarantee himself of the accuracy of the quantities shown in the bid form. The quantities shown are estimates only and indicate only the magnitude of the project and a basis for bid comparison. Any discrepancies in quantity or work necessary to fulfill the intent of the plans shall be included, whether a bid item is included or not. Any work required for which a bid item is not shown shall be considered subsidiary to other work items.
- \* Street base and subgrade material is measured per square yard between curbs of the specified thickness required. The cost of the base and subgrade material under and behind the curb is to be included in the cost of the curb.
- \* Costs associated with installation of wheelchair ramps shall be included in the cost of the sidewalks. (no separate pay item)

**Bidders Initials** \_\_\_\_\_  
**Date** \_\_\_\_\_

**BID PROPOSAL SCHEDULE  
 NORTHLAKE, PHASE 4  
 SANITARY SEWER IMPROVEMENTS**

NO.	DESCRIPTION	UNIT OF MEASURE	APPROX. QUANTITIES	UNIT PRICES	COST
1.	SANITARY SEWER PIPE				
	8" SDR 26	6' - 8'	LF	3,302	\$ _____ \$ _____
	8" SDR 26	8' - 10'	LF	3,499	\$ _____ \$ _____
	8" SDR 26	10' - 12'	LF	622	\$ _____ \$ _____
	8" SDR 26 (160 PSI)	6' - 8'	LF	80	\$ _____ \$ _____
	8" SDR 26 (160 PSI)	8' - 10'	LF	60	\$ _____ \$ _____
	8" SDR 26 (160 PSI)	10' - 12'	LF	40	\$ _____ \$ _____
2.	STANDARD MANHOLE	EACH		25	\$ _____ \$ _____
3.	MANHOLE EXTRA DEPTH	VF		70.3	\$ _____ \$ _____
4.	MANHOLE RING ENCASEMENT	EACH		27	\$ _____ \$ _____
5.	REBUILD TOP OF EXISTING MANHOLE	EACH		2	\$ _____ \$ _____
6.	6" SANITARY SEWER LATERAL (SDR 26)	LF		8,658	\$ _____ \$ _____
7.	6" VERTICAL STACKS	VF		79.1	\$ _____ \$ _____
8.	TIE-IN TO EXISTING MANHOLE	EACH		2	\$ _____ \$ _____
9.	TRENCH EXCAVATION PROTECTION	LF		7,603	\$ _____ \$ _____
10.	TV VIDEO SEWER LINE	LF		7,603	\$ _____ \$ _____

**TOTAL COST** \$ \_\_\_\_\_

**Note to Bidders:**

- \* Unit cost of 6" Sanitary Sewer Lateral shall include WYES, fittings, cleanouts, and trench excavation protection.
- \* Refer quantities to the current AHJ Standard Specifications for Construction. An AHJ GCP (General Construction Permit) is required. Contractor shall provide proof of trench compaction test results as tested by a Geotechnical Engineer, to comply with AHJ GCP. Cost of first time testing to be paid by owner. Cost of required retesting shall be paid by Contractor.
- \* Contractor is to perform an independent quantity take-off prior to signing the contract, to verify that the quantities given in the bid proposal are within three percent (3%) of the actual quantities required to complete the construction represented by the plans and specifications. If any quantity is found to be in error of more than three percent (3%), the Contractor shall notify the Engineer forty-eight (48) hours prior to signing the contract.
- \* Bids shall include all Unit Price costs as indicated by the Contract Documents and Bid Form. The bid price submitted by the Contractor shall be the sum of the unit prices times the estimated quantity of each item shown in the bid form. However, the Contractor shall guarantee himself of the accuracy of the quantities shown in the bid form. The quantities shown are estimates only and indicate only the magnitude of the project and a basis for bid comparison. Any discrepancies in quantity or work necessary to fulfill the intent of the plans shall be included, whether a bid item is included or not. Any work required for which a bid item is not shown shall be considered subsidiary to other work items.

**Bidders Initials** \_\_\_\_\_  
**Date** \_\_\_\_\_

**BID PROPOSAL SCHEDULE  
NORTHLAKE, PHASE 4  
WATER IMPROVEMENTS**

NO.	DESCRIPTION	UNIT OF MEASURE	APPROX. QUANTITIES	UNIT PRICES	COST
1.	TRENCH EXCAVATION PROTECTION	LF	8,296	\$	\$
2.	HYDROSTATIC TESTING	LF	8,296	\$	\$
3.	MACHINE CHLORINATION	LF	8,296	\$	\$
4.	8" C-900 PVC PIPE	LF	7,188	\$	\$
5.	12" C-909 PVC PIPE	LF	1,108	\$	\$
6.	DUCTILE IRON FITTINGS	TON	1.62	\$	\$
7.	12" GATE VALVE & BOXES, M.J.	EACH	6	\$	\$
8.	8" GATE VALVE & BOXES, M.J.	EACH	22	\$	\$
9.	1" SHORT DUAL SERVICE W/ 5/8" METERS	EACH	71	\$	\$
10.	1" LONG DUAL SERVICE W/ 5/8" METERS	EACH	41	\$	\$
11.	1" SHORT SINGLE SERVICE W/ 5/8" METER	EACH	6	\$	\$
12.	1" LONG SINGLE SERVICE W/ 5/8" METER	EACH	4	\$	\$
13.	FIRE HYDRANT ASSEMBLY	EACH	15	\$	\$
14.	1" AIR RELEASE VALVE	EACH	1	\$	\$
15.	SAMPLING STATION ASSEMBLY	EACH	1	\$	\$
16.	2" BLOWOFFS (PERM)	EACH	2	\$	\$
17.	20" STEEL CASING	LF	98	\$	\$
18.	24" STEEL CASING	LF	12	\$	\$
19.	8" WATER TIE IN	EACH	3	\$	\$
20.	12" WATER TIE IN	EACH	1	\$	\$
21.	CAST IRON METER BOXES	EACH	234	\$	\$

**TOTAL COST** \$ \_\_\_\_\_

**Note to Bidders:**

- \* Cost of joint restraint facilities shall be included in the cost for PVC pipe (no separate pay item)
- \* Fitting weights are (and are to be) based on S.A.W.S. weights for Compact M.J. Fittings
- \* Service cost shall include cost of 4" PVC sleeve
- \* Cost of pipe to include bedding & backfill
- \* Water tie-in to include all fittings necessary for completion and sanitization including 2" temporary blowoff
- \* Cost of irrigation services shall include cost of 4" pvc sleeves and/or conduits.
- \* Refer quantities to the current AHJ Standard Specifications for Construction. An AHJ GCP (General Construction Permit) is required. Contractor shall provide proof of trench compaction test results as tested by a Geotechnical Engineer, to comply with AHJ GCP. Cost of first time testing to be paid by owner. Cost of required retesting shall be paid by Contractor.
- \* Contractor is to perform an independent quantity take-off prior to signing the contract, to verify that the quantities given in the bid proposal are within three percent (3%) of the actual quantities required to complete the construction represented by the plans and specifications. If any quantity is found to be in error of more than three percent (3%), the Contractor shall notify the Engineer forty-eight (48) hours prior to signing the contract.
- \* Bids shall include all Unit Price costs as indicated by the Contract Documents and Bid Form. The bid price submitted by the Contractor shall be the sum of the unit prices times the estimated quantity of each item shown in the bid form. However, the Contractor shall guarantee himself of the accuracy of the quantities shown in the bid form. The quantities shown are estimates only and indicate only the magnitude of the project and a basis for bid comparison. Any discrepancies in quantity or work necessary to fulfill the intent of the plans shall be included, whether a bid item is included or not. Any work required for which a bid item is not shown shall be considered subsidiary to other work items.

**Bidders Initials** \_\_\_\_\_  
**Date** \_\_\_\_\_

## BID PROPOSAL SCHEDULE NORTHLAKE, PHASE 4 SEDIMENTATION & EROSION CONTROL

NO.	DESCRIPTION	UNIT OF MEASURE	APPROX. QUANTITIES	UNIT PRICES	COST
1.	STABILIZED CONSTRUCTION ENTRANCE	EA	2	\$ _____	\$ _____
2.	CONCRETE WASHOUT PIT	EA	2	\$ _____	\$ _____
3.	SILT FENCE	LF	13,103	\$ _____	\$ _____
4.	INLET PROTECTION	LF	111	\$ _____	\$ _____
5.	ROCK BERM	LF	27	\$ _____	\$ _____
6.	HIGH SERVICE ROCK BERM	LF	33	\$ _____	\$ _____
7.	TYPE 4 SACK GABIONS	LF	117	\$ _____	\$ _____
<b>TOTAL COST</b>					<b>\$ _____</b>

**Note to Bidders:**

- \* Contractor is to perform an independent quantity take-off prior to signing the contract, to verify that the quantities given in the bid proposal are within three percent (3%) of the actual quantities required to complete the construction represented by the plans and specifications. If any quantity is found to be in error of more than three percent (3%), the Contractor shall notify the Engineer forty-eight (48) hours prior to signing the contract.
- \* Bids shall include all Unit Price costs as indicated by the Contract Documents and Bid Form. The bid price submitted by the Contractor shall be the sum of the unit prices times the estimated quantity of each item shown in the bid form. However, the Contractor shall guarantee himself of the accuracy of the quantities shown in the bid form. The quantities shown are estimates only and indicate only the magnitude of the project and a basis for bid comparison. Any discrepancies in quantity or work necessary to fulfill the intent of the plans shall be included, whether a bid item is included or not. Any work required for which a bid item is not shown shall be considered subsidiary to other work items.
- \* Contractor shall provide BMP to protect the perimeter floodplain from any stockpile.
- \* Commencement of Construction:
  1. Initial project clearing will need to be limited to the locations of the proposed temporary SWP3 Best Management Practices (BMP) designed by the engineer. These BMPs may include, but are not limited to: Stabilized Construction Exit(s), Silt Fence, Discharge Point Rock Berms/Check Dams, Trash containment, Temporary Sediment Basins (if applicable), Demarcation of protected site features for example; Wetlands, Environmental Buffers, Caves or Solution Features, and Habitats
  2. Prior to commencement of additional clearing or earth disturbing activities, the proposed BMPs will need to be installed by the Contractor and inspected by a Lennar Representative. Contractor must provide at minimum, 48-hours of notice to Lennar when the BMPs are scheduled to be installed and completed. The Lennar Representative will coordinate the Land Development Manager to release the project for construction. When the project is located within the Bexar County controlled MS4, the Contractor must provide 48-hours of notice to the assigned Bexar County SWP3 Inspector noted on the Storm Water Quality (SWQ) permit letter.
  3. When a Temporary Sediment Basin is required for the project, limited clearing of the proposed basin location and any material borrow areas to construct the Temporary Sediment Basin may occur during the initial BMP installation period. The Temporary Sediment Basin must be completely constructed to Engineer's design. This may include the following; Construction of the dewatering structure (Riser Pipe or Fair Cloth Skimmer and pump), Construction of the Emergency Overflow Structure, Installation of a sediment depth marker. Note-Once accessible to appropriate equipment, the only the Temporary Sediment Basin berms/slopes shall be temporarily stabilized.
  4. General Contractor is to maintain all pollution control measures in effective operating condition throughout the contract period to the extent achievable. To ensure BMPs are operating effectively, and in accordance with the Construction General Permit, Lennar will provide regular and if applicable, post-rain event BMP inspections and inspection reports. The General Contractor will be provided an electronic copy of the BMP inspection report via email. weekly regarding issues with BMPs at the project through the Lennar SWP3 Inspection process. Items noted in the BMP Inspection report must be addressed by the General Contractor as soon as possible, and within 7 calendar days. General Contractor shall provide documentation to the assigned Lennar Land Development Project Manager to include:
    - a. Actions taken in response to the BMP inspection report and date(s) the actions were completed or,
    - b. Statement of extenuating circumstance as to why an item could not be completed within the 7-day timeframe and proposed scheduled date of completion.
  5. Contractor to maintain Spill Response Supplies/Kit at the project location while actively working onsite.
  6. When dewatering activities discharge into onsite creeks or rivers, or discharge outside the limits of construction, daily dewatering inspections must be documented in accordance with the 03.05.2023 TCEQ Construction General Permit. Daily report must be sent to Lennar within 24-hours.

**Bidders Initials** \_\_\_\_\_  
**Date** \_\_\_\_\_

**BID PROPOSAL SCHEDULE**  
**NORTHLAKE, PHASE 4**  
**MISC. IMPROVEMENTS**

NO.	DESCRIPTION	UNIT OF MEASURE	APPROX. QUANTITIES	UNIT PRICES	COST
1.	EXPORT MATERIAL	CY	10,853	\$ _____	\$ _____
2.	(3) 6" & (2) 4" SCH 80 CONDUITS	LF	135	\$ _____	\$ _____
3.	(4) 6" & (2) 4" SCH 80 CONDUITS	LF	18	\$ _____	\$ _____
4.	(2) 4" SCH 80 CONDUITS	LF	67	\$ _____	\$ _____
5.	PAYMENT & PERFORMANCE BOND	LS	1	\$ _____	\$ _____

**TOTAL COST** \$ \_\_\_\_\_

**Note to Bidders:**

- \* Conduit line items are just to acquire Unit Price. Actual quantities will be pending municipalities final design.
- \* All Conduit to be Schedule 80
- \* Contractor is to perform an independent quantity take-off prior to signing the contract, to verify that the quantities given in the bid proposal are within three percent (3%) of the actual quantities required to complete the construction represented by the plans and specifications. If any quantity is found to be a difference of more than three percent (3%), the Contractor shall notify the Engineer forty-eight (48) hours prior to signing the contract.
- \* Bids shall include all Unit Price costs as indicated by the Contract Documents and Bid Form. The bid price submitted by the Contractor shall be the sum of the unit prices times the estimated quantity of each item shown in the bid form. However, the Contractor shall guarantee himself of the accuracy of the quantities shown in the bid form. The quantities shown are estimates only and indicate only the magnitude of the project and a basis for bid comparison. Any discrepancies in quantity or work necessary to fulfill the intent of the plans shall be included, whether a bid item is included or not. Any work required for which a bid item is not shown shall be considered subsidiary to other work

**Bidders Initials** \_\_\_\_\_  
**Date** \_\_\_\_\_