



BY: _____

DATE: _____

CONST CTR: _____

FERGUSON MAP
GRID: 586 - E6


GAS DESIGN		PROJECT # G-0118	
40680802		NOTTING HILL UNIT 5 (GAS)	
M. SMITH 4194 210-727-2447 11/8/2022		NOTES	
E. CORONA 5135 210-827-2324 11/8/2022		107 LOTS	
1 of 1			
NWD			
X 2189134	Y 13720807	N/A	1" = 100'
CLEAR	COY	WATER	SEWER
NOTED ON MATCH			
ESTIMATED MAN-HOURS:		SKETCH SIZE 24 X 36 1" = 100'	



Associated Work Orders

40680779 - URD
40681923 - STLT

DESIGNED BY
J. MARTINEZ
TXUE, LLC



ATTENTION
DEVELOPERS / ENGINEERS / CONTRACTORS

WHEN TRENCHING IS IN FRONT LOT CONSTRUCTION, WATER &/OR SEWER SERVICES ARE NOT TO BE PLACED UNTIL CPS ENERGY FACILITIES ARE INSTALLED.

WHEN TRENCHING IN RIGHT OF WAY, WATER & SEWER SERVICES WILL NEED TO BE ROLLED BACK &/OR OUT OF CPS ENERGY TRENCHLINE.

CPS ENERGY WILL NOT BE HELD LIABLE FOR ANY DAMAGES TO WATER &/OR OUT OF CPS ENERGY TRENCHLINE

WHERE CPS ENERGY AND WATER SERVICES ARE CROSSING STREET, CPS ENERGY REQUIRES A MINIMUM OF 6' (FEET) OF HORIZONTAL SEPARATION (WHEN CROSSING) TO AVOID CONFLICTS

ATTENTION
FOREMAN

SEE UTILITY PLAT FOR LOCATION OF UTILITIES IN CONSTRUCTION AREA

LOCATE ALL BURIED FACILITIES

FOR MISSING PINS
CONTACT ENGINEER

ENGINEER: CEC TEXAS
CONTACT: LANCE ELLING
PHONE: (210) 641-9999
E-MAIL: LELLING@CECTEXAS.COM

NOTICE

CALL CORROSION CONTROL
AT 210-353-3771

NOTE:

THIS IS A SUPPLY PRESSURE
DISTRIBUTION GAS SYSTEM.
EXCESS FLOW VALVES ARE
NECESSARY ON ALL SERVICES.

**A STORMWATER PERMIT IS ACTIVE
FOR THIS CONSTRUCTION SITE.
PLEASE CALL STORMCON
ENVIRONMENTAL
AT LEAST 48 HOURS
PRIOR TO ANY SOIL DISTURBANCE.**

STORMCON POC: BRANDON BAXTER
210-771-1221 brandon@stormcon.us

