

**PALO ALTO POINTE UNIT 2
BID QUANTITIES**

WATER MAIN IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	QTY	\$/UNIT	AMOUNT
1	12" Water Tie-In	EA.	1	\$ -	\$ -
2	8" Water Tie-In	EA.	2	\$ -	\$ -
3	Trench Excavation Protection	L.F.	3,012	\$ -	\$ -
4	8" Pipe, C900 DR 18 PVC Class 235 (Incl. Joint Restraints)	L.F.	3,012	\$ -	\$ -
5	12" Gate Valve, M.J. with 6" Valve Box, Complete	EA.	1	\$ -	\$ -
6	8" Gate Valve, M.J. with 6" Valve Box, Complete	EA.	7	\$ -	\$ -
7	Standard Fire Hydrant	EA.	4	\$ -	\$ -
8	2" Blow-Off (Temporary)	EA.	3	\$ -	\$ -
9	3/4" Single Service: Short (Shared Trench)	EA.	63	\$ -	\$ -
10	3/4" Single Service: Long (Shared Trench)	EA.	40	\$ -	\$ -
11	D.I. Fittings	TON	0.5	\$ -	\$ -
12	Hydrostatic Testing	EA.	1	\$ -	\$ -
13	Meter Box	EA.	103	\$ -	\$ -
TOTAL COST					\$ -

SANITARY SEWER IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
14	Tie into Existing Sanitary Sewer Main	EA.	2	\$ -	\$ -
15	Trench Excavation Protection	L.F.	1,977	\$ -	\$ -
16	8" Sanitary Sewer Pipe, SDR-26 (6'-10')	L.F.	1,805	\$ -	\$ -
17	8" Sanitary Sewer Pipe, SDR-26 (10'-14')	L.F.	172	\$ -	\$ -
18	Standard Sanitary Sewer Manhole	EA.	9	\$ -	\$ -
19	Reconstruct Existing Sanitary Sewer Manhole	EA.	2	\$ -	\$ -
20	Extra Depth Manhole	V.F.	24.0	\$ -	\$ -
21	Vertical Stacks	V.F.	36.0	\$ -	\$ -
22	Sanitary Sewer Laterals, SDR-26 Class 160	L.F.	3,530	\$ -	\$ -
23	8" Sewer Main Television Inspection	L.F.	1,977	\$ -	\$ -
TOTAL COST					\$ -

STREET WIDENING - ROCKPORT RD (TXDOT)

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
24	Demolition of Existing Asphalt	S.Y.	1,419	\$ -	\$ -
25	Sawcut Existing Asphalt Pavement	L.F.	1,248	\$ -	\$ -
26	Street Excavation (< 1,000 CY)	C.Y.	380	\$ -	\$ -
27	Lime Treatment (6" Compacted Depth)	S.Y.	1,142	\$ -	\$ -
28	Flexible Base (10" Compacted)	S.Y.	1,142	\$ -	\$ -
29	Prime Coat	GAL	230	\$ -	\$ -
30	Tack Coat	GAL	115	\$ -	\$ -
31	HMAC, Type D (2" Thickness) (> 5,000 SY)	S.Y.	2,560	\$ -	\$ -
32	Header Curb (< 1,000 LF)	L.F.	78	\$ -	\$ -
33	4 Inch Wide Solid Double Yellow Lines, Type I, 100 Mils	L.F.	1,565	\$ -	\$ -
34	6 Inch Wide Solid White Line, Type I, 100 Mils	L.F.	1,128	\$ -	\$ -
35	8 Inch Wide Solid White Line, Type I, 100 Mils	L.F.	160	\$ -	\$ -
36	Reflective Pavement Marking, Med. Nose, Yellow, Type I	EA.	1	\$ -	\$ -
37	Left White Arrow	EA.	2	\$ -	\$ -
38	Word "ONLY"	EA.	2	\$ -	\$ -
39	Traffic Button (Type I-C)	EA.	9	\$ -	\$ -
40	Traffic Button (Type II-A-A)	EA.	100	\$ -	\$ -
TOTAL COST					\$ -

**PALO ALTO POINTE UNIT 2
BID QUANTITIES**

STREET IMPROVEMENTS - ONSITE

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
41	Remove Concrete Curb & Barricade Posts	L.F.	56	\$ -	\$ -
42	Street Excavation	C.Y.	1,308	\$ -	\$ -
43	Street Embankment	C.Y.	2,566	\$ -	\$ -
44	Lime Treatment (6" Compacted Depth)	S.Y.	10,911	\$ -	\$ -
45	Flexible Base (10" Compacted) - Local "A"	S.Y.	9,824	\$ -	\$ -
46	Flexible Base (19" Compacted) - Local "B"	S.Y.	1,087	\$ -	\$ -
47	Prime Coat	GAL	1,954	\$ -	\$ -
48	Tack Coat	GAL	977	\$ -	\$ -
49	HMAC, Type D (2" Thickness)	S.Y.	8,784	\$ -	\$ -
50	HMAC, Type D (3" Thickness)	S.Y.	985	\$ -	\$ -
51	Machine Laid Curb	L.F.	5,751	\$ -	\$ -
52	Concrete Sidewalk (Developer Responsibility)	S.Y.	118	\$ -	\$ -
53	ADA Ramps	EA.	18	\$ -	\$ -
54	Concrete Pavement (8" Thickness)	S.Y.	149	\$ -	\$ -
55	R1-1 Stop Sign (30")(High Intensity)	EA.	4	\$ -	\$ -
56	9" Street Name, Block Number (Varies 9")(High Intensity)	EA.	12	\$ -	\$ -
57	Bexar County Maintenance Ends/Begins Sign	EA.	2	\$ -	\$ -
58	Pavement Marker (Type II)(Blue)	EA.	4	\$ -	\$ -
59	Rock Filter Dam (Type 2)	L.F.	30	\$ -	\$ -
60	Silt Fence	EA.	5,642	\$ -	\$ -
61	Construction Exit - Install	S.Y.	168	\$ -	\$ -
62	Construction Exit - Remove	S.Y.	168	\$ -	\$ -
63	Curb Inlet Gravel Filters	L.F.	560	\$ -	\$ -
64	TXDOT Slotted Armor Curb	L.F.	54	\$ -	\$ -
TOTAL COST					\$ -

DRAINAGE IMPROVEMENTS – DRAIN E

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
65	Channel Excavation	C.Y.	80.0	\$ -	\$ -
66	Concrete Structure (Elevated Sidewalk)	C.Y.	1.2	\$ -	\$ -
67	Concrete Riprap (6")	S.Y.	130	\$ -	\$ -
68	Sidewalk Pipe Railing	L.F.	20	\$ -	\$ -
TOTAL COST					\$ -

DRAINAGE IMPROVEMENTS – DRAIN F

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
69	Channel Excavation	C.Y.	16.0	\$ -	\$ -
70	Concrete Structure (Elevated Sidewalk)	C.Y.	1.5	\$ -	\$ -
71	Concrete Structure (Miscellaneous)(Baffle Blocks)	C.Y.	0.3	\$ -	\$ -
72	Concrete Riprap (6")	S.Y.	57	\$ -	\$ -
73	Sidewalk Pipe Railing	L.F.	71	\$ -	\$ -
TOTAL COST					\$ -

DRAINAGE IMPROVEMENTS – DRAIN K

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
74	Channel Excavation	C.Y.	15.0	\$ -	\$ -
75	Concrete Structure (Misc.)(Safety End Treatments)	C.Y.	3.0	\$ -	\$ -
76	Concrete Riprap (6")	S.Y.	13	\$ -	\$ -
77	18" R.C.P., Class IV	L.F.	80	\$ -	\$ -
TOTAL COST					\$ -

**PALO ALTO POINTE UNIT 2
BID QUANTITIES**

SITE WORK/ADD ALTERNATES

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
78	Lot Excavation	C.Y.	8,827	\$ -	\$ -
79	Lot Embankment	C.Y.	39,039	\$ -	\$ -
80	Import Material	C.Y.	30,979	\$ -	\$ -
81	Conduit Bundle (1-6" PVC & 2-4" PVC)	L.F.	750	\$ -	\$ -
82	Conduit Bundle (2-6" PVC & 2-4" PVC)	L.F.	200	\$ -	\$ -
TOTAL COST					\$ -