

Public Bid Items

Parkside Unit 5

Sitework, Street, Sewer, Water Improvements

Thursday, November 20, 2024

BID DATE: _____

BIDDER: _____

The undersigned bidder declares that the only person or parties interested in this proposal as principals are those names herein, that this proposal has been prepared without collusion with any other person, firm, or corporation; that he has carefully examined the specifications and the site of the proposed work and therefore agrees that he will provide all the necessary machinery, tools, apparatus and other means of construction, and will do all the work and furnish all the materials called for in the specifications in the manner prescribed therein and according to the requirements of the Engineer as herein set forth, for the following prices. Contractor is responsible for identifying any cost items on the plans not listed on this Bid Sheet. Contractor shall be responsible to provide prices and quantities that represents the project drawings and specifications, even if different from quantities shown below.

Summary	Subtotal	Per Lot
SW3P & SITEWORK	\$ -	\$ -
STREET IMPROVEMENTS	\$ -	\$ -
DRAINAGE IMPROVEMENTS	\$ -	\$ -
SANITARY SEWER IMPROVEMENTS	\$ -	\$ -
WATER IMPROVEMENTS	\$ -	\$ -
Total	\$ -	\$ -

Exclusions:

Dry Utilities - electric meters, light poles, conduits, etc.
Landscaping, planting, and irrigation installation
Water Meter Set Fees
Amenities
Impact Fees
Construction Staking

Assumptions:

1.) This bid form only captures quantities "on-site" within Unit 4.

SW3P & SITEWORK

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Excavation	CY	27,940	\$	-
2	Embankment	CY	122,620	\$	-
3	Silt Fence	LF	11,643	\$	-
4	Mobilization	LS	1	\$	-
5	Stabilized Construction Entrance	EA	1	\$	-
6	Concrete Washout Pits	EA	1	\$	-
7	Filter Dike Inlet Protection	LF	122	\$	-
8	Rock Berm	LF	170	\$	-
9	Revegetation	SY	41,798	\$	-
10	Clear & Grub/Strip Top Soil	AC.	36.2	\$	-
SUBTOTAL				\$	-

STREET IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	2" Type D HMAC (Local)	SY	17,487	\$	-
2	10" Flex Base (Local)	SY	19,774	\$	-
3	6" Lime Stabilized Subgrade (Local)	SY	19,774	\$	-
4	2" Type D HMAC (Collector)	SY	6,569	\$	-
5	14.5" Flex Base (Collector)	SY	7,288	\$	-
6	6" Lime Stabilized Subgrade (Collector)	SY	7,288	\$	-
7	Concrete Curb & Gutter	LF	9,743	\$	-
8	Valley Gutter	EA	7	\$	-
9	4' Sidewalk	SY	5,309	\$	-
10	10' Sidewalk/ Hike and Bike	SY	665	\$	-
11	Street Signage & Striping (to include temporary road closure signage for construction)	LS	1	\$	-
12	Mailbox Pad	EA	7	\$	-
13	Bollards and Header Curb	EA	3	\$	-
14	Sidewalk Ramps	EA	62	\$	-
SUBTOTAL				\$	-

DRAINAGE IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	15' Curb Inlet	EA	1	\$	-
2	36" RCP	LF	123	\$	-
3	10' Curb Inlet	EA	4	\$	-
4	Mitered Headwall	EA	2	\$	-
5	25' Curb Inlet	EA	1	\$	-
6	18" RCP	LF	136	\$	-
7	24" RCP	LF	68	\$	-
8	15' Curb Inlet	EA	3	\$	-
9	4' x 3'	LF	132	\$	-
10	4' x 2'	LF	23	\$	-
11	Rock RipRap	SY	72	\$	-
12	Pilot Channel	SY	1,135	\$	-
13	Pond Outfall	EA	1	\$	-
SUBTOTAL					\$ -

SANITARY SEWER IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	8" SDR 26 D3034 (4'-8')	LF	714	\$	-
2	8" SDR 26 D3034 (8'-10')	LF	1,873	\$	-
3	8" SDR 26 D3034 (10'-12')	LF	1,258	\$	-
4	8" SDR 26 D3034 (12'-14')	LF	1,918	\$	-
5	8" SDR 26 D3034 (14'+)	LF	1,133	\$	-
6	Green ASTM D3034 SDR 26	LF	336	\$	-
7	White ASTM D3034 SDR 26	LF	220	\$	-
8	Split Casing	LF	36	\$	-
9	Standard Sanitary Manholes	EA	27	\$	-
10	Extra Depth Manhole	VF	145	\$	-
11	Trench Excavation Protection	LF	6,896	\$	-
12	TV Inspection of Sewer Main	LF	6,896	\$	-
13	Mandrel & Vacuum Testing	LF	6,896	\$	-
14	Sanitary Sewer Laterals & Cleanouts	EA	154	\$	-
SUBTOTAL					\$ -

WATER IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Trech Excavation Protection	LF	6,944	\$	-
2	8" C900 Water Line	LF	6,944	\$	-
3	8" Gate Valve w/Box, M.J.	EA	29	\$	-
4	Fire Hydrant Assembly	EA	12	\$	-
5	1" Single Short Water Service	EA	94	\$	-
6	1" Single Long Water Service	EA	34	\$	-
7	1" Dual Short Water Service	EA	10	\$	-
8	1" Dual Long Water Service	EA	5	\$	-
9	3/4" Domestic Meter Boxes	EA	155	\$	-
10	2" Temporary Blow-off	EA	3	\$	-
11	8" Pipe Fittings	TN	2.4	\$	-
SUBTOTAL					\$ -
CONSTRUCTION TOTAL					\$ -
NUMBER OF LOTS					155
COST PER LOT					\$ -