

PRESERVE AT CULEBRA-UNIT 15
BEXAR COUNTY, TX

ITEM NO.	BID ITEM	UNIT	QUANTITY	UNIT PRICE	BID TOTAL
24050	ONSITE STREETS				
	2" Type D HMA/C	SY	7,176		
	8.5" Flex Base	SY	1,966		
	11" Flex Base	SY	5,927		
	Lime Stabilized Subgrade (6" Compacted Depth)	SY	7,893		
	Lime	TON	118		
	Prime Coat	GAL	1,579		
	Tack Coat	GAL	789		
	7" Concrete Curb	LF	2,962		
	4' Sidewalk	SY	15		
	Remove Existing Curb and Sidewalk	SY	50		
	Sidewalk Ramps	EA	20		
	Barricade Posts	EA	6		
	Header Curb	LF	30		
	Signage & Striping	LS	1		
	SUB-TOTAL				
21000	SANITARY SEWER				
	8" Sanitary Sewer Pipe (6'-10' Deep) (SDR-26)	LF	1,280		
	8" Sanitary Sewer Pipe (10'-14' Deep) (SDR-26)	LF	245		
	Tie to Existing Manhole	EA	1		
	Adjust Existing Manhole Rim	EA	4		
	Standard Manhole	EA	6		
	Manhole Extra Depth	VF	20.5		
	Concrete Ring Encasement	EA	6		
	Vertical Stacks	VF	229.8		
	8" x 6" Wye	EA	42		
	6" Sanitary Sewer Lateral (SDR-26)	LF	1,609		
	Trench Excavation Protection	LF	1,525		
	Camera Testing	LF	1,525		
	SUB-TOTAL				
23000	WATER DISTRIBUTION				
	8" PVC C-900, Class 235, DR18	LF	1,605		
	8" Gate Valve, MJ w/ Valve Box	LF	4		
	Standard Fire Hydrant Assembly	EA	3		
	Ductile Iron Fitting	Ton	2.1		
	1" Dual Service w/ 5/8" Meter (Short)	EA	12		
	1" Dual Service w/ 5/8" Meter (Long)	EA	10		
	3/4" Single Service w/ 5/8" Meter (Short)	EA	1		
	3/4" Single Service w/ 5/8" Meter (Long)	EA	2		
	2" Blowoff (Temporary)	EA	1		
	2" Blowoff (Permanent)	EA	3		
	Hydrostatic Testing	LS	1		
	Chlorination	LF	1,605		
	Trench Excavation Protection	LF	1,605		
	Joint Restraints	LS	1		
	Plastic Meter Box with Lid	EA	47		
	SUB-TOTAL				
20080	EARTHWORK, CLEARING, AND SWPPP				
	Street Excavation	CY	3,379		
	Street Embankment	CY	259		
	Channel Excavation	CY	1,538		
	Channel Embankment	CY	3		
	Basin Excavation	CY	88,343		
	Basin Embankment	CY	94		
	Lot Excavation	CY	5,244		
	Lot Embankment	CY	4,490		
	Stockpile and Stabilize Excess Dirt East of Existing Basin	CY	93,658		
	Retaining Walls	SF	133		
	TPDES	LS	1		
	Clearing (Streets)	AC	2.3		
	Clearing (Lots/Offsite Easements)	AC	8.5		
	SUB-TOTAL				
22000	ONSITE DRAINAGE				
	20' Type CI Curb Inlet	EA	1		
	36" UFCMP	LF	144		
	36" RCP (Class III)	LF	282		
	30" RCP (Class III)	LF	66		
	4'x4' Junction Box	EA	1		
	4-Way Inlet (4'X4')	EA	1		
	Concrete Headwall	CY	3.4		
	6" Concrete Rip-Rap	SY	36		
	Trench Excavation Protection	LF	492		
	Concrete Collars	CY	2.8		
	Hydromulching (80% Vegetation Required)	SY	3,648		
	SUB-TOTAL				
22000	ONSITE DRAINAGE - BASIN				
	Hydromulching (80% Vegetation Required)	SY	48,040		
	Temporary Irrigation	SY	48,040		
	SUB-TOTAL				
25060	CONDUITS				
	1-6" SCH 80 & 2-4" SCH 40 Bundle	LF	450		
	2-6" SCH 80 & 2-4" SCH 40 Bundle	LF	150		
	SUB-TOTAL				
	Testing	LS	1		
	Construction Staking	LS	1		
	SUB-TOTAL				
	GRAND TOTAL				