

PRESERVE AT CULEBRA-UNIT 8
BEXAR COUNTY, TX

ITEM NO.	BID ITEM	UNIT	QUANTITY	UNIT PRICE	BID TOTAL
24050	ONSITE STREETS				
	1.5" Type D HMA	SY	5,754		
	2.5" Type C HMA	SY	5,754		
	18.5" Flex Base	SY	6,142		
	21" Flex Base	SY	192		
	Lime Stabilized Subgrade (8" Compacted Depth)	SY	6,334		
	Lime	TON	124		
	Prime Coat	GAL	1,267		
	Tack Coat	GAL	633		
	7" Concrete Curb	LF	2,803		
	4' Sidewalk	SY	43		
	Remove Temporary Turnaround	LS	1		
	Sidewalk Ramps	EA	16		
	Barricade Posts	EA	22		
	Header Curb	LF	110		
	Remove Header Curb and Barricade Posts	LF	34		
	Signage & Striping	LS	1		
	SUB-TOTAL				
21000	SANITARY SEWER				
	8" Sanitary Sewer Pipe (6'-10' Deep) (SDR-26)	LF	120		
	8" Sanitary Sewer Pipe (10'-14' Deep) (SDR-26)	LF	15		
	Tie to Existing Manhole	EA	1		
	Adjust Existing Manhole Rim	EA	1		
	Standard Manhole	EA	1		
	Manhole Extra Depth	VF	3.0		
	Concrete Ring Encasement	EA	1		
	Vertical Stacks	VF	15		
	8" x 6" Wye	EA	47		
	6" Sanitary Sewer Lateral (SDR-26)	LF	2,016		
	Trench Excavation Protection	LF	135		
	Camera Testing	LF	135		
	SUB-TOTAL				
23000	WATER DISTRIBUTION				
	8" PVC C-900, Class 235, DR18	LF	1,581		
	8" Gate Valve, MJ w/ Valve Box	EA	6		
	Standard Fire Hydrant Assembly	EA	4		
	Ductile Iron Fitting	Ton	0.8		
	1" Dual Service w/ 5/8" Meter (Short)	EA	13		
	1" Dual Service w/ 5/8" Meter (Long)	EA	11		
	¾" Single Service w/ 5/8" Meter (Short)	EA	4		
	2" Blowoff (Temporary)	EA	2		
	2" Blowoff (Permanent)	EA	3		
	Hydrostatic Testing	LS	1		
	Chlorination	LF	1,581		
	Trench Excavation Protection	LF	1,581		
	Joint Restraints	LS	1		
	1" Irrigation Service	EA	1		
	Plastic Meter Box with Lid	EA	52		
	SUB-TOTAL				
20080	EARTHWORK, CLEARING, AND SWPPP				
	Street Excavation	CY	4,042		
	Street Embankment	CY	967		
	Channel Excavation	CY	154		
	Lot Excavation	CY	201		
	Lot Embankment	CY	7,589		
	Import	CY	4,159		
	TPDES	LS	1		
	Clearing (Streets)	AC	2.0		
	Clearing (Lots/Offsite Easements)	AC	6.1		
	SUB-TOTAL				
22000	ONSITE DRAINAGE				
	10' Type CI Curb Inlet	EA	2		
	24" RCP (Class III)	LF	35		
	36" UFCMP	LF	159		
	Concrete Headwall	CY	2.0		
	6" Concrete Rip-Rap	SY	41		
	Trench Excavation Protection	LF	194		
	Concrete Collars	CY	1.3		
	SUB-TOTAL				
25060	CONDUITS				
	1-6" SCH 80 & 2-4" SCH 40 Bundle	LF	900		
	2-6" SCH 80 & 2-4" SCH 40 Bundle	LF	120		
	SUB-TOTAL				
	Testing	LS	1		
	Construction Staking	LS	1		
	SUB-TOTAL				
	GRAND TOTAL				