

NOTE: QUANTITIES ARE PROVIDED FOR REFERENCE ONLY. CONTRACTOR RESPONSIBLE FOR QUANTITY CONFIRMATION.

ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
GENERAL ONSITE IMPROVEMENTS				SUBTOTAL:	\$ -
1.	Mobilization	LS	1.00		\$ -
2.	Site Preparation & Clearing	AC	17.70		\$ -
3.	Excavation (Lots)	CY	9,963.00		\$ -
4.	Embankment (Lots)	CY	71,093.00		\$ -
5.	Import Haul in	CY	72,305.00		\$ -
6.	22'X8' Mail Box Pad	EA	1.00		\$ -
7.	Conduit Bundle (2 ~6" & 2~4")	EA	25.00		\$ -
8.	Conduit Bundle (3 ~6" & 2~4")	EA	2.00		\$ -
9.	Lateral Markers at all Sewer Laterals	EA	99.00		\$ -
10.	TPDES Erosion Control (Includes SWPPP and Water Quality Control)	LS	1.00		\$ -
ONSITE STREET IMPROVEMENTS				SUBTOTAL:	\$ -
11.	Excavation (Streets)	CY	5,783.00		\$ -
12.	Embankment (Streets)	CY	16,958.00		\$ -
13.	Tie to Existing - Watson Rd	LS	1.00		
14.	Local Type "A"				\$ -
15.	a. 2" Type "D" HMA	SY	9,613.00		\$ -
16.	b. 10" Crushed Limestone Base	SY	9,613.00		\$ -
17.	c. 6" Lime Stabilized Subgrade	SY	9,613.00		\$ -
18.	ADA Wheelchair Ramps	EA	4.00		\$ -
19.	7" Standard Curb	LF	5,366.00		\$ -
20.	4' Sidewalk	SY	2,345.00		\$ -
21.	Driveway	SY	4,438.00		\$ -
22.	Signage & Striping	LS	1.00		\$ -
ONSITE STORM DRAINAGE IMPROVEMENTS				SUBTOTAL:	\$ -
23.	Drain "A"				\$ -
24.	Reinforced Concrete Class 'A'				\$ -
25.	a. Sidewalk Box	CY	4.50		\$ -
26.	b. Baffle Blocks	CY	0.70		\$ -
27.	6" Concrete U-Channel	SY	100.00		\$ -
28.	Pipe Railing	LF	19.00		\$ -
29.	9"-12" Rock Rubble	SY	93.00		\$ -
30.	Drain "B"				
31.	Reinforced Concrete Class 'A'				\$ -
32.	a. Baffle Blocks	CY	0.40		\$ -
33.	b. 10' Curb Inlet	CY	7.60		\$ -
34.	c. Headwall	CY	1.50		\$ -
35.	Concrete Collars	CY	0.41		\$ -
36.	24" RCP	LF	118.00		\$ -
37.	6" Concrete Rip Rap	SY	20.00		\$ -
38.	9"-12" Rock Rubble	SY	48.00		\$ -
ONSITE POTABLE WATER IMPROVEMENTS				SUBTOTAL:	\$ -
39.	8" PVC Waterline (C900)	LF	2,911.00		\$ -
40.	8" Gate Valve, MJ w/ Valve Box	EA	6.00		\$ -
41.	16" Gate Valve, MJ w/ Valve Box	EA	3.00		\$ -
42.	Ductile Iron Fittings	TON	1.00		\$ -
43.	3/4" Single Service (Short)	EA	49.00		\$ -
44.	3/4" Single Service (Long)	EA	50.00		\$ -
45.	Meter Box	EA	99.00		\$ -
46.	Standard Fire Hydrant Assembly	EA	4.00		\$ -
47.	2" Blowoff Assembly (Temp)	EA	2.00		\$ -
48.	Joint Restraints	LS	1.00		\$ -
49.	Hydrostatic Testing	EA	3.00		\$ -
50.	Tie to Existing Water Main	EA	2.00		\$ -
51.	Trench Excavation Safety Protection	LF	2,911.00		\$ -

NOTE: QUANTITIES ARE PROVIDED FOR REFERENCE ONLY. CONTRACTOR RESPONSIBLE FOR QUANTITY CONFIRMATION.					
ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
	ONSITE SANITARY SEWER IMPROVEMENTS			SUBTOTAL:	\$ -
52.	8" Sanitary Sewer Pipe (0'-6')	LF	99.00		\$ -
53.	8" Sanitary Sewer Pipe (6'-8')	LF	889.00		\$ -
54.	8" Sanitary Sewer Pipe (8'-10')	LF	675.00		\$ -
55.	8" Sanitary Sewer Pipe (10'-12')	LF	358.00		\$ -
56.	8" Sanitary Sewer Pipe (12'-14')	LF	624.00		\$ -
57.	6" Sanitary Sewer Lateral	LF	3,609.00		\$ -
58.	Vertical Stacks	VF	90.00		\$ -
59.	Standard Manhole	EA	9.00		\$ -
60.	Doghouse Manhole	EA	1.00		\$ -
61.	Manhole Ring Encasement	EA	10.00		\$ -
62.	Manhole Extra Depth	VF	37.00		\$ -
63.	8"x6" Wye	EA	93.00		\$ -
64.	Tie to Existing Sewer Main	EA	1.00		\$ -
65.	Camera Testing	LF	2,645.00		\$ -
66.	Trench Excavation Safety Protection	LF	2,645.00		\$ -
GRAND TOTAL					\$ -

	Notes:
	QUANTITIES ARE PROVIDED FOR REFERENCE ONLY. CONTRACTOR RESPONSIBLE FOR QUANTITY CONFIRMATION.