

REDBIRD RANCH PHASE 2

UNIT 2M-2

UNIT PRICES

Date _____

BIDDER'S FULL NAME _____

Address _____

City, State, Zip _____

CONTRACT DAYS: _____ **BASE BID AMOUNT: \$** _____ **-**

1. The Undersigned proposes to furnish all labor, services, materials, tools and necessary equipment for the construction of various improvements and to perform the work required at the locations set out by the Plans and Specifications, in strict accordance with the Contract Documents.
2. In submitting this Bid, it is understood that this Bid may not be altered or withdrawn for a minimum of 90 calendar days, and that the Owner has reserved the right to reject any and all Bids.
3. The Undersigned certifies that this Bid is made in good faith, without collusion or connection with any other person, persons, partnership, company, firm, association, or corporation offering Bids on this work, for the following sum or prices to wit:

SIGNATURES _____

Authorized Signing Officer, Title

SIGNATURES _____

Authorized Signing Officer, Title

UNIT 2M-2:

ITEM	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
ONSITE STREETS					
1.	Local A				
	a. 2" Type D HMA (Face of Curb to Face of Curb)	SY	12,267	\$ -	\$ -
	b. 10" Aggregate Base (1' Behind Back of Curb)	SY	13,642.63	\$ -	\$ -
	c. 6" Treated Subgrade (1' Behind Back of Curb)	SY	13,642.63	\$ -	\$ -
2.	Local B				
	a. 2" Type D HMA (Face of Curb to Face of Curb)	SY	1,839.68	\$ -	\$ -
	b. 2" Type C HMA (Face of Curb to Face of Curb)	SY	1,839.68	\$ -	\$ -
	b. 16" Aggregate Base (1' Behind Back of Curb)	SY	2,005.63	\$ -	\$ -
	c. 8" Treated Subgrade (1' Behind Back of Curb)	SY	2,005.60	\$ -	\$ -
3.	Sidewalk	SY	387	\$ -	\$ -
4.	Sidewalk Ramps	EA	24	\$ -	\$ -
5.	7" Concrete Curb	LF	7,890	\$ -	\$ -
6.	Remove Header Curb & Barricade Post	LF	97	\$ -	\$ -
7.	Prime Coat (0.2 GAL/SY)	GAL	2,821	\$ -	\$ -
8.	Track Coat (0.1 GAL/SY)	GAL	1,411	\$ -	\$ -
9.	Stop Signs (30" X 30") (R1-1)	EA	7	\$ -	\$ -
10.	9" Street Name Sign	EA	18	\$ -	\$ -
11.	Type II Blue Raised Pavement Markers	EA	7	\$ -	\$ -
12.	Lime (30#/SY)	TON	235	\$ -	\$ -
13.	2-6" SCH80 (CPS) & 2-4" SCH40 PVC (Tele/Cable)	LF	52	\$ -	\$ -
14.	TPDES	LS	1	\$ -	\$ -
SUBTOTAL					\$ -

ONSITE WATER DISTRIBUTION

1.	Trench Excavation Protection	LF	3,780	\$	-	\$	-
2.	8" PVC C-900 Class 235, DR 18	LF	3,291	\$	-	\$	-
3.	¾" Poly-Pex Dual Service (Short) w/ 5/8" Meter	EA	20	\$	-	\$	-
4.	1" Poly-Pex Dual Service (Long) w/ 5/8" Meter & 3" SCH 40 Casing	EA	12	\$	-	\$	-
5.	¾" Poly-Pex Single Service (Short) w/ 5/8" Meter	EA	19	\$	-	\$	-
6.	1" Poly-Pex Single Service (Long) w/ 5/8" Meter & 3" SCH 40 Casing	EA	6	\$	-	\$	-
7.	8" Gate Valve, MJ w/ Valve Box	EA	14	\$	-	\$	-
8.	Meter Box	EA	89.0	\$	-	\$	-
9.	Standard Fire Hydrant Assembly	EA	5	\$	-	\$	-
10.	Ductile Iron Fittings	TN	1	\$	-	\$	-
11.	Tie into Existing Main	EA	1	\$	-	\$	-
12.	Hydrostatic Testing	LS	1	\$	-	\$	-
13.	2" Blowoff (Temporary)	EA	2	\$	-	\$	-
14.	2" Blowoff (Permanent)	EA	3	\$	-	\$	-
15.	16" Steel Casing	LF	327	\$	-	\$	-
16.	Joint Restraint	LS	1	\$	-	\$	-
17.	2" HDPE DR9 200 PSI	LF	489	\$	-	\$	-
18.	Test Station	EA	5	\$	-	\$	-
19.	4" PVC Sleeve	LF	55	\$	-	\$	-
				SUBTOTAL		\$	-

ONSITE EARTHWORK, CLEARING, AND SWPPP

1.	Site Clearing	AC	21.7	\$	-	\$	-
2.	Excavation	CY	11,540	\$	-	\$	-
3.	Embankment	CY	18,319	\$	-	\$	-
4.	Rock Filter Dams	LF	121	\$	-	\$	-
5.	Curb Inlet Gravel Filters	LF	90	\$	-	\$	-
6.	Stabilized Construction Entrance/Exit	SY	227	\$	-	\$	-
7.	Silt Fence	LF	3,890	\$	-	\$	-
8.	Concrete Wash Out Pit	EA	1	\$	-	\$	-
9.	Construction Staging Area	LS	1	\$	-	\$	-
				SUBTOTAL		\$	-

ONSITE SANITARY SEWER

1.	8" Sanitary Sewer Pipe (SDR-26)						
	a. 6' to 10' Deep	LF	2,290	\$	-	\$	-
	b. 10' to 14' Deep	LF	1,069	\$	-	\$	-
	c. 14' to 18' Deep	LF	285	\$	-	\$	-
2.	Tie-In To Existing Manholes	EA	1	\$	-	\$	-
3.	Watertight Ring & Cover Sewer Manholes	EA	14	\$	-	\$	-
4.	Extra Depth Manhole	VF	70	\$	-	\$	-
5.	Concrete Manhole Encasement	EA	14	\$	-	\$	-
6.	6" Sanitary Sewer Pipe, Laterals (SDR-26)	LF	3,551	\$	-	\$	-
7.	8"X6" Wye	EA	89	\$	-	\$	-
8.	6" Vertical Stack (SDR-26)	VF	161	\$	-	\$	-
9.	Sewer Main T.V. Inspection	LF	3,644	\$	-	\$	-
10.	Trench Excavation Protection	LF	3,644	\$	-	\$	-
				SUBTOTAL		\$	-

OVERALL DRAINAGE

1.	24" RCP	LF	459	\$	-	\$	-
2.	30" RCP	LF	85	\$	-	\$	-
3.	Hydro-Mulch/Stablize	SY	3,986	\$	-	\$	-
4.	6" Rock Rubble	SY	205	\$	-	\$	-
5.	Reinforced Concrete Class 'A'						
	a. 20' Curb Inlet Type I	EA	3	\$	-	\$	-
	b. 15' Curb Inlet Type I	EA	1	\$	-	\$	-
	c. 10' Curb Inlet Type I	EA	2	\$	-	\$	-
	d. 4' x 4' Junction Box	EA	1	\$	-	\$	-
	e. Headwalls	CY	5.2	\$	-	\$	-
	f. Baffle Blocks	CY	0.4	\$	-	\$	-
	g. Concrete Collars	CY	2.5	\$	-	\$	-
6.	6" Concrete Rip-Rap	SY	10.0	\$	-	\$	-
7.	Trench Excavation Protection	LF	1,519.00	\$	-	\$	-
8.	Demolition Existing Outfall Structure	LS	1.00	\$	-	\$	-
9.	Tie into existing network at Royal Albatross	LS	1.00	\$	-	\$	-
10.	Channel Excavation	CY	1,360.00	\$	-	\$	-
						SUBTOTAL	\$ -
						REDBIRD RANCH PHASE 2 UNIT 2M-2 TOTAL	\$ -