

REDBIRD RANCH PHASE 2

UNIT 3M-4

UNIT PRICES

Date _____

BIDDER'S FULL NAME _____

Address _____

City, State, Zip _____

CONTRACT DAYS: _____ **BASE BID: \$** _____ **-**

1. The Undersigned proposes to furnish all labor, services, materials, tools and necessary equipment for the construction of various improvements and to perform the work required at the locations set out by the Plans and Specifications, in strict accordance with the Contract Documents.
2. In submitting this Bid, it is understood that this Bid may not be altered or withdrawn for a minimum of 90 calendar days, and that the Owner has reserved the right to reject any and all Bids.
3. The Undersigned certifies that this Bid is made in good faith, without collusion or connection with any other person, persons, partnership, company, firm, association, or corporation offering Bids on this work, for the following sum or prices to wit:

SIGNATURES _____
Authorized Signing Officer, Title

SIGNATURES _____
Authorized Signing Officer, Title

ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
ONSITE STREETS					
1.	Local A (50' ROW)				
	a. 2" Type D HMA (Face of Curb to Face of Curb)	SY	10,853	\$ -	\$ -
	b. 10" Aggregate Base (1' Behind Back of Curb)	SY	12,113	\$ -	\$ -
	c. 6" Treated Subgrade (1' Behind Back of Curb)	SY	12,113	\$ -	\$ -
2.	Local B (56' ROW)				
	a. 2" Type D HMA (Face of Curb to Face of Curb)	SY	7,858	\$ -	\$ -
	b. 2" Type C HMA (Face of Curb to Face of Curb)	SY	7,858	\$ -	\$ -
	c. 16" Aggregate Base (1' Behind Back of Curb)	SY	8,357	\$ -	\$ -
	d. 8" Treated Subgrade (1' Behind Back of Curb)	SY	8,357	\$ -	\$ -
3.	Sidewalk	SY	1,367	\$ -	\$ -
4.	Sidewalk Ramps	EA	8	\$ -	\$ -
5.	Hydromulch (Parkways)	SY	6,847	\$ -	\$ -
6.	7" Concrete Curb	LF	9,623	\$ -	\$ -
7.	Remove Header Curb & Barricade Post	LF	83	\$ -	\$ -
8.	Header Curb	LF	193	\$ -	\$ -
9.	Barricade Post	EA	34	\$ -	\$ -
10.	Striping and Signage	LS	1	\$ -	\$ -
11.	TPDES	LS	1	\$ -	\$ -
SUBTOTAL					\$ -

ONSITE DRAINAGE					
1.	24" RCP	LF	865.15	\$ -	\$ -

2.	30" RCP	LF	109.32	\$	-	\$	-
3.	36" RCP	LF	41.17	\$	-	\$	-
4.	3'x3' SBC	LF	13.04	\$	-	\$	-
5.	Curlex Single Net Erosion Control Blankets (Drains & Basins)	SY	15,005	\$	-	\$	-
6.	LandLok 450 Erosion Control Blanket	SY	1,731	\$	-	\$	-
7.	Hydromulch (Drains & Basins)	SY	137,371	\$	-	\$	-
8.	Rock Rubble	SY	563	\$	-	\$	-
9.	Reinforced Concrete Class 'A'						
	a. 10' Curb Inlet Type C	EA	1	\$	-	\$	-
	b. 15' Curb Inlet Type C	EA	2	\$	-	\$	-
	c. 20' Curb Inlet Type CI	EA	2	\$	-	\$	-
	d. 3'x3' Junction Box	EA	1	\$	-	\$	-
	e. 4'x4' Junction Box	EA	1	\$	-	\$	-
	e. RH-15 Headwalls	CY	7	\$	-	\$	-
	f. Baffle Blocks	CY	13.07	\$	-	\$	-
10.	6" Concrete Rip-Rap	SY	1,034	\$	-	\$	-
11.	Chain Link Wire Fence (4' High)	LF	2,496	\$	-	\$	-
12.	Trench Excavation Protection	LF	1,028.68	\$	-	\$	-
13.	15' Wide Gate	EA	2	\$	-	\$	-
						SUBTOTAL	\$ -

ONSITE WATER DISTRIBUTION

1.	2" PVC C-900 Class 235, DR 18	LF	165	\$	-	\$	-
2.	2" Gate Valve, MJ w/ Valve Box	EA	1	\$	-	\$	-
3.	8" PVC C-900 Class 235, DR 18	LF	2,301	\$	-	\$	-
4.	8" Gate Valve, MJ w/ Valve Box	EA	11	\$	-	\$	-
5.	12" PVC C-900 Class 235, DR 18	LF	1,901	\$	-	\$	-
6.	12" Gate Valve, MJ w/ Valve Box	EA	5	\$	-	\$	-
7.	16" Steel Casing	LF	424	\$	-	\$	-
8.	24" Steel Casing	LF	54	\$	-	\$	-
9.	Standard Fire Hydrant Assembly	EA	5	\$	-	\$	-
10.	Ductile Iron Fittings	TON	4.5	\$	-	\$	-
11.	2" Blowoff (Temporary)	EA	1	\$	-	\$	-
12.	2" Blowoff (Permanent)	EA	6	\$	-	\$	-
13.	3/4" Poly-Pex Single Service, Short with 5/8" Meter	EA	62	\$	-	\$	-
14.	1" Poly-Pex Single Service, Long with 5/8" Meter	EA	58	\$	-	\$	-
15.	1" Irrigation Service	EA	1	\$	-	\$	-
16.	Joint Restraint	LS	1	\$	-	\$	-
17.	Hydrostatic Testing	LS	1	\$	-	\$	-
18.	Trench Excavation Protection	LF	4,367	\$	-	\$	-
19.	Meter Box	EA	120	\$	-	\$	-
20.	Tie into Existing Main	EA	1	\$	-	\$	-
						SUBTOTAL	\$ -

ONSITE SANITARY SEWER

1.	8" Sanitary Sewer Pipe (SDR-26)						
	a. 6' to 8' Deep	LF	304	\$	-	\$	-
	b. 8' to 10' Deep	LF	4,216	\$	-	\$	-

c. 10' to 12' Deep	LF	1,432	\$	-	\$	-
d. 12' to 14' Deep	LF	415	\$	-	\$	-
e. 14' to 16' Deep	LF	76	\$	-	\$	-
2. 10" Sanitary Sewer Pipe (SDR-26)						
a. 8' to 10' Deep	LF	375	\$	-	\$	-
3. Standard Manhole	EA	27	\$	-	\$	-
4. Manhole Extra Depth	VF	110.8	\$	-	\$	-
5. 6" Vertical Stacks	VF	23.1	\$	-	\$	-
6. Trench Excavation Protection	LF	6,818	\$	-	\$	-
7. Camera Testing	LF	6,818	\$	-	\$	-
8. 6" Lateral (SDR-26)	LF	4,472	\$	-	\$	-
9. 8" Cap	LF	1	\$	-	\$	-
10. 8"X6" Wye	EA	188	\$	-	\$	-
11. 10"X6" Wye	EA	2	\$	-	\$	-
12. Tie to Existing Manhole	EA	2	\$	-	\$	-
SUBTOTAL					\$	-

ONSITE EARTHWORK, CLEARING, AND SWPPP

1. Clearing	AC	57.5	\$	-	\$	-
2. Excavation (Streets)	CY	15,452	\$	-	\$	-
3. Embankment (Streets)	CY	1,453	\$	-	\$	-
4. Excavation (Lots)	CY	7,265	\$	-	\$	-
5. Embankment (Lots)	CY	20,182	\$	-	\$	-
6. Excavation (Drainage and Basin)	CY	38,448	\$	-	\$	-
7. Embankment (Drainage and Basin)	CY	4,077	\$	-	\$	-
8. Stockpile Excess Material	CY	35,453	\$	-	\$	-
SUBTOTAL					\$	-

ONSITE CONDUITS

1. 2-4" PVC SCH 40 (DR HORTON CONDUIT)	LF	218	\$	-	\$	-
2. 2-6" PVC SCH 80, 2-4" SCH 40	LF	71	\$	-	\$	-
3. 3-6" PVC SCH 80, 2-4" SCH 40	LF	71	\$	-	\$	-
SUBTOTAL					\$	-

REDBIRD RANCH PHASE 2 UNIT 3M-4 - BASE BID AMOUNT: \$ -