# RIVER'S EDGE SUBDIVISION

# CONSTRUCTION DOCUMENT SET NEW BRAUNFELS, TEXAS 78130 COMAL COUNTY

### **NBU NOTES:**

- ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE ENGINEER OF RECORD. IN ACCEPTING THESE PLANS, NEW BRAUNFELS UTILITIES MUST RELY UPON THE ADEQUACY OF THE WORK OF THE ENGINEER OF RECORD.
- THE ENGINEER OF RECORD ACKNOWLEDGES THAT ALL PROPOSED WATER AND WASTEWATER IMPROVEMENTS MUST COMPLY WITH CRITERIA FROM THE TEXAS COMMISSION ON OTHER GOVERNING ENTITY ORDINANCES OR CODES, AND SOUND ENGINEERING JUDGEMENT
- THE ENGINEER OF RECORD ACKNOWLEDGES THAT THE POINT OF DELIVERY FOR THE NBU METER, BACKELOW PREVENTER, OR EASEMENT EDGE, THE CUSTOMER IS RESPONSIBLE FOR
- THE ENGINEERING OF RECORD ACKNOWLEDGES THAT THE POINT OF DELIVERY FOR A NBU WASTEWATER SYSTEM IS THE MAIN SIDE OF THE SERVICE LATERAL FROM THE CUSTOMER'S CLEAN OUT OR PROPERTY LINE. WHICHEVER IS NEARER. THE CUSTOMER IS RESPONSIBLE FOR THE DESIGN, CONSTRUCTION, OPERATION AND MAINTENANCE BEYOND THE POINT OF DELIVERY AND HAS SOLE CONTROL AND SUPERVISION OVER ITS INSTALLATION.
- WATER IS A PRECIOUS COMMODITY IN THE STATE OF TEXAS AND NEW BRAUNFELS UTILITIES (NBU) IS PASSIONATE ABOUT PROTECTING THE LOCAL RESOURCE. THE CONTRACTOR IS FULLY RESPONSIBLE FOR ACQUIRING A FIRE HYDRANT METER SO THAT ALL WATER USED FOR CONSTRUCTION OR TESTING PURPOSED IS PROPERLY ACCOUNTED FOR. NBU WILL NOT TOLERATE ANY WATER THEFT, REGARDLESS OF THE AMOUNT. IF WATER THEFT IS DISCOVERED, THE CONTRACTOR SHALL BE SUBJECT TO MONETARY PENALTIES, CRIMINAL CHARGES, AND STOPPAGE OF ALL CONSTRUCTION ACTIVITIES RELATED TO THE PROJECT. COSTS ASSOCIATED WITH ANY WORK STOPPAGE RESULTING FROM WATER THEFT SHALL BE AT THE FULL EXPENSE OF THE CONTRACTOR.

### **NBU AS-BUILT REQUIREMENTS:**

NBU REQUIRES GPS POINTS FOR CERTAIN WATER, WASTEWATER AND ELECTRIC IMPROVEMENTS SOME OF THIS INFORMATION/DATA MUST BE PERFORMED DURING CONSTRUCTION, PRIOR TO BACKFILLING OPERATIONS. CONTRACTOR SHALL COORDINATE WITH NBU INSPECTOR TO VERIFY ANY ADDITIONAL ITEMS NOT SHOWN BELOW THAT NEED TO BE GPS LOCATED AND THE SURVEY/DELIVERY REQUIREMENTS REGARDING THIS INFORMATION.

GPS POINTS SHALL BE REQUIRED FROM THE DEVELOPER'S CONTRACTOR OR ENGINEER. A MINIMUM OF THREE COORDINATE POINTS FOR GEOREFERENCING SHALL BE REQUIRED. THE WATER AND WASTEWATER GPS POINTS SHALL BE TO SURVEY GRADE. THE ELECTRIC GPS POINTS SHALL BE TO MAP GRADE.

## WATER

VERTICAL BENDS AND EDGE OF STEEL CASING (IF APPLICABLE) PRIOR TO BACKFILL HORIZONTAL BENDS PRIOR TO BACKFILL TEES PRIOR TO BACKFILL

FITTINGS (REDUCERS AND COUPLINGS) PRIOR TO BACKFILL FIRE HYDRANTS (TOP OF FLANGE)

METERS (TOP CENTER OF BOX) **BLOW OFF ASSEMBLY** 

CORNER SLAB OF WATER TANK & GATE VALVE ON TANK

# WASTEWATER

MANHOLES (AND INVERT DEPTH(S)) CLEANOUTS CORNER SLAB OF LIFT STATION

TRANSFORMERS, BOTH ABOVE AND UNDERGROUND (FRONT LOCK)

**PULL BOXES** 

SEE NBU'S "CAD/GPS DELIVERABLES" ON NBU WEBSITE AT NBUTEXAS.COM FOR COMPLETE DETAILS AND REQUIREMENTS.


# TYPE 3 DEVELOPMENT.

- ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE ENGINEER OF RECORD. IN ACCEPTING THESE PLANS, THE CITY OF NEW BRAUNFELS MUST RELY UPON THE ADEQUACY OF THE WORK OF THE ENGINEER RECORD.
- IF CONSTRUCTION HAS NOT COMMENCED WITHIN ONE YEAR OF CITY APPROVAL FOR CONSTRUCTION INSPECTION, THAT APPROVAL IS NO LONGER VALID.
- THIS PROJECT IS WITHIN THE EDWARDS AQUIFER JURISDICTIONAL ZONES.
- A PORTION OF THIS PROJECT IS WITHIN AN INDICATED SPECIAL FLOOD HAZARD ZONE ACCORDING TO THE FEMA FIRM MAP NO.48091C0455G EFFECTIVE DATE 5/8/2024.
- FOLLOWING PERMITS ARE REQUIRED PRIOR TO START OF CONSTRUCTION:
- 1. NEW BRAUNFELS UTILITY APPROVAL
- 2. TCEQ WATER POLLUTION ABATEMENT PLAN APPROVAL 3. COMAL COUNTY OSSF SYSTEM APPROVAL
- 4. TxDOT UTILITY PERMIT

REVISIONS							
NO.	DESCRIPTION			DATE			

LOCATION OF EXISTING UNDERGROUND AND OVERHEAD UTILITIES ARE APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES PRIOR TO BEGINNING WORK AND SHALL BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT OCCUR.





LOCATION MAP 1" = 2000'

SUBMITTAL DATE: FEBRUARY 2025

# PROPERTY DESCRIPTION

DESCRIPTION OF A 124.79 ACRE TRACT OF LAND, SITUATED IN THE ORILLA RUSSELL SURVEY NO. 2, ABSTRACT NO. 485 AND THI ALANSON P. FUQUAY SURVEY NO. 35, ABSTRACT NO. 155, COMAL COUNTY, TEXAS, BEING A PORTION OF A CALLED 39.312 ACRI TRACT DESCRIBED AS TRACT 2 IN DEED CONVEYED TO ANNA GARTH CLARK (1/3 PROPORTION), ARCHIE A. WOHLFAHRT (1/2 PROPORTION), AND JANIS KAY WOMMACK (1/3 PROPORTION), AS RECORDED IN DOCUMENT NO. 201406020560, OFFICIAL PUBLIC RECORDS, COMAL COUNTY, TEXAS (O.P.R.C.C.TX.), AND BEING A PORTION OF A CALLED 90.871 ACRE TRACT AS CONVEYED II DEED TO ANNA GARTH CLARK (1/3 PROPORTION), ARCHIE A. WOHLFAHRT (1/3 PROPORTION), AND JANIS KAY WOMMACK (1. PROPORTION), AS RECORDED IN DOCUMENT NO. 201406020562, O.P.R.C.C.TX.

<u>DEVELOPER:</u> REGAL LAND DEVELOPMENT 6 GRUENE WALD NEW BRAUNFELS, TEXAS 78130 **CONTACT PERSON: CLINT JONES** TELEPHONE: (\_\_\_) \_\_\_-\_\_ LJA ENGINEERING, INC. 9830 COLONNADE BLVD, SUITE 300 SAN ANTONIO, TEXAS 78230 CONTACT PERSON: PRISCILLA FLORES, P.E. PHONE # (210) 503-2700 LJA.COM SURVEYOR: LJA SURVEYING 9830 COLONNADE BOULEVARD.SUITE 300 SAN ANTONIO, TEXAS 78230 CONTACT PERSON: GORDON ANDERSON PHONE # (210) 503-2700

LJA JOB NO. A292-XXXX

## WATER POLLUTION ABATEMENT PLAN SITE PLAN PERMANENT WPAP (SHEET 1 OF 3) PERMANENT WPAP (SHEET 2 OF 3) PERMANENT WPAP (SHEET 3 OF 3) POND OUTFALL PROPOSED DRAINAGE AREA MAP **WQ POND LAYOUT** BASIN DETAILS OFF-SITE DIVERSION BERM FM 306 CULVERT PLAN & PROFILE

DRAINAGE DETAILS (SHEET 1 OF 2)

SHEET NO. DESCRIPTION


DRAINAGE DETAILS (SHEET 2 OF 2) WATER LINE PLAN & PROFILE STA. 1+00 TO STA. 13+00 WATER LINE PLAN & PROFILE STA. 13+00 TO STA. 24+50 WATER LINE PLAN & PROFILE STA. 24+50 TO STA. 35+00 WATER LINE PLAN & PROFILE STA, 35.00 TO STA, 45+50

WATER LINE PLAN & PROFILE STA. 45+50 TO END RIVERS EDGE DR PLAN & PROFILE STA. 1+00 TO STA. 12+00 RIVERS EDGE DR PLAN & PROFILE STA. 12+00 TO STA. 24+00

RIVERS EDGE DR PLAN & PROFILE STA. 24+00 TO STA. 34+50 RIVERS EDGE DR PLAN & PROFILE STA. 34+50 TO STA. 45+50


STORMWATER POLLUTION PREVENTION PLAN DETAILS


RIVERS EDGE DR PLAN & PROFILE STA. 45+50 TO END STORMWATER POLLUTION PREVENTION PLAN




# LJA Engineering, Inc.

9830 Colonnade Blvd Suite 300 San Antonio, Texas 78230 Phone 210.503.2700 LJA.COM FRN-F-1386







K:\a292 regal land development\426 site development plans\dwg—sheets\sh\_P User: smacfarland

- THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES HORIZONTALLY AND VERTICALLY PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATION FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE
- 2. ALL CONCRETE FOR TXDOT DRAINAGE STRUCTURES SHALL MEET TXDOT SPECIFICATIONS. ALL OTHER CONCRETE SHALL BE CLASS "A" CONCRETE AND MEET MINIMUM COMPRESIVE STRENGTH OF 3,000 PSI IN 28 DAYS.
- 3. REFERENCE DRAINAGE DETAILS FOR PIPE TRENCH DETAILS, BOX CULVERT, HEADWALL, AND WINGWALL CONSTRUCTION DETAILS, AND BOX CULVERT BEDDING
- AND EXCAVATION LIMITS. 4. CONTRACTOR SHALL GROUT ALL CURB INLETS AND JUNCTION BOXES TO PROVIDE FOR POSITIVE DRAINAGE.
- 5. EARTHEN CHANNELS WILL BE VEGETATED BY SEEDING OR SODDING 85% OF THE CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATIOON BEFORE THE CITY OF NEW BRAUNFELS WILL ACCEPT.
- 6. CONTRACTOR SHALL MATCH TOP OF CHANNEL TO NATURAL GROUND AND MAINTAIN A MINIMUM CHANNEL DEPTH "D" AS SHOWN IN THE PROFILE.
- 7. ALL RCP SHALL BE AASHTO M170 CLASS III RCP. 8. ALL WORK SHALL BE PERFORMED WITHIN SITE LIMITS OF CONSTRUCTION.
- 9. CONTRACTOR TO PROOF ROLL BOTTOM AND SIDES OF POND TO ENSURE FIRM BOTTOM. IF BOTTOM APPEARS FRACTURED CONTRACTOR TO NOTIFY ENGINEER PRIOR TO PLACEMENT OF SAND BED ON TOPSOIL.
- 10. THE CONTRACTOR WILL BE REQUIRED TO PERFORM TESTING REQUIREMENTS TO SATISFY CITY OF NEW BRAUFNELS INSPECTIONS. THIS SHALL INCLUDE BUT NOT LIMITED TO PROVIDING NECESSARY WATER AS REQUESTED BY INSPECTOR
- 11. THE CONTRACTOR WILL BE RESPONSIBLE FOR POSITIVE DRAINAGE IN BASIN AREA. 12. ALL DISTURBED AREAS TO BE STABILIZED WITH HYDROMULCH IMMEDIATELY AFTER ESTABLISHING FINAL GRADES UNLESS OTHERWISE NOTED.
- 13. UPON COMPLETION OF THE PROPOSED STORMWATER DETENTION, AND PRIOR TO THE RELEASE OF THE CERTIFICATE OF ACCEPTANCE OR OCCUPANCY BY THE PERMIT CENTER, THE DESIGN ENGINEER SHALL CERTIFY IN WRITING THAT THE PROPOSED STRUCTURAL CONTROL(S) WAS INSPECTED (INCLUDING DATE AND TIME OF THE
- INSPECTION) AND CONSTRUCTED IN CONFORMANCE WITH THE APPROVED PLANS. 14. ALL CONCRETE LINING SHALL BE A MINIMUM OF SIX (6) INCHES THICK AND REINFORCED WITH NO. 4 ROUND BARS @ 18 INCHES ON CENTER EACH WAY OR WELDED WIRE FABRIC OF 6" x 6"-W/D6 x W/D6. THE DEPTH OF ALL TOEDOWNS SHALL BE 36 INCHES UPSTREAM, 24 INCHES DOWNSTREAM, AND 18 INCHES FOR SIDE
- 15. CONTRACTOR TO FILL AND COMPACT TO 95% DENSITY IN FILL SECTIONS OVER STORM
- SEWER LINES. 2.0'(MIN) COVER OVER WATER PRIOR TO CONSTRUCTION. 16. ALL PIPE SHALL BE INSTALLED IN ACCORDANCE WITH CITY OF NEW BRAUNFELS
- 17. ALL BENDS AND FITTINGS SHALL BE PREFABRICATED BY MANUFACTURER. NO FIELD FABRICATION OF FITTINGS IS ALLOWED.

# Texas Commission on Environmental Quality Water Pollution Abatement Plan General Construction Notes

Edwards Aquifer Protection Program Construction Notes – Legal Disclaimer The following/listed "construction notes" are intended to be advisory in nature only and do not constitute an approval or conditional approval The following/listed "construction notes" are intended to be advisory in nature only and do not constitute an approval or conditional approval by the Executive Director (ED), nor do they constitute a comprehensive issing of rules or conditions to be followed during construction. Further actions may be required to achieve compliance with TCEC regulations found in Title 30, Texas Administrative Code (TAC), Chapters 213 and 217, as well as boal ordinances and regulations providing for the protection of water quality. Additionally, nothing contained in the following/listed construction notes" restricts the powers of the ED, the commission or any other governmental entity to prevail correct, or curtal advivities that result or may result in pollution of the Edwards Aquifier or hydrologically connected surface waters. The holder of any Edwards Aquifier Protection Plan through all phases of plan implementation. Failure to comply with any condition of the ED's approval, whether or not in contradiction of any "construction notes," is a violation of TCEQ regulation and any violation is adjusted to administrative rules, orders, and penalties as provided under Tile 30, TAC § 1716 30, TOE (regulations and any violation is adjusted to administrative rules, orders, and penalties as provided under Tile 30, TAC § 2116 30, TOE (regulations and any violation is adjusted to administrative rules, orders, and penalties as provided under Tile 30, TAC § 2116 30, TOE (regulations and approved exception by the ED to any part of Title 30 TAC, Chapters 213 and 217, or any other TCEQ applicable regulation

- 1. A written notice of construction must be submitted to the TCEQ regional office at least 48 hours prior to the start of any regulated activities. This notice must include:

  - the name of the approved project;
  - the activity start date; and
  - the contact information of the prime contractor.
- All contractors conducting regulated activities associated with this project must be provided with complete copies of the approved Water Pollution Abatement Plan (WPAP) and the TCEQ letter indicating the specific conditions of its approval. During the course of these regulated activities, the contractors are required to keep on-site copies of the approved plan and
- 3. If any sensitive feature(s) (caves, solution cavity, sink hole, etc.) is discovered during construction, all regulated activities near the sensitive feature must be suspended immediately. The appropriate TCEQ regional office must be immediately notified of any sensitive features encountered during construction. Construction activities may not be resumed until the TCEQ has reviewed and approved the appropriate protective measures in order to protect any sensitive feature and the Edwards Aquifer from potentially adverse impacts to water quality.
- No temporary or permanent hazardous substance storage tank shall be installed within 150 feet of a water supply source, distribution system, well, or sensitive feature.
- 5. Prior to beginning any construction activity, all temporary erosion and sedimentation (E&S) control measures must be properly installed and maintained in accordance with the approved plans and manufacturers specifications. If inspections indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations. These controls must remain in place until the disturbed areas have been permanently stabilized.
- Any sediment that escapes the construction site must be collected and properly disposed of before the next rain event to ensure it is not washed into surface streams, sensitive features,
- 7. Sediment must be removed from the sediment traps or sedimentation basins not later than TCEQ-0592 (Rev. July 15, 2015)

- when it occupies 50% of the basin's design capacity.
- Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from being discharged offsite.
- 9. All spoils (excavated material) generated from the project site must be stored on-site with proper E&S controls. For storage or disposal of spoils at another site on the Edwards Aquifer Recharge Zone, the owner of the site must receive approval of a water pollution abatement plan for the placement of fill material or mass grading prior to the placement of spoils at the
- 10. If portions of the site will have a temporary or permanent cease in construction activity lasting longer than 14 days, soil stabilization in those areas shall be initiated as soon as possible prior to the 14th day of inactivity. If activity will resume prior to the 2fth day, stabilization measures are not required. If drought conditions or inclement weather prevent action by the 14th day, stabilization measures shall be initiated as soon as possible.
- 11. The following records shall be maintained and made available to the TCEQ upon request: the dates when major grading activities occur;
   the dates when construction activities temporarily or permanently cease on a portion of the site; and
  - the dates when stabilization measures are initiated.
- 12. The holder of any approved Edward Aquifer protection plan must notify the appropriate regional office in writing and obtain approval from the executive director prior to initiating any of the following:
- any physical or operational modification of any water pollution abatement structure(s), including but not limited to ponds, dams, berms, sewage treatment plants, and diversionary structures; B. any change in the nature or character of the regulated activity from that which was
- originally approved or a change which would significantly impact the ability of the plan to prevent pollution of the Edwards Aquifer; C. any development of land previously identified as undeveloped in the original water


San Antonio Regional Office 14250 Judson Road San Antonio, Texas 78233-4480 Phone (210) 490-3096 Fax (210) 545-4329

THESE GENERAL CONSTRUCTION NOTES MUST BE INCLUDED ON THE CONSTRUCTION

TCEQ-0592 (Rev. July 15, 2015) Page 2 of 2

REQUIRED TSS REMOVAL FOR ENTIRE SITE				
TOTAL ACREAGE	PRE-DEVELOPMENT IMPERVIOUS COVER	POST-DEVELOPMENT IMPERVIOUS COVER	POST-DEVELOPMENT IMPERVIOUS COVER TREATED BY EX APPROVED PONDS*	Lm-REQUIRED TSS REMOVAL
24.34 ACRES	0.00 ACRES	5.73 ACRES	0.00 ACRES	5,359 LBS

BREAKDOWN OF TSS BEING TREATED BY PERMANENT BMP'S							
PROPOSED BMP	DRAINAGE AREA TO BMP	IMPERVIOUS COVER TO BPM	BMP EFFICIENCY	F	REQUIRED TSS TO BE TREATED (LBS)	TSS BEING REMOVED BY BMP (LBS)	ACTUAL TSS BEING REMOVED BY BMP (LBS)
BATCH DETENTION 'A1'	14.80 ACRES	3.21 ACRES	91%	0.88	2,881 LBS	3,523 LBS	3,100 LBS
VEGETATIVE FILTER STRIP 'A2'	0.5 ACRES	0.22 ACRES	85%	1.0	197 LBS	218 LBS	218 LBS
VEGETATIVE FILTER STRIP 'A3'	0.6 ACRES	0.25 ACRES	85%	1.0	224 LBS	248 LBS	248 LBS
VEGETATIVE FILTER STRIP 'B1'	2.6 ACRES	1.13 ACRES	85%	1.0	1014 LBS	1119 LBS	1119 LBS
VEGETATIVE FILTER STRIP 'C1'	0.8 ACRES	0.34 ACRES	85%	1.0	305 LBS	337 LBS	337 LBS
VEGETATIVE FILTER STRIP 'C2'	0.8 ACRES	0.34 ACRES	85%	1.0	305 LBS	337 LBS	337 LBS
UNTREATED	10.9 ACRES	0.5 ACRES			449 LBS	0 LBS	0 LBS





SION


<u>N</u>

SEAMUS MACFARLAND

# **LEGEND**







SECTION A-A

N.T.S.

**EMERGENCY OVERFLOW** WEIR CALCULATION Q<sub>CAP</sub>=C\*L\*H<sup>3/2</sup> H=1.0' C=2.6  $Q_{CAP} = 2.6*50*1.0^{3/2}$ Q<sub>CAP</sub>=130.0 CFS Q<sub>100</sub>=56.0 CFS 130.0 CFS > 56.0 CFS = OK


> CAUTION: CONTRACTOR TO NOTIFY TEXAS ONE CALL AT 1-800-245-4545 48 HOURS PRIOR TO CONSTRUCTION FOR UTILITY LINE LOCATE. CONTRACTOR SHALL VERIFY HORIZONTAL AND VERTICAL LOCATION OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION, ENGINEER SHALL BE NOTIFIED IMMEDIATELY OF ANY SIGNIFICANT DISCREPANCIES OR REQUIRED DESIGN CHANGES. EXISTING UTILITIES SHOWN HEREON ARE FOR INFORMATIONAL PURPOSES ONLY. ENGINEER ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF THIS INFORMATION.


LOCATION OF EXISTING UNDERGROUND AND OVERHEAD UTILITIES ARE APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES PRIOR TO BEGINNING WORK AND SHALL BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT OCCUR.





JOB NUMBER: A292-426 SHEET NO.








JOB NUMBER:


A292-426


SHEET NO.














PERFORATED 6" SCH 40

PER ROW, 6 ROWS @ 4"

SOLID REMOVABLE CAP-

GALVANIZED STRAP WITH ANCHOR BOLT

TYPE SE SUSPENDED FLOAT SWITCH BY ANCHOR SCIENTIFIC OR APPROVED EQUAL

> CONNECT TO CONTROLLER

SECTION VIEW OF RISER

**FLOAT SENSOR** 

3" TO 4" GRAVEL

2'x2'x4" CONCRETE PAD-

SURROUNDING PIPE

SPACING BETWEEN ROWS

1.5"x1.5" GALVANIZED ANGLE

-IRON TRASH RACK SUPPORT

REMOVABLE TRASH RACK MADE

FROM GALVANIZED WELDED FABRIC

SET INTO CONC PAD

OPENING SIZE 1"x1"

SEDIMENT MARKER

-6" SCH 40 PVC PIPE


NOTE: FLOAT SWITCH TO HAVE

DIFFERENTIAL OF APPROX. 3.5

A MAX ACTIVATION

ATTACHED TO TRASH RACK

PVC RISER W/ (3)- 1" HOLES



# PERFORATED RISER PAD TOP VIEW N.T.S.

1. CONTRACTOR SHALL INSTALL AND ESTABLISH VEGETATION IN BASINS PER BASIN DETAIL SHEET PRIOR TO SITE CLOSEOUT.

SEDIMENT DEPTH MARKER

- 2. UPON COMPLETION OF CONSTRUCTION, AND IN ACCORDANCE WITH TCEQ REGULATIONS, ALL PERMANENT BMP'S (FILTERSTRIPS AND BASINS) MUST BE CERTIFIED BY A REGISTERED PROFESSIONAL ENGINEER.
- 3. ALL AREAS DISTURBED AS PART OF CONSTRUCTION OF BASINS SHALL BE REVEGATATED PRIOR TO COMPLETION.

# SEQUENCE OF OPERATION

SEDIMENT MARKER TO BE

BOTTON POND ELEVATION,

AND GREEN BELOW 6".

PLACED ADJACENT TO

POND OUTLET.

SEDIMENT MARKER TO BE

RED PAINT ABOVE

6" MARK

**GREEN PAINT** 


BELOW 6" MARK

RED COLOR ABOVE 6" OF

- 1. UPON ACTIVATION OF FLOAT SWITCH, DDC CONTROLLER TO START DETENTION
- 2. DETENTION TIMER #1 TO BE MANUALLY SET TO 12 HOURS AND TO BE USER ADJUSTABLE VALUE.
- 3. WHEN DETENTION TIMER #1 HAS ELAPSED, A 8" BUTTERFLY VALVE IS TO OPEN AND RELEASE DETAINED WATER BASIN.
- 4. UPON DEACTIVATION OF FLOAT SWITCH, DDC CONTROL TO START DETENTION
- 5. DETENTION TIMER #2 TO BE MANUALLY SET TO 19-48 HOURS AND TO BE USER
- ADJUSTABLE. 6. WHEN DETENTION TIMER #2 HAS ELAPSED, THE 8" BUTTERFLY VALVE IS TO
- 7. VALVE TO BE ACTUATED PERIODICALLY TO SHOW ACTIVE REGARDLESS OF FLOAT SWITCH OPERATION.

# NOTES TO CONTRACTOR (EACH PHASE OF BASIN CONSTRUCTION)

- 1. CONTRACTOR IS ADVISED THAT TCEQ DOES NOT ALLOW CHANGES TO PERMANENT POLLUTION ABATEMENT MEASURES WITHOUT THEIR PRIOR
- 2. CONTRACTOR SHALL NOTIFY CERTIFYING ENGINEER WHEN:
- REINFORCING STEEL FOR BASIN WALL OR RIPRAP LINER HAS BEEN SET, CONCRETE HAS NOT BEEN PLACED AND DRAIN PIPE AND RISER PIPE IS IN
- 3. WORK SHALL NOT CONTINUE ON THE BASIN UNTIL THE ENGINEER HAS HAD AN OPPORTUNITY TO OBSERVE THE STATUS OF CONSTRUCTION. CONTRACTOR SHALL PROVIDE ENGINEER A MINIMUM OF 24 HOURS ADVANCE NOTICE PRIOR TO TIME THE BASIN WILL BE AT THE REQUIRED STAGE.
- 4. UPON SUBSTANTIAL COMPLETION, OR AS REQUESTED BY ENGINEER, CONTRACTOR TO PROVIDE CERTIFYING ENGINEER WITH FIELD SHOTS VERIFYING ELEVATIONS OF THE FOLLOWING:
- TOP OF BANK/WALL AT EACH CORNER OF BASIN
- TOE OF SLOPE AT EACH CORNER OF BASIN (INSIDE BASIN TOE)
- SPLASH PAD/INLET PIPES OVERFLOW WEIRS
- 5. BEFORE FINAL ACCEPTANCE OF CONSTRUCTION BY THE OWNER, THE CONTRACTOR WILL REMOVE ALL TRASH, DEBRIS, AND ACCUMULATED SILT FROM THE BASINS AND REESTABLISH THEM TO THE PROPER OPERATING CONDITION.



K:\a292 regal land development\426 site development plans\dwg-sheets\sh\_Off—Site Ch User: smacfarland

User: smacfarland Last Modified: Nov. 18, 24 — 07:54 Plot Date/Time: Feb. 04, 25 — 17:53:21


B NUMBER: A292-426 EET NO.

1 NO.

ERSION AN & PF

EDGE DIY

# FM 306 CULVERT STA 1+00 TO END



# LEGEND

PROPOSED CONTOUR

2%
FLOW ARROW

GRASSED DRAIN FLOW

PROPOSED STREET GRADE

EXISTING GROUND LEFT

FXISTING GROUND CENTERLINE

EXISTING GROUND CENTERLINE

EXISTING GROUND RIGHT

SIDEWALK (HOMEOWNER'S RESPONSIBILITY)
SIDEWALK (DEVELOPER'S RESPONSIBILITY)

SUBDIVISION

CULVERT & PROFILE

GE ENTI

G,E,T,CA

GAS, ELECTRIC, TELEPHONE & CABLE TV EASEMENT

BSL


BUILDING SETBACK LINE

ESM'T.

EASEMENT

# RT. RIGHT GENERAL NOTES:

- 1. ALL CONCRETE LINING SHALL BE A MINIMUM OF FIVE (5) INCHES THICK AND REINFORCED WITH NO. 4 ROUND BARS @ 18 INCHES ON CENTER EACH WAY. ALL CONCRETE LINING SHALL DEVELOP A MINIMUM COMPRESSIVE STRENGTH OF NOT LESS THAN THREE THOUSAND (3000) POUNDS PER SQUARE INCH IN TWENTY EIGHT (28) DAYS. THE DEPTH OF ALL TOEDOWNS SHALL BE 36 INCHES UPSTREAM, 24 INCHES DOWNSTREAM, AND 18 INCHES OF SIDE SLOPES.
- 2. IMPROVED EARTHEN CHANNELS AND DETENTION PONDS WILL BE VEGETATED BY SEEDING OR SODDING. EIGHTY-FIVE PERCENT OF THE CHANNEL SURFACE AREA MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT THE CHANNEL FOR MAINTENANCE.
- 3. REFER TO SHEETS 12 & 13 FOR DRAINAGE DETAILS.




HORIZONTAL SCALE 1" = 50' VERTICAL SCALE 1" = 5'

DATE: 2/4/2025 NO. REVISION
DESIGNED BY:
DESIGNED BY:
CHECKED BY:
SMORTH STATE CHANNEL CHANNEL

Phone 210.503.2700 LJA.COM TBPE No. F-1386

**ngineering, Inc.** 

11



RIVER'S EDGE SUBDIVISION

2

 $\sim$ 

DETAILS

REVISIONS
DESCRIPTION
BY DATE


DATE:
DATE:
DATE:
DESIGNED BY:


Phone 210.50 LJ. TBPE No.


LJA Engineering 9830 Colonnade Blvd Suite 300

JOB NUMBER

12







RIVER'S EDGE SUBDIVISION


2

DRAINAGE DETAILS (SHEET

Phone 210.503.2700
LJA.COM
TBPE No. F-1386
TBPE No. F-1386


gineering, Inc.
le Blvd
exas 78230

SHEET NO. **13** 




K:\a292 regal land development\426 site development plans\dwg—sheets\sh\_Waterline User: smacfarland


K:\a292 regal land development\426 site development plans\dwg—sheets\sh\_Waterline P&P. User: smacfarland Lost Modified: Feb. 04, 25 — 17:44



K:\a292 regal land development\426 site development plans\dwg-sheets\sh\_Waterline P User: smacfarland Last Modified: Feb. 04, 25 - 17:44



K:\a292 regal land development\426 site development plans\dwg—sheets\sh\_Waterline P&P.dwg User: smacfarland Last Matifical Eab 04 25 = 17:44



K:\a292 regal land development\426 site development plans\dwg—sheets\sh\_WaUser: smacfarland




HORIZONTAL VALVE


TYPICAL GATE VALVE


1"-2" AIR RELEASE VALVE

INSTALLATION (TYPE I)

N.T.S. 2 OF 2







INSTALLATION (TYPE I)

N.T.S. 1 OF 2

STANDARD FIRE HYDRANT CEARANCE

N.T.S. 1 OF 1

STANDARD FIRE HYDRANT INSTALLATION WITH 5"

STORZ CONNECTOR

1 OF 1


SHEET NO.

A292-426

JOB NUMBER:


K:\a292 regal land development\426 site development plans\dwg—sheets\sh\_Street P&P.dw User: smacfarland Last Modified: Dec. 06, 24 — 10:58

K:\a292 regal land development\426 site development plans\dwg—sheets\sh\_Street P&P.d User: smacfarland Last Modified: Dec. 06, 24 — 10:58



K:\a292 regal land development\426 site development plans\dwg—sheets\sh\_Street User: smacfarland Last Madified: Dec. 06. 24 — 10:58

K:\a292 regal land development\426 site development plans\dwg—sheets\sh\_Street P&P.dw. User: smacfarland Last Modified: Dec. 06, 24 — 10:58





- FENCE POSTS SHOULD BE MADE OF HOT ROLLED STEEL, AT LEAST 4 FEET LONG WITH TEE OR YBAR CROSS SECTION, SURFACE PAINTED OR GALVANIZED, MINIMUM NOMINAL WEIGHT 1.25 LB/FT², AND BRINDELL HARDNESS EXCEEDING 140.
- 2. WOVEN WIRE BACKING TO SUPPORT THE FABRIC SHOULD BE GALVANIZED 2" X 4" WELDED WIRE, 12 GAUGE MINIMUM.
- 3. STEEL POSTS, WHICH SUPPORT THE SILT FENCE, SHOULD BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POST MUST BE EMBEDDED A MINIMUM OF 1-FOOT DEEP AND SPACED NOT MORE THAN 8 FEET ON CENTER. WHERE WATER CONCENTRATES, THE MAXIMUM SPACING SHOULD BE 6 FEET.
- 4. LAY OUT FENCING DOWN-SLOPE OF DISTURBED AREA, FOLLOWING THE CONTOUR AS CLOSELY AS POSSIBLE. THE FENCE SHOULD BE SITED SO THAT THE MAXIMUM DRAINAGE AREA IS 1/4
- 5. THE TOE OF THE SILT FENCE SHOULD BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWN-SLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. WHERE FENCE CANNOT BE TRENCHED IN (E.G., PAVEMENT OR ROCK OUTCROP), WEIGHT FABRIC FLAP WITH 3 INCHES OF PEA GRAVEL ON UPHILL SIDE TO PREVENT FLOW FROM
- 6. THE TRENCH MUST BE A MINIMUM OF 6 INCHES DEEP AND 6 INCHES WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL. SILT FENCE SHOULD BE SECURELY FASTENED TO EACH STEEL SUPPORT POST OR TO WOVEN WIRE, WHICH IS IN TURN ATTACHED TO THE STEEL FENCE POST. THERE SHOULD BE A 3-FOOT OVERLAP, SECURELY FASTENED WHERE ENDS OF FABRIC MEET.
- 8. INSPECT ALL FENDING WEEKLY, AND AFTER ANY RAINFALL. REMOVE SEDIMENT WHEN BUILDUP REACHES 6 INCHES. REPLACE ANY TORN FABRIC OR INSTALL A SECOND LINE OF FENCING PARALLEL TO THE TORN SECTION.
- B. TRIANGULAR SEDIMENT FILTER DIKE
- THE DIKE STRUCTURE SHALL BE CONSTRUCTED OF 6" X 6", 6 GAUGE WELDED WIRE MESH, 18 INCHES PER SIDE, AND WRAPPED WITH GEOTEXTILE FABRIC THE SAME COMPOSITION AS THAT
- FILTER FABRIC SHOULD LAP OVER ENDS SIX (6) INCHES TO COVER DIKE TO DIKE JUNCTION; EACH JUNCTION SHOULD BE SECURED BY SHOAT RINGS.
- 3. POSITION DIKE PARALLEL TO THE CONTOURS, WITH THE END OF EACH SECTION CLOSELY ABUTTING THE ADJACENT SECTIONS.
- 4. FASTENING THE FABRIC SKIRT MAY BE TOED- IN WITH 6 INCHES OF COMPACTED MATERIAL, OR 12 INCHES OF THE FABRIC SKIRT SHOULD EXTEND UPHILL AND BE SECURED WITH A MINIMUM OF 3 INCHES OF OPEN GRADED ROCK, OR WITH STAPLES OR NAILS. IF THESE TWO OPTIONS ARE NOT FEASIBLE THE DIKE STRUCTURE MAY BE TRENCHED IN 4 INCHES.
- 5. TRIANGULAR SEDIMENT FILTER DIKES SHOULD BE INSTALLED ACROSS EXPOSED SLOPES DURING CONSTRUCTION WITH ENDS OF THE DIKE TIED INTO EXISTING GRADES TO PREVENT FAILURE AND SHOULD INTERCEPT NO MORE THAN ONE ACRE OF RUNOFF.
- WHEN MOVED TO ALLOW VEHICULAR ACCESS, THE DIKES SHOULD BE REINSTALLED AS SOON AS POSSIBLE, BUT ALWAYS AT THE END OF THE WORKDAY.
- INSPECTION SHOULD BE MADE WEEKLY OR AFTER EACH RAINFALL EVENT AND REPAIR OR REPLACEMENT SHOULD BE MADE PROMPTLY AS NEEDED BY THE CONTRACTOR. INSPECT AND REALIGN DIKES AS NEEDED TO PREVENT GAPS BETWEEN SECTIONS. 8. ACCUMULATED SILT SHOULD BE REMOVED AFTER EACH RAINFALL, AND DISPOSED OF IN A MANNER WHICH WILL NOT CAUSE ADDITIONAL SILTATION.
- C. TEMPORARY CONSTRUCTION ENTRANCE/EXIT
- 1. AGGREGATE SIZE 4 TO 8 INCHES WASHED, COARSE STONE.
- 2. LENGTH AT LEAST 50 FEET. THICKNESS - MINIMUM 8 INCHES.

WHICHEVER IS GREATER.

- 4. WIDTH MINIMUM WIDTH SHALL BE 12 FEET OR THE FULL WIDTH OF EXIT ROADWAY,
- 5. WASHING WHEN NECESSARY, IF A WASHING FACILITY IS REQUIRED, A LEVEL AREA WITH A MINIMUM 4 INCH DIAMETER WASHED STONE OR COMMERCIAL RACK SHALL BE INSTALLED WHICH DRAINS INTO AN APPROVED TRAP OR SEDIMENT BASIN. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATERCOURSE USING APPROVED
- MAINTENANCE THE ENTRANCE SHALL BE MAINTAINED IN CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC ROADWAYS. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS
  DEMAND, AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED,
  WASHED OR TRACKED ONTO PUBLIC ROADWAY MUST BE REMOVED IMMEDIATELY.
- 7. DRAINAGE IF THE SLOPE TOWARD THE ROAD EXCEEDS 2%, CONSTRUCT A RIDGE 6 TO 8 INCHES HIGH WITH 3:1 (H:V) SIDE SLOPES ACROSS THE FOUNDATION APPROXIMATELY 15 FEET FROM THE ENTRANCE TO DIVERT RUNOFF AWAY FROM THE PUBLIC ROAD.
  INSTALL PIPE UNDER PAD AS NEEDED TO MAINTAIN PROPER PUBLIC ROAD DRAINAGE.
- 8. FABRIC PLACE GEOTEXTILE FABRIC AND GRADE FOUNDATION TO IMPROVE STABILITY, ESPECIALLY WHERE WET CONDITIONS ARE
- D. INTERCEPTOR SWALE
- 1. MAXIMUM DEPTH OF FLOW IN THE SWALE SHALL BE 1 FOOT.
- 2. THE MINIMUM BOTTOM WIDTH OF THE SWALE SHALL BE 2 FEET.
- 3. SIDE SLOPES OF THE SWALE SHALL BE 3:1 OR FLATTER. 4. MINIMUM DESIGN CHANNEL FREEBOARD SHALL BE 6 INCHES
- 5. SWALES MUST MAINTAIN POSITIVE GRADE TO AN ACCEPTABLE OUTLET.
- 6. INTERCEPTOR SWALES MUST BE STABILIZED IMMEDIATELY UPON EXCAVATION SO AS NOT TO CONTRIBUTE TO THE EROSION PROBLEM THEY ARE ADDRESSING. 7. ALL TREES, BRUSH, STUMPS, OBSTRUCTIONS AND OTHER MATERIAL SHALL BE REMOVED AND DISPOSED OF SO AS NOT TO INTERFERE WITH THE PROPER FUNCTIONING OF THE SWALE.
- 8. ALL EARTH REMOVED AND NOT NEEDED IN CONSTRUCTION SHALL BE DISPOSED OF IN AN APPROPRIATE SPOILS SITE.
- 9. INSPECTION MUST BE MADE AFTER EACH RAIN EVENT TO LOCATE AND REPAIR ANY DAMAGE TO THE CHANNEL OR TO CLEAR DEBRIS OR OTHER OBSTRUCTIONS SO AS NOT TO DIMINISH FLOW CAPACITY. DAMAGES WHICH RESULT FROM NORMAL CONSTRUCTION ACTIVITIES SHALL BE REPAIRED AT THE END OF EACH WORK DAY.
- 1. LAY OUT THE WOVEN WIRE SHEATHING PERPENDICULAR TO THE FLOW LINE. THE SHEATHING SHOULD BE 20 GAUGE WOVEN WIRE MESH WITH 1 INCH OPENINGS. 2. BERM SHOULD HAVE A TOP WIDTH OF 2 FEET MINIMUM WITH SIDE SLOPES BEING 2:1 (H:V) OR
- 3. PLACE THE ROCK ALONG THE SHEATHING AS SHOWN IN THE DIAGRAM (FIGURE 1-28), TO A HEIGHT
- WRAP THE WIRE SHEATHING AROUND THE ROCK AND SECURE WITH TIE WIRE SO THAT THE ENDS OF THE SHEATHING OVERLAP AT LEAST 2 INCHES, AND THE BERM RETAINS ITS SHAPE WHEN WALKED UPON. BERM SHOULD BE BUILT ALONG THE CONTOUR AT ZERO PERCENT GRADE OR AS NEAR AS POSSIBLE. THE ENDS OF THE BERM SHOULD BE TIED INTO EXISTING UPSLOPE GRADE AND THE BERM SHOULD BE BURIED IN A TRENCH APPROXIMATELY 3 TO 4 INCHES DEEP TO PREVENT FAILURE OF THE CONTROL
- 6. INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL BY THE RESPONSIBLE PARTY. FOR INSTALLATIONS IN STREAMBEDS, ADDITIONAL DAILY INSPECTIONS SHOULD BE MADE.
- REMOVE SEDIMENT AND OTHER DEBRIS WHEN BUILDUP REACHES 6 INCHES AND DISPOSE OF THE ACCUMULATED SILT IN AN APPROVED MANNER THAT WILL NOT CAUSE ANY ADDITIONAL SILTATION.
- 8. REPAIR ANY LOOSE WIRE SHEATHING. THE BERM SHOULD BE RESHAPED AS NEEDED DURING INSPECTION. THE BERM SHOULD BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED DUE TO SILT ACCUMULATION AMONG THE ROCKS, WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC.
- THE ROCK BERM SHOULD BE LEFT IN PLACE UNTIL ALL UPSTREAM AREAS ARE STABILIZED AND ACCUMULATED SILT REMOVED.
- F. SANDBAG BERMS
- THE BAG LENGTH SHOULD BE 24 TO 30 INCHES, WIDTH SHOULD BE 16 TO 18 INCHES AND THICKNESS SHOULD BE 6 TO 8 INCHES. (3) SANDBAGS SHOULD BE FILLED WITH COARSE GRADE SAND, FREE FROM DELETERIOUS MATERIAL.ALL SAND SHOULD PASS THROUGH A NO. 10 SIEVE. THE FILLED BAG SHOULD HAVE AN APPROXIMATE WEIGHT OF 40 POUNDS.
- THE BERM SHOULD BE A MINIMUM HEIGHT OF 18 INCHES, MEASURED FROM THE TOP OF THE EXISTING GROUND AT THE UPSLOPE TOE TO THE TOP OF THE BERM. THE BERM SHOULD BE SIZED AS SHOWN IN THE PLANS BUT SHOULD HAVE A MINIMUM WIDTH OF 48 INCHES MEASURED AT THE BOTTOM OF THE BERM AND 16 INCHES MEASURED AT THE
- RUNOFF WATER SHOULD FLOW OVER THE TOPS OF THE SANDBAGS OR THROUGH 4-INCH DIAMETER PVC PIPES EMBEDDED BELOW THE TOP LAYER OF BAGS AS SHOWN.
- 5. SANDBAGS SHOULD BE STACKED IN AT LEAST THREE ROWS ABUTTING EACH OTHER, AND IN STAGGERED ARRANGEMENT
- THE BASE OF THE BERM SHOULD HAVE AT LEAST 3 SANDBAGS. THESE CAN BE REDUCED TO 2 AND 1 BAG IN THE SECOND AND THIRD ROWS RESPECTIVELY. FOR EACH ADDITIONAL 6 INCHES OF HEIGHT, AN ADDITIONAL SANDBAG MUST BE ADDED TO EACH ROW WIDTH.
- THE SAND BAG BERM SHOULD BE INSPECTED WEEKLY AND AFTER EACH RAIN. THE SANDBAGS SHOULD BE RESHAPED OR REPLACED AS NEEDED DURING INSPECTION.
- WHEN THE SILT REACHES 6 INCHES, THE ACCUMULATED SILT SHOULD BE REMOVED AND DISPOSED OF AT AN APPROVED SITE IN A MANNER THAT WILL NOT CONTRIBUTE TO

- G. STONE OUTLET SEDIMENT TRAP
- 1. ALL AGGREGATE SHOULD BE AT LEAST 3 INCHES IN DIAMETER AND SHOULD NOT EXCEED A VOLUME OF 0.5 CUBIC
- 2. EARTH EMBANKMENT: PLACE FILL MATERIAL IN LAYERS NOT MORE THAN 8 INCHES IN LOOSE DEPTH. BEFORE COMPACTION, MOISTEN OR AERATE EACH LAYER AS NECESSARY TO PROVIDE THE OPTIMUM MOISTURE CONTENT OF THE MATERIAL. COMPACT EACH LAYER TO 95 PERCENT STANDARD PROCTOR DENSITY. DO NOT PLACE MATERIAL ON SURFACES THAT ARE MUDDLY OR FROZEN. SIDE SLOPES FOR THE EMBANKMENT ARE TO BE
- THE MINIMUM WIDTH OF THE EMBANKMENT SHOULD BE 3 FEET 3. A GAP IS TO BE LEFT IN THE EMBANKMENT IN THE LOCATION WHERE THE NATURAL CONFLUENCE OF RUNOFF CROSSES THE EMBANKMENT LINE. THE GAP IS TO HAVE A WIDTH IN FEET EQUAL TO 6 TIMES THE DRAINAGE AREA IN ACRES.
- GEOTEXTILE COVERED ROCK CORE: A CORE OF FILTER STONE HAVING A MINIMUM HEIGHT OF 1.5 FEET AND A MINIMUM WIDTH AT THE BASE OF 3 FEET SHOULD BE PLACED ACROSS THE OPENING OF THE EARTH EMBANKMENT AND SHOULD BE COVERED BY GEOTEXTILE FABRIC WHICH SHOULD EXTEND A MINIMUM DISTANCE OF 2 FEET IN EITHER DIRECTION FROM THE BASE OF THE FILTER STONE CORE.
- FILTER STONE EMBANKMENT: FILTER STONE SHOULD BE PLACED OVER THE GEOTEXTILE AND IS TO HAVE A SIDE SLOPE WHICH MATCHES THAT OF THE EARTH EMBANKMENT OF 3:1 AND SHOULD COVER THE GEOTEXTILE/ROCK CORE A MINIMUM OF 6INCHES WHEN INSTALLATION IS COMPLETE. THE CREST OF THE OUTLET SHOULD BE AT LEAST 4 FOOT BELOW THE TOP OF THE EMBANKMENT LEAST 1 FOOT BELOW THE TOP OF THE EMBANKMENT.
- INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL. CHECK THE EMBANKMENT, SPILLWAYS, AND OUTLET FOR EROSION DAMAGE, AND INSPECT THE EMBANKMENT FOR PIPING AND SETTLEMENT. REPAIR SHOULD BE MADE PROMPTLY AS NEEDED BY THE CONTRACTOR.
- TRASH AND OTHER DEBRIS SHOULD BE REMOVED AFTER EACH RAINFALL TO PREVENT CLOGGING OF THE
- OUTLET STRUCTURE.
  SEDIMENT SHOULD BE REMOVED AND THE TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO HALF OF THE DESIGN DEPTH OF THE TRAP.
- 1. THE DRAINAGE AREA FOR A SEDIMENT BASIN SHALL BE LESS THAN 100 ACRES.
- SHALL BE REMOVED WHEN SEDIMENT REACHES 50% STORAGE CAPACITY. 3. PLACE FILL MATERIAL IN LAYERS NOT MORE THAN 8 INCHES IN LOOSE DEPTH. BEFORE COMPACTION, MOISTEN OR AERATE EACH LAYER AS NECESSARY TO PROVIDE THE OPTIMUM MOISTURE CONTENT OF THE MATERIAL. COMPACT EACH LAYER TO 95 PERCENT STANDARD PROCTOR DENSITY. DO NOT PLACE MATERIAL ON SURFACES THAT ARE MUDDY OR FROZEN. SIDE SLOPES FOR THE EMBANKMENT SHOULD BE 3:1 (H:V). MINIMUM WIDTH OF THE EMBANKMENT AT THE TOP SHALL BE 8 FEFT.


2. THE BASIN SHOULD INCLUDE A PERMANENT STAKE TO INDICATE THE SEDIMENT LEVEL IN THE POOL AND MARKED TO INDICATE WHEN THE SEDIMENT OCCUPIES 50% OF THE BASIN VOLUME (NOT THE TOP OF THE STAKE). SEDIMENT


- 4. AN EMERGENCY SPILLWAY SHOULD BE INSTALLED ADJACENT TO THE EMBANKMENT ON UNDISTURBED SOIL AND SHOULD BE SIZED TO CARRY THE FULL AMOUNT OF FLOW GENERATED BYA 10-YEAR, 3-HOUR STORM WITH 1 FOOT OF FREEBOARD LESS THE AMOUNT WHICH CAN BE CARRIED BY THE PRINCIPAL OUTLET CONTROL DEVICE. THE EMERGENCY SPILLWAY SHOULD BE LINED WITH RIPRAP AS SHOULD THE SWALE LEADING FROM THE SPILLWAY TO THE NORMAL WATERCOURSE AT THE BASE OF THE EMBANKMENT.
- 5. INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL. CHECK THE EMBANKMENT, SPILLWAYS, AND OUTLET FOR EROSION DAMAGE, AND INSPECT THE EMBANKMENT FOR PIPING AND SETTLEMENT. REPAIR SHOULD BE MADE PROMPTLY AS NEEDED BY THE CONTRACTOR.TRASH AND OTHER DEBRIS SHOULD BE REMOVED AFTER EACH RAINFALL TO PREVENT CLOGGING OF THE OUTLET STRUCTURE.
- 6. ACCUMULATED SILT SHOULD BE REMOVED AND THE BASIN SHOULD BE RE- GRADED TO ITS ORIGINAL DIMENSIONS AT SUCH COUNT THAT THE CAPACITY OF THE IMPOUNDMENT HAS BEEN REDUCED TO 75% OF ITS ORIGINAL STORAGE

### ADDITIONAL NOTES:

H. SEDIMENT BASINS

- 1. UPON COMPLETION OF CONSTRUCTION ALL DISTURBED AREAS SHALL BE REVEGETATED TO 70% OF EXISTING IN ACCORDANCE WITH THE SWPPP AND TPDES REQUIREMENTS.
- 2. THIS SITE IS NOT LOCATED ADJACENT TO ANY SURFACE WATERS.
- 3. THIS SITE WILL NOT HAVE ANY LOCATIONS WHERE STORM WATER DISCHARGES DIRECTLY TO A SURFACE WATER BODY.






### **CURB INLET PROTECTION**

- 1. WHEN A SANDBAG IS FILLED WITH MATERIAL, THE OPEN END OF THE SANDBAG SHOULD BE STAPLED OR TIED WITH NYLON OR POLY CHORD.
- 2. INLET PROTECTION SHALL BE PLACED OVER THE MOUTH OF THE INLET WITH A 2 FOOT OVERLAP ON EITHER SIDE.
- 3. THE FABRIC COVER AND SHALL BE A CONTINUOUS WRAPPING OF GEOTEXTILE.
- 4. THE SKIRT SHALL BE WEIGHTED WITH ONE 18"x24"x6" SANDBAG EVERY 3 FEET. 5. INSPECTION SHALL BE MADE WEEKLY OR AFTER EACH RAINFALL EVENT AND REPAIR OR
- REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED BY THE CONTRACTOR. 6. ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF FOUR INCHES, AND DISPOSED OF IN A MANNER WHICH WILL NOT CAUSE ADDITIONAL SILTATION.
- 7. AFTER THE DEVELOPMENT SITE IS COMPLETELY STABILIZED, THE DIKES AND ANY REMAINING SILT SHALL BE REMOVED. SILT SHALL BE DISPOSED OF IN AN APPROVED SITE AND IN SUCH A MANNER AS TO NOT CONTRIBUTE TO ADDITIONAL SILTATION.


# **GRATE INLET PROTECTION**


- . WIRE MESH SHALL BE LAID OVER THE DROP INLET SO THAT THE WIRE EXTENDS MINIMUM OF 1 FOOT BEYOND EACH SIDE OF THE INLET STRUCTURE. WIRE MESH WITH ½ INCH OPENINGS SHALL BE USED. IF MORE THAN ONE STRIP OF MESH IS NECESSARY, THE STRIPS SHALL BE OVERLAPPED.
- 2. COARSE AGGREGATE SHALL BE PLACED OVER THE WIRE MESH AS INDICATED ABOVE. THE DEPTH OF STONE SHALL BE AT LEAST 12 INCHES OVER THE ENTIRE INLET OPENING. THE STONE SHALL EXTEND BEYOND THE INLET OPENING AT LEAST 18 INCHES ON ALL SIDES.
- 3. IF THE STONE FILTER BECOMES CLOGGED WITH SEDIMENT SO THAT IT NO LONGER ADEQUATELY PERFORMS IT'S FUNCTION, THE STONES MUST BE PULLED AWAY FROM THE INLET, CLEANED AND REPLACED.






**CONSTRUCTION STAGING AREA** 





27.05 ROCK BERM

- 1. USE ONLY OPEN GRADED ROCK 4-8 INCH DIAMETER FOR STREAMFLOW CONDITION; USE OPEN GRADED ROCK 3-5 INCHES DIAMETER FOR OTHER CONDITIONS.
- 2. THE ROCK BERM SHALL BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM 1 INCH OPENINGS AND MINIMUM WIRE DIAMETER OF 20 GAUGE.
- THE ROCK BERM SHALL BE INSPECTED WEEKLY OR AFTER EACH RAIN, AND THE STONE AND/OR FABRIC CORE - WOVEN WIRE SHEATHING, SHALL BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED, DUE TO SILT ACCUMULATION AMONG THE ROCKS, WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC.
- 4. WHEN SILT REACHES A DEPTH EQUAL TO ONE-THIRD THE HEIGHT OF THE BERM OR ONE FOOT, WHICHEVER IS LESS, THE SILT SHALL BE REMOVED AND DISPOSED OF IN AN APPROVED SITE AND IN SUCH A MANNER AS TO NOT CREATE A SILTATION PROBLEM.
- 5. DAILY INSPECTION SHALL BE MADE ON SEVERE SERVICE ROCK BERMS; SILT SHALL BE REMOVED WHEN ACCUMULATION REACHES 6 INCHES.
- 6. WHEN THE SITE IS COMPLETELY STABILIZED, THE BERM AND ACCUMULATED SILT SHALL BE REMOVED AND DISPOSED OF IN AN APPROVED MANNER.



X SEAMUS MACFARLAND 152120 KICENSED COM

JOB NUMBER:

SHEET NO.

A292-426