
ALAMO RANCH PARKWAY PHASE II SAN ANTONIO, TEXAS **CIVIL CONSTRUCTION PLANS**

SHEET INDEX

Sheet Description	Sheet No.
COVER SHEET	C0.00
ULTIMATE CONDITIONS MASTER DRAINAGE PLAN	C1.00
PROPOSED CONDITIONS MASTER DRAINAGE PLAN	C1.00A
DRAIN A1 PLAN & PROFILE (STA. 1+13.15 TO STA. 4+20.00)	C1.01
DRAIN A1 PLAN & PROFILE (STA. 4+20.00 TO END)	C1.02
DRAIN B1 PLAN & PROFILE	C1.03
DRAIN A2 & B2 PLAN & PROFILE	C1.04
DRAIN A3 PLAN & PROFILE	C1.05
DRAIN B3 PLAN & PROFILE	C1.06
DRAIN A3 & B3 DETAILS	C1.07
DRAIN C PLAN & PROFILE (STA. 1+20.00 TO STA. 4+00.00)	C1.08
DRAIN C PLAN & PROFILE (STA. 4+00.00 TO STA. 7+00.00)	C1.09
DRAIN C PLAN & PROFILE (STA. 7+20.00 TO END)	C1.10
DRAIN D1 PLAN & PROFILE (STA. 1+28.00 TO STA. 5+00.00)	C1.11
DRAIN D1 PLAN & PROFILE (STA. 5+00.00 TO END)	C1.12
DRAIN D2 PLAN & PROFILE	C1.13
DRAIN D3 PLAN & PROFILE	C1.14
DRAIN D3 & F3 DETAILS	C1.15
DRAIN D4 PLAN & PROFILE	C1.16
DRAIN D5 PLAN & PROFILE	C1.17
DRAIN E PLAN & PROFILE	C1.18
DRAIN F1 PLAN & PROFILE (STA. 1+20.00 TO STA. 5+00.00)	C1.19
DRAIN F1 PLAN & PROFILE (STA. 5+00.00 TO STA. 9+00.00)	C1.20
DRAIN F1 PLAN & PROFILE (STA. 9+00.00 TO STA. 13+20.00)	C1.21
DRAIN F1 PLAN & PROFILE (STA. 13+20.00 TO END)	C1.22
DRAIN F2 PLAN & PROFILE (STA. 1+00.03 TO STA. 5+00.00)	C1.23
DRAIN F3 PLAN & PROFILE (STA. 5+20.00 TO STA. 9+60.00)	C1.24
DRAIN F4 PLAN & PROFILE (STA. 9+60.00 TO END)	C1.25
DRAIN F4 PLAN & PROFILE	C1.26
DRAIN F4-F6 PLAN & PROFILE	C1.27
DRAIN G PLAN & PROFILE (STA. 1+20.00 TO STA. 5+00.00)	C1.28
DRAIN G PLAN & PROFILE (STA. 5+00.00 TO END)	C1.29
DRAIN H PLAN & PROFILE (STA. 1+10.00 TO STA. 5+50.00)	C1.29A
DRAIN H PLAN & PROFILE (STA. 5+50.00 TO STA. END)	C1.29B
DRAINAGE DETAILS	C1.30
DRAINAGE DETAILS	C1.31
DRAINAGE DETAILS	C1.32
DRAINAGE DETAILS	C1.33
DRAINAGE DETAILS	C1.34
DRAINAGE DETAILS	C1.35
DRAINAGE DETAILS	C1.36
DRAINAGE DETAILS	C1.37
DRAINAGE DETAILS	C1.38

DCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery © 2015, CAPCOG, Digital Globe, Texas Orthoimagery Program, USDA Farm Service Agency



LOCATION MAP NOT-TO-SCALE


PREPARED FOR:

CONTINENTAL HOMES OF TEXAS, L.P. 5419 N LOOP 1604 E SAN ANTONIO, TEXAS 78247

> SEPTEMBER 2021 **UPDATED DECEMBER 2023**



2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.900 TBPE FIRM REGISTRATION #470 | TBPLS FIRM REGISTRATION #1002880



Sheet Title ALAMO RANG ALAMO RANO ALAMO RANO ALAMO RANC ALAMO RANC ALAMO RANC ALAMO RANC INTERSECTIO STREET DET STREET DET STREET DET STREET DET OVERALL SIG OVERALL SIG OVERALL SIG SIGNAGE DE SIGNAGE DE SIGNAGE DE OVERALL WA **OVERALL WA OVERALL WA** WATER DIST WATER DIST A OVERALL SA SANITARY SE SANITARY SE SANITARY SE SANITARY SE OVERALL UT OVERALL UT OVERALL GR STORM WATE

DEVELOPER'S NAME: CON ADDRESS: 5419 N LOO CITY: SAN ANTONIO PHONE# (210)-496-266 SAWS BLOCK MAP# 068 TOTAL LINEAR FOOTAGE NUMBER OF LOTS 0

Sheet List Table

Sheet Title	Sheet Number
ALAMO RANCH EASTBOUND PLAN & PROFILE (STA. 62+56.43 TO STA. 74+00.00)	C2.00
ALAMO RANCH EASTBOUND PLAN & PROFILE (STA. 74+00.00 TO STA. 85+00.00)	C2.01
ALAMO RANCH EASTBOUND PLAN & PROFILE (STA. 85+00.00 TO END)	C2.02
ALAMO RANCH WESTBOUND PLAN & PROFILE (STA. 61+36.38 TO STA. 71+00.00)	C2.03
ALAMO RANCH WESTBOUND PLAN & PROFILE (STA. 71+00.00 TO STA. 81+00.00)	C2.04
ALAMO RANCH WESTBOUND PLAN & PROFILE (STA. 81+00.00 TO STA. 91+00.00)	C2.05
ALAMO RANCH WESTBOUND PLAN & PROFILE (STA. 91+00.00 TO END)	C2.06
INTERSECTION DETAIL	C2.07
STREET DETAILS	C2.10
STREET DETAILS	C2.11
STREET DETAILS	C2.12
STREET DETAILS	C2.13
OVERALL SIGNAGE PLAN	C3.00
OVERALL SIGNAGE PLAN	C3.01
OVERALL SIGNAGE PLAN	C3.02
SIGNAGE DETAILS SHEET 1 OF 3	C3.10
SIGNAGE DETAILS SHEET 2 OF 3	C3.11
SIGNAGE DETAILS SHEET 3 OF 3	C3.12
OVERALL WATER DISTRIBUTION PLAN	C4.00
OVERALL WATER DISTRIBUTION PLAN	C4.01
OVERALL WATER DISTRIBUTION PLAN	C4.02
WATER DISTRIBUTION PLAN DETAILS	C4.10
WATER DISTRIBUTION PLAN NOTES	C4.11
OVERALL SANITARY SEWER PLAN	C5.00
SANITARY SEWER LINE A PLAN & PROFILE (STA. 10+50.00 TO STA. 17+00.00)	C5.01
SANITARY SEWER LINE A PLAN & PROFILE (STA. 17+00.00 TO STA. END)	C5.02
SANITARY SEWER DETAILS	C5.10
SANITARY SEWER NOTES	C5.11
OVERALL UTILITY PLAN	C6.00
OVERALL UTILITY PLAN	C6.01
OVERALL GRADING PLAN	C7.00
STORM WATER POLLUTION PREVENTION PLAN	C8.00
STORM WATER POLLUTION PREVENTION PLAN DETAILS	C8.10

WATER (SAWS PRESSURE ZONE 8)


SEWER

	_
NTINENTAL HOMES OF TEXAS, L.P.	_
DP 1604 E	_
STATE:TEXASZIP:78247	_
68FAX#(210)-496-2668	_
68FAX#(210)-496-2668 8 & 596_TOTAL_EDU'S10TOTAL_ACREAGE22.0	<u>0</u> 3
OF PIPE: <u>12"-3,594 LF</u> PLAT NO. <u>21-11800379</u>	<u>)</u>
SAWS JOB NO. <u>21-1214</u>	_


DEVELOPER'S NAME: CONTINENTAL HOMES OF TEXAS, L.P.
ADDRESS: 5419 N LOOP 1604 E
CITY: SAN ANTONIO STATE: TEXAS ZIP: 78247
PHONE# (210)-496-2668 FAX# (210)-496-2668
PHONE# (210)-496-2668 068598 & FAX# (210)-496-2668 SAWS BLOCK MAP# 068596 TOTAL EDU'S 00 TOTAL ACREAGE 22.00
TOTAL LINEAR FOOTAGE OF PIPE: <u>12"-1161 LF</u> PLAT NO. <u>21-1180037</u>
NUMBER OF LOTS 0 SAWS JOB NO. 21-1679


		(SE DRAIN E EE SHEET C1.11-C1.12	E SHEET	AIN D2 – C1.13)					36		c=101	🗩 DR	AIN E EE SHE			(VOL DF	325.0 IPBELT	PLATTED 70 ACR ON ROA , PG 81	ES ND, LTD	
			8			16 7 19	Lc=33'	23) ARE 1.40			=82'	25						(29)		
(AREA O 4.02 AC			$\overline{20}$		J	c=207	102-500%					IN F3 SHEE	(AREA 1.74) T C1.1		3	1)	- DRAIN (SEE S	F5 SHEET C1.27)	-(32
	UNPLAT 157.48 A VISE OAKS (VOL 9437, PG	TED CRES 5, LTD 963 O.P.R.)	DRAIN SHEET C1.	17)		2		~	SHEE"	E T C1.25	DRAIN 5-C1.:			325 MPBE	LTON	ACRE ROAE	S , LTD OPR)	Lc=15 (SEE	DRAIN F6 - SHEET C1.27)	
						5	DETAIL CALE: 1" =	"B" = 100'												
Point	Structure	Area	ALAMO R/	ANCH PARKWAY Ground		land Flow	CONDITIONS MAST			ARY TABLE ncentrated Surface	Tc (min)		low (6 fps) Tc (min)		с		Q (cfs)	Frequency	Total Q ₂₅	Inter
	Drain H - Curb Inlet in Sump	A	43.39	Avg. Grass	2	100	12	0.53	2812	Paved	33.7	1078	2.2	47.0	0.72	2.88 3.99 4.96 5.28	90.0 124.7 155.0 46.5	5 25 100		
2	Drain A1 - Earthen Channel	E	9.71	Avg. Grass Avg. Grass	2	100	12	2.00	470 81	Unpaved	2.7 0.5	416	5.5	15.0		7.32 9.12 4.94 6.84	64.6 80.5 157.5 218.1	25 100 5 25	-	
4	Drain A2 & Drain B2 - 4 - Way Inlets	F	1.29	Avg. Grass	0	0	5	2.00	0	Paved	0.0	748	2.1	7.0	0.85	8.50 7.11 9.95	271.1 7.8 10.9 13.7	100 5 25	10.9/2=5.45 cfs	
5	Drain B3 - Culvert	E+G	48.15	Avg. Grass	2	100	12	2.00	81	Unpaved	0.5	2723	7.6	20.0	0.74	12.49 4.54 6.28 7.79	161.1 222.9 276.5	100 5 25 100	222.9+5.45=228.35 (cfs
6	Drain B1 - Earthen Channel	G	3.86	Avg. Grass	2	100	12	2.00	653	Unpaved	3.8	213	0.6	16.0	0.93	5.10 7.07 8.79 4.43	18.4 25.5 31.6 6.1	5 25 100 5	-	
7	Drain A3 - Curb Inlet in Sump Drain A3 - Storm Drain	C B+C	1.58	Avg. Grass Avg. Grass	0.5	100	17	2.00	258 470	Unpaved Unpaved	2.6	559	1.6	21.0	0.87	6.12 7.59 5.10 7.07	8.4 10.5 52.1 72.2	25 100 5 25	72.7+5.45= 77.65 ct	fs
9	Drain A3 - Culvert	A+B+C	54.68	Avg. Grass	2	100	12	0.53	2812	Paved	33.7	2454	5.0	50.0	0.76	8.79 2.77 3.84	89.7 114.8 159.2	100 5 25	159.2+5.45= 164.65	~~~
10	Street Capacity Check	D	4.15	Avg. Grass	0.5	100	17	1.00	260	Unpaved	2.7	577	1.6	21.0	0.59	4.78 4.43 6.12 7.59	198.1 10.2 15.0 18.6	100 3 25 100		~~~
11	Street Capacity Check	1	1.83	Avg. Grass	1.15	100	14	0.00	0	Unpaved	0.0	356	1.0	14.0	0.72	5.47 7.6 9.48 4.43	7.2 10.0 12.5 17.3	5 25 100 5	_	
12	Drain A3 - Curb Inlets in Sump Drain A3 - Culvert	D+H+I A+B+C+D+H+I	6.18	Avg. Grass Avg. Grass	1.15 2	100	17	1.00 0.53	260 2812	Unpaved Paved	2.7	577 	1.6 	21.0	0.63	6.12 7.59 2.77 3.84	23.9 20.7 125.6 174.2	25 100 5 25	174.2+5.45 = 179.65	ofe
13	Drain D1 - Earthen Channel	J	9.44	Avg. Grass	2	100	12	2.00	767	Unpaved	4.4	2300	0.8	17.0	0.73	4.78 4.94 6.84	216.8 42.4 58.7	100 5 25		
15	Drain D1 - Earthen Channel	J+L	17.72	Avg. Grass	2	100	12	2.00	767	Unpaved	4.4	505	1.4	17.0	0.92	8.50 4.94 6.84 8.50	73.0 80.4 111.3 138.4	100 5 25 100		
16	Future Drain	K+M	26.26	Avg. Grass	2	100	11	2.00	188	Unpaved	1.1	2512	7.0	19.0	0.73	4.66 6.45 8.00 4.66	89.6 124.0 153.8 165.5	5 25 100 5	-	
17	Drain D3 - Culvert Drain D4 - Curb Inlets in Sump	J+K+L+M N	43.98	Avg. Grass Avg. Grass	2	100 0	5	2.00	188	Unpaved Unpaved	0.0	2545 561	7.1	19.0 6.0	0.81	6.45 8.00 7.45 10.43	229.0 284.0 8.9 12.5	25 100 5 25	229+26.5=255.5 cf	rs
19	Drain D3 - Culvert	J+K+L+M+N	45.38	Avg. Grass	2	100	12	2.00	188	Unpaved	1.1	2545	7.1	20.0	0.81	13.08 4.54 6.28 7.79	15.7 166.6 230.5 285.9	100 5 25 100	230.5+26.5=257 cf	fs
20	Drain D5 - Curb Inlets in Sump	0	4.02	Avg. Grass	1.4	85	13	0.00	0	Unpaved	0.0	612	1.7	14.0	0.72	5.47 7.6 9.48	15.8 22.0 27.4	5 25 100	-	
21	Drain D3 - Culvert	J+K+L+M+N+O	49.40	Avg. Grass	2	100	12	2.00	188	Unpaved	1.1	2752	7.6	20.0	0.80	4.54 6.28 7.79 4.66	179.8 248.7 308.5 38.3	5 25 100 5	248.7+26.5=275.2 c	
22 23	Drain D2 & Drian E - 4-Way Inlets Drain E - Storm Drain	P Q	11.00 36.41	Avg. Grass Avg. Grass	2	62 100	11	0.00	0	Unpaved Unpaved	0.0	3134 2865	8.7	19.0 19.0	0.75	6.45 8.00 4.66 6.45	53.0 65.8 122.2 169.1	25 100 5 25	53/2= 26.5 cfs in each 169.1+26.5 = 195.6 d	
24	Drain F3 - Culvert	R+S+T+U	47.41	Avg. Grass	2	100	12	2.00	23	Unpaved	0.1	3705	10.3	22.0	0.90	8.00 4.33 5.98 7.41	209.7 184.2 254.4 315.3	100 5 25 100	-	
25	Drain F1 - Earthen Channel	S+T+U	44.37	Avg. Grass	2	100	12	2.00	23	Unpaved	0.1	3604	10.0	22.0	0.90	4.33 5.98 7.41	172.1 237.7 294.5	5 25 100		
26	Drain F1 - Earthen Channel	T+U	25.09	Avg. Grass	2	100	12	2.00	23	Unpaved		2831	7.9	19.0	0.87	4.66 6.45 8.00 4.80	101.9 141.1 175.0 63.5	5 25 100 5		
27	Existing Drain Drain F3 - Culvert	U R+S+T+U+V	15.97 50.29	Avg. Grass Avg. Grass	2	100	12	2.00	23	Unpaved Unpaved	0.1	2179	6.1	18.0 22.0	0.83	6.63 8.24 4.33 5.98	87.7 109.0 194.9 269.1	25 100 5 25	-	
28	Drain F2 - Cuivert Drain F2 - Curb Inlets in Sump	K+5+1+U+V V	2.88	Avg. Grass Avg. Grass	0.5	0	5	0.00	0	Unpaved	0.0	1552	4.3	9.0	0.89	7.41 6.54 9.17	333.5 16.1 22.6	100 5 25	-	
30	Drain F3 - Culvert	R+S+T+U+V+W+X+Y	57.82	Avg. Grass	2	100	12	2.00	23	Unpaved	0.1	3996	11.1	23.0	0.87	11.49 4.23 5.84 7.24	28.3 213.3 294.5 365.1	100 5 25 100	_	
31	Drain F5 - Curb Inlets in Sump	W+X+Y	7.53	Avg. Grass	1.55	85	13	0.00	0	Unpaved	0.0	1569	4.4	17.0	0.72	4.94 6.84 8.50 5.10	26.8 37.1 46.1 21.3	5 25 100 5	37.1-8.96-9.14= 19.0	cfs
32	Drain F6 - Curb Inlet on Grade	X+Y	5.79	Avg. Grass	1.55	85	13	0.00	0	Unpaved	0.0	974	3.9	16.0	0.72	7.07 8.79 5.28	29.5 36.6 14.0	25 100 5	29.5-8.96= 20.54 cf	
33	Drain F4 - Curb Inlet on Grade	Y A+B+C+D+E+F+G+H+I	3.67	Avg. Grass Avg. Grass	1.55 2	85 100	13 12	0.00	0 2812	Unpaved Unpaved	0.0	974 	2.7 5.2	15.0 50.0	0.72	7.32 9.12 2.77 3.84	19.3 24.1 227.0 314.7	25 100 5 25		8.96
35	Drain G - Earthen Channel	J+K+L+M+N+O+Q+R+S+T+U+V+W+X+Y	143.63	Avg. Grass	2	100	12	2.00	23	Unpaved	0.1	3996	11.1	23.0	0.81	4.78 4.23 5.84 7.24	391.7 491.7 678.9 841.6	100 5 25 100		
36	Drain F3 - 4 Way Inlet	R	3.04	Avg. Grass	2	100	12	2.00	19	Unpaved	0.1	737	2.0	14.0	0.92	7.24 5.47 7.6 9.48	841.6 15.3 21.3 26.5	5 25 100	-	
					_			-				-		-	_					I


THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.





			ALAMO RANCH PARKWAY PH			and Flow	TER DRAINAGE SC	1		ncentrated		Channel	Flow (6 fps) Total						Curb Inlet
Point	Structure	Area	Total Area (ac)	Ground	Slope %		Tc (min)		1	Surface	*		1	Tc (min)		I	Q (cfs)	Frequency	Total Q ₂₅	Intercept Bypas
																2.96	44.3	5		
1	Drain A1 - Earthen Channel	A	42.75	Avg. Grass	0.5	100	17	0.75	2283	Unpaved	27	596	1.7	45.0	0.35	4.09	61.2	25		
																5.08	76.0	100		
																3.04	10.2	5		
2	Drain A2 & Drain B2 - 4 - Way Inlets	В	9.58	Avg. Grass	0.5	100	17	0.75	2184	Unpaved	26	0	0.0	43.0	0.35	4.2	14.1	25	14.1/2= 7.05 cfs in each inlet	
																5.21	17.5	100		
2	Drain B1 - Earthen Channel	c	18.69	Avg. Grass	0.5	100	17	0.80	2266	Unnavad	26	216	0.6	43.0	0.35	3.04 4.2	19.9 27.5	25		
5	Drain B1 - Earthen Channer	c	18.69	Avg. Glass	0.5	100	17	0.80	2200	Unpaved	20	210	0.0	45.0	0.55	5.21	34.1	100		
																2.92	43.5	5		
4	Drain D1 - Earthen Channel	D	42.56	Avg. Grass	0.5	100	17	0.65	2234	Unpaved	29	223	0.6	46.0	0.35	4.04	60.2	25		
				Ũ												5.02	74.8	100		
																3.17	41.0	5		
5	Drain D2 & Drian E - 4-Way Inlets	E	36.92	Avg. Grass	0.5	100	17	0.95	2199	Unpaved	23	0	0.0	40.0	0.35	4.38	56.6	25	56.6/2= 28.3 cfs in each inlet	
								_								5.43	70.2	100		
																2.77	56.9	5		
6	Drain K - Earthen Channel	F+G+H	58.01	Avg. Grass	0.5	100	17	0.65	2273	Unpaved	29	1661	4.6	50.0	0.35	3.84	78.8	25		
																4.78 2.84	98.1 26.5	100 5		
7	Drain K - Earthen Channel	G+H	26.07	Avg. Grass	0.5	100	17	0.65	2273	Unpaved	29	787	2.2	48.0	0.36	3.94	36.8	25		
<i>,</i>	Brank Earthen chamer	Giii	20.07		0.5	100	1,	0.05	2275	onpavea	25	101	2.2	40.0	0.50	4.89	45.7	100		
												1				2.92	17.4	5		
8	Existing Drain	н	16.40	Avg. Grass	0.5	100	17	0.65	2273	Unpaved	29	0	0.0	46.0	0.36	4.04	24.1	25		
	-															5.02	29.9	100		
















BEXAR COUNTY ROW NOTES:

A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED. **DRAINAGE & GRADING NOTES:**

- 1. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
- 2. ALL CONCRETE FOR TXDOT DRAINAGE STRUCTURES SHALL MEET TXDOT SPECIFICATIONS. ALL OTHER CONCRETE SHALL BE CLASS "A" 3000 PSI CYLINDER STRENGTH IN 28 DAYS.
- 3. REFERENCE DRAINAGE DETAILS FOR PIPE TRENCH DETAILS, BOX CULVERT, HEADWALL, AND WINGWALL CONSTRUCTION DETAILS, AND BOX CULVERT BEDDING AND EXCAVATION LIMITS.
- 4. CONTRACTOR SHALL GROUT ALL CURB INLETS AND JUNCTION BOXES TO PROVIDE FOR POSITIVE DRAINAGE.
- 5. EARTHEN CHANNELS WILL BE VEGETATED BY SEEDING OR SODDING. 85% OF THE CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT.
- 6. CONTRACTOR SHALL MATCH TOP OF CHANNEL TO NATURAL GROUND AND MAINTAIN A MINIMUM CHANNEL DEPTH OF "D" AS SHOWN IN THE PROFILE.


TRENCH EXCAVATION SAFETY PROTECTION:


CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. CAUTION!!


CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO TH ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.

JOB NO DATE DESIGN	ALAMO RANCH PARKWAY PHASE II	I PAPE-DAWSON	ALL SOLUTION AND ALL SOLUTION	NO. REVISION	DATE
)1 ER	SAN ANTONIO, TEXAS	ENGINEERS	W.R. W 653 S/ONA 3/15		
11800379 1680-39 MBER 2021 DL DRAWN_DL	DRAIN A1 PLAN & PROFILE (STA. 1+22.00 TO 4+20.00)	SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TBPE FIRM REGISTRATION #470 I TBPLS FIRM REGISTRATION #10028800	Noor		

C1.01









	HYDRAULIC CALCULATIONS EARTHEN CHANNEL							
_		SECTION A-A						
S	STA.	1+22.00 TO 6+48.00						
Q25	=	64.6 cfs						
Вw	=	10'						
n	=	0.035						
S	=	0.75%						
D	=	2.00'						
dn	=	1.28'						
V	=	3.63 fps						

HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSWITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery @ 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.



EXISTING STORM DRAIN

FLOW ARROW



BEXAR COUNTY ROW NOTES:

A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED. **DRAINAGE & GRADING NOTES:**

- 1. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
- 2. ALL CONCRETE FOR TXDOT DRAINAGE STRUCTURES SHALL MEET TXDOT SPECIFICATIONS. ALL OTHER CONCRETE SHALL BE CLASS "A" 3000 PSI CYLINDER STRENGTH IN 28 DAYS.
- 3. REFERENCE DRAINAGE DETAILS FOR PIPE TRENCH DETAILS, BO CULVERT, HEADWALL, AND WINGWALL CONSTRUCTION DETAILS, AND BOX CULVERT BEDDING AND EXCAVATION LIMITS.
- 4. CONTRACTOR SHALL GROUT ALL CURB INLETS AND JUNCTION BOXES TO PROVIDE FOR POSITIVE DRAINAGE.
- 5. EARTHEN CHANNELS WILL BE VEGETATED BY SEEDING OR SODDING. 85% OF THE CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT.
- 6. CONTRACTOR SHALL MATCH TOP OF CHANNEL TO NATURAL GROUND AND MAINTAIN A MINIMUM CHANNEL DEPTH OF "D" AS SHOWN IN THE PROFILE.


TRENCH EXCAVATION SAFETY PROTECTION:


CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN TH PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OF PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. CAUTION!!


CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO TH ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO TH START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.

о .	3/15	/23
I PAPE-DAWSON	ENGINEERS	SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TBPE FIRM REGISTRATION #470 I TBPLS FIRM REGISTRATION #10028800
ALAMO RANCH PARKWAY PHASE II	SAN ANTONIO, TEXAS	DRAIN A1 PLAN & PROFILE (STA. 4+20.00 TO END)
OB NO ATE DESIGNE	SEPTI R DBL	-11800379 11680-39 EMBER 2021 DL DRAWN DL CRAWN DL C1.02

W.R. WOOD 65364









HYDRAULIC CALCULATIONS EARTHEN CHANNEL SECTION B-B							
S	TA.	3+00.00 TO 3+25.80					
Q25	=	25.5 cfs					
Bw	=	6'					
n	=	0.035					
S	=	0.72%					
D	=	2.60'					
dn	=	0.98'					
۷	=	2.90 fps					

HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.



ate: Mar 15, 2023, 11: 29am User ID: RichardGarcic le: P:\116\80\39\Desian\Civil\DRB1 1168039.dwa



FLOW ARROW

(SEE SHEET C1.11-C1.12)



A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED. DRAINAGE & GRADING NOTES:

- 1. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
- ALL CONCRETE FOR TXDOT DRAINAGE STRUCTURES SHALL MEET TXDOT SPECIFICATIONS. ALL OTHER CONCRETE SHALL BE CLASS "A" 3000 PSI CYLINDER STRENGTH IN 28 DAYS.
- REFERENCE DRAINAGE DETAILS FOR PIPE TRENCH DETAILS, BOX CULVERT, HEADWALL, AND WINGWALL CONSTRUCTION DETAILS, AND BOX CULVERT BEDDING AND EXCAVATION LIMITS.
- CONTRACTOR SHALL GROUT ALL CURB INLETS AND JUNCTION BOXES TO PROVIDE FOR POSITIVE DRAINAGE.
- EARTHEN CHANNELS WILL BE VEGETATED BY SEEDING OR SODDING. 85% OF THE CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT.
- CONTRACTOR SHALL MATCH TOP OF CHANNEL TO NATURAL GROUND AND MAINTAIN A MINIMUM CHANNEL DEPTH OF "D" AS SHOWN IN THE PROFILE.


TRENCH EXCAVATION SAFETY PROTECTION:


CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. **CAUTION!!**


CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.


ALAMO RANCH PARKWAY PHASE II	I PAPE-DAWSON	Nost Hand	NO. REVISION	N	DATE
	ENGINEERS	W.R. W 6530 S/ONA 3/15			
DRAIN B1 PLAN & PROFILE (STA. 1.25+00 TO END)	SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TBPE FIRM REGISTRATION #470 I TBPLS FIRM REGISTRATION #10028800	Nood			


C1.03














IS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.




START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.





HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSWITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery @ 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.



DRAINAGE LEGEND

PROJECT LIMITS 100 YR FLOODPLAIN EXISTING CONTOUR


PROPOSED CONTOUR PROPOSED WATER

PROPOSED SEWER

PROPOSED STORM DRAIN

EXISTING STORM DRAIN

FLOW ARROW



₽₭

Ζ

Ó

CALEB M. CHANCE

98401

7/24/2

с С

- DETAIL B (SEE SHEET C1.07)

VARIABLE WIDTH DRAINAGE EASEMENT

			HYDRAULIC ALCULATIONS TORM DRAIN
	S	TA.	1+00.00 TO 3+72.50
	225	=	222.9 cfs
	n	=	1.52'
5	Sf	=	0.59%
\	/f	=	8.61 fps
r	ı	=	0.013
)	=	3'
S	5	=	0.50%
Ľ			0.50%



BEXAR COUNTY ROW NOTES:

A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED. **DRAINAGE & GRADING NOTES:**


- 1. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
- 2. ALL CONCRETE FOR TXDOT DRAINAGE STRUCTURES SHALL MEET TXDOT SPECIFICATIONS. ALL OTHER CONCRETE SHALL BE CLASS "A" 3000 PSI CYLINDER STRENGTH IN 28 DAYS.
- 3. REFERENCE DRAINAGE DETAILS FOR PIPE TRENCH DETAILS, BO CULVERT, HEADWALL, AND WINGWALL CONSTRUCTION DETAILS, AND BOX CULVERT BEDDING AND EXCAVATION LIMITS.
- 4. CONTRACTOR SHALL GROUT ALL CURB INLETS AND JUNCTION BOXES TO PROVIDE FOR POSITIVE DRAINAGE.
- 5. EARTHEN CHANNELS WILL BE VEGETATED BY SEEDING OR SODDING. 85% OF THE CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT.
- 6. CONTRACTOR SHALL MATCH TOP OF CHANNEL TO NATURAL GROUND AND MAINTAIN A MINIMUM CHANNEL DEPTH OF "D" AS SHOWN IN THE PROFILE.


TRENCH EXCAVATION SAFETY PROTECTION:

CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN TH PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OF PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. CAUTION!!

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO TH ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO TH START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.

ALAMO RANCH PARKWAY PHASE II	SAN ANTONIO, TEXAS	DRAIN B3 PLAN & PROFILE (STA. 1+00.00 TO END)
		- 11800379 11680-39
	SEPTE	EMBER 2021 DL
CHECKE	C	_ drawndl





DETAIL "B" SCALE: 1" = 5'

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.

DRAINAGE LEGEND


PROJECT LIMITS 100 YR FLOODPLAIN EXISTING CONTOUR PROPOSED CONTOUR PROPOSED WATER


PROPOSED SEWER

PROPOSED STORM DRAIN

EXISTING STORM DRAIN

FLOW ARROW





NO

PAPE-DAWS ENGINEERS

BEXAR COUNTY ROW NOTES:

A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED. **DRAINAGE & GRADING NOTES:**

- 1. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXAC LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
- 2. ALL CONCRETE FOR TXDOT DRAINAGE STRUCTURES SHALL MEET TXDOT SPECIFICATIONS. ALL OTHER CONCRETE SHALL BE CLASS "A" 3000 PSI CYLINDER STRENGTH IN 28 DAYS.
- 3. REFERENCE DRAINAGE DETAILS FOR PIPE TRENCH DETAILS, BO CULVERT, HEADWALL, AND WINGWALL CONSTRUCTION DETAILS, AND BOX CULVERT BEDDING AND EXCAVATION LIMITS.
- 4. CONTRACTOR SHALL GROUT ALL CURB INLETS AND JUNCTION BOXES TO PROVIDE FOR POSITIVE DRAINAGE.
- 5. EARTHEN CHANNELS WILL BE VEGETATED BY SEEDING OR SODDING 85% OF THE CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT.
- 6. CONTRACTOR SHALL MATCH TOP OF CHANNEL TO NATURAL GROUND AND MAINTAIN A MINIMUM CHANNEL DEPTH OF "D" AS SHOWN IN THE PROFILE.


TRENCH EXCAVATION SAFETY PROTECTION:


CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN TH PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OF PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. CAUTION!!


CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO TH ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO TH START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL B THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL B AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN O THESE PLANS OR NOT.

Drain as & B3 DETAILS

PLAT NO.	21-11800379
JOB NO.	11680-39
DATE	SEPTEMBER 2021
DESIGNER	DL
CHECKED_	BL DRAWN DL
SHEET	C1.07










THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.

C1.08







Date: Jul 26, 2023, 7:48am User ID: bspielman File: P:\116\80\39\Desian\Civi\DRC 11168039.dwc




THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT. C1.09





)ate: Mar 31, 2023, 9:55am User ID: RichardGarcia ile: P:\116\80\39\Design\Civil\DRD1 1168039.dwg



BEXAR COUNTY ROW NOTES:

A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED. DRAINAGE & GRADING NOTES:

- 1. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
- ALL CONCRETE FOR TXDOT DRAINAGE STRUCTURES SHALL MEET TXDOT SPECIFICATIONS. ALL OTHER CONCRETE SHALL BE CLASS "A" 3000 PSI CYLINDER STRENGTH IN 28 DAYS.
- REFERENCE DRAINAGE DETAILS FOR PIPE TRENCH DETAILS, BOX CULVERT, HEADWALL, AND WINGWALL CONSTRUCTION DETAILS, AND BOX CULVERT BEDDING AND EXCAVATION LIMITS.
- 4. CONTRACTOR SHALL GROUT ALL CURB INLETS AND JUNCTION BOXES TO PROVIDE FOR POSITIVE DRAINAGE.
- EARTHEN CHANNELS WILL BE VEGETATED BY SEEDING OR SODDING. 85% OF THE CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT.
- 6. CONTRACTOR SHALL MATCH TOP OF CHANNEL TO NATURAL GROUND AND MAINTAIN A MINIMUM CHANNEL DEPTH OF "D" AS SHOWN IN THE PROFILE.


TRENCH EXCAVATION SAFETY PROTECTION:


CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. **CAUTION!!**


CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.

PLAT NO. 21- JOB NO. 1 DATE SEPTE DESIGNER CHECKED BL	ALAMO RANCH PARKWAY PHASE II SAN ANTONIO, TEXAS	ENGINEERS	CALEB M. 984 984 SONA
1680–39 MBER 2021 DL	DRAIN D1 PLAN & PROFILE (STA. 1+28.00 TO 5+00.00)	SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TBPE FIRM REGISTRATION #470 I TBPLS FIRM REGISTRATION #10028800	CHANCE 01 BEP GIN 3/31/23


C1.11







HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.



PROPOSED STORM DRAIN

EXISTING STORM DRAIN

FLOW ARROW

BEXAR COUNTY ROW NOTES:


A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED. **DRAINAGE & GRADING NOTES:**


- 1. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
- 2. ALL CONCRETE FOR TXDOT DRAINAGE STRUCTURES SHALL MEET TXDOT SPECIFICATIONS. ALL OTHER CONCRETE SHALL BE CLASS "A" 3000 PS CYLINDER STRENGTH IN 28 DAYS.
- 3. REFERENCE DRAINAGE DETAILS FOR PIPE TRENCH DETAILS, BC CULVERT, HEADWALL, AND WINGWALL CONSTRUCTION DETAILS, AND BOX CULVERT BEDDING AND EXCAVATION LIMITS.
- 4. CONTRACTOR SHALL GROUT ALL CURB INLETS AND JUNCTION BOXES T PROVIDE FOR POSITIVE DRAINAGE.
- 5. EARTHEN CHANNELS WILL BE VEGETATED BY SEEDING OR SODDING 85% OF THE CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT.
- 6. CONTRACTOR SHALL MATCH TOP OF CHANNEL TO NATURAL GROUND AND MAINTAIN A MINIMUM CHANNEL DEPTH OF "D" AS SHOWN IN TH PROFILE.

TRENCH EXCAVATION SAFETY PROTECTION:

CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /O PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OF CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM I ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. CAUTION!!


CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO TH ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO TH START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.






HYDRAULIC CALCULATIONS STORM DRAIN			
STA.	1+00.00 TO 1+63.66		
Q25 =	28.3 cfs		
Dn =	1.98'		
Sf =	0.48%		
Vf =	6.87 fps		
n =	0.013		
D =	30"		
S =	0.50%		


HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.



START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL B THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL B AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.

C1.13 SHEET





HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSWITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery © 2016, CAPCOG, Digital Globe, Texas Orthoimagery Program, USDA Farm Service Agency.


DRAINAGE LEGEND

PROJECT LIMITS 100 YR FLOODPLAIN EXISTING CONTOUR PROPOSED CONTOUR PROPOSED WATER PROPOSED SEWER

PROPOSED STORM DRAIN

EXISTING STORM DRAIN

FLOW ARROW





11680-39

ATE SEPTEMBER 2021

HECKED BL DRAWN DL

C1.15

JOB NO.

ESIGNER

SHEET

BEXAR COUNTY ROW NOTES:


A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED. **DRAINAGE & GRADING NOTES:**


- 1. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXAC LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
- 2. ALL CONCRETE FOR TXDOT DRAINAGE STRUCTURES SHALL MEET TXDOT SPECIFICATIONS. ALL OTHER CONCRETE SHALL BE CLASS "A" 3000 PS CYLINDER STRENGTH IN 28 DAYS.
- 3. REFERENCE DRAINAGE DETAILS FOR PIPE TRENCH DETAILS, BC CULVERT, HEADWALL, AND WINGWALL CONSTRUCTION DETAILS, AND BOX CULVERT BEDDING AND EXCAVATION LIMITS.
- 4. CONTRACTOR SHALL GROUT ALL CURB INLETS AND JUNCTION BOXES PROVIDE FOR POSITIVE DRAINAGE.
- 5. EARTHEN CHANNELS WILL BE VEGETATED BY SEEDING OR SODDING 85% OF THE CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT.
- 6. CONTRACTOR SHALL MATCH TOP OF CHANNEL TO NATURAL GROUNE AND MAINTAIN A MINIMUM CHANNEL DEPTH OF "D" AS SHOWN IN TH PROFILE.

TRENCH EXCAVATION SAFETY PROTECTION:


CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN TH PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /O PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENT THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OF CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. CAUTION!!

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO TH ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO TH START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL E THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL B AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN O THESE PLANS OR NOT.







HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.





AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN O THESE PLANS OR NOT.







IS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE© UNLESS OTHERWISE NOTED. Imagery © 2016, CAPCOG, Digital Globe, Texas Orthoimagery Program, USDA Farm Service Agency.











IS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSWITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.













ate: Mar 15, 2023, 11:36am User ID: RichardGarcia le: P:\116\80\39\Design\Civil\DRF1 1163839.dwg








 \cap

 \mathbf{O}

Э









CAUTION!! CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO TH ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO TH START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL B THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL B AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.


ATE SEPTEMBER 2021 ESIGNER DL HECKED BL DRAWN DL C1.23 SHEET

11680-39

JOB NO.









Q25 = 294.5 cfsDn = 2.76' Sf = 0.61% Vf = 10.52 fps n = 0.013 D = 4' S = 1.15%


PLAN FOR ENERGY DISSIPATIONS

Q25 = 269.1 cfsDn = 3.22'Sf = 0.51% V = 12 fps





ate: Jul 26, 2023, 7:50am User ID: bspielman ile: P:\116\80\39\Desian\Civil\DRF2 — DRF5 11168039.dwa





BEXAR COUNTY ROW NOTES:

A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED. DRAINAGE & GRADING NOTES:

- 1. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
- 2. ALL CONCRETE FOR TXDOT DRAINAGE STRUCTURES SHALL MEET TXDOT SPECIFICATIONS. ALL OTHER CONCRETE SHALL BE CLASS "A" 3000 PSI CYLINDER STRENGTH IN 28 DAYS.
- 3. REFERENCE DRAINAGE DETAILS FOR PIPE TRENCH DETAILS, BOX CULVERT, HEADWALL, AND WINGWALL CONSTRUCTION DETAILS, AND BOX CULVERT BEDDING AND EXCAVATION LIMITS.
- 4. CONTRACTOR SHALL GROUT ALL CURB INLETS AND JUNCTION BOXES TO PROVIDE FOR POSITIVE DRAINAGE.
- 5. EARTHEN CHANNELS WILL BE VEGETATED BY SEEDING OR SODDING. 85% OF THE CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT.
- 6. CONTRACTOR SHALL MATCH TOP OF CHANNEL TO NATURAL GROUND AND MAINTAIN A MINIMUM CHANNEL DEPTH OF "D" AS SHOWN IN THE PROFILE.


TRENCH EXCAVATION SAFETY PROTECTION:

CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN TH PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OF PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. CAUTION!!

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.


NO. REVISION DATE A ADDED ACCESS MANHOLE 7/24/20		CHANCE O1 SEPIGINAL A /23
I PAPE-DAWSON	ENGINEERS	SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TBPE FIRM REGISTRATION #470 I TBPLS FIRM REGISTRATION #10028800
ALAMO RANCH PARKWAY PHASE II	SAN ANTONIO, TEXAS	DRAIN F4 PLAN & PROFILE (STA. 1+10.03 TO STA. 5+00.00)
JOB NO. DATE DESIGNE	1 .R	11800379 1680-39 MBER 2021 DL DRAWN DL

C1.25



HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSWITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery @ 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.





DRAINAGE LEGEND


PROJECT LIMITS 100 YR FLOODPLAIN EXISTING CONTOUR PROPOSED CONTOUR

PROPOSED WATER PROPOSED SEWER

PROPOSED STORM DRAIN

EXISTING STORM DRAIN

FLOW ARROW



W.R. WOOD 65364 3/15/23



BEXAR COUNTY ROW NOTES:

TO REPAIR, AT HIS EXPENSE.

A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED. **DRAINAGE & GRADING NOTES:**

- 1. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY
- 2. ALL CONCRETE FOR TXDOT DRAINAGE STRUCTURES SHALL MEET TXDOT SPECIFICATIONS. ALL OTHER CONCRETE SHALL BE CLASS "A" 3000 PSI CYLINDER STRENGTH IN 28 DAYS.
- 3. REFERENCE DRAINAGE DETAILS FOR PIPE TRENCH DETAILS, BO) CULVERT, HEADWALL, AND WINGWALL CONSTRUCTION DETAILS, AND BOX CULVERT BEDDING AND EXCAVATION LIMITS.
- 4. CONTRACTOR SHALL GROUT ALL CURB INLETS AND JUNCTION BOXES TO PROVIDE FOR POSITIVE DRAINAGE.
- 5. EARTHEN CHANNELS WILL BE VEGETATED BY SEEDING OR SODDING. 85% OF THE CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT.
- 6. CONTRACTOR SHALL MATCH TOP OF CHANNEL TO NATURAL GROUND AND MAINTAIN A MINIMUM CHANNEL DEPTH OF "D" AS SHOWN IN THE PROFILE.


TRENCH EXCAVATION SAFETY PROTECTION:

CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OF PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONVINCE TO A SAFETY OF A CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. CAUTION!!


CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO TH ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO TH START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.


ALAMO RANCH PARKWAY PHASE II SAN ANTONIO, TEXAS DRAIN F4 PLAN & PROFILE (STA.5+00.00 TO 9+40.00)
DLAT NO. 21-11800379 OB NO. 11680-39 DATE SEPTEMBER 2021 DESIGNER DL

C1.26



IS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE© UNLESS OTHERWISE NOTED. Imagery © 2016, CAPCOG, Digital Globe, Texas Orthoimagery Program, USDA Farm Service Agency.







HYDRAULIC CALCULATIONS STORM DRAIN		
ST	Ā.	1+04.67 TO 1+09.48
Q25	=	9.14 cfs
Dn	=	1.0'
Sf	=	0.50%
Vf	=	5.91 fps
n	=	0.013
D	=	30"
S	=	0.50%

$101AL Q_{25} = 10.4 CFS$
Q ₂₅ = 18.4 CFS
$Q_{25} = CA\sqrt{2gh}$ (ORIFICE FLOW EQN.)
A = L(0.50), h = 0.54, g = 32.2, c = 0.70
$L = \frac{18.4 \text{ CFS}}{(0.70) (0.50)\sqrt{2 (32.2) (0.54)}}$
L = 8.91 FT USE 1 ~ 15 FT CURB INLET EACH
CHECK WITH WEIR FORMULA
h = $\left(\frac{Q}{(CL)}\right)^{2/3}$ = $\left(\frac{18.4.1}{(3.087)(15)}\right)^{2/3}$ = 0.54 FT.

HYDRAULIC CALCULATIONS STORM DRAIN				
S	TA.	1+05.00 TO 1+11.78		
Q25	=	19.0 cfs		
Dn	=	1.62'		
Sf	=	0.71%		
Vf	=	7.06 fps		
n	=	0.013		
D	=	24"		
S	=	0.70%		





PAPE-DAWSON ENGINEERS 2

PROFILE ELEVATION

BEXAR COUNTY ROW NOTES:

A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED. **DRAINAGE & GRADING NOTES:**

1. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXAC LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE. GRADE. AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.

2. ALL CONCRETE FOR TXDOT DRAINAGE STRUCTURES SHALL MEET TXDOT SPECIFICATIONS. ALL OTHER CONCRETE SHALL BE CLASS "A" 3000 PSI CYLINDER STRENGTH IN 28 DAYS.

3. REFERENCE DRAINAGE DETAILS FOR PIPE TRENCH DETAILS, BC CULVERT, HEADWALL, AND WINGWALL CONSTRUCTION DETAILS, AND BOX CULVERT BEDDING AND EXCAVATION LIMITS.

4. CONTRACTOR SHALL GROUT ALL CURB INLETS AND JUNCTION BOXES TH PROVIDE FOR POSITIVE DRAINAGE.

5. EARTHEN CHANNELS WILL BE VEGETATED BY SEEDING OR SODDING 85% OF THE CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT.

6. CONTRACTOR SHALL MATCH TOP OF CHANNEL TO NATURAL GROUND AND MAINTAIN A MINIMUM CHANNEL DEPTH OF "D" AS SHOWN IN TH PROFILE.


TRENCH EXCAVATION SAFETY PROTECTION:


CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN TH PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /O PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OF CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. CAUTION!!


CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO TH ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO TH START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL B THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL B AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.


	SAN AN I UNIO, I EXAS	DRAIN F-4, F-5, & F-6 PLAN & PROFILE
PLAT NO. JOB NO		80037 30–39


JOB DATE SEPTEMBER 2021 DESIGNER DL HECKED BL DRAWN DL C1.27 SHEET











SCALE: 1"= 20' DRAINAGE LEGEND PROJECT LIMITS 100 YR FLOODPLAIN EXISTING CONTOUR PROPOSED CONTOUR PROPOSED WATER PROPOSED SEWER PROPOSED STORM DRAIN EXISTING STORM DRAIN FLOW ARROW

$\left\{ \right\}$	HYDRAULIC CALCULATIONS			
$\left\{ \right\}$	<u>STORM DRAIN</u> STA. 1+10.00 TO 6+56.70			
$\left\{ \right\}$	Q25	=	124.7 cfs	
$\left\{ \right\}$	Sf	=	0.37%	
$\left \right\rangle$	Vf	=	6.93 fps	
$\left \right $	n	=	0.013	
ζ	D	=	3'	
$\left \right $	S	=	0.50%	



PLAT NO.	21-11800379
JOB NO	11680-39
DATE	SEPTEMBER 2021
	DL
CHECKED_	BL DRAWN DL
SHEET	C1.29A

BEXAR COUNTY ROW NOTES:


A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED. **DRAINAGE & GRADING NOTES:**

- 1. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
- 2. ALL CONCRETE FOR TXDOT DRAINAGE STRUCTURES SHALL MEET TXDOT SPECIFICATIONS. ALL OTHER CONCRETE SHALL BE CLASS "A" 3000 PS CYLINDER STRENGTH IN 28 DAYS.
- 3. REFERENCE DRAINAGE DETAILS FOR PIPE TRENCH DETAILS, BO CULVERT, HEADWALL, AND WINGWALL CONSTRUCTION DETAILS, AND BOX CULVERT BEDDING AND EXCAVATION LIMITS.
- 4. CONTRACTOR SHALL GROUT ALL CURB INLETS AND JUNCTION BOXES T PROVIDE FOR POSITIVE DRAINAGE.
- 5. EARTHEN CHANNELS WILL BE VEGETATED BY SEEDING OR SODDING. 85% OF THE CHANNEL SURFACE MUST HAVE ESTABLISHED VEGETATION BEFORE THE CITY OF SAN ANTONIO WILL ACCEPT.
- 6. CONTRACTOR SHALL MATCH TOP OF CHANNEL TO NATURAL GROUND AND MAINTAIN A MINIMUM CHANNEL DEPTH OF "D" AS SHOWN IN TH PROFILE.


TRENCH EXCAVATION SAFETY PROTECTION:


CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OF PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. CAUTION!!

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO TH ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO TH START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN O THESE PLANS OR NOT.





te: Jul 10, 2023, 4: 33pm User ID: bspielman e: P:\116\80\39\Design\Civil\DRH 11168039 — .dwg







:e: Sep 17, 2021, 3:40pm User ID: dlevine :: P:\116\80\39\Design\Civil\DRDT1168039.dwg







Date: Oct 20, 2022, 5: 37pm User ID: RichardGarc







					1		to top of BAS	I JLAD				+
			Base Slab			Base Unit or Riser Walls			Below Grade Reducing	Slab (w/PJB) Slab (w/PB)		
		t Span F Steel	Long Span Reinf Steel Area	Thickness	t Span f Steel	Long Span Reinf Steel Area	Thickness	Reduced Riser Size	t Span f Steel	Long Span Reinf Steel Area	Thickness	
	Size	Short Reinf Area	Long Reint Area	Thick	Short Reinf Area	Long Reint Area	Thick	Redu Risei	Short Reinf Area	Long Reint Area	Thick	
	ХхҮ	Ashort	Along	BS	Bshort	Blong	W	RWSxRWL or ID	Dshort	Dlong	TS	Å
	ft.	in²/ft	in²/ft	in.	in²/ft	in²/ft	in.	ft. **	in²/ft	in²/ft	in.	_
(Bľa	3x3	0.23	0.23	6 6	0.19	0.19	6	N/A	0.37	0.37	9 9	_
Precast Junction Box (PJB)	4x4 3x5	0.29	0.29	6	0.24	0.24	6	N/A N/A	0.41	0.41	9	
B uc	4x5	0.36	0.18	6	0.22	0.34	6	N/A	0.42	0.42	9	
nctia	5x5	0.36	0.36	6	0.34	0.34	6	N/A	0.43	0.43	9	+
t Ju	5x6	0.27	0.27	9	0.34	0.45	6	N/A	0.48	0.48	9	
ecas	6x6	0.27	0.27	9	0.45	0.45	6	N/A	0.56	0.56	9	
Pr	8×8	0.46	0.46	9	0.51	0.51	8	N/A	0.45	0.45	12	
	3x3	0.23	0.23	6	0.19	0.19	6	N/A	N/A	N/A	N/A	
	4x4	0.29	0.29	6	0.24	0.24	6	N/A	N/A	N/A	N/A	
	3x5	0.29	0.18	6	0.19	0.35	6	3x3	0.30	0.34	9	
	4x5	0.36	0.18	6	0.22	0.34	6	3x3	0.30	0.30	9	
	4x5	0.36	0.18	6	0.22	0.34	6	4x4	0.30	0.30	9	_
-	4x5 4x5	0.36	0.18	6	0.22	0.34	6	48" 3x5	0.39	0.39	9 9	-
	5x5	0.36	0.36	6	0.34	0.34	6	3x3	0.34	0.34	9	-
	5x5	0.36	0.36	6	0.34	0.34	6	4x4	0.36	0.36	9	+
(<i>B</i> c	5x5	0.38	0.38	6	0.34	0.34	6	48"	0.36	0.36	9	
Base (PB)	5x5	0.36	0.36	6	0.34	0.34	6	3x5	0.34	0.40	9	
t Ba	5x6	0.31	0.31	9	0.34	0.45	6	3x3	0.34	0.34	9	
Precast	5x6	0.27	0.27	9	0.34	0.45	6	4x4	0.36	0.45	9	
Pre	5x6	0.29	0.29	9	0.34	0.45	6	48"	0.36	0.45	9	
	5x6	0.29	0.29	9	0.34	0.45	6	3x5	0.45	0.45	9	
	6x6	0.29	0.29	9	0.45	0.45	6	3x3	0.41	0.41	9	_
	6x6	0.27	0.27	9	0.45	0.45	6	4x4 48"	0.45	0.45	9	+
	6x6 6x6	0.29	0.29	9	0.45	0.45	6	40 3x5	0.45	0.45	9	_
ŀ	8x8	0.52	0.52	9	0.51	0.51	8	3x3	0.61	0.61	12	-
	8x8	0.52	0.52	9	0.51	0.51	8	4x4	0.70	0.70	12	
	8x8	0.52	0.52	9	0.51	0.51	8	48"	0.70	0.70	12	
	8x8	0.52	0.52	9	0.51	0.51	8	3x5	0.70	0.85	12	










5 H T U 12 No. 8/0 6/0 Longh Weight ''.'.' ''.' ''.'		,	2						
8 - 0 9 - 0 10	S H T		Bars B	Bars C		Bars D	Bars M ~ #4	Bars F1 ~ #4 at 18" Spa	Bars F2 at 18"
3 - 0 $3 - 0$ $7 - 16$ $6 - 6$ $6 - 1 - 1$ 1.06 $6 - 9$ $7 - 1$ 1.08 $7 - 1$ 1.08 $7 - 1$ 1.08 $7 - 1$ 1.08 $7 - 1$ 1.08 $7 - 1$ 1.08 $7 - 1$ 1.08 $7 - 1$ 1.08 $6 - 1 - 1$ 1.08 $6 - 1 - 1$ 1.08 $6 - 1$ $7 - 1$ 1.08 $6 - 1$ $7 - 1$ 1.08 $6 - 1$ $7 - 1$ 1.08 $6 - 1$ $7 - 1$ 1.08 $6 - 1$ $7 - 1$ 1.08 $6 - 1$ $7 - 1$ 1.08 $6 - 1$ $7 - 1$ 1.08 $6 - 1$ $7 - 1$ 1.08 $6 - 1$ $7 - 1$ 1.08 $1 - 1$ 1.08 $1 - 1$ 1.08 $1 - 1$ 1.08 $1 - 1$ 1.08 1.08 $1 - 1$ 1.08 $1 - 1$ 1.08 $1 - 1$ 1.08 $1 - 1$ 1.08 $1 - 1$ 1.08 $1 - 1$ 1.08 $1 - 1$ 1.08 $1 - 1$ 1.08 $1 - 1$ 1.08 $1 - 1$ <		U U	No. 25 8 Length Weight	No. 25 80 Length Weight " X "	" ү "	No. $\frac{\partial Z}{\partial G}$ $\frac{\partial Q}{\partial G}$ Length Weight "Y" "Z" M	No. C. Length Weight	No. Length Wt	No. Lengt
g-r 10r 8r 2r 10r 8r 2r 10r 8r 2r 2r 10r 8r 2r					-				
g-0 3-0 167 97 168 6 9 7 148 9-1 1415 9-7 108 9 7-0 106 6 9-7 148 9-7 108 9 7-0 106 6 9-7 1415 9-7 7-0 108 9 7-0 206 6 9-7 108 9 7-0 206 6 9-7 108 9 7-0 206 6 9-7 108 9 7-0 206 6 9-7 108 9 7-0 108 9 7-0 108 6 9-7 108 6 9 7-0 108 6 9-7 108 6 9-7 108 6 9-7 108 6 9-7 108 6 9-7 108 6 9-7 108 6 9-7 108 6 9-7 108 6 9-7 108 6 9-7 108 6 9-7 108 </td <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>									
8-0 6-0 8- 7- 13 162 6-6 8- 7- 138 6-2 3-7- 108 6-4 0-2 6-5 39-0 139 2 39 8-0 6-0 8-7 7- 108 6-7 8-7 130 6-7 9-7 130 6-7 9-7 130 6-7 9-7 130 6-7 0-7 150 6 39-7 150 6 39-7 150 2 39 8-0 4-0 11 8 23 162 6 8-7 130 6 9 9-7 130 6-7 130 5-0 150 130 5-0 150 130 5-0 150 130 5-0 150 130 5-0 5-2 108 6 9 7-0 310 6 9 7-0 310 6 9 9 100 9 100 9 100 9 100 9									
g - g - g <th< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></th<>									
9 - 0' 4 - 0' 11' 8' 27 12' 6' 6' 9 - 1'' 160 6' 9 - 2'' 160 6' 9'' 100 6'' 9''' 100 6'' 9''' 100 6'' 9''' 100 6'' 9''' 100 6'' 9''' 100 6'' 9''' 100 6'' 9''' 100 6''' 9'''' 100 6''' 9'''' 100 6'''' 9'''''' 100 6''''''''''''''''''''''''''''''''''''									
B - U I - U S - U <th< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></th<>									
\$\begin{bmatrix} \ny \nu \ny	8' - 0'' 4' - 0'' 13''	9" 30'	162 #6 6" 9'-3" 2,251	108 #6 9" 10'-2" 1,649 4'-11"	5' - 3''	108 #6 9" 8'-9" 1,419 5'-3" 3'-6" 1	108 9" 4' - 0" 289	6 39' - 9" 159	32 39' - 9
8 - 0° 9 - 0° 8 - 20° 100 8 - 0° 9 - 20° 100 8 - 0° 9 - 20° 100 100 17.70 9 - 20° 100 40 9 - 20° <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>									
$g - 0^{-}$ $5 - 0^{-}$ 13^{+} g^{-} 30^{-} 162^{-} 6^{-} $g - 3^{-}$ 108^{-} $g - 3^{-}$ 108^{-} $g - 3^{-}$ 108^{-} $g - 3^{-}$ 108^{-} $g - 3^{-}$ 110^{-} $11^{-}2^{-}$ 181^{-} $5 - 3^{-}$ 108^{-} $g - 3^{-}$ 110^{-} $10^{-}2^{-}$ $11^{-}2^{-}$ $110^{-}8^{-}$ $10^{-}6^{-}$ $5 - 2^{-}$ 108^{-} $g - 3^{-}$ $110^{-}8^{-}$ $10^{-}8^{-}$ $11^{-}8^{-}$ $110^{-}8^{-}$ $10^{-}8^{-}$ $5 - 2^{-}$ $108^{-}8^{-}6^{-}$ $31^{-}5^{-}2^{-}$ $3^{-}1^{-}$ $108^{-}9^{-}$ $433^{-}6^{-}$ $6^{-}3^{-}9^{-}$ $11^{-}10^{-}1^{-}1^{-}1^{-}1^{-}1^{-}1^{-}1^{-}1$									
8 0" 6'-0" 8" 7" 13 162 #6 6'' 8'-11" 2,170 108 #6 9'' 17'' 108 9'' 6'-0" 433 6 39-9'' 159 40 39 8'-0" 6'' 8''' 1'' 16 162 46 6'' 8'-11" 2,170 108 #6 9'' 8'-2" 108 #6 9'' 8'-3" 1,338 5'-2" 3''' 108 9'' 6'-0" 433 6 39-9'' 159 40 39'' 8'-0" 6'' 11'' 8'' 9''' 10''' 108 6'' 5'-2"' 108 6''' 8'''' 1'''''' 108 5''''''''''''''''''''''''''''''''''''			162 #6 6" 9'-1" 2,210						
8 - 0" 6' - 0" 8'' 7" 16 162 #6 6'' 9'' 11'' 8'' 10'' 8'' 10'' 8''' 10'' 8''' 10'' 8''' 10'' 8''' 10''' 8''' 10''' 8'''' 10''' 8'''' 10''' 8'''' 10''' 8'''' 10''' 8'''' 10'''' 8'''' 10''''' 10''''' 10'''''' 10''''' 10'''''' 10'''''''' 10''''''' 10''''''''''''''''''''''''''''''''''''									
8 - 0" 11" 8" 23 162 #6 6" 9 - 1" 2,210 108 #6 9" 5' - 2" 108 #6 9" 8' - 6" 1,379 5' - 2" 3' - 4" 82 12" 6' - 0" 329 6 39 - 9" 159 40 39 8' - 0" 13" 9" 30 162 #6 6" 9' - 3" 2,251 108 #6 9" 8' - 0" 1,419 5' - 3" 3' - 6" 108 9" 6' - 0" 329 6 39 - 9" 159 40 39 8' - 0" 7'' 13 162 #6 6" 8' - 11" 2,170 108 #6 9" 8' - 2" 1,133 5' - 2" 108 #6 9" 8' - 3" 1,338 5' - 2" 108 8'' 8''' 8'''' 8''''''''''''''''''''''''''''''''''''									
8 - 0' 13' 9' 30' 162 #6 9' 2,251 108 #6 9' 1,23' 108 #6 9' 8'-3' 1,33 5 - 3'' 3 - 6'' 108 9' 6' - 0'' 433 6 39-9' 159 40 39' 8'-0' 7''-0' 8'' 7'' 16 162 6'' 8'-11'' 2,170 162 6'' 12'-2'' 3,082 7'-6'' 5'-2'' 108 6'' 8''' 1,338 5'-2'' 3.01'' 108 9' 7'-0'' 505 6 39-9'' 159 40 39''' 8'-0'' 7''''' 8''' 7''''' 8''' 7''''' 108 6''''''''''''''''''''''''''''''''''''									
8 - 0" 7" 13 162 #6 6" 8 - 11" 2,170 108 #6 9" 7 - 0" 5.2" 13.38 5 - 2" 3 - 1" 108 9" 7" - 0" 505 6 39 - 9" 159 40 39 8 - 0" 7" - 0" 8" 7" 16 162 #6 6" 8 - 11" 2,170 162 #6 0" 2 - 2" 162 #6 6" 8 - 3" 2,007 5 - 2" 3 - 1" 108 9" 7" - 0" 505 6 39 - 9" 159 40 39 8 - 0" 7" - 0" 8" 7" 16 8" 2" 162 46 6" 8 - 3" 1,338 5 - 2" 3 - 1" 108 9" 7" - 0" 505 6 39 - 9" 159 40 39 8 - 0" 7" - 0" 11" 8" 2" 162 46 6" 8 - 5" 162 8 - 6" 8 - 5" 3 - 3" 82 12" 7" - 0" 555 6 39 - 9" 159 40 39 <td></td> <td></td> <td></td> <td></td> <td>-</td> <td>· · · · · · · · · · · · · · · · · · ·</td> <td></td> <td></td> <td></td>					-	· · · · · · · · · · · · · · · · · · ·			
8 - 0" 7' - 0" 10" 8" 20 162 6" 9' - 1" 2.10 162 6" 12 - 10" 3.123 7' - 8" 5' - 2" 162 6" 8' - 5" 2.048 5' - 2" 3' - 3" 82 12" 7' - 0" 383 6 39' - 9" 159 40 39' 8' - 0" 7' - 0" 11" 8" 23 162 6" 9' - 5' - 2" 162 6" 8' - 5" 2.048 5' - 2" 3' - 3" 82 12" 7' - 0" 383 6 39' - 9" 159 40 39' 8' - 0" 13" 9" 30 162 6" 8' - 5" 162 6" 8' - 6" 2.048 5' - 2" 3' - 3" 82 12" 7' - 0" 383 6 39' - 9" 159 40 39' 8' - 0" 13" 9" 30 162 6" 8' - 0" 5' - 2" 162 6" 8' - 9" 1.13 3' - 5" 3' - 5" 162 6" 8' - 9" 1.33 5' - 2" 3' - 5" 3' - 5" 1									
8 - 0" 7' - 0" 11" 8" 23 162 #6 6" 12' - 11" 3,143 7' - 9" 5' - 2" 162 6" 12' - 11" 3,143 7' - 9" 5' - 2" 162 6" 8' - 6" 2,068 5' - 2" 3' - 4" 82 12" 7' - 0" 383 6 39' - 9" 159 40 39' 8' - 0" 7' - 0" 13" 9" 30' 162 46 6" 12' - 11" 3,143 7' - 9" 5' - 2" 162 6" 8' - 6" 2,068 5' - 2" 3' - 4" 82 12" 7' - 0" 383 6 39' - 9" 159 40 39' 8' - 0" 13" 9" 30' 162 46 6" 8' - 6" 2,088 5' - 2" 3' - 4" 8'' 10''' 10''' 10'''' 10'''' 10''''''''''''''''''''''''''''''''''''									
8' - 0'' 13'' 9'' 30' 162 #6 6'' 13'' 3,204 7' - 11'' 5' - 3'' 162 6'' 8' - 9'' 2,129 5 - 3'' 3' - 6'' 108 9'' 7' - 0'' 505 6 39' - 9'' 159 40 39'' 8' - 0'' 8'' 7'' 13' 162 #6 6'' 13'' 9'' 13'' 102 #6 9'' 3''' 108 6'' 8' - 9'' 13'' 103'' 5'''' 8'''''' 108 6''' 8''''''''''''''''''''''''''''''''''''									
8'-0'' 8'' 7'' 16' 162 #6 6'' 8'-11'' 2,170 162 #6 6'' 13'' 9 162 7'' 16 162 #6 6'' 13'' 9'' 162 16 4'' 39'' 8'-0'' 10'' 8''' 20'' 10'' 8'''' 10''' 336 8'-6'' 5'-2'' 162 6''' 8'-5''' 2,08 5'-2''' 3'-3''' 108 9'''''' 8''''''''''''''''''''''''''''''''''''									
8'-0" 10" 8" 20' 162 #6 6" 9'-1" 2,210 162 #6 6" 13'-10" 3,366 8'-8" 5'-2" 162 #6 6" 8'-0" 5'-2" 3'-3" 108 9" 8'-0" 577 6 39'-9" 159 44 39' 8'-0" 8'-0" 11" 8" 23' 162 #6 6" 13'-11" 3,366 8'-9" 5'-2" 162 #6 6" 8'-5" 2,048 5'-2" 3'-3" 108 9" 8'-0" 55' 6 39'-9" 159 44 39' 8'-0" 11" 8" 23' 162 #6 6" 13'-11" 3,366 8'-9" 5'-2" 162 #6 6" 8'-5" 3'-4" 162 6" 8'-0" <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>									
8'-0" 8'-0" 13" 9" 30 162 #6 6" 9'-3" 2,251 162 #6 6" 14'-2" 3,447 8'-11" 5'-3" 162 #6 6" 8'-9" 2,129 5'-3" 3'-6" 162 6" 8'-0" 866 6 39'-9" 159 44 39"									
					-				
					(For direct traffic culverts (fill height ≤ 2 ft.), identif and select the option with the minimum fill height.	y the required box size		



Oct 20, 2022, 5: 38pm User ID: RichardGarci











lar 31, 2023, 9:55am User ID: RichardGarc \116\80\39\Design\Civil\DRDT1168039.dwg

	NON NON NON NON NON NON NON NON NON NON
	The provide the problem of the probl
	ALAMO RANCH PARKWAY PHASE II SAN ANTONIO, TEXAS DRAINAGE DETAILS
<u>AND RING</u> DE OF CITY OF SAN ANTONIO, DELETE "SAN ANTONIO PUBLIC WORKS DEPT." MANUFACTURER'S I.D. ON LID AND RING. JTY OF H5–20 MINIMUM. RFACES SHALL BE MACHINE GROUND. OF THE MANHOLE RING AND COVER MUST BE AT LEAST 260 LBS. ROVIDED A SECURE/LOCKING LID ON THE MANHOLE COVER TOLE LID AND RING DETAIL NOT-TO-SCALE	PLAT NO. 21-11800379 JOB NO. 11680-39 DATE SEPTEMBER 2021 DESIGNER DL CHECKED BL DRAWN DL SHEET C1.38














HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSWITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery © 2016, CAPCOG, Digital Globe, Texas Orthoimagery Program, USDA Farm Service Agency.


























HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016, CAPCOG, Digital Globe, Texas Orthoimagery Program, USDA Farm Service Agency.







			PAVEME	NT SECTION	ON DETAIL				
STREET NAME	STATION	TYPE "D" HMAC	TYPE "C" HMAC	TYPE "B" HMAC	CRUSHED LIMESTONE BASE	TREATED SUBGRADE	CBR	GEOGRID (TENSAR TRIAX TX5)	STF
ALAMO RANCH (EASTBOUND)	62+56.43 TO 77+75.00	1.50"	2.50"	*	21.50"	*	4.0	NO	
ALAMO RANCH (EASTBOUND)	77+75.00 TO 78+50.00	2.00"	3.00"	6.00"	*	*	6.66	NO	
ALAMO RANCH (EASTBOUND)	78+50.00 TO 89+50.00	1.50"	2.50"	*	21.50"	*	4.0	NO	
ALAMO RANCH (EASTBOUND)	89+50.00 TO 90+25.00	2.00"	3.00"	6.00"	*	*	6.66	NO	
ALAMO RANCH (EASTBOUND)	90+25.00 TO END	1.50"	2.50"	*	21.50"	*	4.0	NO	
ALAMO RANCH (WESTBOUND)	61+36.38 TO 71+00.00	2.00"	3.00"	6.00"	*	*	6.66	NO	
ALAMO RANCH (WESTBOUND)	71+00.00 TO 81+00.00	1.50"	2.50"	*	21.50"	*	4.0	NO	
ALAMO RANCH (WESTBOUND)	81+00.00 TO 91+00.00	2.00"	3.00"	6.00"	*	*	6.66	NO	
ALAMO RANCH (WESTBOUND)	91+00.00 TO END	1.50"	2.50"	*	21.50"	*	4.0	NO	

GENERAL NOTES:

- CONTRACTOR SHALL REFERENCE THE PROJECT PAVEMENT DESIGN REPORT PREPARED BY INTEC DATED MARCH 11, 2021 (INTEC PROJECT# S191159-P-A5 AND MAY 20, 2021 (INTEC PROJECT# S191159-P-R1)
- CONTRACTOR SHALL RETAIN A GEOTECHNICAL ENGINEER TO VERIFY THE SUB GRADE CONDITION PRIOR TO PLACING ANY BASE MATERIAL. GEOTECHNICAL ENGINEER SHALL DETERMINE THE SUB GRADE CONDITION AND IF LIME STABILIZATION IS REQUIRED.
- GEOTECHNICAL ENGINEER SHOULD VERIFY THE STREET SUBGRADE AT THE TIME OF CONSTRUCTION PRIOR TO PLACEMENT OF AGGREGATE BASE.
- 4. THE FLEXIBLE BASE COURSE SHOULD BE CRUSHED LIMESTONE CONFORMING TO TXDOT STANDARD SPECIFICATIONS, ITEM 247, TYPE A, GRADES 1 OR 2.
- THE MOISTURE CONTENT OF THE FILL SHOULD BE MAINTAINED WITHIN THE RANGE OF OPTIMUM WATER CONTENT TO 3 PERCENTAGE POINTS ABOVE THE OPTIMUM WATER CONTENT UNTIL PERMANENTLY COVERED.
- IN THE EVENT THAT THE CLAY FILL USED IS DIFFERENT THAN THE EXISTING SUBGRADE, THE RECOMMENDATIONS IN THE GEOTECHNICAL REPORT COULD BE INVALIDATED AND THE DESIGN ENGINEER MUST BE CONSULTED TO DETERMINE IF ADDITIONAL CBR TESTING AND THICKER PAVEMENT SECTIONS ARE REQUIRED.
- WHERE PAVEMENT SUBGRADE IS LOCATED WITHIN 2-FEET OF THE EXISTING GROUND SURFACE (STRATUM 1 CLAYS), MOISTURE CONDITIONED SUBGRADE WILL BE REQUIRED. GEOTECHNICAL ENGINEER SHOÙLD VERIFY THE STREET SUBGRADE AT THE TIME OF CONSTRUCTION PRIOR TO PLACEMENT OF AGGREGATE BASE TO DETERMINE WHERE THE MOISTURE CONDITIONED SUBGRADE IS NEEDED. REFERENCE GEOTECHNICAL ENGINEERING REPORT FOR MORE INFORMATION.
- THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING ALL MATERIAL TESTING WITH THE PROJECT GEOTECHNICAL ENGINEER. TESTING SHALL BE PAID FOR BY THE OWNER.
- 9. FILL MATERIAL SHOULD BE NATIVE ON-SITE MATERIAL, FREE OF DELETERIOUS MATERIAL WITH A MINIMUM CBR VALUE OF 4 AND A PI LESS THAN OR EQUAL TO 20. THE GRAVEL SIZE SHOULD NOT EXCEED 3 INCHES IN DIAMETER. LIME OR CEMENT APPLICATION RATES SHOULD BE RE-EVALUATED FOR THE FILL MATERIAL. THE MATERIAL SHOULD BE PLACED AS PER APPLICABLE CITY OR COUNTY GUIDELINES. CONTRACTOR TO VERIFY EXACT SPECIFICATIONS WITH PROJECT GEOTECHNICAL ENGINEERING REPORT.
- A BEXAR COUNTY PERMIT MUST BE OBTAINED BEFORE WORKING IN THE BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE CONSTRUCTED.


SUBGRADE NOTES (*):


- . CUT AND FILL DATA ARE NOT AVAILABLE AT THIS TIME . BASED ON THE REVIEW OF GEOLOGIC AND SOILS MAP, WE ANTICIPATE THE FINAL PAVEMENT SUBGRADE
- PLASTICITY INDEX VALUE TO BE LESS THAN OR EQUAL TO 20.
- 3. IF THE SUBGRADE PLASTICITY INDEX VALUES ARE LESS THAN OR EQUAL TO 20, AS PER CITY OF SAN ANTONIO OR BEXAR COUNTY REQUIREMENTS, SUBGRADE STABILIZATION IS NOT NEEDED.
- 4. IF FILL IS USED TO RAISE THE GRADE, FILL MATERIAL UNDERNEATH THE PAVEMENT SHOULD BE APPROVED FILL MATERIAL, FREE OF DELETERIOUS MATERIAL AND WITH A MINIMUM CBR VALUE OF 4.0 AND A MAXIMUM PLASTICITY INDEX VALUE OF 20. THE MATERIAL SHOULD BE PLACED AS PER APPLICABLE CITY OR COUNTY GUIDELINES
- HOWEVER, IF THE FINAL STREET SUBGRADE PLASTICITY INDEX VALUES ARE GREATER THAN 20, THEN ONE OF THE FOLLOWING OPTIONS MAY BE FOLLOWED:

• REMOVE THE CLAYS SOILS (WITH PLASTICITY INDEX VALUES GREATER THAN 20) AND REPLACE WITH FILL MATERIAL WITH PLASTICITY INDEX VALUES LESS THAN OR EQUAL TO 20. IF SUBGRADE STABILIZATION IS REQUIRED, THE FOLLOWING SPECIFICATIONS MUST BE MET. THE CONTRACTOR SHALL COORDINATE WITH THE GEOTECHNICAL ENGINEER IN THE FIELD FOR SUBGRADE STABILIZATION. • TREAT THE SUBGRADE:


- THE SUBGRADE SHOULD BE TREATED TO A DEPTH OF 6 INCHES USING 6 ½ PERCENT LIME CONTENT
- THE SUBGRADE SOILS SHOULD BE TESTED FOR SOIL SULFATE CONTENT PRIOR TO STABILIZATION. IF THE SOIL SULFATE CONTENT IS OVER 3000 PPM, AN ALTERNATE PROCEDURE WILL BE REQUIRED.
- THE SUBGRADE MAY ALSO BE TREATED USING CEMENT.
- REMOVE THE STRATUM I CLAYS AND REPLACE WITH FILL MATERIAL WITH PLASTICITY INDEX VALUE LESS THAN OR EQUAL TO 20. - LIME OR CEMENT MAY BE USED TO TREAT THE SOILS TO A DEPTH OF 8 INCHES. APPLICATION RATE
- OF 42 LBS PER SQ YARD FOR 8 INCH DEPTH OF TREATMENT MAY BE USED.

TXDOT NOTES:	MBGF LEN	GTH OF NEED
LU = LENGTH OF GUARD FENCE NEEDED (UPSTREAM)	ADT	GREATER THAN 750'
LD = LENGTH OF GUARD FENCE NEEDED (DOWNSTREAM) DU = DISTANCE FROM EDGE OF TRAVEL LANE TO OUTSIDE EDGE (UPSTREAM) DD = DISTANCE FROM EDGE OF TRAVEL LANE TO OUTSIDE EDGE (DOWNSTREAM)	DU	21'
GU = GUARD FENCE OFFSET FROM EDGE OF TRAVEL LANE GD = GUARD FENCE OFFSET FROM EDGE OF OPPOSING DIRECTION OF TRAVEL LANE LU = GUARD FENCE LENGTH UPSTREAM	GU	18'
LP = GUARD FENCE LENGTH PARALLEL LD = GUARD FENCE LENGTH DOWNSTREAM LT = TOTAL LENGTH OF GUARD FENCE	LU	35.71'
	DD	219'
LD = 0 FT.	GD	216'
LU = $250' - \left(\frac{250'}{21'}\right) * 18' = 35.71$ FT.	LD	3.42'
	LP	51.43'
	LT	90.56'








e: Feb 16, 2023, 8:04am User ID: RichardGarcia : P:\116\80\39\Design\Civil\STDT1168039.dwg




THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery B' 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.









HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLES UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoiragery Program, USDA Farm Service Agency.



te: Jul 26, 2023, 7:53am User ID: bspielman e: P:\116\80\39\Design\Civil\SG0A1168039.dwg



THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.





CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.


C3.01

SHEET

HECKED<u>BL</u>DRAWN<u>DL</u>










SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.


HECKED BL DRAWN DL C3.02 SHEET






HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery @ 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.






HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery @ 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.



Det 20, 2022, 5:57pm User ID: RichardGarcia P. V116/R0V34/Design/Civil/SGDT116R039 dwn

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery B' 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.




HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.


DEVELOPER'S NAME: CONTINENTAL HOMES OF TEXAS, L.P.
ADDRESS: 5419 N LOOP 1604 E
CITY: SAN ANTONIO STATE: TEXAS ZIP: 78247
PHONE# (210)-496-2668 FAX# (210)-496-2668
068598 &
TOTAL LINEAR FOOTAGE OF PIPE: 12"-3,594 LF PLAT NO. 21-11800379
NUMBER OF LOTS 0 SAWS JOB NO. 21-1214

JOE DA			- Animaine	NO. RE
AT B N TE_ SIGN		PAPE_DAWSON	to the second se	
0.			AL	
SE	SAN ANTONIO. TEXAS		EB	
PTE			0 M. 984 2017	
I16 EME				
80- 8ER	OVERALL WATER DISTRIBUTION PLAN	SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS		
- 39 20	2	2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000	AS CE	
))21		TBPE FIRM REGISTRATION #470 I TBPLS FIRM REGISTRATION #10028800	* 42	
			~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	

C4.00

SHEET





# PRESSURE REDUCING VALVE NOTE:

PRESSURE REDUCING VALVE TO BE INSTALLED ON CUSTOMER'S SIDE OF METER BY HOMEBUILDER.

PRESSURE NOTE:

REDUCING VALVE (PRV).

CONTRACTOR TO VERIFY THAT NO PORTION OF THE TRACT IS BELOW GROUND ELEVATION OF 985 FEET WHERE THE STATIC PRESSURE WILL NORMALLY EXCEED 80 PSI. AT ALL SUCH LOCATIONS WHERE THE GROUND LEVEL IS BELOW 985 FEET, THE DEVELOPER OR BUILDER SHALL INSTALL AT EACH LOT, ON THE CUSTOMER'S SIDE OF THE METER, AN APPROVED TYPE PRESSURE REGULATOR IN CONFORMANCE WITH THE PLUMBING CODE OF THE CITY OF SAN ANTONIO. NO DUAL SERVICES ALLOWED FOR ANY LOT(S) IF *PRV IS/ARE REQUIRED FOR SUCH LOT(S), ONLY SINGLE SERVICE CONNECTIONS SHALL BE ALLOWED. *NOTE: A PRESSURE REGULATOR IS ALSO KNOWN AS A PRESSURE

# JOINT RESTRAINT NOTE:

CONTRACTOR SHALL INSTALL RETAINER GLANDS AT ALL FITTINGS AND PROVIDE JOINT RESTRAINING HARNESSES OR FIELD LOCK GASKETS AT ALL JOINTS WITHIN THE LENGTH SHOWN. CONTRACTOR SHALL INSURE THAT ALL TEES, BENDS, VALVES, ETC. HAVE A MINIMUM OF 5 FT OF PIPE WITH NO JOINTS ON EACH SIDE OF THE FITTING. JOINT RESTRAINTS AND RETAINER GLANDS SHALL BE CALCULATED BY SAWS APPROVED PROGRAMS. THERE WILL BE NO SEPARATE PAY ITEM FOR RETAINER GLANDS AND OTHER JOINT RESTRAINING HARNESSES AND GASKETS, BUT SHALL BE SUBSIDIARY TO THE UNIT COST PER LINEAL FOOT OF PIPE INSTALLED.


# TRENCH EXCAVATION SAFETY PROTECTION:

CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. **WATER (SAWS PRESSURE ZONE 8)** 


DEVELOPER'S NAME: CONTI	NENTAL HOMES OF	TEXAS, L.P.	
ADDRESS: 5419 N LOOP	1604 E		
CITY: SAN ANTONIO	STATE:TEX/	AS ZIP:	78247
PHONE# (210)-496-2668	FAX#	(210)-496-	-2668
068598 SAWS BLOCK MAP#_06859	<u>6</u> TOTAL EDU'S <u>10</u>	TOTAL ACR	EAGE 22.00
TOTAL LINEAR FOOTAGE OF	PIPE: <u>12"-3,594 LF</u>	_ PLAT NO. <u>21-</u>	-11800379
NUMBER OF LOTS 0	SAWS JOB N	NO. <u>21–1214</u>	

PAPE-DAWSON	THE ENGINEERS	SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TBPE FIRM REGISTRATION #470 I TBPLS FIRM REGISTRATION #10028800
ALAMO RANCH PARKWAY PHASE II	SAN ANTONIO, TEXAS	OVERALL WATER DISTRIBUTION PLAN
PLAT NO		1800379 680-39


HEET	C4.0	1
HECKED		N D
ESIGNER	DL	
ATE	SEPTEMBER	2021



s document has been produced from material that was stored and/or transmitted electronically and may earing the consultant's original signature and seal. Aerial imagery Provided by google@ unless otherwise noted. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.



bate: Feb 16, 2023, 8:07am User ID: RichardGarcia ile: P:\116\80\39\Desian\Civil\WTDT1168039.dwa



THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.

	SAWS CONSTRUCTION NOTES (LAST REVISED JULY 2017)	
-	AWS GENERAL SECTION	SAWS WATER NOTES
1.	ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL BE APPROVED BY THE SAN ANTONIO WATER SYSTEM (SAWS) AND COMPLY WITH THE PLANS, SPECIFICATIONS, GENERAL CONDITIONS AND WITH THE FOLLOWING AS APPLICABLE: A.CURRENT TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) 'DESIGN	1. PRIOR TO TIE-INS, ANY SHUTDOWNS BE COORDINATED WITH THE SAWS LEAST ONE WEEK IN ADVANCE OF T ALSO PROVIDE A SEQUENCE OF WOR AT NO ADDITIONAL COST TO SAW RESPONSIBILITY OF THE CONTR
	CRITERIA FOR DOMESTIC WASTEWATER SYSTEM", TEXAS ADMINISTRATIVE CODE (TAC) TITLE 30 PART 1 CHAPTER 217 AND "PUBLIC DRINKING WATER", TAC TITLE 30 PART 1 CHAPTER 290. B.CURRENT TXDOT "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS AND DRAINAGE".	ACCORDINGLY. • FOR WATER MAINS 12" OR HIGHE CENTER (210) 233–2014
	<ul> <li>C.CURRENT "SAN ANTONIO WATER SYSTEM STANDARD SPECIFICATIONS FOR WATER AND SANITARY SEWER CONSTRUCTION".</li> <li>D.CURRENT CITY OF SAN ANTONIO "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION".</li> <li>E.CURRENT CITY OF SAN ANTONIO "UTILITY EXCAVATION CRITERIA MANUAL" (UECM).</li> </ul>	2. ASBESTOS CEMENT (AC) PIPE, ALSO KNOWN TO CONTAIN ASBESTOS- LOCATED WITHIN THE PROJECT PROCEDURES AND HEALTH AND SAF WHEN REMOVAL AND/OR DISTURBAN IS TO BE MADE UNDER SPECIAL S
2.	THE CONTRACTOR SHALL NOT PROCEED WITH ANY PIPE INSTALLATION WORK UNTIL THEY OBTAIN A COPY OF THE APPROVED COUNTER PERMIT OR GENERAL CONSTRUCTION PERMIT (GCP) FROM THE CONSULTANT AND HAS BEEN NOTIFIED BY SAWS CONSTRUCTION INSPECTION DIVISION TO PROCEED WITH THE WORK AND HAS ARRANGED A MEETING WITH THE INSPECTOR AND CONSULTANT FOR THE WORK REQUIREMENTS. WORK COMPLETED BY THE CONTRACTOR WITHOUT AN APPROVED COUNTER PERMIT AND/OR A GCP WILL BE SUBJECT TO REMOVAL AND	SPECIFICATION FOR HANDLING ASBES 3. VALVE REMOVAL: WHERE THE CONTR THE CONTROL VALVE LOCATED ON REMOVED AND REPLACED WITH A CA
3.	REPLACEMENT AT THE EXPENSE OF THE CONTRACTORS AND/OR THE DEVELOPER. THE CONTRACTOR SHALL OBTAIN THE SAWS STANDARD DETAILS FROM THE SAWS WEBSITE, HTTP://WWW.SAWS.ORG/BUSINESS_CENTER/SPECS. UNLESS OTHERWISE	4. SUITABLE ANCHORAGE/THRUST BLOG PROVIDED AT ALL OF THE FOLLOWING CAPS, TEES, CROSSES, VALVES, AI STANDARD DRAWINGS DD-839 SERI STANDARD SPECIFICATIONS FOR CONS
۴.	NOTED WITHIN THE DESIGN PLANS. THE CONTRACTOR IS TO MAKE ARRANGEMENTS WITH THE SAWS CONSTRUCTION INSPECTION DIVISION AT	5. ALL VALVES SHALL READ "OPEN RIG
	(210) 233–2973, ON NOTIFICATION PROCEDURES THAT WILL BE USED TO NOTIFY AFFECTED HOME RESIDENTS AND/OR PROPERTY OWNERS 48 HOURS PRIOR TO BEGINNING ANY WORK.	<ol> <li>PRVS REQUIRED: CONTRACTOR TO V IS BELOW GROUND ELEVATION OF 9 WILL NORMALLY EXCEED 80 PSI. GROUND LEVEL IS BELOW 985 FEE INSTALL AT EACH LOT, ON THE</li> </ol>
•	LOCATION AND DEPTH OF EXISTING UTILITIES AND SERVICE LATERALS SHOWN ON THE PLANS ARE UNDERSTOOD TO BE APPROXIMATE. ACTUAL LOCATIONS AND DEPTHS MUST BE FIELD VERIFIED BY THE CONTRACTOR AT LEAST 1 WEEK PRIOR TO CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO LOCATE UTILITY SERVICE LINES AS REQUIRED FOR CONSTRUCTION AND TO PROTECT THEM DURING CONSTRUCTION AT NO COST TO SAWS.	APPROVED TYPE PRESSURE REGU PLUMBING CODE OF THE CITY OF ALLOWED FOR ANY LOT(S) IF *PRV ONLY SINGLE SERVICE CONNECTION PRESSURE REGULATOR IS ALSO KNO (PRV).
	THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF UNDERGROUND UTILITIES AND DRAINAGE STRUCTURES AT LEAST 1–2 WEEKS PRIOR TO CONSTRUCTION WHETHER SHOWN ON PLANS OR NOT. PLEASE ALLOW UP TO 7 BUSINESS DAYS FOR LOCATES REQUESTING PIPE LOCATION MARKERS ON SAWS FACILITIES. THE FOLLOWING CONTACT INFORMATION ARE SUPPLIED FOR VERIFICATION PURPOSES:	<ol> <li>PIPE DISINFECTION WITH DRY HTH I FEET. (ITEM NO. 847.3): MAINS WHERE SHOWN IN THE CONTRACT INSPECTOR, AND SHALL NOT EXCEED METHOD OF DISINFECTION WILL ALSO</li> </ol>
	<ul> <li>SAWS UTILITY LOCATES: HTTP://WWW.SAWS.ORG/SERVICE/LOCATES</li> <li>COSA DRAINAGE (210) 207-0724 OR (210) 207-6026</li> <li>COSA TRAFFIC SIGNAL OPERATIONS (210) 206-8480</li> <li>COSA TRAFFIC SIGNAL DAMAGES (210) 207-3951</li> <li>TEXAS STATE WIDE ONE CALL LOCATOR 1-800-545-6005 OR 811</li> </ul>	CONTRACTOR SHALL UTILIZE ALL PROTECT HIS PERSONNEL DURING DIS 8. BACKFLOW PREVENTION DEVICES:
•	THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING EXISTING FENCES, CURBS, STREETS, DRIVEWAYS, SIDEWALKS, LANDSCAPING AND STRUCTURES TO ITS ORIGINAL OR BETTER CONDITION IF DAMAGES ARE MADE AS A RESULT OF THE PROJECT'S CONSTRUCTION.	<ul> <li>ALL IRRIGATION SERVICES WITHIN HAVE BACKFLOW PREVENTION DE</li> <li>ALL COMMERCIAL BACKFLOW PRE BY SAWS PRIOR TO INSTALLATION</li> </ul>
	ALL WORK IN TEXAS DEPARTMENT OF TRANSPORTATION (TXDOT) AND/OR BEXAR COUNTY RIGHT-OF-WAY SHALL BE DONE IN ACCORDANCE WITH RESPECTIVE CONSTRUCTION SPECIFICATIONS AND PERMIT REQUIREMENTS.	9. FINAL CONNECTION TO THE EXISTIN UNTIL THE WATER MAIN HAS BEEN SAWS HAS RELEASED THE MAIN FOR
	THE CONTRACTOR SHALL COMPLY WITH CITY OF SAN ANTONIO OR OTHER GOVERNING MUNICIPALITY'S TREE ORDINANCES WHEN EXCAVATING NEAR TREES.	
Э.	THE CONTRACTOR SHALL NOT PLACE ANY WASTE MATERIALS IN THE 100-YEAR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN PERMIT.	
	HOLIDAY WORK: CONTRACTORS WILL NOT BE ALLOWED TO PERFORM SAWS WORK ON SAWS RECOGNIZED HOLIDAYS. REQUEST SHOULD BE SENT TO CONSTWORKREQ@SAWS.ORG.	
	WEEKEND WORK: CONTRACTORS ARE REQUIRED TO NOTIFY THE SAWS INSPECTION CONSTRUCTION DEPARTMENT 48 HOURS IN ADVANCE TO REQUEST WEEKEND WORK. REQUEST SHOULD BE SENT TO CONSTWORKREQ@SAWS.ORG.	
1.	ANY AND ALL SAWS UTILITY WORK INSTALLED WITHOUT HOLIDAY/WEEKEND APPROVAL WILL BE SUBJECT TO BE UNCOVERED FOR PROPER INSPECTION.	
2.	COMPACTION NOTE (ITEM 804): THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEETING THE COMPACTION REQUIREMENTS ON ALL TRENCH BACKFILL AND FOR PAYING FOR THE TESTS PERFORMED BY A THIRD PARTY. COMPACTION TESTS WILL BE DONE AT ONE LOCATION POINT RANDOMLY SELECTED, OR AS INDICATED BY THE SAWS INSPECTOR AND/OR THE TEST ADMINISTRATOR, PER EACH 12-INCH LOOSE LIFT PER 400 LINEAR FEET AT A MINIMUM. THIS PROJECT WILL NOT BE ACCEPTED AND FINALIZED BY SAWS WITHOUT THIS REQUIREMENT BEING MET AND VERIFIED BY PROVIDING ALL NECESSARY DOCUMENTED TEST RESULTS.	
13.	A COPY OF ALL TESTING REPORTS SHALL BE FORWARDED TO SAWS CONSTRUCTION INSPECTION DIVISION.	
		1

# OF EXISTING MAINS OF ANY SIZE MUST | 1. MACHINE CHLORINATION BY THE S.A.W.S. CONSTRUCTION INSPECTION DIVISION AT THE SHUTDOWN. THE CONTRACTOR MUST RK AS RELATED TO THE TIE-INS; THIS IS WS OR THE PROJECT AND IT IS THE

IER: SAWS EMERGENCY OPERATIONS

- KNOWN AS TRANSITE PIPE WHICH IS CONTAINING MATERIAL (ACM), MAY BE LIMITS. SPECIAL WASTE MANAGEMENT ETY REQUIREMENTS WILL BE APPLICABLE NCE OF THIS PIPE OCCURS. SUCH WORK PECIFICATION ITEM NO. 3000, "SPECIAL STOS CEMENT PIPE".
- RACTOR IS TO ABANDON A WATER MAIN, THE ABANDONING BRANCH WILL BE P/PLUG. (NSPI)
- CKING OR JOINT RESTRAINT SHALL BE NG MAIN LOCATIONS: DEAD ENDS, PLUGS, AND BENDS, IN ACCORDANCE WITH THE RES AND ITEM NO. 839, IN THE SAWS STRUCTION.
- HT**"**.
- ERIFY THAT NO PORTION OF THE TRACT 985 FEET WHERE THE STATIC PRESSURE T, THE DEVELOPER OR BUILDER SHALL CUSTOMER'S SIDE OF THE METER, AN ' IS/ARE REQUIRED FOR SUCH LOT(S), NS SHALL BE ALLOWED. *NOTE: Â
- FOR PROJECTS LESS THAN 800 LINEAR SHALL BE DISINFECTED WITH DRY HTH DOCUMENTS OR AS DIRECTED BY THE A TOTAL LENGTH OF 800 FEET. THIS BE FOLLOWED FOR MAIN REPAIRS. THE APPROPRIATE SAFETY MEASURE TO SINFECTION OPERATIONS.
- RESIDENTIAL AREAS ARE REQUIRED TO VICES. EVENTION DEVICES MUST BE APPROVED
- PRESSURE TESTED, CHLORINATED, AND TIE-IN AND USE.

# PROJECT WATER NOTES


- 2. ALL 8", 12" AND 16" PIPE SHALL BE P.V.C. C-900 CLASS 235 DR 18.
- RACTOR TO SEQUENCE THE WORK 3. ALL MAINS SHALL BE HYDROSTATICALLY TESTED BY THE CONTRACTOR, AS PROVIDED FOR IN THE SPECIAL CONDITIONS.
  - 4. THE WATER LINES WILL BE SET FROM THE STREET HUBS BEFORE THIS CONTRACT BEGINS. STREET CUT SHEETS WILL BE SUPPLIED TO THE CONTRACTOR. THERE SHOULD BE NO ADDITIONAL STAKES REQUIRED, AND SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO INSPECT THE SITE AND VERIFY THAT ALL STAKES REQUIRED FOR HIS WORK ARE IN PLACE AT TH TIME THE CONSTRUCTION BEGINS. IF ANY STAKES ARE MISSING TH ENGINEER SHOULD BE NOTIFIED IMMEDIATELY. AFTER CONSTRUCTION BEGINS ALL CONSTRUCTION STAKES, MARKS, ETC., SHALL BE CAREFULLY PRESERVED BY THE CONTRACTOR, AND IN CASE OF DESTRUCTION OR REMOVAL BY THE CONTRACTOR, HIS EMPLOYEE OR ANY OTHER MEANS, SUCH STAKES, MARKS ETC., SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
  - . THE CONTRACTOR SHALL FURNISH THE ENGINEER WITH ALL THE FINAL MEASUREMENTS, TAPS AND LENGTH OF SERVICE CONNECTIONS.
  - 6. THE LOT CORNERS WILL BE SET BY THE ENGINEER FOR INSTALLATION OF ALI WATER SERVICES. THESE LOT CORNERS SHALL BE CAREFULLY PRESERVED BY THE CONTRACTOR SO THE METER BOXES CAN BE SET IN PHASE II. ANY LOT CORNER DESTROYED OR REMOVED BY THE CONTRACTOR, HIS EMPLOYEES, C BY ANY OTHER MEANS SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE
  - . STREETS WILL HAVE BEEN EXCAVATED DOWN TO SUBGRADE AND THE PARKWAY WILL BE CUT DOWN TO TOP OF CURB BY THE STREET CONTRACTOR PRIOR TO CONSTRUCTION OF THE WATER MAINS. IT WILL BE THE UTILITY CONTRACTOR'S RESPONSIBILITY TO PROVIDE A PAD FOR HIS EQUIPMENT.
- AT ALL SUCH LOCATIONS WHERE THE 8. WATER METER BOXES IF APPLICABLE SHALL BE INSTALLED NINE FEET FROM FACE OF CURB TO CENTER OF THE METER BOX.
- SAN ANTONIO. NO DUAL SERVICES 9. ALL GARBAGE OR SPOIL MATERIAL FROM THIS WORK SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR, AT HIS EXPENSE.
- DWN AS A PRESSURE REDUCING VALVE | 10. FINAL CONNECTION TO THE EXISTING WATER MAIN SHALL NOT BE MADE UNTIL WATER MAIN HAS BEEN PRESSURE TESTED, CHLORINATED AND THE S.A.W.S. RELEASES THE MAIN FOR TIE-IN AND USE.
  - I. UNIT PRICE BID FOR "STANDARD FIRE HYDRANT ASSEMBLY" SHALL INCLUDE FIRE HYDRANT, 6-INCH GATE VALVE AND 6-INCH VALVE BOX COMPLETE ANCHOR BEND, AND ALL 6-INCH DI PIPE REQUIRED (DI PIPE REQUIRED SHALI INCLUDE ALL PIPE FROM THE TEE ON THE MAIN LINE TO THE FIRE HYDRANT).
  - 12. WHEN SEWER LINES ARE INSTALLED IN THE VICINITY OF WATER MAINS, SUCH INSTALLATION SHALL BE IN STRICT ACCORDANCE WITH THE TEXAS NATURAL RESOURCE CONSERVATION COMMISSION "RULES AND REGULATIONS FOR PUBLIC WATER SYSTEMS" (1988 OR ANY REVISIONS THERETO).
  - 13. A CLEAR SPACE SHALL BE PROVIDED AROUND ALL FIRE HYDRANTS. THIS AREA SHOULD HAVE A MINIMUM DIAMETER OF 3.0' AND BE CLEAN OF VERTICAL OBSTRUCTIONS, VALVES, AND METER BOXES.
- ING WATER MAIN SHALL NOT BE MADE 14. SAWS REQUIRES LEAD FREE (< 0.25%) FIRE HYDRANTS.
  - 15. UNLESS OTHERWISE NOTED ALL SERVICES SHALL BE 3/4" WITH 5/8" METER.


		NO. R	REVISION DATE	
SAN ANTONIO, TEXAS	ENGINEERS			
WATER DISTRIBUTION PLAN NOTES	SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TBPE FIRM REGISTRATION #470 I TBPLS FIRM REGISTRATION #10028800	DF $TE + TS$ A. CHANCE 401 NBEP GN AL ENGL 2.114/2.3		

ECKED BL DRAWN


			וחר		· 0/
WATER (	SAM2	<b>LUESO</b>	JULE	ZUNE	: 0)


DEVELOPER'S NAME: CONTINENTAL HOMES OF TEXAS, L.P.
ADDRESS: 5419 N LOOP 1604 E
CITY: SAN ANTONIO STATE: TEXAS ZIP: 78247
PHONE# <u>(210)-496-2668</u> FAX# <u>(210)-496-2668</u> 068598 & SAWS BLOCK MAP <u># 068596</u> TOTAL EDU'S <u>10</u> TOTAL ACREAGE <u>22.0</u> TOTAL LINEAR FOOTAGE OF PIPE: <u>12"-3.594 LF</u> PLAT NO. <u>21-11800379</u>
SAWS BLOCK MAP# IOTAL EDU S IOTAL ACREAGE22.
NUMBER OF LOTS 0 SAWS JOB NO. 21-1214






HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.







THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOC,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.


ate: Dec 11, 2023, 7:37pm User ID: Richardgarcia le: P:\116\80\39\Desian\Civil\SSA1168039.4wa









HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSWITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.





ate: Feb 16, 2023, 8:09am User ID: RichardGarcia le: P:\116\80\39\Design\Civil\SSR1168039.dwg






HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSWITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery @ 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.








HECKED BL DRAWN DL

SHEET

C5.10

NUMBER OF LOTS <u>0</u>

_ SAWS JOB NO. <u>21-1679</u>



IS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.

SAWS CONSTRUC
SAWS GENERAL SECTION
1. ALL MATERIALS AND CONSTRUCTION PROCED CONTRACT SHALL BE APPROVED BY THE SAN COMPLY WITH THE PLANS, SPECIFICATIONS, O FOLLOWING AS APPLICABLE:
<ul> <li>A. CURRENT TEXAS COMMISSION ON ENVIRON CRITERIA FOR DOMESTIC WASTEWATER CODE (TAC) TITLE 30 PART 1 CHAPT WATER", TAC TITLE 30 PART 1 CHAPTER 2</li> <li>B. CURRENT TXDOT "STANDARD SPECIFIC/ HIGHWAYS, STREETS AND DRAINAGE".</li> <li>C. CURRENT "SAN ANTONIO WATER SYSTEM WATER AND SANITARY SEWER CONSTRUCTI D. CURRENT CITY OF SAN ANTONIO "STAND WORKS CONSTRUCTION".</li> <li>E. CURRENT CITY OF SAN ANTONIO "UTILITY (UECM).</li> </ul>
2. THE CONTRACTOR SHALL NOT PROCEED WITH THEY OBTAIN A COPY OF THE APPROVE CONSTRUCTION PERMIT (GCP) FROM THE CONS SAWS CONSTRUCTION INSPECTION DIVISION TO ARRANGED A MEETING WITH THE INSPECTOR REQUIREMENTS. WORK COMPLETED BY THE C COUNTER PERMIT AND/OR A GCP WILL REPLACEMENT AT THE EXPENSE OF THE CONTER
<ol> <li>THE CONTRACTOR SHALL OBTAIN THE SAWS WEBSITE, HTTP://WWW.SAWS.ORG/BUSINESS_C NOTED WITHIN THE DESIGN PLANS.</li> </ol>
<ol> <li>THE CONTRACTOR IS TO MAKE ARRANGEMENT INSPECTION DIVISION AT (210) 233-2973, ON NOTIFICATION PROCEDUR AFFECTED HOME RESIDENTS AND/OR PROPENT BEGINNING ANY WORK.</li> </ol>
5. LOCATION AND DEPTH OF EXISTING UTILITIES THE PLANS ARE UNDERSTOOD TO BE APP DEPTHS MUST BE FIELD VERIFIED BY THE CON CONSTRUCTION. IT SHALL BE THE CONTRA UTILITY SERVICE LINES AS REQUIRED FOR CC DURING CONSTRUCTION AT NO COST TO SAWS.
6. THE CONTRACTOR SHALL VERIFY THE EXACT I AND DRAINAGE STRUCTURES AT LEAST 1- WHETHER SHOWN ON PLANS OR NOT. PLEASE LOCATES REQUESTING PIPE LOCATION MAI FOLLOWING CONTACT INFORMATION ARE SUPPLI
<ul> <li>SAWS UTILITY LOCATES: HTTP://WWW.SAW</li> <li>COSA DRAINAGE (210) 207-0724 OR (210)</li> <li>COSA TRAFFIC SIGNAL OPERATIONS (210)</li> <li>COSA TRAFFIC SIGNAL DAMAGES (210) 20</li> <li>TEXAS STATE WIDE ONE CALL LOCATOR 1-</li> </ul>
<ol> <li>THE CONTRACTOR SHALL BE RESPONSIBLE CURBS, STREETS, DRIVEWAYS, SIDEWALKS, LAI ORIGINAL OR BETTER CONDITION IF DAMAGES PROJECT'S CONSTRUCTION.</li> </ol>
8. ALL WORK IN TEXAS DEPARTMENT OF TRANS COUNTY RIGHT-OF-WAY SHALL BE DONE CONSTRUCTION SPECIFICATIONS AND PERMIT RE
9. THE CONTRACTOR SHALL COMPLY WITH C GOVERNING MUNICIPALITY'S TREE ORDINANCES
10. THE CONTRACTOR SHALL NOT PLACE ANY W FLOOD PLAIN WITHOUT FIRST OBTAINING AN AF
<ol> <li>HOLIDAY WORK: CONTRACTORS WILL NOT BE A SAWS RECOGNIZED HOLIDAYS. REQUEST SHOULD CONSTWORKREQ@SAWS.ORG.</li> </ol>
WEEKEND WORK: CONTRACTORS ARE REQUIRE CONSTRUCTION DEPARTMENT 48 HOURS IN AD REQUEST SHOULD BE SENT TO CONSTWORKREQ
ANY AND ALL SAWS UTILITY WORK INSTALLED APPROVAL WILL BE SUBJECT TO BE UNCOVERE
12. COMPACTION NOTE (ITEM 804): THE CONTRA MEETING THE COMPACTION REQUIREMENTS O PAYING FOR THE TESTS PERFORMED BY A TH BE DONE AT ONE LOCATION POINT RANDOMLY SAWS INSPECTOR AND/OR THE TEST ADMINIS LIFT PER 400 LINEAR FEET AT A MINIMUM. T AND FINALIZED BY SAWS WITHOUT THIS REQUI
PROVIDING ALL NECESSARY DOCUMENTED TEST 13. A COPY OF ALL TESTING REPORTS SHALL BE INSPECTION DIVISION.

# CTION NOTES JLY 2017)

CEDURES WITHIN THE SCOPE OF THIS AN ANTONIO WATER SYSTEM (SAWS) AND GENERAL CONDITIONS AND WITH THE

ONMENTAL QUALITY (TCEQ) 'DESIGN SYSTEM", TEXAS ADMINISTRATIVE PTER 217 AND "PUBLIC DRINKING 290. ICATIONS FOR CONSTRUCTION OF

- TEM STANDARD SPECIFICATIONS FOR 1OIT: NDARD SPECIFICATIONS FOR PUBLIC
- LITY EXCAVATION CRITERIA MANUAL"

### TH ANY PIPE INSTALLATION WORK UNTIL OVED COUNTER PERMIT OR GENERAL NSULTANT AND HAS BEEN NOTIFIED BY TO PROCEED WITH THE WORK AND HAS OR AND CONSULTANT FOR THE WORK CONTRACTOR WITHOUT AN APPROVED BE SUBJECT TO REMOVAL AND ITRACTORS AND/OR THE DEVELOPER.

STANDARD DETAILS FROM THE SAWS _CENTER/SPECS. UNLESS OTHERWISE

URES THAT WILL BE USED TO NOTIFY PERTY OWNERS 48 HOURS PRIOR TO

### IES AND SERVICE LATERALS SHOWN ON APPROXIMATE. ACTUAL LOCATIONS AND CONTRACTOR AT LEAST 1 WEEK PRIOR TO RACTOR'S RESPONSIBILITY TO LOCATE CONSTRUCTION AND TO PROTECT THEM

LOCATION OF UNDERGROUND UTILITIES -2 WEEKS PRIOR TO CONSTRUCTION ALLOW UP TO 7 BUSINESS DAYS FOR IARKERS ON SAWS FACILITIES. TH PLIED FOR VERIFICATION PURPOSES:

AWS.ORG/SERVICE/LOCATES

210) 207–6026 10) 206-8480

207-3951 1-800-545-6005 OR 811

_E FOR RESTORING EXISTING FENCES, ANDSCAPING AND STRUCTURES TO ITS SES ARE MADE AS A RESULT OF THE

NSPORTATION (TXDOT) AND/OR BEXAR IN ACCORDANCE WITH RESPECTIVE REQUIREMENTS.

CITY OF SAN ANTONIO OR OTHER WHEN EXCAVATING NEAR TREES.

WASTE MATERIALS IN THE 100-YEAR APPROVED FLOOD PLAIN PERMIT.

OULD BE SENT TO

IRED TO NOTIFY THE SAWS INSPECTION ADVANCE TO REQUEST WEEKEND WORK. EQ@SAWS.ORG.

WITHOUT HOLIDAY/WEEKEND RED FOR PROPER INSPECTION.

TRACTOR SHALL BE RESPONSIBLE FOR ON ALL TRENCH BACKFILL AND FOR THIRD PARTY. COMPACTION TESTS WILL LY SELECTED, OR AS INDICATED BY THE NISTRATOR, PER EACH 12-INCH LOOSE THIS PROJECT WILL NOT BE ACCEPTED UIREMENT BEING MET AND VERIFIED BY ST RESULTS.

BE FORWARDED TO SAWS CONSTRUCTION

# SAWS SEWER NOTES

THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT NO SANITARY SEWER OVERFLOW (SSO) OCCURS AS A RESULT OF THEIR WORK. ALL CONTRACTOR PERSONNEL RESPONSIBLE FOR SSO PREVENTION AND CONTROL SHALL BE TRAINED ON PROPER RESPONSE. SHOULD AN SSO OCCUR, THE CONTRACTOR SHALL:

- A. IDENTIFY THE SOURCE OF THE SSO AND NOTIFY SAWS EMERGENCY OPERATIONS CENTER (EOC) IMMEDIATELY AT (210) 233-2014. PROVIDE THE ADDRESS OF THE SPILL AND AN ESTIMATED VOLUME OR FLOW. B.ATTEMPT TO ELIMINATE THE SOURCE OF THE SSO.
- C.CONTAIN SEWAGE FROM THE SSO TO THE EXTENT OF PREVENTING A POSSIBLE CONTAMINATION OF WATERWAYS. D.CLEAN UP SPILL SITE (RETURN CONTAINED SEWAGE TO THE
- COLLECTION SYSTEM IF POSSIBLE) AND PROPERLY DISPOSE OF CONTAMINATED SOIL/MATERIALS.
- E.CLEAN THE AFFECTED SEWER MAINS AND REMOVE ANY DEBRIS. F.MEET ALL POST-SSO REQUIREMENTS AS PER THE EPA CONSENT DECREE, INCLUDING LINE CLEANING AND TELEVISING THE AFFECTED SEWER MAINS (AT SAWS DIRECTION) WITHIN 24 HOURS.

SHOULD THE CONTRACTOR FAIL TO ADDRESS AN SSO IMMEDIATELY AND TO SAWS SATISFACTION, THEY WILL BE RESPONSIBLE FOR ALL COSTS INCURRED BY SAWS, INCLUDING ANY FINES FROM EPA, TCEQ AND/OR ANY OTHER FEDERAL, STATE OR LOCAL AGENCIES.

NO SEPARATE MEASUREMENT OR PAYMENT SHALL BE MADE FOR THIS WORK. ALL WORK SHALL BE DONE ACCORDING TO GUIDELINES SET BY THE TCEQ AND SAWS.

- MENTS WITH THE SAWS CONSTRUCTION 2. IF BYPASS PUMPING IS REQUIRED, THE CONTRACTOR SHALL PERFORM SUCH WORK IN ACCORDANCE WITH SAWS STANDARD SPECIFICATION FOR WATER AND SANITARY SEWER CONSTRUCTION, ITEM NO. 864, "BYPASS PUMPING".
  - PRIOR TO TIE-INS, ANY SHUTDOWNS OF EXISTING FORCE MAINS OF ANY SIZE MUST BE COORDINATED WITH THE SAWS CONSTRUCTION INSPECTION DIVISION AT (210) 233-2973 AT LEAST ONE WEEK IN ADVANCE OF THE SHUTDOWN. THE CONTRACTOR MUST ALSO PROVIDE A SEQUENCE OF WORK AS RELATED TO THE TIE-INS; THIS IS AT NO ADDITIONAL COST TO SAWS OR THE PROJECT AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SEQUENCE THE WORK ACCORDINGLY.
  - SEWER PIPE WHERE WATER LINE CROSSES SHALL BE 160 PSI AND MEET THE REQUIREMENTS OF ASTM D2241, TAC 217.53 AND TCEQ 290.44(E)(4)(B). CONTRACTOR SHALL CENTER A 20' JOINT OF 160 PSI PRESSURE RATED PVC AT THE PROPOSED WATER CROSSING.
  - ELEVATIONS POSTED FOR TOP OF MANHOLES ARE FOR REFERENCE ONLY: IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO MAKE ALLOWANCES AND ADJUSTMENTS FOR TOP OF MANHOLES TO MATCH THE FINISHED GRADE OF THE PROJECT'S IMPROVEMENTS. (NSPI)
  - 6. SPILLS, OVERFLOWS, OR DISCHARGES OF WASTEWATER: ALL SPILLS, OVERFLOWS, OR DISCHARGES OF WASTEWATER, RECYCLED WATER, PETROLEUM PRODUCTS, OR CHEMICALS MUST BE REPORTED IMMEDIATELY TO THE SAWS INSPECTOR ASSIGNED TO THE COUNTER PERMIT OR GENERAL CONSTRUCTION PERMIT (GCP). THIS REQUIREMENT APPLIES TO EVERY SPILL, OVERFLOW, OR DISCHARGE RÉGARDLESS OF SIZE.
  - MANHOLE AND ALL PIPE TESTING (INCLUDING THE TV INSPECTION) MUST BE PERFORMED AND PASSED PRIOR TO FINAL FIELD ACCEPTANCE BY SAWS CONSTRUCTION INSPECTION DIVISION, AS PER THE SAWS SPECIFICATIONS FOR WATER AND SANITARY SEWER CONSTRUCTION.
  - . ALL PVC PIPE OVER 14 FEET OF COVER SHALL BE EXTRA STRENGTH WITH MINIMUM PIPE STIFFNESS OF 115 PSI.


# ALLOWED TO PERFORM SAWS WORK ON PROJECT SEWER NOTES

- ALL RESIDENTIAL SEWER SERVICE LATERALS ARE 6" DIA. AND SHALL BE EXTENDED TO 10' PAST THE PROPERTY LINE AND CAPPED AND SEALED. CONTRACTOR SHALL INSTALL A 2" X 4" STAKE, FOUR (4) FEET LONG, TWO (2) FEET DEEP INTO THE GROUND AT THE END OF EACH SERVICE. NO SEPARATE PAY ITEM.
- . CONTRACTOR TO INSTALL CLEANOUTS AT THE END OF ALL SEWER LATERALS, PER LATERAL DETAIL SHEET C5.10
- 3. NO VERTICAL STACKS ALLOWED FOR ANY LOTS UNLESS OTHERWISE SPECIFIED BY THE ENGINEER.
- 4. ALL 6" SEWER LATERALS WILL BE SET AT 2% GRADE FROM THE MAIN TO THE PROPERTY LINE.
- WHEN HORIZONTAL DISTANCE BETWEEN SEWER PIPES AND WATER MAIN IS LESS THAN 9 FOOT OF SEPARATION, SEWER MAIN SHALL BE INSTALLED WITH 150 PSI (MIN) PRESSURE PIPE AND FITTINGS IN ACCORDANCE WITH SAWS CONSTRUCTION CRITERIA FOR CONSTRUCTION OF SEWER MAINS IN THE VICINITY OF WATER MAINS.
- . CONTRACTOR SHALL ENSURE THAT MANHOLES OUTSIDE OF PAVED AREAS ARE SET WITH TOP ELEVATIONS 6" ABOVE FINISHED GRADE WITH CONCRETE RING ENCASEMENT.
- '. ALL SEWER PIPES SHALL BE 8" PVC (SDR 26), UNLESS OTHERWISE NOTED.
- B. CONTRACTOR IS TO VERIFY EXISTING INVERT OF EXISTING SANITARY SEWER MAINS AND ALERT ENGINEER IMMEDIATELY OF ANY DIFFERENCE FROM INVERT SHOWN ON PLANS.
- 9. CONTRACTOR SHALL PROTECT ALL EXISTING FENCES. ANY FENCE DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT THEIR EXPENSE.
- 10. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
- I. CONCRETE RING ENCASEMENT TO BE INSTALLED ON ALL MANHOLES AND, WITHIN LIMITS OF PAVEMENT, BE INSTALLED TO THE TOP OF THE BASE LAYER WITH A MINIMUM OF 2" OF ASPHALT ON TOP OF THE RING ENCASEMENT.
- 12. MANHOLE OPENING INCREASED TO 30" AS PER TAC CHAPTER 217.55.
- 13. ALL SEWER PIPE LATERALS SHALL BE SDR 26 (CLASS 160) PVC PIPE.
- 14. IF THE GIVEN TOP OF MANHOLE ELEVATION DOES NOT AGREE ON ACTUAL GROUND SURFACE OR FINISH PAVEMENT, THE CONTRACTOR SHALL ADJUST ELEVATIONS SUCH THAT THE TOP OF MANHOLE SHALL BE 0.5' ABOVE EXISTING GROUND, OR FLUSH TO FINISH ASPHALT PAVEMENT.
- 15. ALL MANHOLES CONSTRUCTED OVER THE EDWARDS AQUIFER RECHARGE ZONE SHOULD BE WATERTIGHT.


# SEWER

I	DEVELODER'S NAME CONTINENTAL HOMES OF TEXAS I D
I	DEVELOPER'S NAME: CONTINENTAL HOMES OF TEXAS, L.P.
I	ADDRESS: 5419 N LOOP 1604 E
	CITY: SAN ANTONIO STATE: TEXAS ZIP: 78247
	PHONE# (210)-496-2668 FAX# (210)-496-2668
	PHONE# <u>(210)-496-2668</u> FAX# <u>(210)-496-2668</u> 068598 & SAWS BLOCK MAP <u># 068596</u> TOTAL EDU'S <u>00</u> TOTAL ACREAGE <u>22.00</u> 12"-1,368 LF & TOTAL LINEAR FOOTAGE OF PIPE: <u>18"-978 LF</u> PLAT NO. <u>21-11800379</u>
	TOTAL LINEAR FOOTAGE OF PIPE: 18"-978 LF" PLAT NO. 21-11800379
	NUMBER OF LOTS 0 SAWS JOB NO. 21-1679
1	


ALANO RANCH PARKWAY PHASE II       Pare-Dawson         San antonio, texas       Engineers         San antonio, texas       Engineers         Santary sewer notes       Engine 1 HOUSTON 17 28213 1 210.375,900         Tanantary sewer notes       Engine 1 HOUSTON 17 28213 1 210.375,900	NO. REVISION DATE		.4.0
ALAMO RANCH PARKWAY PHASE II SAN ANTONIO, TEXAS SANITARY SEWER NOTES	PAPE-DAWSON	ENGINEERS	SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TBPE FIRM REGISTRATION #470 I TBPLS FIRM REGISTRATION #10028800
	ALAMO RANCH PARKWAY PHASE II	SAN ANTONIO, TEXAS	SANITARY SEWER NOTES





HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery © 2016, CAPCOG, Digital Globe, Texas Orthoimagery Program, USDA Farm Service Agency.




ate: Dec 11, 2023, 7:38pm User ID: Richardgarcia le: P:\116\80\39\Desian\Civil\UT0A11680.39.dwa







HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSWITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery @ 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.





18. FOR FILL PLACEMENT ON HILL SIDES OR STEEP SLOPE AREAS, TH CONTRACTOR SHALL REFERENCE THE PROJECT SPECIFICATIONS AN GEOTECHNICAL REPORT FOR SPECIAL INSTRUCTIONS REGARDING BENCHING. 19. NO WORK SHALL BE PERFORMED IN A PUBLIC RIGHT-OF-WAY WITHOUT A PERMIT.

C7.00 HEET

HECKED BL DRAWN DL

ESIGNER






**BEXAR COUNTY ROW NOTE:** A BEXAR COUNTY ROW PERMIT MUST BE OBTAINED BEFORE WORKING IN

CONSTRUCTED.

	S	WP3 MODIFICA
DATE	SIGNATURE	

BEXAR COUNTY ROW. CONTRACTOR SHALL COORDINATE A TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN THE ROW. ADDITIONAL WARNING SIGNS MAY BE RECOMMENDED BY THE ENGINEER ONCE THE ROADWAYS ARE


ATIONS	
DESCRIPTION	



PURPOSE OF DEMONSTRATING COMPLIANCE WITH THE TPDES-STORM WATER POLLUTION PREVENTION PLAN (SWP3) REGULATIONS. THIS SHEET HAS BEEN PREPARED FOR PURPOSES OF THE SWP3 ONLY. ALL OTHER EXHIBIT CIVIL ENGINEERING RELATED INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SHEET IN THE CIVIL IMPROVEMENT PLANS.

THE ENGINEERING SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR TH

OB NO. 11680-39 ATE SEPTEMBER 2021 ESIGNER DL HECKED BL DRAWN DL C8.00 HEET



FERTILIZE ACCORDING TO SOIL TESTS. FERTILIZER NEEDS CAN BE DETERMINED BY A SOIL TESTING LABORATORY OR REGIONAL RECOMMENDATIONS CAN BE MADE BY COUNTY AGRICULTURAL EXTENSION AGENTS. FERTILIZE SHOULD BE WORKED INTO THE SOIL TO A DEPTH OF 3 INCHES WITH A DISC SPRINGTOOTH HARROW OR OTHER SUITABLE EQUIPMENT. ON SLOPING LAND, THE FINAL HARROWING OR DISCING OPERATION SHOULD BE ON THE CONTOUR.

# INSTALLATION IN CHANNELS

SOD STRIPS IN WATERWAYS SHOULD BE LAID PERPENDICULAR TO THE DIRECTION OF FLOW. CARE SHOULD BE TAKEN TO BUTT ENDS OF STRIPS TIGHTLY (SEE FIGURE ABOVE).

AFTER ROLLING OR TAMPING, SOD SHOULD BE PEGGED OR STAPLED TO RESIST WASHOUT DURING THE ESTABLISHMENT PERIOD. MESH OR OTHER NETTING MAY BE PEGGED OVER THE SOD FOR EXTRA PROTECTION IN CRITICAL AREAS.

8. THE FIRST MOWING SHOULD NOT BE ATTEMPTED UNTIL THE SOD IS FIRMLY ROOTED, USUALLY 2-3 WEEKS. NOT MORE THAN ONE THIRD OF THE GRASS LEAF SHOULD BE REMOVED AT ANY ONE CUTTING.

UNTIL SUCH TIME A GOOD ROOT SYSTEM BECOMES DEVELOPED, IN THE

THE UNDERSIDE OF THE SOD PAD AND THE SOIL 4 INCHES BELOW THE SOD IS

ABSENCE OF ADEQUATE RAINFALL, WATERING SHOULD BE PERFORMED AS

OFTEN AS NECESSARY TO MAINTAIN MOIST SOIL TO A DEPTH OF AT LEAST 4


### NSPECTION AND MAINTENANCE GUIDELINES SOD SHOULD BE INSPECTED WEEKLY AND AFTER EACH RAIN EVENT TO LOCATE AND REPAIR ANY DAMAGE.

. DAMAGE FROM STORMS OR NORMAL CONSTRUCTION ACTIVITIES SUCH AS TIRE RUTS OR DISTURBANCE OF SWALE STABILIZATION SHOULD BE REPAIRED AS SOON AS PRACTICAL

HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE UNLESS OTHERWISE NOTED. Imagery © 2016, CAPCOG, Digital Globe, Texas Orthoimagery Program, USDA Farm Service Agency.

THOROUGHLY WET.

NOT-TO-SCALE



# ISOMETRIC PLAN VIEW

# ROCK BERMS

THE PURPOSE OF A ROCK BERM IS TO SERVE AS A CHECK DAM IN AREAS OF CONCENTRATED FLOW, TO INTERCEPT SEDIMENT-LADEN RUNOFF, DETAIN THE SEDIMENT AND RELEASE THE WATER IN SHEET FLOW. THE ROCK BERM SHOULD BE USED WHEN THE CONTRIBUTING DRAINAGE AREA IS LESS THAN 5 ACRES. ROCK BERMS ARE USED IN AREAS WHERE THE VOLUME OF RUNOFF IS TOO GREAT FOR A SILT FENCE TO CONTAIN. THEY ARE LESS EFFECTIVE FOR SEDIMENT REMOVAL THAN SILT FENCES, PARTICULARLY FOR FINE PARTICLES, BUT ARE ABLE TO WITHSTAND HIGHER FLOWS THAN A SILT FENCE. AS SUCH, ROCK BERMS ARE OFTEN USED IN AREAS OF CHANNEL FLOWS (DITCHES, GULLIES, ETC.). ROCK BERMS ARE MOST EFFECTIVE AT REDUCING BED LOAD IN CHANNELS AND SHOULD NOT BE SUBSTITUTED FOR OTHER EROSION AND SEDIMENT CONTROL MEASURES FARTHER UP THE WATERSHED.

### INSPECTION AND MAINTENANCE GUIDELINES INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL BY THE


RESPONSIBLE PARTY. FOR INSTALLATIONS IN STREAMBEDS, ADDITIONAL DAILY INSPECTIONS SHOULD BE MADE.

REMOVE SEDIMENT AND OTHER DEBRIS WHEN BUILDUP REACHES 6 INCHES AND DISPOSE OF THE ACCUMULATED SILT IN AN APPROVED MANNER THAT WILL NOT CAUSE ANY ADDITIONAL SILTATION.

3. REPAIR ANY LOOSE WIRE SHEATHING.

4. THE BERM SHOULD BE RESHAPED AS NEEDED DURING INSPECTION 5. THE BERM SHOULD BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED DUE TO SILT ACCUMULATION AMONG THE ROCKS, WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC.

6. THE ROCK BERM SHOULD BE LEFT IN PLACE UNTIL ALL UPSTREAM AREAS ARE STABILIZED AND ACCUMULATED SILT REMOVED.



# MATERIALS

THE BERM STRUCTURE SHOULD BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM OPENING OF 1 INCH AND A MINIMUM WIRE DIAMETER OF 20 GAUGE GALVANIZED AND SHOULD BE SECURED WITH SHOAT RINGS.

2. CLEAN, OPEN GRADED 3-INCH TO 5-INCH DIAMETER ROCK SHOULD BE USED, EXCEPT IN AREAS WHERE HIGH VELOCITIES OR LARGE VOLUMES OF FLOW ARE EXPECTED, WHERE 5-INCH TO 8-INCH DIAMETER ROCKS MAY BE USED.

# INSTALLATION

1. LAY OUT THE WOVEN WIRE SHEATHING PERPENDICULAR TO THE FLOW LINE. THE SHEATHING SHOULD BE 20 GAUGE WOVEN WIRE MESH WITH 1 INCH OPENINGS.

2. BERM SHOULD HAVE A TOP WIDTH OF 2 FEET MINIMUM WITH SIDE SLOPES BEING 2:1 (H: V) OR FLATTER.

3. PLACE THE ROCK ALONG THE SHEATHING AS SHOWN IN THE DIAGRAM TO A HEIGHT NOT LESS THAN 18".

4. WRAP THE WIRE SHEATHING AROUND THE ROCK AND SECURE WITH TIE WIRE SO THAT THE ENDS OF THE SHEATHING OVERLAP AT LEAST 2 INCHES, AND THE BERM RETAINS ITS SHAPE WHEN WALKED UPON.

5. BERM SHOULD BE BUILT ALONG THE CONTOUR AT ZERO PERCENT GRADE OR AS NEAR AS POSSIBLE

6. THE ENDS OF THE BERM SHOULD BE TIED INTO EXISTING UPSLOPE GRADE AND THE BERM SHOULD BE BURIED IN A TRENCH APPROXIMATELY 3 TO 4 INCHES DEEP TO PREVENT FAILURE OF THE CONTROL.


## COMMON TROUBLE POINTS

. INSUFFICIENT BERM HEIGHT OR LENGTH (RUNOFF QUICKLY ESCAPES OVER THE TOP OR AROUND THE SIDES OF BERM).

2. BERM NOT INSTALLED PERPENDICULAR TO FLOW LINE (RUNOFF ESCAPING AROUND ONE SIDE).



NOT-TO-SCALE



## SILT FENCE

A SILT FENCE IS A BARRIER CONSISTING OF GEOTEXTILE FABRIC SUPPORTED BY METAL POSTS TO PREVENT SOIL AND SEDIMENT LOSS FROM A SITE. WHEN PROPERLY USED, SILT FENCES CAN BE HIGHLY EFFECTIVE AT CONTROLLING SEDIMENT FROM DISTURBED AREAS. THEY CAUSE RUNOFF TO POND, ALLOWING HEAVIER SOLIDS TO SETTLE OUT. IF NOT PROPERLY INSTALLED, SILT FENCES ARE NOT LIKELY TO BE EFFECTIVE.

THE PURPOSE OF A SILT FENCE IS TO INTERCEPT AND DETAIN WATER-BORN SEDIMENT FROM UNPROTECTED AREAS OF A LIMITED EXTENT. SILT FENCE IS USED DURING THE PERIOD OF CONSTRUCTION NEAR THE PERIMETER OF A DISTURBED AREA TO INTERCEPT SEDIMENT WHILE ALLOWING WATER TO PERCOLATE THROUGH. THIS FENCE SHOULD REMAIN IN PLACE UNTIL THE DISTURBED AREA IS PERMANENTLY STABILIZED. SILT FENCE SHOULD NOT BE USED WHERE THERE IS A CONCENTRATION OF WATER IN A CHANNEL OF DRAINAGE WAY. IF CONCENTRATED FLOW OCCURS AFTER INSTALLATION, CORRECTIVE ACTION MUST BE TAKEN SUCH AS PLACING A ROCK BERM IN THE AREAS OF CONCENTRATED FLOW.

SILT FENCING WITHIN THE SITE MAY BE TEMPORARILY MOVED DURING THE DAY TO ALLOW CONSTRUCTION ACTIVITY PROVIDED IT IS REPLACED AND PROPERLY ANCHORED TO THE GROUND AT THE END OF THE DAY. SILT FENCES ON THE PERIMETER OF THE SITE OR AROUND DRAINAGE WAYS SHOULD NOT BE MOVED AT ANY TIME.

## MATERIALS

SILT FENCE MATERIAL SHOULD BE POLYPROPYLENE, POLYETHYLENE, OR POLYAMIDE WOVEN OR NONWOVEN FABRIC. THE FABRIC SHOULD BE 36 INCHES, WITH A MINIMUM UNIT WEIGHT OF 4.5 OZ/YD, MULLEN BURST STRENGTH EXCEEDING 190 LB/IN2, ULTRAVIOLET STABILITY EXCEEDING 70%, AND MINIMUM APPARENT OPENING SIZE OF U.S. SIEVE NUMBER 30.

FENCE POSTS SHOULD BE MADE OF HOT ROLLED STEEL, AT LEAST 4 FEET LONG WITH TEE OR Y-BAR CROSS SECTION, SURFACE PAINTED OR GALVANIZED, MINIMUM WEIGHT 1.25 LB/FT, AND BRINDELL HARDNESS EXCEEDING 140.

3. WOVEN WIRE BACKING TO SUPPORT THE FABRIC SHOULD BE GALVANIZED 2" X 4" WELDED WIRE, 12 GAUGE MINIMUM.

## INSTALLATION

1. STEEL POSTS, WHICH SUPPORT THE SILT FENCE, SHOULD BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POSTS MUST BE EMBEDDED A MINIMUM OF 1-FOOT DEEP AND SPACED NOT MORE THAN 8 FEET ON CENTER. WHERE WATER CONCENTRATES, THE MAXIMUM SPACING SHOULD BE 6 FEET.

LAY OUT FENCING DOWN-SLOPE OF DISTURBED AREA, FOLLOWING THE CONTOUR AS CLOSELY AS POSSIBLE. THE FENCE SHOULD BE SITED SO THAT THE MAXIMUM DRAINAGE AREA IS 1/4 ACRE/100 FEET OF FENCE.

3. THE TOE OF THE SILT FENCE SHOULD BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWN-SLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. WHERE FENCE CANNOT BE TRENCHED IN (E.G., PAVEMENT OR ROCK OUTCROP). WEIGHT FABRIC FLAP WITH 3 INCHES OF PEA GRAVEL ON UPHILL SIDE TO PREVENT FLOW FROM SEEPING UNDER FENCE.

4. THE TRENCH MUST BE A MINIMUM OF 6 INCHES DEEP AND 6 INCHES WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL.

5. SILT FENCE SHOULD BE SECURELY FASTENED TO EACH STEEL SUPPORT POST OR TO WOVEN WIRE, WHICH IS IN TURN ATTACHED TO THE STEEL FENCE POST. THERE SHOULD BE A 3-FOOT OVERLAP, SECURELY FASTENED WHERE ENDS OF FABRIC MEET.

6. SILT FENCE SHOULD BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.

# COMMON TROUBLE POINTS

FENCE NOT INSTALLED ALONG THE CONTOUR CAUSING WATER TO CONCENTRATE AND FLOW OVER THE FENCE.

2. FABRIC NOT SEATED SECURELY TO GROUND (RUNOFF PASSING UNDER FENCE).

3. FENCE NOT INSTALLED PERPENDICULAR TO FLOW LINE (RUNOFF ESCAPING AROUND SIDES)

4. FENCE TREATING TOO LARGE AN AREA, OR EXCESSIVE CHANNEL FLOW (RUNOFF OVERTOPS OR COLLAPSES FENCE).


## INSPECTION AND MAINTENANCE GUIDELINES


1. INSPECT ALL FENCING WEEKLY, AND AFTER RAINFALL 2. REMOVE SEDIMENT WHEN BUILDUP REACHES 6 INCHES.

3. REPLACE TORN FABRIC OR INSTALL A SECOND LINE OF FENCING PARALLEL TO THE TORN SECTION.

4. REPLACE OR REPAIR SECTIONS CRUSHED OR COLLAPSED IN THE COURSE OF CONSTRUCTION ACTIVITY. IF A SECTION OF FENCE IS OBSTRUCTING VEHICULAR ACCESS, CONSIDER RELOCATING IT TO A SPOT WHERE IT WILL PROVIDE EQUAL PROTECTION, BUT WILL NOT OBSTRUCT VEHICLES. TRIANGULAR FILTER DIKE MAY BE PREFERABLE TO A SILT FENCE AT COMMON VEHICLE ACCESS POINTS.

WHEN CONSTRUCTION IS COMPLETE, THE SEDIMENT SHOULD BE DISPOSED OF IN A MANNER THAT WILL NOT CAUSE ADDITIONAL SILTATION AND THE PRIOR LOCATION OF THE SILT FENCE SHOULD BE REVEGETATED. THE FENCE ITSELF SHOULD BE DISPOSED OF IN AN APPROVED LANDFILL.





SILT FENCE DETAIL

NOT-TO-SCALE