

ROOSEVELT LANDING UNIT 3

BID QUANTITIES

WATER IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Water Main Tie-In (8" and 12")	EA.	3	\$ -	\$ -
2	Trench Excavation Protection	L.F.	4,976	\$ -	\$ -
3	2" Pipe, HDPE DR 9	L.F.	315	\$ -	\$ -
4	8" Pipe, C900 DR 18 PVC Class 235 (Incl. Restraints)	L.F.	3,694	\$ -	\$ -
5	12" Pipe, C900 DR 18 PVC Class 235 (Incl. Restraints)	L.F.	967	\$ -	\$ -
6	8" Ductile Iron Pipe	L.F.	17	\$ -	\$ -
7	8" Gate Valve, M.J.	EA.	10	\$ -	\$ -
8	12" Gate Valve, M.J.	EA.	8	\$ -	\$ -
9	Standard Fire Hydrant (Complete)	EA.	6	\$ -	\$ -
10	2" Blow-Off Valve (Temporary)	EA.	3	\$ -	\$ -
11	2" Blow-Off Valve (Permanent)	EA.	3	\$ -	\$ -
12	3/4" Single Service: Short	EA.	87	\$ -	\$ -
13	3/4" Single Service: Long	EA.	38	\$ -	\$ -
14	3/4" Irrigation Service: Short	EA.	1	\$ -	\$ -
15	3/4" Irrigation Service: Long	EA.	1	\$ -	\$ -
16	12"x 8" Cut-In Tee	EA.	1	\$ -	\$ -
17	12"x 12" Cut-In Tee	EA.	1	\$ -	\$ -
18	D.I. Fittings	TON	2.7	\$ -	\$ -
19	Hydrostatic Testing	EA.	1	\$ -	\$ -
20	Meter Boxes	EA.	127	\$ -	\$ -
TOTAL COST					\$ -

SANITARY SEWER IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
21	Tie Into Existing Sewer Main	EA.	1	\$ -	\$ -
22	Trench Excavation Safety Protection	L.F.	4,038	\$ -	\$ -
23	8" Sanitary Sewer Pipe, SDR-26 (0'-6')	L.F.	2,489	\$ -	\$ -
24	8" Sanitary Sewer Pipe, SDR-26 (6'-10')	L.F.	1,549	\$ -	\$ -
25	Standard Sanitary Sewer Manhole	EA.	12	\$ -	\$ -
26	Sanitary Sewer Drop Manhole	EA.	1	\$ -	\$ -
27	Extra Depth Manhole	V.F.	40.3	\$ -	\$ -
28	Vertical Stack	V.F.	73.8	\$ -	\$ -
29	6" Sanitary Sewer Lateral, SDR-26	L.F.	4,834	\$ -	\$ -
30	Wye(s) or Tee(s) Only	EA.	12	\$ -	\$ -
31	8" Sewer Main TV Inspection	L.F.	4,038	\$ -	\$ -
TOTAL COST					\$ -

ROOSEVELT LANDING UNIT 3

BID QUANTITIES

STREET IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
32	Remove Existing Header Curb & End of Road Markers	L.F.	40	\$ -	\$ -
33	Street Excavation	C.Y.	8,845	\$ -	\$ -
34	Street Embankment	C.Y.	3,338	\$ -	\$ -
35	Lime Stabilized Subgrade (6" Compacted Depth) (29 lb/SY)	S.Y.	13,137	\$ -	\$ -
36	Lime Stabilized Subgrade (8" Compacted Depth) (38 lb/SY)	S.Y.	5,603	\$ -	\$ -
37	Flexible Base (8.5" Compacted Depth)	S.Y.	13,137	\$ -	\$ -
38	Flexible Base (17.5" Compacted Depth)	S.Y.	1,703	\$ -	\$ -
39	Flexible Base (19.5" Compacted Depth)	S.Y.	3,900	\$ -	\$ -
40	Prime Coat	GAL.	3,748	\$ -	\$ -
41	Tack Coat	GAL.	1,874	\$ -	\$ -
42	Hot Mix Asphalt Pavement, Type D - (2" Comp. Depth)	S.Y.	11,869	\$ -	\$ -
43	Hot Mix Asphalt Pavement, Type D - (3" Comp. Depth)	S.Y.	5,180	\$ -	\$ -
44	Concrete Curb	L.F.	8,505	\$ -	\$ -
45	Header Curb	L.F.	124	\$ -	\$ -
46	Concrete Sidewalks (Developer Responsibility)	S.Y.	1,297	\$ -	\$ -
47	ADA Ramps	EA.	31	\$ -	\$ -
48	Timber Guard Posts	EA.	13	\$ -	\$ -
49	R2-1 Speed Limit (24" X 30")(High Intensity)	EA.	1	\$ -	\$ -
50	Lane Use Control (30" x 30")(High Intensity)	EA.	1	\$ -	\$ -
51	No Parking Anytime (18" x 24")(High Intensity)	EA.	5	\$ -	\$ -
52	R1-1 Stop (30")(High Intensity)	L.F.	7	\$ -	\$ -
53	OM4-3 End of Road Marker (18"x18")(High Intensity)	EA.	13	\$ -	\$ -
54	9" Street Name, Block Number (High Intensity)	EA.	20	\$ -	\$ -
55	W14-1a Dead End Street Marker(36" x 9") (High Intensity)	EA.	1	\$ -	\$ -
56	Bexar County Maintenance Begins/Ends (High Intensity)	EA.	2	\$ -	\$ -
57	R3-17 (Bike Lane)(30" x 24")(High Intensity)	EA.	5	\$ -	\$ -
58	R3-17b (Ends)(30" x 12")(High Intensity)	EA.	1	\$ -	\$ -
59	6 Inch Wide Yellow Line	L.F.	1,034	\$ -	\$ -
60	6 Inch Wide Dashed Yellow Line	L.F.	622	\$ -	\$ -
61	24 Inch Wide White Line	L.F.	28	\$ -	\$ -
62	8 Inch Wide White Line	L.F.	1,369	\$ -	\$ -
63	Right White Arrow	EA.	2	\$ -	\$ -
64	Left White Arrow	EA.	12	\$ -	\$ -
65	Word "Only"	EA.	4	\$ -	\$ -
66	Straight White Arrow Bicycle Facility	EA.	12	\$ -	\$ -
67	Bicycle Rider Symbol	EA.	12	\$ -	\$ -
68	Pavement Marker (Type I)(C)	EA.	8	\$ -	\$ -
69	Pavement Marker (Type II A-A)	EA.	32	\$ -	\$ -
70	Pavement Marker (Type II)(Blue)	EA.	6	\$ -	\$ -
71	Rock Filter Dams (Type II)(Install & Remove)	L.F.	100	\$ -	\$ -
72	Construction Exit (Installation)	S.Y.	167	\$ -	\$ -
73	Construction Exit (Removal)	S.Y.	167	\$ -	\$ -
74	Temporary Sediment Control Fence (Phase I - Sitework)	L.F.	4,536	\$ -	\$ -
75	Temporary Sediment Control Fence (Phase II)	L.F.	6,890	\$ -	\$ -
76	Curb Inlet Gravel Filters	L.F.	740	\$ -	\$ -
				TOTAL COST	\$ -

ROOSEVELT LANDING UNIT 3 BID QUANTITIES

DRAINAGE IMPROVEMENTS (DRAIN A)

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
77	Channel Excavation	C.Y.	20	\$ -	\$ -
78	Concrete Structure (Elevated Sidewalk)	C.Y.	3.9	\$ -	\$ -
79	Concrete Riprap (6" Thick)	S.Y.	92	\$ -	\$ -
80	Sidewalk Pipe Railing	L.F.	11	\$ -	\$ -
81	Rock Gabion Mattress	S.Y.	3.5	\$ -	\$ -
82	Hydromulching	S.Y.	154	\$ -	\$ -
TOTAL COST					# \$ -

DRAINAGE IMPROVEMENTS (DRAIN B)

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
83	Concrete Structure (Baffle Blocks)	C.Y.	0.5	\$ -	\$ -
84	Misc. Concrete Structure (e.g., Aprons, Collars, etc.)	C.Y.	5.0	\$ -	\$ -
85	30" R.C.P. (Class IV)	L.F.	106	\$ -	\$ -
86	36" H.D.P.E. Pipe	L.F.	144	\$ -	\$ -
87	4-Way Inlet (4'x 4')(Complete)	EA.	1	\$ -	\$ -
88	Curb Inlet (Type C)(20')(Complete)	EA.	1	\$ -	\$ -
89	Rock Gabion Mattress	S.Y.	41.0	\$ -	\$ -
90	Hydromulching	S.Y.	318	\$ -	\$ -
TOTAL COST					# \$ -

DRAINAGE IMPROVEMENTS (INTERCEPTOR DRAIN C)

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
91	Channel Excavation	C.Y.	420	\$ -	\$ -
92	Channel Embankment	C.Y.	300	\$ -	\$ -
93	Hydromulching	S.Y.	1,220	\$ -	\$ -
TOTAL COST					# \$ -

SITE WORK AND ADD ALTERNATES

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
94	Clearing and Grubbing	Ac.	25.2	\$ -	\$ -
95	Lot Excavation	C.Y.	1,722	\$ -	\$ -
96	Lot Embankment	C.Y.	29,254	\$ -	\$ -
97	Import Material	C.Y.	21,885	\$ -	\$ -
98	Conduit Bundle (1-6" PVC & 2-4" PVC)	L.F.	1,140	\$ -	\$ -
99	Conduit Bundle (2-6" PVC & 2-4" PVC)	L.F.	392	\$ -	\$ -
TOTAL COST					\$ -

GRAND TOTAL COST: