

LEGEND

WASHOUT CROWN	
SIDEWALK TO BE BUILT BY DEVELOPER	\otimes
TOP OF PVMT. ELEVATION	940.00
EXISTING STREET LIGHT	•ELP
PROPOSED STREET LIGHT (100 WATT)	۰́C LP
PROPOSED POWER POLE	● PP
PROPOSED FIRE HYDRANT	
EXISTING FIRE HYDRANT	\searrow

GENERAL NOTES

1. All materials and construction procedures within the scope of this project shall, be approved by the City of San Antonio Public Works and comply with the following as applicable:

A. Reference to Current "San Antonio Water System Utility Specifications"

B. Reference to Current City of San Antonio "Standard Specifications for Public Works Construction"

2. The locations and depths of existing utilities, including service laterals, and drainage structures shown on the plans are approximate only The Contractor shall verify the exact location and depths of underground utilities at least 48 hours prior to construction whether shown on plans or not, and to protect the same during construction. Texas State Wide One Call Locator 1-800-545-6005 City Public Service AT&T Time Warner Valero Energy Co.

3. The Contractor shall notify the City prior to the start of each phase of street construction and call for inspections with a minimum of 24 hours

4. Testing will be paid for by Developer, coordinated by Contractor, and witnessed by City

5. Minimum Testing Schedule:

Densities - Subgrade Densities - Base Proctors - Subgrade Proctors - Base Concrete - Structures

required.

1 Per 500 Foot Minimum 1 Per 500 Foot Minimum 1 Per Material Per Subdivision 1 Per 5,000 C.Y. Lime Series - Subgrade 1 Per Material Per Subdivision 1 Set (3) Per 50 C.Y.

6. Transition washout crown to normal crown in 25'.

7. No extra payment shall be allowed for work called for on the plans, but not included in the bid proposal. This incidental work will be required and shall be included in the pay item to which it relates.

8. The contractor shall be responsible for restoring to its original or better condition any damage done to existing fences, concrete islands, street paving, curbs, shrubs, bushes or driveways. (No separate pay item).

9. Due to federal regulations Title 49, Part 192.171 CPS must maintain access to gas valves at all times. The contractor must protect and work around any gas valves that are in the project area.

10. Contractor shall notify the city inspector twenty four (24) hours prior to backfill of any utility trenches to schedule for density test as

11. All waste material shall become property of the contractor and shall be his sole responsibility to dispose of this material off the limits of the project. No waste material shall be placed in existing lows that will block or alter flow limits of existing artificial or natural drainage.

12. The contractor shall not place any waste material in the 100-year flood plain without first obtaining an approved Flood Plain Development Permit.

13. The contractor shall maintain all adjoining streets and traveled routes free from spilled and/or tracked construction materials and/or debris.

14. It is the contractor's responsibility to see that all signs and barricades are properly installed and maintained. All locations and distances will be decided upon in the field by the contractor, using the "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES". The City's construction inspector will only be responsible to inspect barricades and signs. If, in the opinion of the construction inspector, the barricades and signs do not conform to established standards or are incorrectly placed or are insufficient in quantity to protect the general public, the inspector shall have the option to stop operations until such time as the conditions are corrected.

TRENCH EXCAVATION SAFETY PROTECTION

Contractor and/or contractor's independently retained employee or structural design/geotechnical/safety/equipment consultant, if any, shall. review these plans and available geotechnical information and the anticipated installation site(s) within the project work area in order to implement Contractor's trench excavation safety protection systems, programs and/or procedures. The Contractor's implementation of the systems, programs and/or procedures shall provide for adequate trench excavation, safety protection that complies with as a minimum, OSHA standards for trench excavations. Specifically, Contractor and/or Contractor's independently retained employee or safety consultant shall implement a trench safety program in accordance with OSHA standards governing the presence and activities of individuals working in and around trench excavation.



IF YOU DIG IN TEXAS CALL US FIRST, IT'S THE LAW 1-800-344-8377



CONSTRUCTION PLAN for SA SOUTH BUSINESS PARK

LOCATION MAP SCALE: 1"=100'

> OWNER: SA SOUTH BUSINESS PARK LP 828 MEYER RD KINGSBURY, TEXAS 78638



CIVIL ENGINEERING CONSULTANTS dba. DON DURDEN, INC 11550 IH 10 WEST, SUITE 395 SAN ANTONIO, TEXAS 78230-1037 TEL: (210) 641-9999 FAX: (210) 641-6440 REGISTRATION #F-2214 / #10041000



Sheet List Table

Sheet Number	Sheet Title
100	COVER SHEET
101	EXISTING AND DEMOLITION PLAN
200	UTILITY COVER SHEET
201	OVERALL UTILITY PLAN
300	WATER COVER SHEET
301	OVERALL WATER PLAN
302	WATER DETAILS
303	WATER DETAILS
400	STREET & DRAIN COVER SHEET
401	OVERALL GRADING PLAN
402	STREET NORTH PRO ROAD PLAN & PROFILE
403	STREET EAST PRO ROAD PLAN & PROFILE
404	STREET SOUTH PRO ROAD PLAN & PROFILE
405	DETENTION POND PLAN
406	CHANNEL 'A' PLAN & PROFILE
407	CHANNEL 'B' PLAN & PROFILE
408	DETENTION POND DETAILS - FENCE
409	STREET DETAILS
410	STREET DETAILS
411	SIGNAGE PLAN
412	SIGNAGE DETAILS
500	SEDIMENTATION & EROSION COVER SHEET
501	SEDIMENTATION & EROSION CONTROL PLAN
502	SEDIMENTATION & EROSION CONTROL DETAIL
503	SEDIMENTATION & EROSION CONTROL DETAIL





UTILITY CONSTRUCTION PLAN for SA SOUTH BUSINESS PARK

<u>NOTE:</u>

- 1. 6" P.V.C. SCHEDULE 80 CONDUIT WILL BE REQUIRED FOR C.P.S. UTILITY CROSSING FROM ROW TO ROW AT A DEPTH OF 36" BELOW FINAL GRADE, WHEN STREET OR DRAIN CONSTRUCTION PRECEDES UTILITY INSTALLATION.
- 2. 4" P.V.C. SCHEDULE 40 CONDUIT WILL BE REQUIRED FOR UNDERGROUND TELEPHONE AND CABLE T.V. FROM ROW TO ROW AT A DEPTH OF 36" BELOW FINAL GRADE, WHEN STREET OR DRAIN CONSTRUCTION PRECEDES UTILITY INSTALLATION.
- 3. P.V.C. CONDUIT SHALL HAVE 90° SWEEPS/BENDS TO 6" ABOVE GRADE WITH CAP. IF CONDUIT IS NOT INSTALLED 6" ABOVE FINAL GRADE IT SHALL BE CONTRACTORS RESPONSIBILITY TO UNDERCOVER CONDUIT ENDS FOR EACH UTILITY PROVIDER AS NECESSARY.
- 4. IF OWNER ELECTS TO HAVE DRY UTILITIES INSTALLED PRIOR TO STREET CONSTRUCTION NO CONDUIT FOR CPS & CABLE TV WILL BE INDICATED ON THIS PLAN. IF CONTRACTOR ELECTS TO PROCEED WITH ANY PORTION OF DRAIN CONSTRUCTION PRIOR TO UTILITY INSTALLATION, THEN CONTRACTOR WILL BE REQUIRED TO INSTALL ALL DRY UTILITY CONDUIT REQUIRED AT EACH DRAIN CROSSING AT NO EXTRA PAY.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEETING 98% COMPACTION ON ALL TRENCH BACKFILL AND PAYING FOR THE TESTS TO BE PERFORMED BY A THIRD PARTY. COMPACTION TESTS WILL BE DONE AT ONE LOCATION POINT RANDOMLY SELECTED OR AS INDICATED BY THE SAWS INSPECTOR/TEST ADMINISTER, PER EACH 12-INCH LOOSE LIFT PER 400 LINEAR FEET AT A MINIMUM. THIS PROJECT WILL NOT BE ACCEPTED AND FINALIZED BY SAWS WITHOUT THIS REQUIREMENT BEING MET AND VERIFIED BY PROVIDING ALL NECESSARY DOCUMENTED TEST RESULTS.



NOT TO SCALE

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL. REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF THE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION, SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.



She	et List Table
Sheet No.	Sheet Title
200	UTILITY COVER SHEET
201	OVERALL UTILITY PLAN

LEGEND

EXISTING LIGHT POLE	þ
EXISTING OVERHEAD ELECTRIC	от
EXISTING WATER MAIN	Wx
EXISTING FIRE HYDRANT	7
EXISTING GAS LINE	Gx
EXISTING GAS LINE SIGN	-o-
PROPOSED WATER MAIN	
PROPOSED LIGHT POLE (RELOCATION)	•
PROPOSED FIRE HYDRANT	X
PROPOSED LIGHT POST	¢
PROPOSED POWER POLE	PP

OWNER: SA SOUTH BUSINESS PARK LP 828 MEYER RD KINGSBURY, TEXAS 78638



CIVIL ENGINEERING CONSULTANTS dba. DON DURDEN, INC 11550 IH 10 WEST, SUITE 395 SAN ANTONIO, TEXAS 78230-1037 TEL: (210) 641-9999 FAX: (210) 641-6440 REGISTRATION #F-2214 / #10041000



TRENCH EXCAVATION SAFETY PROTECTION CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/ EQUIPMENT CONSULTANT, IF ANY, SHALL. REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF THE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION, SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND

- TELEPHONE AND CABLE T.V. FROM ROW TO ROW AT A DEPTH OF 36" BELOW FINAL GRADE, WHEN STREET OR DRAIN CONSTRUCTION PRECEDES UTILITY
- CAP. IF CONDUIT IS NOT INSTALLED 6" ABOVE FINAL GRADE IT SHALL BE CONTRACTORS RESPONSIBILITY TO UNDERCOVER CONDUIT ENDS FOR
- DRAIN CONSTRUCTION PRIOR TO UTILITY INSTALLATION, THEN



WATERLINE CONSTRUCTION PLAN SA SOUTH BUSINESS PARK

SAWS CONSTRUCTION NOTES Revised July 2017

General Section Notes

1. All materials and construction procedures within the scope of this contract shall be approved by the San Antonio Water System (SAWS) and comply with the Plans, Specifications, General Conditions and with the following as applicable:

- A. Current Texas Commission on Environmental Quality (TCEQ) "Design Criteria for Domestic Wastewater System", Texas
- Administrative Code (TAC) Title 30 Part 1 Chapter 217 and "Public Drinking Water", TAC Title 30 Part 1 Chapter 290. B. Current TXDOT "Standard Specifications for Construction of Highways, Streets and Drainage".
- C. Current "San Antonio Water System Standard Specifications for Water and Sanitary Sewer Construction" D. Current City of San Antonio "Standard Specifications for Public Works Construction".
- E. Current City of San Antonio "Utility Excavation Criteria Manual" (UECM).

2. The contractor shall not proceed with any pipe installation work until they obtain a copy of the approved Counter Permit or General Construction Permit (GCP) from the consultant and has been notified by SAWS Construction Inspection Division to proceed with the work and has arranged a meeting with the inspector and consultant for the work requirements. Work completed by the contractor without an approved Counter Permit and/or a GCP will be subject to removal and replacement at the expense of the contractors and/or the developer.

3. The Contractor shall obtain the SAWS Standard Details from the SAWS website, http://www.saws.org/business_center/specs. Unless otherwise noted within the design plans

4. The Contractor is to make arrangements with the SAWS Construction Inspection Division at (210) 233-2973, on notification procedures that will be used to notify affected home residents and/or property owners 48 hours prior to beginning any work.

5. Location and depth of existing utilities and service laterals shown on the plans are understood to be approximate. Actual locations and depths must be field verified by the Contractor at least 1 week prior to construction. It shall be the Contractor's responsibility to locate utility service lines as required for construction and to protect them during construction at no cost to SAWS.

6. The Contractor shall verify the exact location of underground utilities and drainage structures at least 1-2 weeks prior to construction whether shown on plans or not. Please allow up to 7 business days for locates requesting pipe location markers on SAWS facilities. The following contact information are supplied for verification purposes:

- SAWS Utility Locates: http://www.saws.org/Service/Locates
- COSA Drainage (210) 207-0724 or (210) 207-6026
- COSA Traffic Signal Operations (210) 206-8480 - COSA Traffic Signal Damages (210) 207-3951
- Texas State Wide One Call Locator 1-800-545-6005 or 811

7. The Contractor shall be responsible for restoring existing fences, curbs, streets, driveways, sidewalks, landscaping and structures to its original or better condition if damages are made as a result of the project's construction.

8. All work in Texas Department of Transportation (TxDOT) and/or Bexar County right-of-way shall be done in accordance with respective construction specifications and permit requirements.

9. The Contractor shall comply with City of San Antonio or other governing municipality's tree ordinances when excavating near trees. 10. The Contractor shall not place any waste materials in the 100-year Flood Plain without first obtaining an approved Flood Plain

11. Holiday Work: Contractors will not be allowed to perform SAWS work on SAWS recognized holidays. Request should be sent to

constworkreq@saws.org.

Weekend Work: Contractors are required to notify the SAWS Inspection Construction Department 48 hours in advance to request weekend work. Request should be sent to constworkreq@saws.org.

Any and all SAWS utility work installed without holiday/weekend approval will be subject to be uncovered for proper inspection.

12. Compaction note (Item 804): The contractor shall be responsible for meeting the compaction requirements on all trench backfill and for paying for the tests performed by a third party. Compaction tests will be done at one location point randomly selected, or as indicated by the SAWS Inspector and/or the test administrator, per each 12-inch loose lift per 400 linear feet at a minimum. This project will not be accepted and finalized by SAWS without this requirement being met and verified by providing all necessary documented test results.

13. A copy of all testing reports shall be forwarded to SAWS Construction Inspection Division.

Water Notes

1. Prior to tie-ins, any shutdowns of existing mains of any size must be coordinated with the SAWS Construction Inspection Division at least one week in advance of the shutdown. The Contractor must also provide a sequence of work as related to the tie-ins; this is at no additional cost to SAWS or the project and it is the responsibility of the Contractor to sequence the work accordingly.

For water mains 12" or higher: SAWS Emergency Operations Center (210) 233-2014

2. Asbestos Cement (AC) pipe, also known as transite pipe which is known to contain asbestos-containing material (ACM), may be located within the project limits. Special waste management procedures and health and safety requirements will be applicable when removal and/or disturbance of this pipe occurs. Such work is to be made under Special Specification Item No. 3000, "Special Specification for Handling Asbestos Cement Pipe".

3. Valve removal: Where the contractor is to abandon a water main, the control valve located on the abandoning branch will be removed and replaced with a cap/plug. (NSPI)

4. Suitable anchorage/thrust blocking or joint restraint shall be provided at all of the following main locations: dead ends, plugs, caps, tees, crosses, valves, and bends, in accordance with the Standard Drawings DD-839 Series and Item No. 839, in the SAWS Standard Specifications for Construction.

5. All valves shall read "open right".

6. PRVs Required: Contractor to verify that no portion of the tract is below ground elevation of 1215 feet where the static pressure will normally exceed 80 PSI. At all such locations where the ground level is below 1215 feet, the Developer or Builder shall install at each lot, on the customer's side of the meter, an approved type pressure regulator in conformance with the Plumbing Code of the City of San Antonio. No dual services allowed for any lot(s) if *PRV is/are required for such lot(s), only single service connections shall be allowed. *Note: A pressure regulator is also known as a pressure reducing valve (PRV).

7. Pipe Disinfection with Dry HTH for Projects less than 800 linear feet. (Item No. 847.3): Mains shall be disinfected with dry HTH where shown in the contract documents or as directed by the Inspector, and shall not exceed a total length of 800 feet. This method of disinfection will also be followed for main repairs. The Contractor shall utilize all appropriate safety measure to protect his personnel during disinfection operations.

8. Backflow Prevention Devices:

All irrigation services within residential areas are required to have backflow prevention devices.

All commercial backflow prevention devices must be approved by SAWS prior to installation.

9. Final connection to the existing water main shall not be made until the water main has been pressure tested, chlorinated, and SAWS has released the main for tie-in and use.

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL. REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF THE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION, SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS, SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

RESIDENTIAL FIRE FLOW:

THE PUBLIC WATER MAIN SYSTEM HAS BEEN DESIGNED FOR A MINIMUM FIRE FLOW DEMAND OF 1500 GPM AT 25 PSI RESIDUAL PRESSURE. THE FIRE FLOW REQUIREMENTS FOR INDIVIDUAL STRUCTURES WILL BE REVIEWED DURING THE BUILDING PERMIT PROCESS IN ACCORDANCE WITH THE PROCEDURES SET FORTH BY THE CITY OF SAN ANTONIO DIRECTOR OF DEVELOPMENT SERVICES AND THE SAN ANTONIO FIRE DEPARTMENT FIRE MARSHAL.

SIDEWALK NOTE: SIDEWALKS AND FIRE HYDRANTS SHALL BE INSTALLED PER CITY OF SAN ANTONIO STANDARD SPECIFICATIONS FOR CONSTRUCTION AND SAWS STANDARD SPECIFICATIONS FOR CONSTRUCTION.

1) SAWS REQUIRES GCPs AND COUNTER PERMITS TO USE LEAD FREE (<0.25% LEAD) FIRE HYDRANTS.

- 2) ANCHORAGE/THRUST BLOCKING AND JOINT RESTRAINTS SHALL BE DONE IN ACCORDANCE WITH SAWS STANDARD SPECIFICATIONS FOR CONSTRUCTION. (ITEM NO. 839)
- 3) ALL 8" PVC WATER PIPE BEING USED FOR THIS PROJECT IS C-900, CLASS 235 (DR-18).
- OF INGRESS AND EGRESS ACROSS GRANTOR'S ADJACENT PROPERTY TO ACCESS THE WATER AND/OR WASTEWATER EASEMENTS SHOWN.



NOT TO SCALE



Sheet	Sheet List Table			
Sheet Number	Sheet Title			
300	WATER COVER SHEET			
301	OVERALL WATER PLAN			
302	WATER DETAILS			

303

WATER DETAILS

4) THE SAN ANTONIO WATER SYSTEM IS HEREBY GRANTED THE RIGHT



OWNER: SA SOUTH BUSINESS PARK LP 828 MEYER RD KINGSBURY, TEXAS 78638

CIVIL ENGINEERING CONSULTANTS dba. DON DURDEN, INC. 11550 IH 10 WEST, SUITE 395 SAN ANTONIO, TEXAS 78230-1037 TEL: (210) 641-9999 FAX: (210) 641-6440 REGISTRATION #F-2214 / #10041000

WATER	QUANTITIES

	Onsite Water		
Item No:	Description	Unit	Quantity
550.0	Trench Protection	L.F.	2361
818.0	8" Pipe, P.V.C. C-900, Class 235 (DR-18)	L.F.	2361
834.1	Standard Fire Hydrant	EA.	6
836.0	D.I. MJ Compact Fittings (C153)	TON	1.4
840.0	8" PVC Water Tie-In To Existing 8" PVC	EA.	2
841.0	Hydrostatic Test	EA.	1
844.0	2" Blowoff (Temporary)	EA.	2
847.0	Disenfection	EA.	1

LEGEND

EXISTING WATER MAIN
PROPOSED WATER MAIN
PROPOSED LIGHT POLE (100 WATT LED)
PROPOSED POWER POLE
PROPOSED FIRE HYDRANT



— — — F8"PVC — — —

]	
THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY, JESSE F. CANTU II, P.E. NO. *93639 ON. 10/12/2022 DATE						
REV DATE DESCRIPTION						
SHE	TT		80)()	

TANTS INC E 395 0-1037

ENGINEERING CONSULT, D O N D U R D E N, I 0 IH 10 WEST, SUITE ANTONIO, TEXAS 78230-TEL: (210) 641-9999 FAX: (210) 641-6440 STRATION #F-2214 / #100

. • ¥

CIVIL d b a 1155 SAN

PRESSURE ZONE: 790
Developer's Name <u>PALACE WAY MANAGEMENT, LLC</u> Developer's Address 6531 FOX RUN
City SAN ANTONIO State TEXAS Zip 78233
Phone #(210) 210.413.7230 Fax #()
SAWS Block Map# <u>140534</u> Total EDU's <u>0</u> Total Acreage <u>27.94 AC</u>
Total Linear Footage of Pipe:8": 2,370 LF Plat NoPLAT No. 22-11800197
Number of Lots:16 SAWS JOB NOXXXX
ALL WATER PIPE TO BE C-900, CLASS 235 (DR-18)

UNLESS OTHERWISE NOTED





UNLESS OTHERWISE NOTED

302

NOTES:	
 SAWS REQUIRES GCPs AND COUN FIRE HYDRANTS. 	NTER PERMITS TO USE LEAD FREE (<0.25% LEAD)
 ANCHORAGE/THRUST BLOCKING ACCORDANCE WITH SAWS STANE NO. 839) 	AND JOINT RESTRAINTS SHALL BE DONE IN DARD SPECIFICATIONS FOR CONSTRUCTION. (ITE
3. THE SAN ANTONIO WATER SYSTE AND EGRESS ACROSS GRANTOR' AND/OR WASTEWATER EASEMEN	M IS HEREBY GRANTED THE RIGHT OF INGRESS S ADJACENT PROPERTY TO ACCESS THE WATER TS SHOWN.

	LEC.	5	LC	CCUC/01	770701	E0685501
	NFD RY.		'N BY:			0.: E
	DESIG		DRAW	DATE.		JOB N
		SULTANTS	JITE 395	199 40	#1004100	
			/EST, SL TEXAS 79	0) 641-99 0) 641-99	#F-2214 / #	
		ENGINEER D O N D		TEL: (21 FAX: (21	TRATION #	
		CIVIL d b a.	11550 SAN A		REGIS	
) T	
	┝		EO	F TE	\ } ⊬ },	
	hinis	JESSI PROT	E F. 930	CANT 639 NSED		
		SEA		PPE	ARII	NG
	ON THIS DOCUMENT WAS AUTHORIZED BY: JESSE F. CANTU II, P.E. NO. #93639				BYı P.E.	
	ONI 10/12/2022 DATE					
	DESCRIPTION					
	DATE					
	REV					
		ARK XX				
S TO USE LEAD FREE (<0.25% LEAD)		S D		U	Ŋ	
GRANTED THE RIGHT OF INGRESS PROPERTY TO ACCESS THE WATER		С Ш П		TAI		
		NIS N				
		H BC				
	!			\sim	>	
790 , LLC		SO				
Zip <u>78233</u>) 0 Total Acreage <u>27.94</u> AC		SA				
Plat No. PLAT No. 22-11800197	SHEE	T NO.				

303

PRESSURE ZONE: 790
Developer's Name PALACE WAY MANAGEMENT, LLC
Developer's Address 6531 FOX RUN City SAN ANTONIO State TEXAS Zip 78233
Phone #(210) 210.413.7230 Fax #()
AWS Block Map# <u>140534</u> Total EDU's <u>0</u> Total Acreage <u>27.94 AC</u> Total Linear Footage of Pipe: <u>8": 2,370 LF</u> Plat No. <u>PLAT No. 22-11800197</u>
lumber of Lots:16 SAWS JOB NOXXXX
ALL WATER PIPE TO BE C-900, CLASS 235 (DR-18)

UNLESS OTHERWISE NOTED

STREET & DRAIN CONSTRUCTION PLANS for SA SOUTH BUSINESS PARK

GENERAL NOTES

1. All materials and construction procedures within the scope of this project shall, be approved by the City of San Antonio Public Works and comply with the following as applicable: A. Reference to Current "San Antonio Water System Utility Specifications"

B. Reference to Current City of San Antonio "Standard Specifications for Public Works Construction"

2. The locations and depths of existing utilities, including service laterals, and drainage structures shown on the plans are approximate only The Contractor shall verify the exact location and depths of underground utilities at least 48 hours prior to construction whether shown on plans or not, and to protect the same during construction. Texas State Wide One Call Locator 1-800-545-6005 City Public Service AT&T Time Warner Valero Energy Co.

3. The Contractor shall notify the City prior to the start of each phase of street construction and call for inspections with a minimum of 24 hours notice.

4. Testing will be paid for by Developer, coordinated by Contractor, and witnessed by City

5. Minimum Testing Schedule:	
Densities - Subgrade	1 Per 500 Foot Minimum
Densities - Base	1 Per 500 Foot Minimum
Proctors - Subgrade	1 Per Material Per Subdivisio
Proctors - Base	1 Per 5,000 C.Y.
Lime Series - Subgrade	1 Per Material Per Subdivision
Concrete - Structures	1 Set (3) Per 50 C.Y.

6. Transition washout crown to normal crown in 25'.

7. No extra payment shall be allowed for work called for on the plans, but not included in the bid proposal. This incidental work will be required and shall be included in the pay item to which it relates.

8. The contractor shall be responsible for restoring to its original or better condition any damage done to existing fences, concrete islands, street paving, curbs, shrubs, bushes or driveways. (No separate pay item).

9. Due to federal regulations Title 49, Part 192.171 CPS must maintain access to gas valves at all times. The contractor must protect and work around any gas valves that are in the project area.

10. Contractor shall notify the city inspector twenty four (24) hours prior to backfill of any utility trenches to schedule for density test as required.

11. All waste material shall become property of the contractor and shall be his sole responsibility to dispose of this material off the limits of the project. No waste material shall be placed in existing lows that will block or alter flow limits of existing artificial or natural drainage.

12. The contractor shall not place any waste material in the 100-year flood plain without first obtaining an approved Flood Plain Development Permit.

13. The contractor shall maintain all adjoining streets and traveled routes free from spilled and/or tracked construction materials and/or debris. 14. It is the contractor's responsibility to see that all signs and barricades are properly installed and maintained. All locations and distances will be decided upon in the field by the contractor, using the "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES". The City's construction inspector will only be responsible to inspect barricades and signs. If, in the opinion of the construction inspector, the barricades and signs do not conform to established standards or are incorrectly placed or are insufficient in quantity to protect the general public, the inspector shall have the option to stop operations until such time as the conditions are corrected.

IF YOU DIG IN TEXAS CALL US FIRST, IT'S THE LAW 1-800-344-8377

			T		_
N r	ιροτ	ICT	12	n	$ \mathbf{O} $
J		IJL.	IU	N	ľ

Sheet No.	Sheet Title
400	STREET & DRAIN COVER SHEET
401	OVERALL GRADING PLAN
402	STREET NORTH PRO ROAD PLAN & PROFILE
403	STREET EAST PRO ROAD PLAN & PROFILE
404	STREET SOUTH PRO ROAD PLAN & PROFILE
405	DETENTION POND PLAN
406	CHANNEL 'A' PLAN & PROFILE
407	CHANNEL 'B' PLAN & PROFILE
408	DETENTION POND DETAILS - FENCE
409	STREET DETAILS
410	STREET DETAILS
411	SIGNAGE PLAN
412	SIGNAGE DETAILS

OWNER: SA SOUTH BUSINESS PARK LP 828 MEYER RD

KINGSBURY, TEXAS 78638

CIVIL ENGINEERING CONSULTANTS dba. DON DURDEN, INC. 11550 IH 10 WEST, SUITE 395 SAN ANTONIO, TEXAS 78230-1037 TEL: (210) 641-9999 FAX: (210) 641-6440 REGISTRATION #F-2214 / #10041000

F	പ	F	NI	D
			I N	

WASHOUT CROWN	
SIDEWALK TO BE BUILT BY DEVELOPER	\otimes
TOP OF PVMT. ELEVATION	9
EXISTING STREET LIGHT	
PROPOSED STREET LIGHT (100 WATT)	-
PROPOSED POWER POLE	(
PROPOSED FIRE HYDRANT	
EXISTING FIRE HYDRANT	

TRENCH EXCAVATION SAFETY PROTECTION Contractor and/or contractor's independently retained employee or structural design/geotechnical/safety/equipment consultant, if any, shall. review these plans and available geotechnical information and the anticipated installation site(s) within the project work area in order to implement Contractor's trench excavation safety protection systems, programs and/or procedures. The

Contractor's implementation of the systems, programs and/or procedures shall provide for adequate trench excavation, safety protection that complies with as a minimum, OSHA standards for trench excavations. Specifically, Contractor and/or Contractor's independently retained employee or safety consultant shall implement a trench safety program in accordance with OSHA standards governing the presence and activities of individuals working in and around trench excavation.

	DESIGNED BY: JFC		DRAWN BY: LC		DATE: 10/2022		JOB NO.: E0685501			
CIVIL ENGINEERING CONSULTANTS d b a. D O N D U R D E N, I N C. 11550 IH 10 WEST, SUITE 395 SAN ANTONIO, TEXAS 78230-1037 TEL: (210) 641-9999 FAX: (210) 641-6440 REGISTRATION #F-2214 / #10041000 JOB 1										
JESSE F. CANTU II 93639 CENSE CENSE THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY, JESSE F. CANTU II, P.E. NO. *93639 ON. 10/12/2022 DATE										
REV DATE DESCRIPTION										
RE						COVER SHEEL				
SHE	ETI	чо. 4)()					

Line Table							
Line Length Direction							
L1	679.33'	S01°39'48"E					
L2	5.36'	N88°20'12"E					
L3	25.46'	S01°39'48"E					

34+00		35+00		36+00		37+00		38+00		39+00	
590.30 589.1(590.45 589.4	. 590.62 589.6(590.81 589.9	590.86 590.16	590.84 590.4	590.66	591.14 590.9	591.54 591.10	591.31 591.4	591.12 591.66	590.79 . 591.4
	·		·		•						•
•	•		•	•	•	•	•	•	•	•	•

DETENTION	POND ELE
C	DISCHARGE
ELEVATION	STORAGE
578.10	0
579.00	9583
580.00	35284
581.00	8102
581.60	11804
582.00	13895
582.60	17206
582.90	18774
583.00	19645

SEDIMENTATION & EROSION CONTROL PLANS for SA SOUTH BUSINESS PARK

GENERAL NOTES

1. All materials and construction procedures within the scope of this project shall, be approved by the City of San Antonio Public Works and comply with the following as applicable: A. Reference to Current "San Antonio Water System Utility Specifications"

B. Reference to Current City of San Antonio "Standard Specifications for Public Works Construction"

2. The locations and depths of existing utilities, including service laterals, and drainage structures shown on the plans are approximate only. The Contractor shall verify the exact location and depths of underground utilities at least 48 hours prior to construction whether shown on plans or not, and to protect the same during construction. Texas State Wide One Call Locator 1-800-545-6005 City Public Service AT&T Time Warner Valero Energy Co.

3. The Contractor shall notify the City prior to the start of each phase of street construction and call for inspections with a minimum of 24 hours notice.

4. Testing will be paid for by Developer, coordinated by Contractor, and witnessed by City.

5. Minimum Testing Schedule: Densities - Subgrade

Densities - Base

Proctors - Base

Proctors - Subgrade

1 Per 500 Foot Minimum 1 Per 500 Foot Minimum 1 Per Material Per Subdivision 1 Per 5,000 C.Y. Lime Series - Subgrade 1 Per Material Per Subdivision Concrete - Structures 1 Set (3) Per 50 C.Y.

6. Transition washout crown to normal crown in 25'.

7. No extra payment shall be allowed for work called for on the plans, but not included in the bid proposal. This incidental work will be required and shall be included in the pay item to which it relates.

8. The contractor shall be responsible for restoring to its original or better condition any damage done to existing fences, concrete islands, street paving, curbs, shrubs, bushes or driveways. (No separate pay item).

9. Due to federal regulations Title 49, Part 192.171 CPS must maintain access to gas valves at all times. The contractor must protect and work around any gas valves that are in the project area.

10. Contractor shall notify the city inspector twenty four (24) hours prior to backfill of any utility trenches to schedule for density test as required.

11. All waste material shall become property of the contractor and shall be his sole responsibility to dispose of this material off the limits of the project. No waste material shall be placed in existing lows that will block or alter flow limits of existing artificial or natural drainage.

12. The contractor shall not place any waste material in the 100-year flood plain without first obtaining an approved Flood Plain Development Permit.

13. The contractor shall maintain all adjoining streets and traveled routes free from spilled and/or tracked construction materials and/or debris.

14. It is the contractor's responsibility to see that all signs and barricades are properly installed and maintained. All locations and distances will be decided upon in the field by the contractor, using the "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES". The City's construction inspector will only be responsible to inspect barricades and signs. If, in the opinion of the construction inspector, the barricades and signs do not conform to established standards or are incorrectly placed or are insufficient in quantity to protect the general public, the inspector shall have the option to stop operations until such time as the conditions are corrected.

TRENCH EXCAVATION SAFETY PROTECTION

Contractor and/or contractor's independently retained employee or structural design/geotechnical/safety/equipment consultant, if any, shall. review these plans and available geotechnical information and the anticipated installation site(s) within the project work area in order to implement Contractor's trench excavation safety protection systems, programs and/or procedures. The Contractor's implementation of the systems, programs and/or procedures shall provide for adequate trench excavation, safety protection that complies with as a minimum, OSHA standards for trench excavations. Specifically, Contractor and/or Contractor's independently retained employee or safety consultant shall implement a trench safety program in accordance with OSHA standards governing the presence and activities of individuals working in and around trench excavation.

Sheet List Table					
Sheet No.	Sheet Title				
500	SEDIMENTATION & EROSION COVER SHEET				
501	SEDIMENTATION & EROSION CONTROL PLAN				
502	SEDIMENTATION & EROSION CONTROL DETAILS				
503	SEDIMENTATION & EROSION CONTROL DETAILS				

OWNER: SA SOUTH BUSINESS PARK LP 828 MEYER RD KINGSBURY, TEXAS 78638

CIVIL ENGINEERING CONSULTANTS dba. DON DURDEN, INC. 11550 IH 10 WEST, SUITE 395 SAN ANTONIO, TEXAS 78230-1037 TEL: (210) 641-9999 FAX: (210) 641-6440 REGISTRATION #F-2214 / #10041000

	SEDIMENT & EROSION CONTROL		
ITEM NO.	DESCRIPTION	UNIT	QUANTITY
540.1	TEMPORARY ROCK FILTER DAM "TYPE 2"	LF	100
540.6	TYPE I CONSTRUCTION EXIT	EA	1
540.9	SILT CONTROL FENCE (INCLUDES J-HOOKS)	LF	4,010
540.10	GRAVEL FILTER BAGS	LF	50
-	CONCRETE WASHOUT PIT	EA	1

LEGEND

SCF	TEMPORARY SEDIMENT CONTROL FENCE
	TYPE 1 CONSTRUCTION EXIT
	CONCRETE WASHOUT PIT
$\infty \infty \infty$	GRAVEL FILTER BAGS

	DESIGNED BY: JFC		DRAWN BY: LC		DATE: 10/2022		JOB NO.: E0685501
CIVIL ENGINEERING CONSULTANTS d b a. D O N D U R D E N, I N C. 11550 IH 10 W E ST, S UITE 395 SAN ANTONIO, T EXAS 78230-1037 T E L: (210) 641-9999 FAX: (210) 641-6440 REGISTRATION #F-2214 / #10041000 JOB N							
JESSE F. CANTU II 93639 CENSE CENS							
REV DATE DESCRIPTION							
REV							
SHE	500						

SITE DESCRIPTION

PROJECT LIMITS: 27.940 acre unit locate	d south of the intersection of Camerons Way and Palo Alto Road, San Antonio, Texas.
_ATITUDE 29.302651 LONGITUDE -98.55571	0
	of subdivision improvements including: streets water lines and drainage improvements
ROJECT DESCRIPTION. Construction	
	r_{0} Solidicturbing activities will include propering right of way clearing, and grubbing, grading, exceptation and
MAJOR SOIL DISTURBING ACTIVITII	\Box S: Solid disturbing activities will include preparing high-or-way cleaning, and grubbing, grading, excavation and
27.040 AC	
TOTAL PROJECT AREA: 27.940 AC	
	24.59 AC, out of 27.940 AC (88%)
TOTAL AREA TO BE DISTURBED:	
(PRE-CONSTRUCTION)	0.70
WEIGHTED RUNOEE COEFFICIENT	
(POST-CONSTRUCTION):	0.95
· · · · · · · · · · · · · · · · · · ·	
EXISTING CONDITION OF SOIL & VE	EGETATIVE
COVER AND % OF EXISTING VEGET	TATIVE COVER: The existing topsoil is Brayon Clay, Lewis Silty Clay, Tinn and Frio Soils, and Willacy Loam.

NAME OF RECEIVING WATERS: The storm water will flow into the Leon Creek Watershed.

EROSION AND SEDIMENT CONTROLS

SOIL STABILIZATION PRACTICES:	OTHER EROSION AND SEDIMENT CONTROLS:
TEMPORARY SEEDING	MAINTENANCE. All erosion and sediment controls will be maintained in good working order. If a repair is necessary, it will be done at the earliest date possible, but no
PERMANENT PLANTING, SODDING, OR SEEDING	later than 7 calendar days after the surrounding exposed ground has dried sufficiently to prevent further damage from heavy equipment. The areas adjacent to creeks and
MULCHING	drainage ways shall have priority followed by devices protecting storm sewer inlets.
SOIL RETENTION BLANKET	
BUFFER ZONES	
PRESERVATION OF NATURAL RESOURCES	
OTHER: Disturbed areas on which construction activity has ceased (temporarily or permanently) shall be stabilized within 14 days unless activities are scheduled to resume	
and do within 21 days.	INSPECTION An inspection will be performed by a designated inspector every week as well as after every half inch or more of rain (as recorded on a non-freezing rain
	gauge to be located at the Project Site). An inspection and Maintenance Report will be made per each Inspection. Based on the inspection results, the controls shall be
	located at the Project Site). An inspection and Maintenance Report will be made per each
STRUCTURAL PRACTICES:	revised per the inspection report.
HAY BALES	
DIVERSION, INTERCEPTOR, OR PERIMETER DIKES	
DIVERSION, INTERCEPTOR, OR PERIMETER SWALES	WASTE MATERIALS:All waste materials will be collected and stored in a secured metal dumpster. The dumpster will meet all state and local city solid waste
DIVERSION DIKE AND SWALE COMBINATIONS	management regulations. All trash and construction debris from the site will be deposited in the dumpster. The dumpster will be emptied as necessary or as required by local
TIMBER MATTING AT CONSTRUCTION EXIT	
CHANNEL LINERS	
SEDIMENT TRAPS	
SEDIMENT BASINS	
STORM INLET SEDIMENT TRAP	HAZARDOUS WASTE (INCLUDING SPILL REPORTING): <u>At a minimum, any products in the following categories are considered to be hazardous:</u>
STONE OUTLET STRUCTURES	event of a bazardous material spill, the spill coordinator shall be contacted immediately
CURBS AND GUTTERS	
VELOCITY CONTROL DEVICES	
OTHER:	
	SANITARY WASTE: All samilary waste will be collected from portable units as necessary, or as required by local regulations by a Licensed Samilary waste
NARRATIVE - SEQUENCE OF CONSTRUCTION (STORM WATER MANAGEMENT) ACTIVITIES	
The order of activities will be as follows:	
1. Install temporary control, establish limits of construction, install silt fence,	
construction entrance/exit, and concrete wash out area.	
2. Clear and grub.	OFFSITE VEHICLE TRACKING:
	HAUL ROADS DAMPENED FOR DUST CONTROL
3. Excavate and Embank for Channels/Drains/Pond/Utilities.	LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
	EXCESS DIRT ON ROAD REMOVED DAILY
4. Construct storm drain.	STABILIZED CONSTRUCTION ENTRANCE
5. Install berm controls/BMP's.	
6. Construct water lines.	
7. Construct streets.	
8. Follow up with developer on BMP removal sequence.	REMARKS: Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving
	waters. Disposal areas shall not be located in any wetland, waterbody or streambed. Construction staging areas and vehicle maintenance areas shall be constructed by the
9. When all construction activity is complete and the site is stabilized and approved by the	Contractor in a manner to minimize the runoff of pollutants. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting,
project engineer, remove all temporary structural controls and stabilize areas disturbed	Taisework, pliing, debris or other obstructions placed during construction operations that are not a part of the finished work.
10. The contractor is responsible for implementing and maintaining the storm water pollution	
STORM WATER MANAGEMENT: Storm water drainage will be conveyed by existing drainage structures, storm sewer, and streets.	
	OWNERS CERTIFICATION
	certify under penalty of law that this document and all attachments were prepared under my direction or supervision in
	accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system or these persons directly responsible
of the non-storm water water is from the San Antonio Water System and should have no detrimental effect on the site or downstream from the site.	for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete L and aware that there are significant penalties for submitting false information including the possibility of fine

SIGNATURE

ANTS N C 395 -1037 2 — ш ु NG CONSULT U R D E N, I E S T, S U I T E E X AS 78230 E 41-9999 6 641-6440 641-6440 NNEERING 10 N D U 10 NIO, TE) 10 NIO, TE) 10 NE 10 NE 10 NF 10 NF οĀ CIVIL d b a 1155 SAN 11110 JESSE F. CANTU I 93639 11112 THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY. JESSE F. CANTU II, P.E. NO. **#**93639 ON: 10/12/2022 DATE Ζ ARK 0 S \mathbf{O} S ဟ SINE ∞ Ζ O \supset Ш Η SOU⁻ Ш \leq \square Ш S S HEET NO. 502

y under penalty of law that this document and all attachments were prepared under my direction or supervision in ance with a system designed to assure that qualified personnel properly gathered and evaluated the information tted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

DATE

CONTRACTOR'S CERTIFICATION

I certify under penalty of law that I understand the terms and conditions of the general Texas Pollutant Discharge Elimination System (TPDES) permit that authorizes the storm water discharges associated with industrial activity from the construction site identified as part of this certification plan.

SIGNATURE (CONTRACTOR)

DATE

Figure 1-26 Schematic of a Silt Fence Installation (NCTCOG, 1993b)

GENERAL NOTES:

- 1. Silt fence material should be polypropylene, polyethylene or polyamide woven or nonwoven fabric. The fabric width should be 36 inches, with a minimum unit weight of 4.5 oz/yd, mullen burst strength exceeding 190 lb/in2, ultraviolet stability exceeding 70%, and minimum apparent opening size of U.S. Sieve No. 30.
- 2. Fence posts should be made of hot rolled steel, at least 4 feet long with Tee or Ybar cross section, surface painted or galvanized, minimum nominal weight 1.25 lb/ft2, and Brindell hardness exceeding
- 3. Woven wire backing to support the fabric should be galvanized 2"x 4" welded wire, 12 gauge minimum.
- Installation 1. Steel posts, which support the silt fence, should be installed on a slight angle toward the anticipated runoff source. Post must be embedded a minimum of 1-foot deep and spaced not more than 8 feet on center. Where water concentrates, the maximum spacing should be 6 feet.
- 2. Lay out fencing down-slope of disturbed area, following the contour as closely as possible. The fence should be sited so that the maximum drainage area is $\frac{1}{4}$ acre/100 feet of fence.
- 3. The toe of the silt fence should be trenched in with a spade or mechanical trencher, so that the down-slope face of the trench is flat and perpendicular to the line of flow. Where fence cannot be trenched in (e.g., pavement or rock outcrop), weight fabric flap with 3 inches of pea gravel on uphill side to prevent flow from seeping under fence.
- 4. The trench must be a minimum of 6 inches deep and 6 inches wide to allow for the silt fence fabric to be laid in the ground and backfilled with compacted material.
- 5. Silt fence should be securely fastened to each steel support post or to woven wire, which is in turn attached to the steel fence post. There should be a 3-foot overlap, securely fastened where ends of fabric meet
- 6. Silt fence should be removed when the site is completely stabilized so as not to block or impede storm flow or drainage.

.4.6 High Service Rock Berms

A high service rock berm should be designated in areas of important environmental significance such as in steep canyons or above permanent springs, pools, recharge features, or other environmentally sensitive areas that may require a higher level of protection. This type of sediment barrier combines the characteristics of a silt fence and a rock berm to provide a substantial level of sediment reduction and a sturdy enough barrier to withstand higher flows. The drainage area to this device should not exceed 5 acres and the slope should be less than 30%.

Figure 1-29 Schematic Diagram of High Service Rock Berm (LCRA, 1998)

- 1. Silt fence material should be polypropylene, polyethylene or polyamide woven or nonwoven fabric. The fabric width should be 36 inches, with a minimum unit weight of 4.5 oz/yd, mullen burst strength exceeding 190 lb/in2, ultraviolet stability exceeding 70%, and minimum apparent opening size of U.S. Sieve No. 30.
- 2. Fence posts should be made of hot rolled steel, at least 4 feet long with Tee or Ybar cross section, surface painted or galvanized, minimum nominal weight 1.25 lb/ft2, and Brindell hardness exceeding 140. Rebar (either #5 or #6) may also be used to anchor the berm. 3. Woven wire backing to support the fabric should be galvanized 2"x 4"
- welded wire, 12 gauge minimum. 4. The berm structure should be secured with a woven wire sheathing
- having maximum opening of 1 inch and a minimum wire diameter of 20 gauge galvanized and should be secured with shoat rings. Clean, open graded 3- to 5-inch diameter rock should be used,
- except in areas where high velocities or large volumes of flow are expected, where 5- to 8-inch diameter rocks may be used. Installation:
- Lay out the woven wire sheathing perpendicular to the flow line. The sheathing should be 20 gauge woven wire mesh with 1- inch openings. Install the silt fence along the center of the proposed berm
- placement, as with a normal silt fence described in Section 2.4.3. Place the rock along the sheathing on both sides of the silt fence as shown in the diagram (Figure 1-29), to a height not less than 24inches. Clean, open graded 3 - 5" diameter rock should be used,
- except in areas where high velocities or large volumes of flow are expected, where 5- to 8- inch diameter rock may be used. 4. Wrap the wire sheathing around the rock and secure with tie wire so
- that the ends of the sheathing overlap at least 2 inches, and the berm retains its shape when walked upon. 5. The high service rock berm should be removed when the site is
- revegetated or otherwise stabilized or it may remain in place as a permanent BMP if drainage is adequate.

HIGH SERVICE ROCK BERM

- 1. The aggregate should consist of 4 to 8 inch washed stone over a stable foundation as specified in the plan
- 2. The aggregate should be placed with a minimum thickness of 8 inches. 3. The geotextile fabric should be designed specifically for use as a soil filtration media with an approximate weight of 6 oz/yd2, a mullen burst rating of 140 lb/in2, and an equivalent opening size greater than a number 50 sieve.
- 4. If a washing facility is required, a level area with a minimum of 4 inch diameter washed stone or commercial rack should be included in the plans. Divert wastewater to a sediment trap or basin.
- Installation: 1. Avoid curves on public roads and steep slopes. Remove vegetation and other objectionable material from the foundation area. Grade crown foundation for positive drainage.
- 2. The minimum width of the entrance/exit should be 12 feet or the full width of exit roadway, whichever is greater.
- 3. The construction entrance should be at least 50 feet long. 4. If the slope toward the road exceeds 2%, construct a ridge, 6 to 8 inches
- high with 3:1 (H:V) side slopes, across the foundation approximately 15 feet from the entrance to divert runoff away from the public road. 5. Place geotextile fabric and grade foundation to improve stability, especially where wet conditions are anticipated.
- 6. Place stone to dimensions and grade shown on plans. Leave surface smooth and slope for drainage.
- 7. Divert all surface runoff and drainage from the stone pad to a sediment trap or basin.
- 8. Install pipe under pad as needed to maintain proper public road drainage. Washing: When necessary, wheels shall be cleaned to remove sediment prior to entrance onto public roadway, when washing is required, it shall be done on an area stabilized basin. all sediment shall be prevented from entering
- any storm drain, ditch, or watercourse using approved methods. Maintenance: The entrance shall be maintained in a condition which will prevent tracking or flowing of sediment onto public roadways. This may require periodic top dressing with additional stone as conditions demand, and repair and/or cleanout of any measures used to trap sediment. All sediment spilled, dropped, washed or tracked onto public roadway must be removed immediately.

CONSTRUCTION EXIT

Figure 1-28 Schematic Diagram of a Rock Berm (NCTCOG, 1993)

- 1. The berm structure should be secured with a woven wire sheathing having maximum opening of 1 inch and a minimum wire diameter of 20 gauge galvanized and should be secured with shoat rings.
- Clean, open graded 3- to 5-inch diameter rock should be used, except in areas where high velocities or large volumes of flow are expected, where 5- to 8-inch diameter rocks may be used.
- Installation: 1. Lay out the woven wire sheathing perpendicular to the flow line. The sheathing should be 20 gauge woven wire mesh with 1 inch openings. Berm should have a top width of 2 feet minimum with side
- slopes being 2:1 (H:V) or flatter.
- 3. Place the rock along the sheathing as shown in the diagram (Figure 1-28), to a height not less than 18". 4. Wrap the wire sheathing around the rock and secure with tie
- wire so that the ends of the sheathing overlap at least 2 inches, and the berm retains its shape when walked upon. 5. Berm should be built along the contour at zero percent grade
- or as near as possible. 6. The ends of the berm should be tied into existing upslope
- grade and the berm should be buried in a trench approximately 3 to 4 inches deep to prevent failure of the control.

ROCK BERM

FOR EROSION AND SEDIMENT CONTROL OVER THE EDWARDS AQUIFER CONTRIBUTING ZONE. THE RESPECTIVE BMP DETAILS HAVE BEEN SHOWN ON THIS SHEET AND SW1. THE DETAILS ARE EXCERPTS FROM THE EDWARDS AQUIFER TECHNICAL GUIDANCE MANUAL; RG-348, JULY 2005.

REFER TO THE EROSION CONTROL PLAN (SW1), FOR USE LOCATIONS / PARAMETERS OF THE DETAILS SHOWN IN THE PLAN SET.

Figure 1-24 Schematic of Temporary Construction Entrance/Exit (after NC, 1993)

Figure 1-25 Cross-section of a Construction Entrance/Exit (NC, 1993)

GENERAL NOTES:

INLET PROTECTION (GRAVEL FILTER BAGS)