

LANDON RIDGE SPECIAL IMPROVEMENT DISTRICT
BID TAB - SH 211 & LANDON RIDGE ROADWAY AND TRAFFIC SIGNAL IMPROVEMENTS

PROJECT	BID TAB - SH 211 & LANDON RIDGE ROADWAY AND TRAFFIC SIGNAL IMPROVEMENTS				DATE	24-May-24
NAME:	LANDON RIDGE SPECIAL IMPROVEMENT DISTRICT				JOB NO.	23007667A
CLIENT:	COLLIERS ENGINEERING & DESIGN					
ENGINEER:						
ITEM NO.	DESC. NO.	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
100	6002	PREPARING RIGHT OF WAY	STA	22	\$	-
110	6001	EXCAVATION (ROADWAY AND MILL)	CY	8,242	\$	-
110	6002	EXCAVATION (CHANNEL)	CY	2,550	\$	-
132	6003	EMBANKMENT (FINAL) (ORD COMP) (TY B) (NET FILL AFTER EXCAVATION)	CY	2,250	\$	-
160	6003	FURNISHING & PLACING TOPSOILS (4")	SY	10,000	\$	-
247	6467	FL BS (CMP IN PLACE)(TY D GR 1-2 OR 5)6"	SY	12,626	\$	-
260	6043	LIME (HYD. COM OR QK)(SLURRY)	TON	275	\$	-
260	6079	LIME TRT (SUBGRADE)(6")	SY	12,626	\$	-
310	6001	PRIME COAT (MULTI OPTION)	GAL	1,262	\$	-
416	6031	DRILL SHAFT (TRF SIG POLE) (36 IN)	LF	13	\$	-
416	6034	DRILL SHAFT (TRF SIG POLE) (48 IN)	LF	66	\$	-
464	6005	RC PIPE (CL III) (24 IN)	LF	313	\$	-
464	6008	RC PIPE (CL III) (36 IN)	LF	40	\$	-
464	6026	RC PIPE (CL V) (24 IN)	LF	267	\$	-
467	6395	SET (TY II) (24 IN) (RCP) (6:1) (P)	EA	12	\$	-
467	6453	SET (TY II) (36 IN) (RCP) (6:1) (C)	EA	2	\$	-
500	6001	MOBILIZATION	LS	1	\$	-
502	6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	LS	1	\$	-
514	6001	PERM CTB(SGL SLOPE)(TY I)(42)	LF	1,454	\$	-
531	6013	CURB RAMPS (TY 10)	EA	6	\$	-
545	6013	CRASH CUSH ATTEN (INSTL) (R) (N) (TL3)	EA	4	\$	-
618	6046	CONDT (PVC) (SCH 80) (2")	LF	270	\$	-
618	6047	CONDT (PVC) (SCH 80) (2") BORE	LF	490	\$	-
618	6053	CONDT (PVC) (SCH 80) (3")	LF	165	\$	-
618	6054	CONDT (PVC) (SCH 80) (3") BORE	LF	980	\$	-
620	6009	ELEC CONDR (NO. 6) BARE	LF	1,730	\$	-
620	6010	ELEC CONDR (NO. 6) INSULATED	LF	80	\$	-
621	6005	TRAY CABLE (4 CONDR) (12 AWG)	LF	810	\$	-
624	6010	GROUND BOX TY D (162922) W/APRON	EA	4	\$	-
628	6167	ELC SRV TY D 120/240 070(NS)AL(E)TP(O)	EA	1	\$	-
636	6001	ALUMINUM SIGNS (TY A)	SF	191	\$	-
644	6001	IN SM RD SN SUP&AM TY10BWG(1)SA(P)	EA	12	\$	-
644	6004	IN SM RD SN SUP&AM TY10BWG(1)SA(T)	EA	3	\$	-
644	6009	IN SM RD SN SUP&AM TY10BWG(1)SB(P) (MOD PER SAT DIST. STANDARD)	EA	3	\$	-
644	6068	RELOCATE SM RD SN SUP&AM TY 10BWG	EA	7	\$	-
658	6027	INSTL DEL ASSM (D-SY) SZ (BRF) CTB (BI)	EA	15	\$	-
666	6036	REFL PAV MRK TY I (W)8"(SLD)(100 MIL)	LF	2,553	\$	-
666	6048	REFL PM TY I (W)24"(SLD)(100MIL)	LF	547	\$	-
666	6054	REFL PM TY I (W)(ARROW)(100MIL)	EA	21	\$	-
666	6078	REFL PM TY I (W)(WORD)(100MIL)	EA	19	\$	-
666	6306	RE PM W/RET REQ TY I (W)6"(BRK)(100 MIL)	LF	1,756	\$	-
666	6309	RE PM W/RET REQ TY I (W)6"(SLD)(100 MIL)	LF	8,510	\$	-
666	6321	RE PM W/RET REQ TY I (Y)6"(SLD)(100MIL)	LF	5,405	\$	-
672	6009	REF PAV MARKR TY II-A-A	EA	85	\$	-
672	6010	REF PAV MARKR TY II-C-R	EA	152	\$	-
678	6002	PAV SURF PREP FOR MRK (6")	LF	15,671	\$	-
678	6004	PAV SURF PREP FOR MRK (8")	LF	2,553	\$	-
678	6008	PAV SURF PREP FOR MRK (24")	LF	547	\$	-
678	6009	PAV SURF PREP FOR MRK (ARROW)	EA	21	\$	-
678	6016	PAV SURF PREP FOR MRK (WORD)	EA	19	\$	-
680	6003	INSTALL HWY TRF SIG (ISOLATED)	EA	1	\$	-
	**	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	EA	1	**	\$
	**	TRAFFIC SIGNAL CONTROLLER FOUNDATION	EA	1	**	\$
	**	ROD. 5/8" X 10' COPPER GROUND (CONTROLLER ONLY)	EA	1	**	\$
	**	CELLULAR MODEM (CISCO MODEL IR1101)	EA	1	**	\$
	**	ETHERNET SWITCH (MOXA MODEL EDR-810-VPN-2GSFP-T)	EA	1	**	\$
	**	IP CAMERA (AXIS M5525-E)	EA	1	**	\$
	**	IP CAMERA MOUNTING BRACKET (AXIS T94AO1D PENDANT KIT)	EA	1	**	\$
	**	POWER STRIP	EA	1	**	\$
	**	SWITCH POWER SUPPLY	EA	1	**	\$
	**	POE POWER SUPPLY - FOR CAMERA ONLY	EA	1	**	\$
	**	R10-17T (30" X 36")	EA	4	**	\$
	**	STREET NAME SIGNS	EA	2	**	\$
	**	ETHERNET CABLE	LF	80	**	\$
682	6001	VEH SIG SEC (12") LED (GRN)	EA	8	\$	-
682	6002	VEH SIG SEC (12") LED (GRN ARW)	EA	4	\$	-
682	6003	VEH SIG SEC (12") LED (YEL)	EA	8	\$	-
682	6004	VEH SIG SEC (12") LED (YEL ARW)	EA	8	\$	-
682	6005	VEH SIG SEC (12") LED (RED)	EA	8	\$	-
682	6006	VEH SIG SEC (12") LED (RED ARW)	EA	4	\$	-
682	6018	PED SIG SEC (LED) (COUNTDOWN)	EA	6	\$	-
682	6054	BACKPLATE W/ REF BRDR (3 SEC) (VENT) ALUM	EA	8	\$	-
682	6055	BACKPLATE W/ REFL BRDR (4 SEC) (VENT) ALUM	EA	4	\$	-
684	6009	TRF SIG CBL (TY A) (12 AWG) (4 CONDR)	LF	1095	\$	-
684	6012	TRF SIG CBL (TY A) (12 AWG) (7 CONDR)	LF	1615	\$	-
684	6080	TRF SIG CBL (TY C) (14 AWG) (2 CONDR)	LF	1095	\$	-
686	6047	INS TRF SIG PL AM(S) 1 ARM (44') LUM	EA	1	\$	-
686	6055	INS TRF SIG PL AM(S) 1 ARM (50') LUM	EA	2	\$	-
686	6063	INS TRF SIG PL AM(S) 1 ARM (60') LUM	EA	1	\$	-
687	6001	PED POLE ASSEMBLY	EA	7	\$	-
	**	DRILL SHAFT (24")	LF	42	**	\$
688	6001	PED DETECT PUSH BUTTON (APS)	EA	6	\$	-
	**	R10-3e (L/R)	EA	6	**	\$
688	6003	PED DETECTOR CONTROLLER UNIT	EA	1	\$	-
3076	6001	D-GR HMA TY B PG64-22 (3.5")	TON	2519	\$	-
3076	6015	D-GR HMA TY C PG64-22 (2")	TON	2866	\$	-
3076	6066	TACK COAT	GAL	1257	\$	-
6001	6001	PORTABLE CHANGEABLE MESSAGE SIGN	DAY	20	\$	-
6185	6002	TMA (STATIONARY)	DAY	5	\$	-
6292	6001	RVDS (PRESENCE DETECTION ONLY)	EA	4	\$	-
	**	RVDS CABLE	LF	765	**	\$
6292	6002	RVDS (ADVANCE DETECTION ONLY)	EA	2	\$	-
	**	RVDS CABLE	LF	520	**	\$
					TOTAL:	\$ -

**Materials subsidiary to pertinent items.

Bidder Company: _____

Authorized Representative: _____

Authorized Representative Signature: _____

Date: _____

Substantial Complete Calendar Days: _____