

SERENO SPRINGS - UNIT 3

Bexar County, TX

ITEM NO.	BID ITEM			UNIT	
		UNIT	QUANTITY	PRICE	BID TOTAL
	DEMOLITION, EARTHWORK, CLEARING, AND SWPPP				
	Street Excavation (up to ROW)	CY	2,241		
	Street Embankment (up to ROW)	CY	3,347		
	Lot Excavation	CY	1,448		
	Lot Embankment	CY	25,741		
	Channel Excavation	CY	634		
	Channel Embankment	CY	5		
	Net Import	CY	24,769		
	TPDES	LS	1		
	Clearing (Streets up to ROW)	AC	2.4		
	Clearing (Lots/Offsite Easements)	AC	9.3		
	Remove Header Curb and Barricade Posts	LF	64		
	SUB-TOTAL				
	SANITARY SEWER				
	8" Sanitary Sewer Pipe (6'-10' Deep) (SDR-26)	LF	1,377		
	8" Sanitary Sewer Pipe (10'-14' Deep) (SDR-26)	LF	198		
	8" Sanitary Sewer Pipe (6'-10' Deep) (SDR-26 160 PSI)	LF	40		
	8" Sanitary Sewer Pipe (14'-18' Deep) (SDR-26 160 PSI)	LF	20		
	6" Sanitary Sewer Lateral (SDR-26)	LF	2,355		
	Standard Manhole	EA	6		
	Manhole Ring Encasement	EA	6		
	Tie to Existing 8" Sanitary Sewer Main	EA	2		
	Manhole Extra Depth	VF	14.4		
	8" x 6" Wye	EA	58		
	Trench Excavation Protection	LF	2,355		
	Camera Testing	LF	2,355		
	6" Sewer Cleanout	EA	65		
	SUB-TOTAL				
	ONSITE DRAINAGE				
	5' Sidewalk Box	EA	1		
	6" Rip Rap	SY	24		
	9" Rock Rubble 1.5' in Depth	SY	30		
	Pipe Railing	LF	12		
	Revegetation	SY	4,319		
	SUB-TOTAL				
	WATER DISTRIBUTION				
	8" PVC C-900, Class 235, DR 18	LF	1,755		
	12" PVC C-900, Class 235, DR 18	LF	707		
	8" Gate Valve, M.J. with Valve Box	EA	10		
	12" Gate Valve, M.J. with Valve Box	EA	5		
	Standard Fire Hydrant Assembly	EA	4		
	Ductile Iron Fitting	Ton	1.9		
	2" Blow Off (Permanent)	EA	1		
	Tie to Existing 8" Main	EA	2		
	Tie to Existing 12" Main	EA	1		
	Joint Restraints	LS	1		
	Hydrostatic Testing	LS	1		
	Chlorination	LF	2,462		
	Trench Excavation Protection	LF	2,462		
	3/4" Single Short Service w/ 5/8" meter	EA	3		
	3/4" Double Short Service w/ 5/8" meter	EA	20		
	3/4" Single Long Service w/ 5/8" meter	EA	1		
	3/4" Double Long Service w/ 5/8" meter	EA	11		
	Plastic Meter Box with Lid	EA	66		
	Remove and Replace Existing Pavement, Curb, Sidewalk, Landscaping, and Signage	LS	1		
	Traffic Control	LS	1		
	SUB-TOTAL				
	ONSITE STREETS				
	Local A				
	2" Type D HMAC	SY	6,370		
	10" Aggregate Base	SY	7,051		
	8" Lime Stabilized Subgrade	SY	7,051		
	Local B				
	1.5" Type D HMAC	SY	938		
	2.5" Type C HMAC	SY	938		
	18.5" Aggregate Base	SY	1,022		
	6" Lime Stabilized Subgrade	SY	1,022		
	Lime	TON	167		
	7" Concrete Curb	LF	3,962		
	ADA Ramps (Developer Responsibility)	EA	26		
	4' Sidewalk	SY	1,686		
	Header Curb	LF	30		
	Barricade Posts	EA	5		
	Signage	LS	1		
	SUB-TOTAL				
	CONDUITS				
	(1) 6" PVC SCH. 80 (Electric) and (2) 4" PVC SCH. 40 (Telephone & Cable)	LF	650		
	(2) 6" PVC SCH. 80 (Electric) and (2) 4" PVC SCH. 40 (Telephone & Cable)	LF	50		
	SUB-TOTAL				
	GRAND TOTAL				