

BID PROPOSAL LINE ITEMS

Line No.	Spec Item	Description	Unit	Qty	Unit Price	Total Price
1	103	REVEGETATION	S.Y.	3765	\$	\$
2	202.1	PRIME COAT (0.20 GAL/SY) (COSA SPEC)	GAL	46	\$	\$
3	203.1	TACK COAT (0.10 GAL/SY) (COSA SPEC)	GAL	23	\$	\$
4	205.2	HMAC TYPE B (10" COMPACTED) (COSA SPEC)	S.Y.	167	\$	\$
5	205.4	HMAC TYPE D (2" COMPACTED) (COSA SPEC)	S.Y.	228	\$	\$
6	299	FLOWABLE FILL	C.Y.	37	\$	\$
7	307	REMOVE AND REPLACE 36" SAFETY END TREATMENT	EA	1	\$	\$
8	316	CHIP SEAL, CRSP/CRS2P EMULSION, GR 5 TRAP ROCK (TxDOT SPEC)	S.Y.	975	\$	\$
9	401.1	REINFORCED CONCRETE PIPE (CLASS III) (18") (COSA SPEC)	L.F.	261	\$	\$
10	401.4	SAFETY END TREATMENT (TYPE 2) (COSA SPEC)	EA	14	\$	\$
11	503.4	OPEN CUT AND RESTORE EXISTING DRIVEWAY (ASPHALTIC) (COSA SPEC)	S.Y.	38	\$	\$
12	503.5	OPEN CUT AND RESTORE EXISTING DRIVEWAY (GRAVEL) (COSA SPEC)	S.Y.	524	\$	\$
13	513.1	REMOVE AND RELOCATE MAILBOX (ALL TYPES) (COSA SPEC)	EA	12	\$	\$
14	515	TOPSOIL (COSA SPEC)	S.Y.	419	\$	\$
15	520.1	HYDROMULCHING (COSA SPEC)	S.Y.	3765	\$	\$
16	530.1	BARRICADES, SIGNS AND TRAFFIC HANDLING (COSA SPEC)	L.S.	1	\$	\$
17	531.3	REMOVE AND REPLACE TRAFFIC SIGNAGE (R1-1) (COSA SPEC)	EA	1	\$	\$
18	531.55	INSTALL TRAFFIC SIGNAGE (OM-3) (COSA SPEC)	EA	17	\$	\$
19	531.6	REMOVE AND REPLACE TRAFFIC SIGNAGE (R2-1) (COSA SPEC)	EA	1	\$	\$
20	540.1	TEMPORARY EROSION, SEDIMENTATION, AND WATER POLLUTION PREVENTION CONTROL (COSA SPEC)	L.S.	1	\$	\$
21	550.1	TRENCH EXCAVATION SAFETY AND PROTECTION	L.F.	4252	\$	\$

Project Name: Silver Mountain 12-Inch Water Main
Solicitation No. : CO-00803
Job No: 24-6007 & 25-7001

22	760	CLEANING RESHAPING DITCHES (TxDOT SPEC)	L.F.	4004	\$	\$
23	812	REMOVE AND DISCARD EXISTING 6" PVC WATER MAIN	L.F.	123	\$	\$
24	815	6" HDPE WATER LINE (DR-11)	L.F.	138	\$	\$
25	815	12" HDPE WATER LINE (DR-11)	L.F.	4004	\$	\$
26	824	RELAY SHORT 3/4" SERVICE	EA	3	\$	\$
27	828	6" GATE VALVE ASSEMBLY	EA	4	\$	\$
28	828	12" GATE VALVE ASSEMBLY	EA	5	\$	\$
29	831	12" CUT-IN TEE	EA	1	\$	\$
30	840	12" WATER TIE-IN	EA	2	\$	\$
31	840	6" WATER TIE-IN	EA	3	\$	\$
32	841	HYDROSTATIC TESTING	EA	2	\$	\$
33	844	2" BLOWOFF (TEMPORARY)	EA	3	\$	\$
34	846	1" COMBINATION AIR VALVE ASSEMBLY	EA	3	\$	\$
35	856.1	12" HDPE CARRIER PIPE (DR-11)	L.F.	275	\$	\$
36	856.2	24" STEEL CASING (BORE)	L.F.	165	\$	\$
37	856.2	24" STEEL CASING (OPEN CUT)	L.F.	110	\$	\$
38	844	2" PERMANENT BLOW-OFF ASSEMBLY	EA	2	\$	\$
39	858	CONCRETE ENCASEMENT	C.Y.	7	\$	\$
SUBTOTAL (ITEMS 1-39)					\$	

40	3001	CPS POLE BRACING ALLOWANCE	ALW	1	\$ 25,000.00	\$ 25,000.00
SUBTOTAL (ITEM 40)					\$	

SUBTOTAL (ITEMS 1-40)					\$	
------------------------------	--	--	--	--	-----------	--

100	MOBILIZATION AND DEMOBILIZATION, MAX 10% OF LINE ITEMS 1 - 39	L.S.	1	\$
101	PREPARING ROW, MAX 5 % OF LINE ITEMS 1-39	L.S.	1	\$
102	INTERMEDIATE DEMOBILIZATION AND REMOBILIZATION (OPEN TRENCH)	EA	1	\$
102A	INTERMEDIATE DEMOBILIZATION AND REMOBILIZATION (TRENCHLESS)	EA	1	\$
SUBTOTAL (ITEMS 100-102, 102A)				\$

MOBILIZATION AND DEMOBILIZATION LUMP SUM BID SHALL BE LIMITED TO A MAXIMUM OF 10% OF THE LINE ITEM "1-39" SUB-TOTAL BASE BID AMOUNT. PREPARING RIGHT-OF-WAY LUMP SUM BID SHALL BE LIMITED TO A MAXIMUM OF 5% OF THE LINE ITEM "1-39" SUB-TOTAL BASE BID AMOUNT. THE LINE ITEM "1-39" SUB-TOTAL BASE BID IS DEFINED AS ALL BID ITEMS EXCLUDING ITEM 100, MOBILIZATION AND DEMOBILIZATION, ITEM 101, PREPARATION OF RIGHT-OF-WAY, ITEM 102 INTERMEDIATE DEMOBILIZATION AND REMOBILIZATION(OPEN TRENCH), 102A INTERMEDIATE DEMOBILIZATION AND REMOBILIZATION (TRENCHLESS) AND ITEM 3001 CPS POLE BRACING ALLOWANCE. IN THE EVENT OF A DISCREPANCY BETWEEN THE WRITTEN PERCENTAGE AND DOLLAR AMOUNT SHOWN FOR MOBILIZATION AND DEMOBILIATION AND PREPARATION OF ROW BID ITEMS THE WRITTEN PERCENTAGE WILL GOVERN. IF THE PERCENTAGE WRITTEN EXCEEDS THE ALLOWABLE MAXIMUM STATED FOR MOBILIZATION AND DEMOBILIZATION OR PREPARATION OF ROW, SAWS RESERVES THE RIGHT TO CAP THE AMOUNT AT THE PERCENTAGES SHOWN AND ADJUST THE EXTENSIONS OF THE BID ITEMS ACCORDINGLY.

TOTAL BID PRICE (TO INCLUDE LINE ITEMS 1-40, 100-102, AND 102A)	\$
--	----