

SONORA-UNIT 3
Bexar County, TX

ITEM NO.	BID ITEM				
		UNIT	QUANTITY	UNIT PRICE	BID TOTAL
	DEMOLITION, EARTHWORK, CLEARING, AND SWPPP				
	Remove Header Curb and Barricade Posts	LF	60		
	Street Excavation	CY	3,011		
	Street Embankment	CY	4,082		
	Lot Excavation	CY	2,096		
	Lot Embankment	CY	15,303		
	Channel Excavation	CY	693		
	Channel Embankment	CY	3		
	Import	CY	13,588		
	TPDES	LS	1		
	Clearing (Streets)	AC	1.5		
	Clearing (Lots/Offsite Easements)	AC	5.0		
	Modular Block Retaining Wall	SF	3,478		
	SUB-TOTAL				
	SANITARY SEWER				
	8" Sanitary Sewer Pipe (6'-10' Deep) (SDR-26)	LF	1,025		
	8" Sanitary Sewer Pipe (10'-14' Deep) (SDR-26)	LF	119		
	6" Sanitary Sewer Lateral (SDR-26)	LF	1,903		
	Standard Manhole	EA	2		
	Drop Manhole	EA	1		
	Manhole Ring Encasement	EA	3		
	Tie to Existing Manhole	EA	1		
	Manhole Extra Depth	VF	4.2		
	Vertical Stacks	VF	3.2		
	8" x 6" Wye	EA	49		
	Trench Excavation Protection	LF	1,144		
	Camera Testing	LF	1,144		
	SUB-TOTAL				
	ONSITE DRAINAGE				
	24" CMP	LF	45		
	15' Type C Curb Inlet	EA	1		
	Concrete Collars	CY	0.3		
	Baffle Blocks	CY	0.3		
	Concrete Headwall	CY	3.9		
	6" Concrete Rip-Rap	SY	8		
	Channel Revegetation	SY	1,450		
	Trench Excavation Protection	LF	45		
	SUB-TOTAL				
	WATER DISTRIBUTION				
	8" PVC C-900, Class 235, DR 18	LF	1,240		
	8" Gate Valve, M.J. with Valve Box	EA	1		
	Standard Fire Hydrant Assembly	EA	2		
	Ductile Iron Fitting	Ton	0.5		
	2" Blow Off (Temporary)	EA	1		
	Hydrostatic Testing	LS	1		
	Chlorination	LF	1,240		
	Trench Excavation Protection	LF	1,240		
	Joint Restraints	LS	1		
	3/4" Single Short Service w/ 5/8" meter	EA	39		
	3/4" Single Long Service w/ 5/8" meter	EA	14		
	Plastic Meter Box with Lid	EA	53		
	SUB-TOTAL				
	ONSITE STREETS				
	2" Type D HMA C	SY	4,355		
	8.5" Flex Base	SY	4,846		
	7" Concrete Curb	LF	2,399		
	4' Sidewalk	SY	268		
	Signage and Striping	LS	1		
	SUB-TOTAL				
	CONDUITS				
	2-6" SCH 80 & 2-4" SCH 40 Bundle	LF	30		
	SUB-TOTAL				
	GRAND TOTAL				