#### **GENERAL INFORMATION**

- ALL CONSTRUCTION SHALL CONFORM TO THE CITY OF SAN ANTONIO STANDARD SPECIFICATIONS FOR CONSTRUCTION
- NO EXTRA PAYMENT SHALL BE ALLOWED FOR WORK CALLED FOR ON THE PLANS BUT NOT INCLUDED IN THE BID. PROPOSAL. THIS INCIDENTAL WORK WILL BE REQUIRED AND SHALL BE INCLUDED IN THE PAY ITEM TO WHICH IT RELATES
- THE CONTRACTOR SHALL PROVIDE ACCESS FOR THE DELIVERY OF MAIL BY THE U.S. POSTAL SERVICE. 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING TO ITS ORIGINAL OR BETTER CONDITION ANY DAMAGE DONE TO EXISTING FENCES, CONCRETE ISLANDS, STREET PAVING, CURBS, SHRUBS, BUSHES OR DRIVEWAYS. (NO SEPARATE PAY
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO SEE THAT ALL SIGNS AND BARRICADES ARE PROPERLY INSTALLED AND MAINTAINED. ALL LOCATIONS AND DISTANCES WILL BE DECIDED UPON IN THE FIELD BY THE CONTRACTOR, USING THE NGINEERING REPRESENTATIVE WILL ONLY BE RESPONSIBLE TO INSPECT BARRICADES AND SIGNS. IF, IN THE OPINION C THE TRAFFIC ENGINEERING REPRESENTATIVE AND THE CONSTRUCTION INSPECTOR. THE BARRICADES AND SIGNS DO NO CONFORM TO ESTABLISHED STANDARDS OR ARE INCORRECTLY PLACED OR ARE INSUFFICIENT IN QUANTITY TO PROTECT THE GENERAL PUBLIC, THE CONSTRUCTION INSPECTOR SHALL HAVE THE OPTION TO STOP OPERATIONS UNTIL SUCH TIME
- IF THE NEED ARISES, ADDITIONAL BARRICADES AND DIRECTIONAL DEVICES MAY BE ORDERED BY THE TRAFFIC ENGINEERING REPRESENTATIVE AT THE CONTRACTOR'S EXPENSE.
- DUE TO FEDERAL REGULATIONS TITLE 49. PART 192.171 C.P.S. MUST MAINTAIN ACCESS TO GAS VALVES AT ALL TIMES. THE CONTRACTOR MUST PROTECT AND WORK AROUND ANY GAS VALVES THAT ARE IN THE PROJECT AREA.
- CONTRACTOR SHALL NOTIFY THE CITY INSPECTOR TWENTY FOUR (24) HOURS PRIOR TO BACKFILL OF ANY UTILITY TRENCHES TO SCHEDULE FOR DENSITY TEST AS REQUIRED
- CONTRACTOR SHALL PRESERVE ALL CONSTRUCTION STAKES, MARKS, ETC. IF ANY ARE DESTROYED OR REMOVED BY THI CONTRACTOR OR HIS EMPLOYEES, THEY SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
- CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES PRIOR TO CONSTRUCTION TO DETERMINE THE LOCATION OF EXISTING UTILITIES. CONTRACTOR SHALL NOTIFY THE FOLLOWING AT LEAST FORTY-EIGHT (48) HOURS PRIOR TO

COSA SIGNAL OPERATIONS

TEXAS STATE WIDE ONE CALL LOCATOR CITY PUBLIC SERVICE ENERGY - TIME WARNER - AT&T - MCI

- THE EXISTENCE AND LOCATION OF UNDERGROUND UTILITIES INDICATED ON THE PLANS ARE TAKEN FROM AVAILABLE RECORDS AND ARE NOT GUARANTEED, BUT SHALL BE INVESTIGATED AND VERIFIED BY THE CONTRACTOR BEFORE STARTING WORK. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY DAMAGE TO AND FOR THE MAINTENANCE AN PROTECTION OF THE EXISTING UTILITIES EVEN IF THEY ARE NOT SHOWN ON THE PLANS. LOCATION AND DEPTH OF EXISTING UTILITIES SHOWN HERE ARE APPROXIMATE ONLY ACTUAL LOCATIONS AND DEPTHS MUST BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION AND HE SHALL BE RESPONSIBLE FOR PROTECTION OF SAME DURING
- ALL WASTE MATERIAL SHALL BECOME PROPERTY OF THE CONTRACTOR AND SHALL BE HIS SOLE RESPONSIBILITY TO DISPOSE OF THIS MATERIAL OFF THE LIMITS OF THE PROJECT. NO WASTE MATE- RIAL SHALL BE PLACED IN EXISTING LOW THAT WILL BLOCK OR ALTER FLOW LIMITS OF EXISTING ARTIFICIAL OR NATURAL DRAINAGE
- THE CONTRACTOR SHALL NOT PLACE ANY WASTE MATERIAL IN THE 100-YEAR FLOOD PLAIN WITHOUT FIRST OBTAINING A APPROVED FLOOD PLAIN DEVELOPMENT PERMIT
- THE CONTRACTOR SHALL MAINTAIN ALL ADJOINING STREETS AND TRAVELED ROUTES FREE FROM SPILLED AND / OF
- CONTRACTOR MUST STOP EXCAVATION IMMEDIATELY, CONTACT THE CITY INSPECTOR, AND CALL THE CITY HISTORIC PRESERVATION OFFICE AT 207-7306 OR 207-3327 FOR AN ARCHAEOLOGICAL INVESTIGATION. THE CONTRACTOR CANNOT BEGIN EXCAVATION AGAIN WITHOUT WRITTEN PERMISSION FROM THE CITY. IF MORE THAN THREE (3) DAYS ARE REQUIRED FOR INVESTIGATION (NOT INCLUDING HOLIDAY AND WEEKENDS) AND IF THE CONTRACTOR IS UNABLE TO WO IN OTHER AREAS. THEN THE CONTRACTOR WILL BE ALLOWED TO NEGOTIATE FOR ADDITIONAL CONSTRUCTION TIME UPON WRITTEN REQUEST WITHIN TEN (10) DAYS AFTER THE FIRST NOTICE TO THE CITY OF ARCHAEOLOGICAL INVESTIGATION FOR EACH EVENT. IF THE TIME REQUIRED FOR INVESTIGATION IS LESS THAN OR EQUAL TO THREE (3) DAYS FOR EACH EVENT. CONTRACT DURATION WILL NOT BE EXTENDED
- IMMEDIATELY WHEN CONTAMINATED SOILS AND / OR GROUNDWATER ARE ENCOUNTERED AT LOCATIONS NOT IDENTIFIE. CONTAMINATED SOIL AND / OR GROUNDWATER SHALL NOT BE REMOVED FROM THE LOCATION WITHOUT PRIOR C.O.S.A. APPROVAL. THE CONTRACTOR MUST STOP THE EXCAVATION IMMEDIATELY AND CONTACT THE C.O.S.A. INSPECTOR. THI CONTRACTOR CANNOT BEGIN EXCAVATION ACTIVITIES WITHOUT WRITTEN PERMISSION FROM THE CITY.
- CONTRACTOR IS TO INCLUDE A MAILBOX POST BLOCKOUT FOR VACANT LOTS AND ALL RESIDENCES WHICH DO NOT HAVE MAILBOXES AT THE CURB. BLOCKOUTS ARE PROVIDED FOR FUTURE USE BY THE POST OFFICE.
- CONTRACTOR SHALL NOT REMOVE OR ADJUST ANY VIA FACILITIES. THE CONTRACTOR MUST  $\,\,$  CONTACT VIA FOURTEEN DAYS PRIOR, FOR THE REMOVAL OF BENCHES, STOP POLES OR ANY OTHER VIA FACILITIES THAT MAY BE PRESENT. PLEASE PROVIDE THIRTY DAYS PRIOR NOTICE FOR SHELTER REMOVAL (TELEPHONE NOS: (210) 362-2155 OR (210) 362-2096). THE CONTRACT- OR WILL BE LIABLE FOR ANY DAMAGES TO VIA FACILITIES NOT REMOVED BY VIA. THE CON-TRACTOR IS REQUIRED TO REPLACE ALL FLATWORK REMOVED OR DAMAGED IN THE COURSE OF EXECUTING THE CONTRACT UNLESS OTHERWISE NOTED BY VIA. THE CONTRACTOR WILL BE RESPONSIBLE FOR PROTECTING VIA FACILITIES IF ADJACENT TO WORK AREA.

### REE PROTECTION AND PRESERVATION GENERAL NOTES

- NO UTILITY OR STREET EXCAVATION WORK SHALL BEGIN IN AREAS WHERE TREE PRESERVATION AND TREATMENT MEASURES HAVE NOT BEEN COMPLETED AND APPROVED
- TREE PROTECTION FENCING SHALL BE REQUIRED. TREE PROTECTION FENCING SHALL BE INSTALLED, MAINTAINED AND REPAIRED BY THE CONTRACTOR DURING SITE CONSTRUCTION. DURING CONSTRUCTION ACTIVITY, AT LEAST A SIX-INCH LAYER OF COARSE MULCH SHALL BE PLACED AND MAINTAINED OVER THE ROOT PROTECTION ZONE (NO SEPARATE PAY
- THE CONTRACTOR SHALL AVOID CUTTING ROOTS LARGER THAN ONE INCH IN DIAMETER WHEN EXCAVATING NEAR EXISTING TREES. EXCAVATION IN THE VICINITY OF TREES SHALL PROCEED WITH CAUTION. THE CONTRACTOR SHALL CONTACT THE
- ROOTS WILL BE CUT WITH A ROCK SAW OR BY HAND, NOT BY AN EXCAVATOR OR OTHER ROAD CONSTRUCTION EQUIPMENT.
- ALL CURB AND SIDEWALK WORK SHALL USE ALTERNATIVE CONSTRUCTION METHODS TO MINIMIZE EXTENSIVE ROOT DAMAGE TO TREES (REFER TO DETAILS)
- EXPOSED ROOTS SHALL BE COVERED AT THE END OF THE DAY USING TECHNIQUES SUCH AS COVERING WITH SOIL, MULCH

NO EQUIPMENT. VEHICLES OR MATERIALS SHALL OPERATE OR BE STORED WITHIN THE ROOT PROTECTION ZONE OF ANY

- TREE NEAR THE PROJECT. ROOT PROTECTION ZONE IS 1 FOOT OF RADIUS PER INCH OF TREE'S DIAMETER. A 10-INCH DIAMETER TREE WOULD HAVE A 10 FOOT RADIUS ROOT PROTECTION ZONE AROUND THE TREE. ROOTS OR BRANCHES IN CONFLICT WITH THE CONSTRUCTION SHALL BE CUT CLEANLY ACCORDING TO PROPER PRUNING METHODS. OAK WOUNDS SHALL BE PAINTED OVER WITHIN 30 MINUTES TO PREVENT OAK WILT.
- SAPLINGS, SHRUBS OR BUSHES TO BE CLEARED FROM THE PROTECTED ROOT ZONE AREA OF A LARGE TREE SHALL BE REMOVED BY HAND AS DESIGNATED BY THE INSPECTOR.
- NO WIRES, NAILS OR OTHER MATERIAL MAY BE ATTACHED TO PROTECTED TREES.
- TREES, TREE LIMBS, BUSHES AND SHRUBS LOCATED IN THE CITY STREET OR ALLEY RIGHT-OF-WAY OR PERMANENT EASEMENTS WHICH INTERFERE WITH PROPOSED CONSTRUCTION ACTIVITIES SHALL BE PROPERLY PRUNED FOLLOWING THE ANSI A-300 STANDARDS FOR PRUNING. ALL TREE PRUNING SHALL BE COMPLETED BY A CITY OF SAN ANTONIO TREE MAINTENANCE LICENSED CONTRACTOR (ARTICLE 21-171, CITY CODE) ONLY AFTER APPROVAL FROM THE CAPITAL PROJECTS MANAGEMENT THROUGH THE INSPECTOR
- NO EXCESSIVE TREE TRIMMING WILL BE PERMITTED
- ALL DEBRIS GENERATED BY THE PRUNING AND TRIMMING OF THE TREES AND / OR BUSHES SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF PROPERLY (NO SEPARATE PAY ITEM,
- TREES MUST BE MAINTAINED IN GOOD HEALTH THROUGHOUT THE CONSTRUCTION PROCESS. MAINTENANCE MAY INCLUDE BUT NOT LIMITED TO: WATERING THE ROOT PROTECTION ZONE, WASHING FOLIAGE, FERTILIZATION, PRUNING, ADDITIONAL MULCH APPLICATIONS AND OTHER MAINTENANCE AS NEEDED ON THE PROJECT.
- ANY TREE REMOVAL SHALL BE APPROVED BY THE CITY ARBORIST. (207-0278).
- TREES WHICH ARE DAMAGED OR LOST DUE TO THE CONTRACTOR'S NEGLIGENCE DURING CONSTRUCTION SHALL BE
- TREE PLANTING FOR MITIGATION OR ENHANCEMENT: ALL PLANTED TREES SHALL BE MAINTAINED IN A HEALTHY CONDITION AT ALL TIMES. THIS INCLUDES IRRIGATION, FERTILIZING, PRUNING AND OTHER MAINTENANCE AS NEEDED ON THE PROJECT. TREES THAT DIE WITHIN TWELVE (12) MONTHS SHALL BE REPLACED WITH A TREE OF EQUAL SIZE AND


### CCESSIBILITY REQUIREMENTS

- THE CONTRACTOR SHALL PROVIDE AND MAINTAIN VEHICULAR AND PEDESTRIAN ACCESS AT ALL TIMES TO LOCAL RESIDENCES AND BUSINESSES.
- WHEN THE WORK REQUIRES THE EXCAVATION OF THE STREET AND THE REMOVAL OF THE EXISTING DRIVEWAY APPROACHES AND SIDEWALKS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING TEMPORARY ALL-WEATHER ACCESS TO THE BUSINESSES AND RESIDENCES. THE TEMPORARY DRIVEWAY APPROACHES SHALL BE CONSTRUCTED WITH FLEXIBLE BASE OR GRAVEL MATERIAL AT NO SEPARATE COST TO THE CITY.
- PRIOR TO INITIATING THE CONSTRUCTION OF NEW DRIVEWAY APPROACHES, THE CONTRACTOR SHALL GIVE ADVANCE WARNING IN PERSON, OR IN WRITING, OF AT LEAST 48 HOURS TO EACH RESIDENCE THAT WILL BE IMMEDIATELY AFFECTED SO THAT ALTERNATE PLANS MAY BE MADE BY THE RESIDENTS.
- FOR BUSINESSES WITH MORE THAN ONE DRIVEWAY, AT LEAST ONE DRIVEWAY SHALL REMAIN OPEN WHILE THE OTHER NEW DRIVEWAY APPROACHES ARE CONSTRUCTED. FOR BUSINESSES WITH ONLY ONE DRIVEWAY, THE NEW DRIVEWAY APPROACH SHALL BE CONSTRUCTED IN HALF WIDTHS, UNLESS A TEMPORARY ASPHALT DRIVEWAY IS FIRST INSTALLED A NO SEPARATE COST TO THE CITY.

# SOUTHEAST MEADOWS UNIT 3

## BEXAR COUNTY, TX

## STREET, DRAINAGE, WATER, SANITARY SEWER, AND UTILITY IMPROVEMENTS



## LOCATION MAP NOT-TO-SCALE

OWNER/DEVELOPER MEH HOLDING COMPANY LTD 5210 THOUSAND OAKS, SUITE 1318 SAN ANTONIO, TX 78233

## INDEX

	SHEET
	NO.
COVER SHEET	0.0
OVERALL UTILITY PLAN	1.0
OVERALL UTILITY PLAN	1.1
MASTER DRAINAGE PLAN	2.0
OVERALL GRADING PLAN	3.0
OVERALL GRADING PLAN	3.1
DRAIN "A" PLAN & PROFILE	4.0
DRAIN "B" PLAN & PROFILE	4.1
DRAIN "C" PLAN & PROFILE	4.2
DRAIN "D" PLAN & PROFILE (1 OF 3)	4.3
DRAIN "D" PLAN & PROFILE (2 OF 3)	4.4
DRAIN "D" PLAN & PROFILE (3 OF 3)	4.5
DRAIN "E" PLAN & PROFILE	4.6
INTERCEPTOR DRAIN "F" PLAN & PROFILE (1 OF 2)	4.7
INTERCEPTOR DRAIN "F" PLAN & PROFILE (2 OF 2)	4.8
HIGH PERFORMANCE TURF REINFORCEMENT  MATTING DETAILS	4.9
ROCKET VIEW PLAN & PROFILE	5.0
ROCKET VIEW PLAN & PROFILE	5.1
ROCKET VIEW, SOLACE WALK & SPECTRE HILL PLAN & PROFILE	5.2
SPECTRE HILL PLAN & PROFILE	5.3
SKYFALL AND LASER COVE PLAN & PROFILE	5.4
FIELDSTONE WAY PLAN & PROFILE	5.5
STREET DETAIL SHEET	5.6
WHEELCHAIR RAMP DETAIL SHEET	5.7
MISCELLANEOUS DETAIL SHEET	5.8
MISCELLENEOUS DETAIL SHEET	5.9
TRAFFIC SIGNAGE AND PEDESTRIAN PLAN	5.10
TRAFFIC SIGNAGE AND PEDESTRIAN PLAN	5.11
TRAFFIC SIGNAGE DETAIL SHEET	5.12
TRAFFIC SIGNAGE NOTES & DETAILS SHEET	5.13
PAVEMENT MARKING DETAILS	5.14
SANITARY SEWER COVER SHEET	6.0
OVERALL SANITARY SEWER PLAN	6.1
OVERALL SANITARY SEWER PLAN	6.2
LINE "A" PLAN & PROFILE	6.3
LINE "A" PLAN & PROFILE	6.4
LINE "B" PLAN & PROFILE	6.5
LINE "C" AND LINE "D" PLAN & PROFILE	6.6
WATER DISTRIBUTION COVER SHEET	7.0
WATER DISTRIBUTION PLAN	7.1
WATER DISTRIBUTION PLAN	7.2
WATER DISTRIBUTION DETAILS	7.3
WATER DISTRIBUTION DETAILS	7.4
WATER DISTRIBUTION DETAILS	7.5
STORMWATER POLLUTION PREVENTION PLAN	8.0
STORMWATER POLLUTION PREVENTION PLAN	8.1
STORMWATER POLLUTION PREVENTION DETAILS	8.2

## & Design

www.colliersengineering.com

nom the services were contracted or to whom it is certified. This drawing ma e copied, reused, disclosed, distributed or relied upon for any other pu without the express written consent of Colliers Engineering & Design

EXCAVATORS, DESIGNERS, OR ANY PER FOR STATE SPECIFIC DIRECT PHONE NUMBERS



**PRELIMINARY** 

SOUTHEAST MEADOWS UNIT 3 PLAT# 23-11800440

> SAN ANTONIO **BEXAR COUNTY**

> > TEXAS


Engineering & Design


San Antonio, TX 78231 Phone: 210.979.8444


SAN ANTONIO (KFW)


/2054307


**COVER SHEET** 



























### TRENCH EXCAVATION SAFETY PROTECTION CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. THE CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITED TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.



1. ALL CONCRETE SHALL DEVELOP A **Colliers** MINIMUM COMPRESSIVE STRENGTH OF NOT LESS THAN 3000 PSI IN 28 DAYS. 2. ANY DISTURBED AREAS WILL BE VEGETATED BY SEEDING OR SODDING. Engineering DISTURBED SURFACE AREA MUST HAVE ESTABLISHED VEGETATION BEFORE THE & Design CITY OF SAN ANTONIO WILL ACCEPT. 3. AT THE PRE-FINAL INSPECTION: THE ENGINEER MUST ISSUE CERTIFICATION www.colliersengineering.com TO THE CITY INSPECTOR THAT THE TURF REINFORCEMENT MAT (TRM) WAS oyright © 2024. Colliers Engineering & Design All Rights Reserved. This draw INSTALLED IN ACCORDANCE WITH THE whom the services were contracted or to whom it is certified. This drawing may n be copied, reused, disclosed, distributed or relied upon for any other purpo CERTIFICATION MUST ALSO NOTE THAT without the express written consent of Colliers Engineering & Design. THE MATERIAL AND INSTALLATION HAS Formerly Known as PROTECT YOURSELF


ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSO PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM JEFFREY W. MARTIN PRELIMINARY FOR SOUTHEAST MEADOWS UNIT 3 PLAT# 23-11800440 SAN ANTONIO **BEXAR COUNTY TEXAS** SAN ANTONIO (KFW) 3421 Paesanos Colliers Parkway San Antonio, TX 78231 Phone: 210.979.8444 Engineering COLLIERS ENGINEERING & DESIGN, INC. TBPE Firm#: F-14909 TBPLS Firm#: 10194550 & Design DR2054307 - CE 205-43-07 DRAIN "D" PLAN & PROFILE (3 OF 3)


EIGHTY-FIVE PERCENT OF THE


PLANS AND SPECIFICATIONS. THE


MET CITY AND MANUFACTURER

SPECIFICATIONS.











Product Data LANDLOK 300®

LANDLOK 300® high performance turf reinforcement mat (HPTRM) is a three-dimensional, lofty, woven polypropylene geotextile that is available in green or tan which is specially designed for erosion control applications on steep slopes and vegetated waterways. The matrix is composed of polypropylene monofilament yarns featuring X3® technology woven into a uniform configuration of resilient pyramid-like projections. The material exhibits very high interlock and reinforcement capacity with both soil and root systems, demonstrates superior UV resistance, and enhances seedling emergence.

LANDLOK 300® conforms to the property values listed below¹ and is manufactured at a Propex facility having achieved ISO 9001:2000 certification. Propex performs internal Manufacturing Quality Control (MQC) tests that have been accredited by the Geosynthetic Accreditation Institute – Laboratory Accreditation Program (GAI-LAP).

PROPERTY	TEST METHOD	ENGLISH	METRIC
ORIGIN OF MATERIALS	1		
% U.S. Manufactured Inputs		100%	100%
% U.S. Manufactured		100%	100%
PHYSICAL			
Mass/Unit Area	ASTM D-6566	7.5 oz/yd <sup>2</sup>	254.3 g/m <sup>2</sup>
Thickness	ASTM D-6525	0.25 in	6.35 mm
Light Penetration (% Passing)	ASTM D-6567	50% (Max)	50%
Color	Visual	Greer	n or Tan
MECHANICAL			
Tensile Strength (Grab)	ASTM D-6818	2000 x 1800 lb/ft	29.2 x 26.3 kN/m
Elongation	ASTM D-6818	50% (max)	50% (max)
Resiliency	ASTM D-6524	70%	70%
Flexibility	ASTM D-6575	0.195 in-lb (avg)	10.8 mg-cm (avg)
ENDURANCE			
UV Resistance % Retained 3000 hrs	ASTM D-4355	90%	90%
PERFORMANCE			
Velocity <sup>3</sup> (Vegetated)	Large Scale	20 ft/sec	6.10 m/sec
Shear Stress <sup>3</sup> (Vegetated)	Large Scale	12 lb/ft <sup>2</sup>	575 Pa
Manning's "n" 4 (Unvegetated)	Calculated	0.030	0.030
Seedling Emergence <sup>4</sup>	ECTC Draft Method #4	-	-
ROLL SIZES		8.5 ft x 106 ft	2.6 m x 32.3 m

- The property values listed are effective 04/2011 and are subject to change without notice.
- 2. MARV indicates minimum average roll value calculated as the typical minus two standard deviations. Statistically, it yields a 97.7% degree of confidence that any sample taken during quality assurance testing will exceed the value reported.
- 3. Maximum permissible velocity and shear stress has been obtained through vegetated testing programs featuring specific soil types, vegetation classes, flow conditions, and failure criteria. These conditions may not be relevant to every project nor are they replicated by other manufacturers. Please contact Propex for further information.
- 4. Calculated as typical values from large-scale flexible channel lining test programs with a flow depth of 6 to 12 inches. GEOTEXTILE

BY PROPEX

**ENGINEERING EARTH** www.geotextile.com

**Propex Operating Company, LLC** · 6025 Lee Highway, Suite 425 · PO Box 22788 · Chattanooga, TN 37422 ph 423 899 0444 · ph 800 621 1273 · fax 423 899 7619

Geotex®, Landlok®, Pyramat®, X3®, SuperGro®, Petromat® and Petrotac® are registered trademarks of Propex Operating Company, LLC. This publication should not be construed as engineering advice. While information contained in this publication is accurate to the best of our knowledge, Propex does not warrant its accuracy or completeness. The ultimate customer and user of the products other written warranty as may be agreed by Propex and individual customers. Propex specifically disclaims all other warranties, express or implied, including without limitation, warranties of merchantability or fitness for a particular purpose, or arising from

© 2011 Propex Operating Company, LLC


**Colliers** 

Engineering & Design


www.colliersengineering.com

Copyright © 2023. Colliers Engineering & Design All Rights Reserved. This drawing and all the information contained herein is authorized for use only by the party for whom the services were contracted or to whom it is certified. This drawing may not pe copied, reused, disclosed, distributed or relied upon for any other purpos without the express written consent of Colliers Engineering & Design.

Formerly Known as



FOR STATE SPECIFIC DIRECT PHONE NUMBERS



JEFFREY W. MARTIN 11/15/23

**PRELIMINARY** 

FOR SOUTHEAST MEADOWS UNIT 3 PLAT# 23-11800440


> SAN ANTONIO BEXAR COUNTY TEXAS


	Colliers
ı	Engineering & Design


SAN ANTONIO (KFW) Parkwav San Antonio, TX 78231 Phone: 210.979.8444 COLLIERS ENGINEERING & DESIGN, INC TBPE Firm#: F-14909 TBPLS Firm#: 10194550


AS SHOWN 07/20/2023 205-43-07


HIGH PERFORMANCE TURF REINFORCEMENT MATTING **DETAILS** 












TRENCH EXCAVATION SAFETY PROTECTION CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR


ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

CAUTION!!:
THE CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES


THE CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES

OF WERE THE EDWONE AND FIBER OPTIC LINES. igcap INCLUDING BUT NOT LIMITED TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE igcapLIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS. LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT. 









LEGEND

BEXAR COUNTY R.O.W. NOTE

A BEXAR COUNTY PERMIT

MUST BE OBTAINED BEFORE

WORKING IN BEXAR COUNTY

R.O.W.

= FLOW ARROW

= WASHOUT CROWN

E.G.T.TV.E. = ELECTRIC, GAS, TELEPHONE & CABLE EASEMENT V.N.A.E. = VEHICULAR NON-ACCESS EASEMENT

W.C.R. = WHEELCHAIR RAMPS SEE SHEET 5.7

> = WHEELCHAIR RAMP TYPE I SEE SHEET 5.7

= WHEELCHAIR RAMP TYPE II SEE SHEET 5.7

S.D.W.C.R. = SINGLE DIRECTIONAL WHEEL CHAIR RAMP SEE SHEET 5.7

D.D.W.C.R. = DOUBLE DIRECTIONAL WHEEL CHAIR RAMP SEE SHEET 5.7

\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\* = SIDEWALK TO BE CONSTRUCTED BY DEVELOPER. = SIDEWALK TO BE BUILT AT THE TIME

OF HOME CONSTRUCTION 732.87 = TOP OF CURB ELEVATIONS

= PROPOSED DRIVEWAY LOCATIONS

**Colliers** 

Engineering & Design

www.colliersengineering.com

Copyright © 2024. Colliers Engineering & Design All Rights Reserved. This drawi and all the information contained herein is authorized for use only by the party whom the services were contracted or to whom it is certified. This drawing may


pe copied, reused, disclosed, distributed or relied upon for any other purpo

without the express written consent of Colliers Engineering & Design.

ormerly Known as

PROTECT YOURSELF
ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE

FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM



JEFFREY W. MARTIN

**PRELIMINARY** 

FOR SOUTHEAST MEADOWS UNIT 3 PLAT# 23-11800440

> SAN ANTONIO BEXAR COUNTY **TEXAS**

& Design

Parkwav San Antonio, TX 78231 COLLIERS ENGINEERING & DESIGN, INC. TBPE Firm#: F-14909 TBPLS Firm#: 10194550


SAN ANTONIO (KFW)

AS SHOWN 205-43-07

TPP2054307

FIELDSTONE WAY PLAN & PROFILE

5.5



MINIMUM 2.0" TYPE "D"

CONCRETE PAVEMENT

HEADER CURB

ITEM 500 ON SAND OR GRAVEL NOT TO SCALE

HOT MIX ASPHALTIC

MINIMUM 10" AGGREGATE BASE

6" x 6" W / D 2.9 x W / D 2.9 WELDED WIRE FLAT SHEETS (ITEM 303) OR

#3 BARS @ 18" O.C. EACH WAY CENTERED IN SLAB (ITEM 301)

4" CLASS "A" CONCRETE\_

CONCRETE SIDEWALK

ABUTTING CURB SECTION

NOT TO SCALE

SIDEWALK - ITEM 502

NO. 4 BARS DOWEL INTO-

Colliers

Engineering

& Design

AS SHOWN

205-43-07

NOTE: DO NOT SCALE DRAWINGS FOR CONSTRUCTION.

**Colliers** 

Engineering

& Design

www.colliersengineering.com pyright © 2024. Colliers Engineering & Design All Rights Reserved. This draw

hom the services were contracted or to whom it is certified. This drawing ma

e copied, reused, disclosed, distributed or relied upon for any other purp

without the express written consent of Colliers Engineering & Design.

FOR STATE SPECIFIC DIRECT PHONE NUMBERS

VISIT: WWW.CALL811.COM

JEFFREY W. MARTII

**PRELIMINARY** 

SOUTHEAST

**MEADOWS UNIT 3** 

PLAT# 23-11800440

SAN ANTONIO

**BEXAR COUNTY** 

**TEXAS** 

TDT2054307

STREET DETAIL SHEET

SAN ANTONIO (KFW)

3421 Paesanos

Parkway

San Antonio, TX 78231

Phone: 210.979.8444

COLLIERS ENGINEERING & DESIGN, INC

TBPE Firm#: F-14909


TBPLS Firm#: 10194550


6/28/24


PROTECT YOURSELF
ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON


PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE


ormerly Known as
















NOTE: DO NOT SCALE DRAWINGS FOR CONSTRUCTION

**DETAIL SHEET** 




### TYPICAL RESIDENTIAL DRIVEWAY SECTION

WITH SIDEWALK ABUTTING CURB ITEM 503.1



### TYPICAL RESIDENTIAL DRIVEWAY SECTION

WHERE PROPERTY IS LOWER THAN STREET & SIDEWALK IS ABUTTING CURB ITEM 503.1



## TYPICAL COMMERCIAL DRIVEWAY SECTION

WITH SIDEWALK ABUTTING CURB

ITEM 503.2

## CONCRETE DRIVEWAY NOTES


- 1. DRIVEWAY PENETRATION REFERS TO A PORTION OF THE DRIVEWAY THAT MAY BE NECESSARY TO RECONSTRUCT WITHIN PRIVATE PROPERTY TO COMPLY WITH A MAXIMUM DRIVEWAY SLOPE. THIS PORTION OF THE DRIVEWAY SHALL BE PAID FOR UNDER THE FOLLOWING ITEMS AS MAY APPLY:
- A.) CONCRETE DRIVEWAY PAID FOR UNDER ITEM NO. 503.1 OR 503.2.

  B.) ASPHALTIC CONCRETE DRIVEWAY PAID FOR UNDER ITEM NO. 503.4 AND SHALL INCLUDE A MINIMUM OF 1" ASPHALT TYPE 'D' & 6" FLEXIBLE BASE
- C.) GRAVEL DRIVEWAY PAID FOR UNDER ITEM NO. 503.5 AND SHALL INCLUDE A MINIMUM OF 6" FLEXIBLE BASE
- 2. 7" MINIMUM HEIGHT WILL NOT NECESSARILY OCCUR AT THE PROPERTY LINE. IT MAY OCCUR WITHIN THE RIGHT OF WAY OR WITHIN THE DRIVEWAY PENETRATION ON PRIVATE PROPERTY.
- 3. THE PROPOSED DRIVEWAY SHOULD MATCH THE EXISTING WIDTH AT THE PROPERTY LINE BUT UNLESS AUTHORIZED BY THE CITY TRAFFIC ENGINEER, THE WIDTH SHALL BE WITHIN THE FOLLOWING VALUES:

TYPE	мінімим	MAXIMUM
RESIDENTIAL	10'	20'
COMMERCIAL - ONE WAY	12'	20'


COMMERCIAL - TWO WAY 24'

- 4. FOR LOCAL TYPE "A" STREETS, SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 4' AND IF SEPARATED FROM THE CURB, THE SIDEWALK SHALL BE LOCATED A MINIMUM OF 3' FROM THE BACK OF CURB.
- 5. FOR OTHER THAN LOCAL TYPE "A" STREETS, THE SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 4' AND SEPARATED A MINIMUM OF 3' FROM THE BACK OF CURB OR, AS AN OPTION, THE SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 6' WHEN LOCATED AT THE BACK OF CURB.
- 6. DUMMY JOINTS PARALLEL TO THE CURB SHALL BE PLACED WHERE THE SIDEWALK MEETS THE DRIVEWAY. DUMMY JOINTS PERPENDICULAR TO THE CURB, AND WITHIN THE BOUNDARIES OF THE PARALLEL DUMMY JOINTS, SHALL BE PLACED AT INTERVALS EQUAL TO THE WIDTH OF THE SIDEWALK.
- 7. A MINIMUM OF TWO ROUND AND SMOOTH DOWEL BARS 3 /8" IN DIAMETER AND 18" IN LENGTH SHALL BE SPACED 18" APART AT EACH EXPANSION JOINT.
- 8. SIDEWALK RAMP LENGTHS SHALL BE OF SUFFICIENT LENGTH TO MAINTAIN 8.33% (1:12) MAXIMUM SLOPE. WHERE SIDEWALKS CROSS DRIVEWAYS, SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2%.
- 9. SIDEWALK RAMP SURFACE SHALL BE BRUSH FINISHED.



## TYPICAL RESIDENTIAL DRIVEWAY SECTION


WITH SIDEWALK SEPARATED FROM CURB



② THE ALGEBRAIC DIFFERENCE OF G1 & G2 SHALL BE 14% OR LESS


### TYPICAL RESIDENTIAL DRIVEWAY SECTION

WHERE PROPERTY IS LOWER THAN STREET & SIDEWALK IS SEPARATED FROM CURB



## TYPICAL COMMERCIAL DRIVEWAY SECTION

WITH SIDEWALK SEPARATED FROM CURB ITEM 503.2




COST OF REINFORCEMENT TO BE INCLUDED IN UNIT COST OF ITEM 307.1.
 CONCRETE RETAINING WALL COMBINATION TYPE SHALL BE USED FOR

## DRIVEWAY - CONCRETE RETAINING WALL


ON COMPACTED SUBGRADE ITEM 307.1

CONCRETE DRIVEWAYS.




## CURB PROFILE AT DRIVEWAY

WITH SIDEWALK ABUTTING CURB



### TYPICAL DRIVEWAY PLAN VIEW


WITH SIDEWALK ABUTTING CURB



② RESIDENTIAL : 2' MAXIMUM; COMMERCIAL: SEE PLAN VIEW

## CURB PROFILE AT DRIVEWAY

WITH SIDEWALK SEPARATED FROM CURB



② 45 FOR COMMERCIAL DRIVEWAY

### TYPICAL DRIVEWAY PLAN VIEW

WITH SIDEWALK SEPARATED FROM CURB

## MAY 2009

## CITY OF SAN ANTONIO

CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

## CONCRETE DRIVEWAY STANDARDS

% SUBMITTAL	PROJECT NO.:		DATE:	
DRWN. BY: V. VASQUEZ	DSGN. BY:	CHKD. BY: R.S. HOSSEINI, P.E.	SHEET NO.:	OF

Colliers

Engineering & Design

www.colliersengineering.com

Copyright © 2024. Colliers Engineering & Design All Rights Reserved. This draw and all the information contained herein is authorized for use only by the party whom the services were contracted or to whom it is certified. This drawing may be copied, reused, disclosed, distributed or relied upon for any other purp without the express written consent of Colliers Engineering & Design.

ormerly Known as



 REV
 DATE
 DRAWN BY
 DESCRIPTION

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...


 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...



PRELIMINARY

FOR
SOUTHEAST
MEADOWS UNIT 3
PLAT# 23-11800440

SAN ANTONIO BEXAR COUNTY TEXAS

SAN ANTONIO (KFW)

3421 Paesanos
Parkway
San Antonio, TX 78231

Phone: 210.979.8444

COLLIERS ENGINEERING & DESIGN, INITERPE FIRM#: F-14909


AS SHOWN 07/20/2023 SD SC


PROJECT NUMBER: DRAWING NAME:
205-43-07 STDT2054307


SHEET TITLE:


MISCELLENEOUS DETAIL SHEET


T NUMBER:













Engineering & Design

www.colliersengineering.com

Copyright © 2023. Colliers Engineering & Design All Rights Reserved. This drawing und all the information contained herein is authorized for use only by the party for whom the services were contracted or to whom it is certified. This drawing may not be copied, reused, disclosed, distributed or relied upon for any other purpose

without the express written consent of Colliers Engineering & Design.

Formerly Known as

PROTECT YOURSELF

ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE

FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

JEFFREY W. MARTIN

139094

CENSE

ONAL

11/15/23

PRELIMINARY

FOR SOUTHEAST MEADOWS UNIT 3 PLAT# 23- 11800440

> SAN ANTONIO BEXAR COUNTY TEXAS

Colliers

Engineering
& Design

SAN ANTONIO (KFW)

3421 Paesanos
Parkway
San Antonio, TX 78231
Phone: 210.979.8444


COLLIERS ENGINEERING & DESIGN, INC
TBPE Firm#: F-14909

SCALE: DATE: DRAWN BY:
AS SHOWN 07/20/2023 SD
PROJECT NUMBER: DRAWING NAME:


205-43-07 TSDT2054307
ET TITLE:


TRAFFIC SIGNAGE DETAIL SHEET

5.12




18" OVERHEAD STREET NAME SIGNS





FILE NO.: 805H801.Dwg






Engineering & Design

www.colliersengineering.com

Copyright © 2023. Colliers Engineering & Design All Rights Reserved. This drawing and all the information contained herein is authorized for use only by the party for whom the services were contracted or to whom it is certified. This drawing may not be copied, reused, disclosed, distributed or relied upon for any other purpose without the express written consent of Colliers Engineering & Design.

Formerly Known as



ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSO PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE

FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

 REV
 DATE
 DRAWN BY
 DESCRIPTION

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...
 ...

 ...
 ...
 ...

JEFFREY W. MARTIN

139094

//CENSE
JONAL

11/15/23

PRELIMINARY

FOR SOUTHEAST MEADOWS UNIT 3 PLAT# 23- 11800440

> SAN ANTONIO BEXAR COUNTY TEXAS

**Colliers**Engineering

& Design

3421 Paesanos
Parkway
San Antonio, TX 78231
Phone: 210.979.8444
COLLIERS ENGINEERING & DESIGN, INC
TBPE Firm#: F-14909
TBPLS Firm#: 10194550

SAN ANTONIO (KFW)

CALE: DATE: DRAWN BY:

AS SHOWN 07/20/2023 SD

ROJECT NUMBER: DRAWING NAME:

205.43.07 TSDT2054307


205-43-07 TSDT2054307


EET TITLE:


TRAFFIC SIGNAGE NOTES &


DETAILS SHEET

5.13









SDT2054307

PAVEMENT MARKING DETAIL

5.14

AS SHOWN

205-43-07

### **GENERAL INFORMATION**

#### SAWS STANDARD GENERAL CONSTRUCTION NOTES ASSOCIATED WITH 2021 SAWS STANDARD SPECS

Updated January 2022

#### General Section

- 1. All materials and construction procedures within the scope of this contract shall be approved by the San Antonio Water System (SAWS) and comply with the Plans, Specifications, General Conditions and with the
- A. Current Texas Commission on Environmental Quality (TCEQ) "Design Criteria for Domestic Wastewater System", Texas Administrative Code (TAC) Title 30 Part 1 Chapter 217 and "Public Drinking Water", TAC
- B. Current TXDOT "Standard Specifications for Construction of Highways, Streets and Drainage". C. Current "San Antonio Water System Standard Specifications for Water and Sanitary Sewer
- D. Current City of San Antonio "Standard Specifications for Public Works Construction". E. Current City of San Antonio "Utility Excavation Criteria Manual" (UECM).
- The contractor shall not proceed with any pipe installation work until they obtain a copy of the approved Counter Permit or General Construction Permit (GCP) from the consultant and has been notified by SAWS Construction Inspection Division to proceed with the work and has arranged a meeting with the inspector and consultant for the work requirements. Work completed by the contractor without an approved Counter Permit and/or a GCP will be subject to removal and replacement at the expense of the contractors and/or the
- 3. The Contractor shall obtain the SAWS Standard Details from the SAWS website, http://www.saws.org/business\_center/specs. Unless otherwise noted within the design plans.
- 4. The Contractor is to make arrangements with the SAWS Construction Inspection Division at (210) 233-2973. on notification procedures that will be used to notify affected home residents and/or property owners 48 hours prior to beginning any work.
- 5. Location and depth of existing utilities and service laterals shown on the plans are understood to be approximate. Actual locations and depths must be field verified by the Contractor at least 1 week prior to construction. It shall be the Contractor's responsibility to locate utility service lines as required for construction and to protect them during construction at no cost to SAWS.
- 6. The Contractor shall verify the exact location of underground utilities and drainage structures at least 1-2 weeks prior to construction whether shown on plans or not. Please allow up to 7 business days for locates requesting pipe location markers on SAWS facilities. The following contact information are supplied for
  - SAWS Utility Locates: http://www.saws.org/Service/Locates COSA Drainage (210) 207-0724 or (210) 207-6026
  - COSA Traffic Signal Operations (210) 206-8480 COSA Traffic Signal Damages (210) 207-3951
  - Texas State Wide One Call Locator 1-800-545-6005 or 811
- 7. The Contractor shall be responsible for restoring existing fences, curbs, streets, driveways, sidewalks, landscaping and structures to its original or better condition if damages are made as a result of the project's
- 8. All work in Texas Department of Transportation (TxDOT) and/or Bexar County right-of-way shall be done in accordance with respective construction specifications and permit requirements.
- 9. The Contractor shall comply with City of San Antonio or other governing municipality's tree ordinances when
- 10. The Contractor shall not place any waste materials in the 100-year Flood Plain without first obtaining an
- 11. Holiday Work: Contractors will not be allowed to perform SAWS work on SAWS recognized holidays. Request should be sent to constworkreg@saws.org. Weekend Work: Contractors are required to notify the SAWS Inspection Construction Department 48 hours in advance to request weekend work. Request should be sent to constworkreg@saws.org. Any and all SAWS utility work installed without holiday/weekend approval will be subject to be uncovered for proper inspection.
- 12. Compaction note (Item 804): The contractor shall be responsible for meeting the compaction requirements or all trench backfill and for paying for the tests performed by a third party. Compaction tests will be done at one location point randomly selected, or as indicated by the SAWS Inspector and/or the test administrator, per each 12-inch loose lift per 400 linear feet at a minimum. This project will not be accepted and finalized by SAWS without this requirement being met and verified by providing all necessary documented test results.
- 13. A copy of all testing reports shall be forwarded to SAWS Construction Inspection Division.

- 1. The Contractor is responsible for ensuring that no Sanitary Sewer Overflow (SSO) occurs as a result of their work. All contractor personnel responsible for SSO prevention and control shall be trained on proper response. Should an SSO occur, the contractor shall:
- A. Identify the source of the SSO and notify SAWS Emergency Operations Center (EOC) immediately at (210) 233-2014. Provide the address of the spill and an estimated volume or flow.
- Attempt to eliminate the source of the SSO. Contain sewage from the SSO to the extent of preventing a possible contamination of waterways.
- D. Clean up spill site (return contained sewage to the collection system if possible) and properly dispose of contaminated soil/materials.
- E. Clean the affected sewer mains and remove any debris. Meet all post-SSO requirements as per the EPA Consent Decree, including line cleaning and televising the affected sewer mains (at SAWS direction) within 24 hours. Should the Contractor fail to address an SSO immediately and to SAWS satisfaction, they will be responsible for all costs incurred by SAWS, including any fines from EPA, TCEQ and/or any other Federal, State or Local Agencies. No separate measurement or payment shall be made for this work. All work shall be done according to guidelines set by the TCEQ and SAWS.
- 2. If bypass pumping is required, the Contractor shall perform such work in accordance with SAWS Standard Specification for Water and Sanitary Sewer Construction, Item No. 864, "Bypass Pumping".
- 3. Prior to tie-ins, any shutdowns of existing force mains of any size must be coordinated with the SAWS Construction Inspection Division at (210) 233-2973 at least one week in advance of the shutdown. The Contractor must also provide a sequence of work as related to the tie-ins; this is at no additional cost to SAWS or the project and it is the responsibility of the Contractor to sequence the work accordingly.
- 4. Sewer pipe where water line crosses shall be 160 psi and meet the requirements of ASTM D2241, TAC 217.53 and TCEQ 290.44(e)(4)(B). Contractor shall center a 20' joint of 160 psi pressure rated PVC at the
- 5. ELEVATIONS POSTED FOR TOP OF MANHOLES ARE FOR REFERENCE ONLY: It shall be the responsibility of the Contractor to make allowances and adjustments for top of manholes to match the finished grade of the project's improvements. (NSPI)
- 6. Spills, Overflows, or Discharges of Wastewater: All spills, overflows, or discharges of wastewater, recycled water, petroleum products, or chemicals must be reported immediately to the SAWS Inspector assigned to the Counter Permit or General Construction Permit (GCP). This requirement applies to every spill, overflow, or discharge regardless of size.
- 7. Manhole and all pipe testing (including the TV inspection) must be performed and passed prior to Final Field Acceptance by SAWS Construction Inspection Division, as per the SAWS Specifications For Water and
- 8. All PVC pipe over 14 feet of cover shall be extra strength with minimum pipe stiffness of 115 psi.

# SOUTHEAST MEADOWS UNIT 3

## BEXAR COUNTY, TX SANITARY SEWER IMPROVEMENTS



## LOCATION MAP NOT-TO-SCALE

OWNER/DEVELOPER MEH HOLDING COMPANY LTD 5210 THOUSAND OAKS, SUITE 1318 SAN ANTONIO, TX 78233

## INDEX

1112 = 11	
DESCRIPTION	SHEET NO.
SANITARY SEWER COVER SHEET	6.0
OVERALL SANITARY SEWER PLAN	6.1
OVERALL SANITARY SEWER PLAN	6.2
LINE "A" PLAN & PROFILE	6.3
LINE "A" PLAN & PROFILE	6.4
LINE "B" PLAN & PROFILE	6.5
LINE "C" AND LINE "D" PLAN & PROFILE	6.6

LOWER - EASTER SEWERSHED - DOS RIOS / LEON CREEK

TOTAL LINEAR FOOTAGE OF PIPE: 3,751 LF OF 8" SDR 26 PLAT NO.: 23-11800440

SAWS JOB#: 23-1654

DEVELOPER'S NAME: MEH HOLDING COMPANY, LTD

SAWS BLOCK MAP#: 214558, 214560, 216560

CITY: SAN ANTONIO

PHONE#: (210) 493-2811

NUMBER OF LOTS: 112

DEVELOPER'S ADDRESS: 5210 THOUSAND OAKS, SUITE 1318

Engineering


& Design

www.colliersengineering.com

hom the services were contracted or to whom it is certified. This drawing ma e copied, reused, disclosed, distributed or relied upon for any other pur without the express written consent of Colliers Engineering & Design.



FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW CALL811 COM



**PRELIMINARY** 

SOUTHEAST **MEADOWS UNIT 3** PLAT# 23-11800440

> SAN ANTONIO **BEXAR COUNTY** TEXAS

> > SAN ANTONIO (KFW)

Engineering & Design

ZIP: 78233


TOTAL ACREAGE: 28.07 ACRES


TOTAL EDU'S: 112


San Antonio, TX 78231 Phone: 210.979.8444 TBPLS Firm#: 10194550


AS SHOWN 205-43-07


SANITARY SEWER COVER SHEET












CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND


ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.


- 1. SEWER PIPE WHERE WATER LINE CROSSES SHALL BE MEET THE REQUIREMENTS OF ASTM D2241. CONTRACTOR SHALL CENTER A 20 FOOT JOINT OF 160 P.S.I. PRESSURE RATED P.V.C. AT THE PROPOSED WATER CROSSING (NO SEPARATE PAY ITEM).
- 2. SEE THIS SHEET FOR BENCHMARK INFORMATION.
- 3. PIPE TYPE DESIGNATIONS ARE SDR 26. 4. SEE THIS SHEET FOR TYPICAL SANITARY SEWER / WATER CROSSING DETAIL.
- 5. ALL MANHOLES SHALL HAVE CONCRETE RING ENCASEMENT AND A WATER TIGHT RING AND COVER. 6. ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL BE IN ACCORDANCE WITH THE SAN ANTONIO WATER SYSTEM (SAWS) STANDARD SPECIFICATIONS.


#### THE CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITED TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE $\mid$ REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.


ALL MANHOLES MUST BE WATERTIGHT, WITH WATERTIGHT RINGS AND COVERS. THESE MANHOLES MUST BE VENTED PER SAWS DETAIL DD852-02. 














Engineering

& Design

www.colliersengineering.com

hom the services were contracted or to whom it is certified. This drawing may e copied, reused, disclosed, distributed or relied upon for any other purp without the express written consent of Colliers Engineering & Design.

FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

PROTECT YOURSELF
ALL STATES REQUIRE NOTIFICATION OF
EXCAVATORS, DESIGNERS, OR ANY PERSO
PREPARING TO DISTURB THE EARTH'S
SURFACE ANYWHERE IN ANY STATE



FOR SOUTHEAST **MEADOWS UNIT 3** PLAT# 23-11800440

> SAN ANTONIO **BEXAR COUNTY TEXAS**





3421 Paesanos San Antonio, TX 78231 Phone: 210.979.8444 COLLIERS ENGINEERING & DESIGN, INC TBPE Firm#: F-14909 TBPLS Firm#: 10194550

SAN ANTONIO (KFW)

LINE "C" AND LINE "D" PLAN & PROFILE

NOTE: DO NOT SCALE DRAWINGS FOR CONSTRUCTION





2+00


3+00

1+00

GENERAL INFORMATION

# SOUTHEAST MEADOWS UNIT 3

# BEXAR COUNTY, TX WATER IMPROVEMENTS



# LOCATION MAP NOT-TO-SCALE

OWNER/DEVELOPER MEH HOLDING COMPANY LTD 5210 THOUSAND OAKS, SUITE 1318 SAN ANTONIO, TX 78233

## INDEX


DESCRIPTION	SHEET NO.
WATER DISTRIBUTION COVER SHEET	7.0
WATER DISTRIBUTION PLAN	7.1
WATER DISTRIBUTION PLAN	7.2
WATER DISTRIBUTION DETAILS	7.3
WATER DISTRIBUTION DETAILS	7.4
WATER DISTRIBUTION DETAILS	7.5




Engineering & Design

copied, reused, disclosed, distributed or relied upon for any other p








**PRELIMINARY** 


SOUTHEAST MEADOWS UNIT 3 PLAT# 23-11800440


> SAN ANTONIO **BEXAR COUNTY TEXAS**

SAN ANTONIO (KFW) San Antonio, TX 78231 Phone: 210.979.8444

WATER DISTRIBUTION **COVER SHEET** 







21.60

NOTE: DO NOT SCALE DRAWINGS FOR CONSTRUCTION.

Engineering

& Design

AS SHOWN

205-43-07

SAN ANTONIO

**BEXAR COUNTY** 

**TEXAS** 

SAN ANTONIO (KFW) 3421 Paesanos San Antonio, TX 78231 Phone: 210.979.8444

COLLIERS ENGINEERING & DESIGN, INC

TBPE Firm#: F-14909 TBPLS Firm#: 10194550

SD

OWDT2054307

WATER DISTRIBUTION DETAILS

— 2" 90° G.I. ELL, THD.

2" X 12" G.I. NIPPLE, THE

2" GATE VALVE, THD. 2" X 6" G.I. NIPPLE, THD.

GREEN VALLEY SPECIAL UTILITY DISTRICT STANDARD SPECIFICATIONS & DETAILS

2" TEMPORARY BLOW-OFF ASSEMBLY ON 12" TO 16" MAINS N.T.S.


2" OR 16" X 48" D.I. MIPPLE, P.E. X M.J. ANCHOR WITH REACTION STOP 12" OR 16" X 2" ECCENTRICALLY RING IN CENTER TAPPED CAP, M.J.


RIVER CITY


ENGINEERING


Soot SOUTH 1" STREET OF AUSTIN, EXCAS TROVA FOR THE STREET OF AUSTIN, EXCAS TROVA F































JEFFREY W. MARTIN 139094 11/15/23 **PRELIMINARY MEADOWS UNIT 3** PLAT# 23-11800440 SAN ANTONIO **BEXAR COUNTY TEXAS** SAN ANTONIO (KFW) 3421 Paesanos Colliers Parkway San Antonio, TX 78231 Phone: 210.979.8444 Engineering COLLIERS ENGINEERING & DESIGN, IN & Design TBPE Firm#: F-14909 AS SHOWN WDT2054307 205-43-07


ANTERIORING A A D... CRITEMAN


NOTE: DO NOT SCALE DRAWINGS FOR CONSTRUCTION.

WATER DISTRIBUTION DETAILS











Lr = Length of Pipe Along

L = Length to be Restrained


the Run Free of Joints





Engineering & Design

www.colliersengineering.com



1. These Calculations are Provided for Reference. The Restrained Length Shall be Designed Based Upon the Conditions

RESTRAINED LENGTHS

**VERTICAL OFFSETS** 


3. If your distance between fittings is less than or equal to the calculated restraint length, restrain all joints between those fittings.


JULY 2022


DET-839-06


Encountered During Installation.


2. All joints within the calculated length must be restrained.











PRELIMINARY

FOR
SOUTHEAST
MEADOWS UNIT 3
PLAT# 23- 11800440

SAN ANTONIO BEXAR COUNTY TEXAS

Colliers

Engineering
& Design

3421 Paesanos
Parkway
San Antonio, TX 78231

Phone: 210.979.8444

COLLIERS ENGINEERING & DESIGN, INC
TBPE Firm#: F-14909
TBPLS Firm#: 10194550

SAN ANTONIO (KFW)

CALE: DATE: DRAWN BY: CHECK!

AS SHOWN 07/20/2023 SD S


ROJECT NUMBER: DRAWING NAME:
205-43-07 OWDT2054307


WATER DISTRIBUTION
DETAILS


NUMBER: 7.5

NOTE: DO NOT SCALE DRAWINGS FOR CONSTRUCTION.

BIMARTED OURTWORE 4007 4....... 7 E D.. CPUITBUALI







SECTION A-A


GENERAL NOTES:

THE FILTER BAG MATERIAL SHALL BE MADE OF POLYPROPYLENE,

POLYETHYLENE OR POLYAMIDE WOVEN FABRIC, MIN UNIT WEIGHT OF 4 OUNCES/SY, MULLEN BURST STRENGTH EXCEEDING 300 PSI AND ULTRAVIOLET

GRAVEL FILTER BAG DETAIL

THE FILTER BAG SHALL BE FILLED WITH CLEAN, MEDIUM TO COARSE GRAVEL (0.31 TO 0.75 INCH DIAMETER).



FIBER ROLL

Install fiber roll

measured along the

TYPICAL FIBER ROLL INSTALLATION

ENTRENCHMENT DETAIL

max 4'

face of the slope

varies between

10' and 20'

along a level contour

Install a fiber roll near

into a steeper slope

slope where it transitions

THE TOP OF THE SACK GABIONS SHOULD BE LEVEL AND ORIENTED PERPENDICULAR TO THE DIRECTION OF FLOW. FILTER FABRIC MATERIAL SHALL BE FASTENED TO WOVEN WIRE FILTER FABRIC MATERIAL SHOULD MEET THE FOLLOWING SPECIFICATIONS: RESISTANT TO ULTRAVIOLET LIGHT. FABRIC OUNCES PER SQUARE YARD. MINIMUM MULLEN BURST STRENGTH OF GALLONS PER MINUTE PER SQUARE FOOT OF FRONTAL AREA. STONE SIZE: ±4"-8" OPEN GRADED CRUSHED LIMESTONE NSPECT WEEKLY OR AFTER EACH RAINFALL EVENT AND REPAIR OR REPLACE AS NEEDED. WHEN SILT REACHES A DEPTH OF 6 INCHES OR MORE ABOVE NATURAL GROUND, SILT SHALL BE REMOVED AND DISPOSED IN AN APPROVED MANNER THAT WILL NOT CONTRIBUTE TO RESILTATION. CONTAMINATED SEDIMENT MUST BE REMOVED AND DISPOSED OF DFF-SITE IN ACCORDANCE WITH APPLICABLE REGULATIONS.

THE MATERIAL, INSTALLATION, INSPECTION, AND MAINTENANCE OF

(1) Core material: Core material should be biodegradable or recyclable. Material

FIBER ROLLS WILL BE PER THE MANUFACTURE'S SPECIFICATIONS

AND SHALL ALSO COMPLY WITH THE TEXAS COMMISSION OF

may be compost, mulch, aspen wood fibers, chipped site vegetation, agricultural rice or wheat straw, coconut fiber, 100% recyclable fibers, or

(2) Containment Mesh: Containment mesh should be 100% biodegradable,

photodegradable or recyclable such as burlap, twine, UV photodegradable

as part of a vegetative system use biodegradable or photodegradable mesh.

Slope inclination of 4:1 (H:V) or flatter: Fiber rolls should be placed at a

Slope inclination 2:1 (H:V) or greater: Fiber Rolls should be placed at a

Slope inclination between 4:1 and 2:1 (H:V): Fiber Rolls should be placed at a

(2) Turn the ends of the fiber roll up slope to prevent runoff from going around the

(3) Stake fiber rolls into a 2 to 4 in. deep trench with a width equal to the diameter of

(4) Drive stakes at the end of each fiber roll and spaced 4 ft maximum on center.

(5) Use wood stakes with a nominal classification of 0.75 by 0.75 in. and minimum

(6) If more than one fiber roll is placed in a row, the rolls should be overlapped, not

(3) If the fiber roll is used as a sediment capture device, or as an erosion control device to maintain sheet flows, sediment that accumulates behind the role must be

periodically removed in order to maintain its effectiveness. Sediment should be

incorporated into earthwork on the site or disposed of at an appropriate location.

depth, usually one-half the distance between the top of the fiber roll and the adjacent ground surface. Sediment removed during maintenance may be

removed when the accumulation reaches one-half the designated sediment storage

plastic, polyester, or similar material. When the fiber role will remain in place

BEST MANAGEMENT PRACTICES" AS NOTED BELOW.

For temporary installation recyclable mesh is recommended.

(1) Locate fiber rolls on level contours spaced as follows:

maximum interval of 15 ft. (a closer spacing is more effective).

maximum interval of 10 ft. (a closer spacing is more effective).

(2) Repair or replace split, torn, unraveling, or slumping fiber rolls.

similar materials.

maximum interval of 20 ft

Inspection and Maintenance Guidelines:


the fiber roll.


abutted.


(1) Inspect weekly

ENVIRONMENTAL QUALITY CURRENT "TECHNICAL GUIDANCE ON

TYPE 4 SACK GABIONS







(1) The aggregate should consist of 4 to 8 inch washed stone over a stable foundation as specified in the plan. PUBLIC ROAD (2) The aggregate should be placed with a minimum thickness of 8 inches (3) The geotextile fabric should be designed specifically for use as a soil filtration media with an approximate weight of 6 oz/yd2, a mullen burst rating of 140 lb/in2, and an equivalent opening size greater than a number

(4) If a washing facility is required, a level area with a minimum of 4 inch diameter washed stone or commercial rack should be included in the plans. Divert wastewater to a sediment trap or basin.

Installation: (North Carolina, 1993) 1) Avoid curves on public roads and steep slopes. Remove vegetation and other objectionable material from the foundation

(2) The minimum width of the entrance/exit should be 12 feet or the full width of exit roadway, whichever is greater. (3) The construction entrance should be at least 50 feet long. (4) If the slope toward the road exceeds 2%, construct a ridge, 6 to 8 inches high with 3:1 (H:V) side slopes, across the foundation approximately 15 feet from the entrance to divert runoff away from the public road. (5) Place geotextile fabric and grade foundation to improve stability, especially where wet conditions are anticipated. (6) Place stone to dimensions and grade shown on plans. Leave surface smooth and slope for drainage. (7) Divert all surface runoff and drainage from the stone pad to a sediment trap or basin. (8) Install pipe under pad as needed to maintain proper public road drainage.


The entrance should be maintained in a condition, which will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repair andlor cleanout of

any measures used to trap sediment. (2) All sediment spilled, dropped, washed or tracked onto public rights-of-way should be removed immediately by contractor (3) When necessary, wheels should be cleaned to remove sediment prior to entrance onto public right-of-way.

(4) When washing is required, it should be done on an area stabilized with crushed stone that drains into an approved sedimen CONSTRUCTION ENTRANCE/EXIT (5) All sediment should be prevented from entering any storm drain, ditch or water course by using approved methods.

STABILIZED CONSTRUCTION ENTRANCE / EXIT

area. Grade crown foundation for positive drainage.



ISOMETRIC PLAN VIEW **CROSS SECTION** 

GEOTEXTILE FABRIC

TO STABILIZE FOUNDATION

(1) The berm structure should be, secured with a woven wire sheathing having maximum opening of 1 inch and a minimum wire diameter of 20 gauge galvanized and should be secured with shoat rings. (2) Clean, open graded 3- to 5-inch diameter rock should be used, except in areas where high velocities or large volumes of flow are expected, where 5- to 8-inch diameter rocks may be used.

(1) Lay out the woven wire sheathing perpendicular to the flow line. The sheathing should be 20 gauge woven wire mesh with 1 inch openings. (2) Berm should have a top width of 2 feet minimum with side slopes being 2:1 (H:V) or flatter. (3) Place the rock along the sheathing as shown in the diagram Figure 1-28), to a height not less than

(4) Wrap the wire sheathing around the rock and secure with tie wire so that the ends of the sheathing overlap at least 2 inches, airl the berm retains its shape when walked upon (5) Berm should be built along the contour at zero percent grade or as near as possible. (6) The ends of the berm should be tied into existing upslope grade and the berm should be buried in a

trench approximately 3 to 4 inches deep to prevent failure of the control.

Inspection and Maintenance Guidelines: (1) Inspection should be made weekly by the responsible party. For installations in streambeds, additional daily inspections should be made.


(2) Remove sediment and other debris when buildup reaches 6 inches and dispose of the accumulated silt in an approved manner that will not cause any additional siltation.

(3) Repair any loose wire sheathing.

(4) The berm should be reshaped as needed during inspection.

(5) The berm should be replaced when the structure ceases to function as intended due to silt accumulation among the rocks, washout, construction traffic damage, etc.

(6) The rock berm should be left in place until all upstream areas are stabilized and accumulated silt



(1) SILT FENCE MATERIAL SHOULD BE POLYPROPYLENE, POLYETHYLENE OR POLYAMIDE WOVEN OR NONWOVEN FABRIC. THE FABRIC WIDTH SHOULD BE 36 INCHES, WITH A MINIMUM UNIT WEIGHT OF 4.5 OZ/YD, MULLEN BURST STRENGTH EXCEEDING 190 LB/IN2, ULTRAVIOLET STABILITY EXCEEDING 70%, AND MINIMUM APPARENT OPENING SIZE OF U.S. SIEVE NO. 30. (2) FENCE POSTS SHOULD BE MADE OF HOT ROLLED STEEL, AT LEAST 4 FEET LONG WITH TEE OR YBAR CROSS SECTION, SURFACE PAINTED

USED TO ANCHOR THE BERM. (3) WOVEN WIRE BACKING TO SUPPORT THE FABRIC SHOULD BE GALVANIZED 2" X 4" WELDED WIRE, 12 GAUGE MINIMUM. (4) THE BERM STRUCTURE SHOULD BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM OPENING OF 1 INCH. AND A MINIMUM WIRE DIAMETER OF 20 GAUGE GALVANIZED AND SHOULD BE SECURED WITH SHOAT RINGS.

OR GALVANIZED, MINIMUM NOMINAL WEIGHT 1.25 LB/FL2, AND BRINDELL HARDNESS EXCEEDING 140. REBAR (EITHER #5 OR #6) MAY ALSO BE

(5) CLEAN, OPEN GRADED 3- TO 5-INCH DIAMETER ROCK SHOULD BE USED, EXCEPT IN AREAS WHERE HIGH VELOCITIES OR LARGE VOLUMES OF FLOW ARE EXPECTED, WHERE 5- TO 8-INCH DIAMETER ROCKS MAY BE USED.

(1) LAY OUT THE WOVEN WIRE SHEATHING PERPENDICULAR TO THE FLOW LINE. THE SHEATHING SHOULD BE 20 GAUGE WOVEN WIRE MESH

WITH 1-INCH OPENINGS (2) INSTALL THE SILT FENCE ALONG THE CENTER OF THE PROPOSED BERM PLACEMENT, AS WITH A NORMAL SILT FENCE DESCRIBED IN SECTION 2.4.3. (3) PLACE THE ROCK ALONG THE SHEATHING ON BOTH SIDES OF THE SILT FENCE AS SHOWN IN THE DIAGRAM (FIGURE 1-29), TO A HEIGHT NOT LESS THAN 24 INCHES. CLEAN, OPEN GRADED 3- 5" DIAMETER ROCK SHOULD BE USED, EXCEPT IN AREAS WHERE HIGH VELOCITIES OR LARGE VOLUMES OF FLOW ARE EXPECTED, WHERE 5- TO 8-INCH DIAMETER ROCK MAY BE USED.

(4) WRAP THE WIRE SHEATHING AROUND THE ROCK AND SECURE WITH TIE WIRE SO THAT THE ENDS OF THE SHEATHING OVERLAP AT LEAST 2 INCHES, AND THE BERM RETAINS ITS SHAPE WHEN WALKED UPON. (5) THE HIGH SERVICE ROCK BERM SHOULD BE REMOVED WHEN THE SITE IS REVEGETATED OR OTHERWISE STABILIZED OR IT MAY REMAIN IN PLACE AS A PERMANENT BMP IF DRAINAGE IS ADEQUATE.

(3) REPAIR ANY LOOSE WIRE SHEATHING.

(1) INSPECTION SHOULD BE MADE WEEKLY BY THE RESPONSIBLE PARTY. FOR INSTALLATIONS IN STREAMBEDS, ADDITIONAL DAILY INSPECTIONS SHOULD BE MADE ON ROCK BERM. (2) REMOVE SEDIMENT AND OTHER DEBRIS WHEN BUILDUP REACHES 6 INCHES AND DISPOSE OF THE ACCUMULATED SILT OF IN AN APPROVED

(4) THE BERM SHOULD BE RESHAPED AS NEEDED DURING INSPECTION. (5) THE BERM SHOULD BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED DUE TO SILT ACCUMULATION AMONG THE ROCKS, WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC. (6) THE ROCK BERM SHOULD BE LEFT IN PLACE UNTIL ALL UPSTREAM AREAS ARE STABILIZED AND ACCUMULATED SILT REMOVED.

HIGH SERVICE ROCK BERM

Engineering & Design

www.colliersengineering.com

pyright © 2023. Colliers Engineering & Design All Rights Reserved. This drav d all the information contained herein is authorized for use only by the party hom the services were contracted or to whom it is certified. This drawing may e copied, reused, disclosed, distributed or relied upon for any other purp

without the express written consent of Colliers Engineering & Design.

Formerly Known as



FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

JEFFREY W. MART.

**PRELIMINARY** 

SOUTHEAST **MEADOWS UNIT 3** PLAT# 23-11800440

> SAN ANTONIO BEXAR COUNTY

> > TEXAS

	SAN ANTONIO (KFW)
Colliers	3421 Paesanos
	Parkway
	San Antonio, TX 78231
Engineering	Phone: 210.979.8444

& Design

421 Paesanos Antonio, TX 78231 one: 210.979.8444 COLLIERS ENGINEERING & DESIGN, IN TBPE Firm#: F-14909 TBPLS Firm#: 10194550

AS SHOWN SW3P-DT2054307

STORMWATER POLLUTION PREVENTION DETAILS

8.2